



This is a digital copy of a book that was preserved for generations on library shelves before it was carefully scanned by Google as part of a project to make the world's books discoverable online.

It has survived long enough for the copyright to expire and the book to enter the public domain. A public domain book is one that was never subject to copyright or whose legal copyright term has expired. Whether a book is in the public domain may vary country to country. Public domain books are our gateways to the past, representing a wealth of history, culture and knowledge that's often difficult to discover.

Marks, notations and other marginalia present in the original volume will appear in this file - a reminder of this book's long journey from the publisher to a library and finally to you.

Usage guidelines

Google is proud to partner with libraries to digitize public domain materials and make them widely accessible. Public domain books belong to the public and we are merely their custodians. Nevertheless, this work is expensive, so in order to keep providing this resource, we have taken steps to prevent abuse by commercial parties, including placing technical restrictions on automated querying.

We also ask that you:


- + *Make non-commercial use of the files* We designed Google Book Search for use by individuals, and we request that you use these files for personal, non-commercial purposes.
- + *Refrain from automated querying* Do not send automated queries of any sort to Google's system: If you are conducting research on machine translation, optical character recognition or other areas where access to a large amount of text is helpful, please contact us. We encourage the use of public domain materials for these purposes and may be able to help.
- + *Maintain attribution* The Google "watermark" you see on each file is essential for informing people about this project and helping them find additional materials through Google Book Search. Please do not remove it.
- + *Keep it legal* Whatever your use, remember that you are responsible for ensuring that what you are doing is legal. Do not assume that just because we believe a book is in the public domain for users in the United States, that the work is also in the public domain for users in other countries. Whether a book is still in copyright varies from country to country, and we can't offer guidance on whether any specific use of any specific book is allowed. Please do not assume that a book's appearance in Google Book Search means it can be used in any manner anywhere in the world. Copyright infringement liability can be quite severe.


About Google Book Search


Google's mission is to organize the world's information and to make it universally accessible and useful. Google Book Search helps readers discover the world's books while helping authors and publishers reach new audiences. You can search through the full text of this book on the web at <http://books.google.com/>














The map is wanting.

©

A

GEOGRAPHICAL AND HISTORICAL

DESCRIPTION

OF

// ASIA MINOR; //

WITH A MAP.

John Artington
BY
J. A. CRAMER, D.D.

PRINCIPAL OF NEW INN HALL, AND PUBLIC ORATOR OF THE
UNIVERSITY OF OXFORD.

IN TWO VOLUMES.

Νῦν δὲ αὐτὸν παραλίης Ἀσίης πόρον ἔξενέποιμι
·Οσ ρά τε πρὸς νότου εἰσιν, ἐφ' Ἐλλήσποντον δδεύων
Καὶ ποτὶ μηκίστου νότιου ρόου Αἴγαιοιο.

DIONYS. PERIEG. v. 799.

VOL. I.

OXFORD,

AT THE UNIVERSITY PRESS,

MDCCCXXXII.

AH 2107.5

~~7024401~~

P R E F A C E.

THE present volumes complete the plan I had originally proposed to myself of illustrating the geographical antiquities of the three countries, which offered the greatest interest to the classical student. Asia Minor presents a field of inquiry hardly inferior to the other two in historical importance, since it exhibits a nearly unbroken chain of events, from the siege of Troy to the downfall of Constantinople; and it possesses moreover one point of peculiar interest, from being so closely connected with the name and labours of St. Paul.

With respect to the comparative geography of this extensive and diversified country, our information on several points, more especially in the interior, is still inadequate and defective. Much certainly has been done by that eminent geographer and antiquary

Col. Leake, in his work on Asia Minor^a, and some further light has since been derived from the journals of Mr. Arundell and Major Keppel, and from foreign sources; but still our knowledge of Anatolia is in many respects incomplete.


The late celebrated Major Rennell had apparently bestowed much time and labour on the comparative geography of Western Asia, and had he lived to complete the work, he would certainly have produced a valuable map of those extensive regions. But the two volumes which have been published from his papers contain little that was not known before; and present rather a series of detailed notes and observations, than a systematic and organized work^b.

Such being the state of our information respecting the comparative geography of Asia Minor, I cannot pretend to offer the map

^a Journal of a Tour in Asia Minor, with Comparative Remarks on the Ancient and Modern Geography of that country, by W. L. Leake. 8vo. Lond. 1824.

^b A Treatise on the Comparative Geography of Western Asia, accompanied with an Atlas of Maps, in two vols. 8vo. Lond. 1831.

which accompanies these volumes as at all equal in truth and accuracy to those of Italy and Greece, but I may express the hope that it will be found superior to any that have preceded it. And I think considerable credit is due to Mr. Findlay for the manner in which he has put together and arranged the different materials within his reach.



CONTENTS

OF

THE FIRST VOLUME.

SECTION I. ASIA MINOR.

PRELIMINARY observations on the name of Asia—Principal geographical features of the peninsula commonly called Asia Minor—Inquiry into the origin of the various nations by which it was peopled—Divisions.

Page 1.

SECTION II. MYSIA AND TROAS.

Origin and history of the Mysians—The Hellespont and Propontis—Interior of Mysia—The Teucri and Dardani—Ancient Ilium and the Homeric topography—The Troad—Æolian colonies—Kingdom of Pergamus—Island of Lesbos.

30.

SECTION III. BITHYNIA.

Origin and history of the Bithynians—Boundaries of the province under the Roman empire—Description of the coast on the Propontis—Interior of the country around mount Olympus and the lake Ascanius—Nicæa and Nicomedia, with the adjoining bays—Chalcedon and the Thracian Bosphorus—The Euxine—Coast of that sea as far as the Sangarius—The Mariandyni and Caucones—Interior of eastern Bithynia.

167.

SECTION IV.

PAPHLAGONIA.

Origin and history of the Paphlagonians—Boundaries of their country—Description of the coast between the rivers Parthenius and Halys—Interior of the province.

216.

SECTION V.

PONTUS.

Dynasty of Pontus from its foundation as a kingdom till its conquest by the Roman arms—Boundaries and geographical features—Course of the river Halys—Description of the coast—Interior.

242.

SECTION VI.

IONIA AND LYDIA.

General history of the Ionian colonies and their confederacy—Description of the twelve states of Ionia and the adjacent islands—Origin of the Maeonians and Lydians—Dynasties of Lydia—Boundaries and topography of that country.

323.

SECTION I.

ASIA MINOR.

Preliminary observations on the name of Asia—Principal geographical features of the peninsula commonly called Asia Minor—Inquiry into the origin of the various nations by which it was peopled—Divisions.

AS EARLY as the time of Herodotus we find the name of Asia employed to designate the vast continent situated to the east of Europe, and almost entirely subject at that period to the Persian dominion. The Greeks, as we learn from that historian, pretended that it was derived from Asia, the wife of Prometheus, but the Lydians, on the other hand, affirmed that its origin was to be sought for in their country. For that Asius, from whom it was deduced, was the grandson of Manes, one of their earliest monarchs; and, to corroborate this assertion, they adduced the fact of the name of Asias having been originally attached to a Sardian tribe^a. (IV. 45.) The evidence which can be brought forward in favour of the Lydian tradition, leaves little doubt respecting the issue of this question. It may be ob-

^a Bochart derives the name from *Asi*, a Phœnician word signifying a *middle part*, or something intermediate; according to which etymology

Asia would signify the continent situated between Europe and Africa. Geogr. Sacr. IV. 33. p. 298.

served that Homer applied the name of Asia to a small district of Mæonia, or Lydia, situated near the river Caystrus,

'Ασίω ἐν λειμῶνι, Καῦστρίου ἀμφὶ ρέεθρα.

IL. B. 461.

a passage which Virgil has imitated in his Georgics :

. quæ Asia circum
Dulcibus in stagnis rimantur prata Caystri.

I. 383.

Euripides also evidently restricts the appellation to a portion of Lydia, where he says,

*'Ασίας ἀπὸ γᾶς
ἰερὸν Τμῆλον ἀμείψασα—*

БАССИ. 64.

(Cf. Dionys. Perieg. 836. et Eustath. Comm.)

By what process this specific name came to be applied generally to the whole peninsula, and after that to the entire Asiatic continent, it is not easy to determine. But it is probable that the Ionian Greeks, on their first arrival on the banks of the Mæander and Caystrus, adopted the name which they found already attached to the country, and communicated it to their European countrymen. These gradually learned to apply it first to that maritime portion with which they were most familiar, then to the interior also, and finally to all those countries which were situated to the east of Greece. This final extension had already taken place, as I have before observed, in the time of Herodotus, who employs the division of Upper and Lower Asia. The latter of these answers in fact to what we now call Asia Minor, while the former denotes the vast

tract of country situated to the east of the Euphrates. Notwithstanding, however, this wide acceptance given to the name, it appears clearly that it always remained attached in a peculiar and restricted sense to a portion of Asia Minor, which strongly confirms the notion that the appellation originated in that district. In proof of the above assertion it is only necessary to refer to the title of *Asia Propria*, ή ἴδιως καλουμένη Ἀσία, given to the Roman proconsular province forming a part only of the Asiatic peninsula. (Strab. XIII. p. 626. II. p. 188.) It is in this sense too that we always find the word used in the New Testament, as in the Acts ii. 9. where Asia is distinguished from Cappadocia, Pontus, Phrygia, and Pamphylia; and xvi. 6. it is said, “Now when they had gone through “ out Phrygia and the region of Galatia, and were “ forbidden of the Holy Ghost to preach the word “ in Asia.” From the book of Revelations, which is addressed to the seven churches in Asia, it is further seen that the name was strictly confined to that portion of ancient Lydia which contained Ephesus, Smyrna, Pergamus, Sardis, &c.^b It is not exactly known when the peninsula came to be designated by the name of Asia Minor, now generally used by the European nations; but it does not, I believe, appear in any author prior to Orosius, who employs it, (I. 2.) as well as Constantine Porphyrogenetes, (de Themat. I. 8.) The term *Anatolia*, used by the Turks to denote this portion of the Ottoman

^b See Cellarius *Dissertatio de Sept. Eccles. Asiæ inter Dissert. Academ. p. 412.*; also archbishop Usher's *Geogr.* and

Hist. disquisition touching the Asia properly so called. Oxford, 1643.

empire, is evidently of Greek origin, and answers to the Frank word *Levant*. Towards the decline of the Roman empire we find Asia Minor divided into two dioceses, or provinces, called *Asiana* and *Pontica*, (*Notit. Imper. I.*) each governed by a lieutenant termed *Vicarius*. (*Cod. Theod. V. tit. 2.*) Other divisions were afterwards adopted by the Byzantine emperors, but these do not come within the scope of a work especially intended to illustrate classical geography.

Asia Minor is bounded on the north by the *Pontus Euxinus*, or *Black sea*, which communicates with the *Propontis*, or *sea of Marmara*, by means of the *Bosphorus*, or *straits of Constantinople*; and this again with the *Ægæum Mare* by the *Helles-pontus*, now *straits of the Dardanelles*. The *Ægean sea*, called *Archipelago* in modern geography, forms its western boundary, while on the south its shores are washed by that inland sea to which the name of *Internum* or *Mediterraneum* was more particularly applied. In order to define the eastern limit of the peninsula, we must follow the river sometimes called *Acampsis*, at others *Apsarus*, now *Tchorok-sou*, which divides *Pontus* from *Colchis*, from its termination into the *Euxine*, to where it meets the great chain of Armenian mountains formerly called *Scydisces*. This ridge, running in a south-westerly direction from the *Acampsis* to the *Euphrates*, then forms one boundary as far as the latter river, the course of which, dividing the two *Armenias*, traces the line of separation as far as the little district of *Melitene*, belonging to *Cappadocia*. At this point the great chain of mount *Taurus*, running from west to east, is intersected by the river. Our line,

therefore, leaving the Euphrates, follows Taurus to the west, till it meets mount Amanus, which, branching off from the central ridge in a south-westerly direction, closes upon the Cilician sea at the defile called the *Syriæ Pylæ*, and thus completes the angular line which joins the two seas, and forms the fourth side of the Asiatic peninsula.-

Were we to form our notions of the shape and extent of Asia Minor from the measurements transmitted to us by the geographers of antiquity, we should be led into numerous errors, and those of no trifling kind. This will be at once evident by merely attending to those of Strabo; for being a native of the country, and, generally speaking, the best informed writer on the subject of which he treats, he may fairly be considered as affording the best criterion of the accuracy of the ancients on the point in question.

Now with respect to the northern coast of Asia Minor, Strabo's want of accuracy is rendered apparent, by his supposing the shore of the Euxine to form nearly a straight line from Byzantium to Amisus; (II. p. 74.) whereas it advances in a north-easterly direction nearly the whole way, from the Thracian Bosphorus to the *Cape Inje*, formerly Syrias, above Sinope; so that the difference of latitude between this promontory and Byzantium is more than one degree. From Sinope it bends to the south again as far as Amisus, which is nearly forty miles below the parallel of the former town. From Chalcedon to Sinope, Strabo reckons 3500 stadia, and 900 from Sinope to Amisus, in all 4400; and for the southern coast about 5000, from Rhodes to Issus in Cilicia. Thus Issus would be 600 stadia to

the east of Amisus, and yet Strabo himself elsewhere looks upon these two places as situated under the same meridian. (II. p. 126. XIV. p. 678.^c) With regard to the southern coast, the same geographer, when he affirms that it extended from Rhodes to Tarsus in a south-easterly direction, does not appear to have been aware of the great sweep it takes, first round the province of Lycia to the great gulf of *Attalia*, the ancient Mare Pamphylium, and round Cilicia to the mouth of the Cydnus. With respect to the breadth of the peninsula, Strabo has given us no positive statement; but from his measurement of the western coast, and the too great elevation he assigns to Byzantium, it appears he considered it to be much broader than it is. He informs us, however, that Eratosthenes reckoned 3000 stadia between Issus and Amisus, where the neck of the isthmus is the narrowest. This statement comes very near the truth; for the best modern maps allow about 330 miles from one sea to another in this part. It may be here observed, that Herodotus was very wide from the mark, when he estimated the distance from the coast of Cilicia to Sinope to be only five days' march for a person lightly equipped. (II. 34.^d) The peninsula is widest between capes Anemurium, *Anemur*, in Cilicia, and Carambis, *Kerempe*, in Paphlagonia.

Asia Minor contains numerous chains of mountains, some of which attain to a great elevation. The most

^c Gosselin, *Géogr. des Grecs Analysée*, p. 95.

^d The ancients themselves were aware of the error made by Herodotus in this matter,

for Scymnus of Chios corrects his statement, and observes, that the distance is not less than seven days' journey. *Fragm. v. 885.*

considerable is that of mount Taurus, which, commencing at the Sacrum Promontorium on the Lycian and Pamphylian coast, stretches in a north-easterly direction through Pisidia, Isauria, and Cappadocia, till it is intersected by the Euphrates near Melitene. It extends, however, much further, according to Strabo, as that geographer connects it with the great Indian ridge of Imaus, or Emodius, now *Himalaya*. (XI. p. 511.) He looks, indeed, upon this great chain as forming the belt of the entire Asiatic continent for the space of 4500 stadia, (XI. p. 490.) whilst its breadth in some parts is not less than 3000 stadia. That part of mount Taurus which belongs to Asia Minor, and with which we are alone concerned at present, is called by the Turks *Sultan dagh*. To the west it is connected with the chain of lofty mountains known to the ancients by the name of Cragus, and which rises precipitously above the coast of Lycia throughout nearly the whole of its extent. To the north-east Taurus sends out one of its ramifications under the name of Anti-taurus, through Cappadocia and Armenia Minor; the highest point of this ridge was mount Argæus, its summit, as Strabo affirms, being covered with perpetual snow. (XII. p. 538.) Further north, Anti-taurus is connected with the inferior chains which traverse Paphlagonia and Pontus; such as mount Teches, Scydisces, Paryadres, and others, uniting afterwards with the central Armenian range of which Ararat forms the highest point; and stretching also into Colchis, where it meets the no less elevated ridge of Caucasus. In the north-western parts of Asia Minor we have the celebrated chain of Ida, which rises above the coast of the an-

cient Troad, and unites to the north-east with the high range of the Mysian, and Bithynian Olympus ; this again is connected with several chains which form the principal basons and valleys of Phrygia and Galatia. To the south of Ida, and in the ancient kingdom of Lydia, we have the parallel chains of Sipylus and Tmolus running from west to east, and uniting with the different ranges which surround Phrygia on every side. From these and other mountains, which will be specified in the course of this work, descend numerous rivers, forming large and fertile valleys, and finally discharging their waters into the several seas which wash the shores of the peninsula. Of those which fall into the Ægean sea the principal are the Caicus, now *Bakir-tchai*, Hermus, *Kodus*, Caystrus, now *Lesser Mendere*, and the Maeander, *Greater Mendere*. All these, with the exception of the first, which rises in Mysia, come from the mountains of Phrygia, together with their numerous tributary streams, and have their course generally parallel to each other. The rivers which flow into the Propontis from mount Ida and Olympus are the Granicus, *Satal-dere*, Æsepus, *Boklu*, or *Guimenen-tchai*, and Rhindacus, *Edrene-sou*. Those which discharge their waters into the Euxine are the Sangarius, now *Sakaria*, which rises in Galatia and traverses a great portion of Phrygia and Bithynia, the Billæus, *Filbas*, and Parthenius, or *Bartan*. But the largest of these rivers, and indeed of all Asia Minor, is the Halys, now *Kizil-ermak*, which consists of two branches, one rising in the Cappadocian mountains on the frontiers of Cilicia, the other in Armenia Minor on the borders of Pontus, and after a long

and tortuous course, in which it nearly traverses the peninsula from south-west to north-east, falls into the Euxine to the south-east of Sinope. Beyond is the Iris, formed by the junction of the Scylax, Lycus, and other streams; its mouth is a little to the east of *Samsoun*, the ancient Amisus. The rivers which discharge their waters into the Pamphylian and Cilician seas are much less considerable, owing to the proximity of mount Taurus, from which they descend, to the coast. They are the Catarrhactes, now *Duden*, Calycadnus, *Ghiuk-sou*, Cydnus, *Tersoos*, Sarus, *Sihoun*, and Pyramus, now *Gihoun*.

Asia Minor contains several lakes, but most of them are inconsiderable, and unnoticed by classical writers. Those which can be identified are the Aphnitis, Dascylitis, Miletopolitis, and Apolloniatis, in Mysia; the Ascanius and Sophon, in Bithynia. In Phrygia we find the great salt lake Tattæus, noticed by Strabo, (XII. p. 568.) now *Tusla*, together with the Palus Trogitis and Caralitis, besides several others, whose ancient names are unknown.

Few countries present such a diversity of soil and climate as the great peninsula to which our attention is at present directed. The genial temperature of Ionia, Lydia, and Caria, and indeed, generally speaking, of the whole of western Asia, together with the extreme fertility of those provinces, are proved beyond dispute by the number and opulence of the towns they contained, especially those founded by Grecian colonists. Herodotus affirms, that the climate of Ionia surpassed that of every country with which he was acquainted, (I. 142.) and the testimony of antiquity is in this respect fully confirmed by the accounts of modern travellers and geogra-

phers. On the other hand, large tracts of country were very thinly inhabited, from the coldness of the climate and the unproductiveness of the soil. This was more especially the case in the mountainous districts of Lycia, Pisidia, Cilicia, and Cappadocia, where the land is very elevated, and the snow remains for a considerable part of the year. Many parts of Phrygia and Galatia were also nearly deserted, from the barrenness of the ground, which was strongly impregnated with salt, and exhibited, besides, other indications of volcanic agency. This was principally observed in that part of Lydia called Catacecaumene, or *the burnt*, and near the Maeander. Several other provinces presented similar appearances, though in a less degree; but the whole country appears to have been subject at an early period to violent earthquakes, which destroyed or damaged many flourishing cities. (Strab. XII. p. 578.)

Nevertheless, taken collectively, Asia Minor was one of the most productive and opulent countries of which antiquity has left us any account. The wealth of the kings of Phrygia and Lydia had become proverbial at a time when Greece and the rest of Europe were yet without civilization or commerce. Under the empire of the Persians, Asia Minor was divided into five nomes or districts, if we include the tribes which belong to the province commonly known by the name of Pontus; these poured annually into the royal treasury the sum of 2060 Euboic silver talents, or little short of one seventh of the whole revenue, which is estimated by Herodotus at 14,560 talents. Of this sum it should be observed, that India alone furnished in

gold ore the value of 4680 silver talents, and Assyria 1000 talents. (Herod. III. 90.) So that if we deduct the produce of these two satrapies from the whole amount, it will reduce the proportion of the revenue of Asia Minor to that of the remaining 18 satrapies as 2 to 9. And it may be seen by the map that Asia Minor does not constitute one tenth part of the Persian empire in the time of Darius. It was by means of the great resources which the younger Cyrus derived from this country, that the Lacedæmonians, whom he befriended, were enabled to conquer Athens, and to put an end to the Peloponnesian war. By the help of the same resources that prince had nearly succeeded in his ambitious enterprise against the throne of his brother Artaxerxes. Persia may be said to have been already conquered when the battles of the Granicus and Issus secured to Alexander the possession of Asia Minor. Its annexation to the crown of Syria, after the death of that prince, in consequence of the defeat and death of Antigonus in the battle of Ipsus, threw a degree of weight in the political scale in favour of the Seleucidæ, which might have proved prejudicial to the independence of the surrounding countries, or at least have served to check the rapacious designs of the Romans, if the sovereigns of that house had been gifted with greater energy and powers of mind. One battle, however, wrested it from the feeble grasp of Antiochus, and annexed it to the empire of his enterprising and restless foes. In their hands Asia Minor became a source of vast profit and wealth; and we have the authority of Cicero for stating, that the Roman treasury derived its largest and surest revenues from that great pro-

vince. (Orat. pro Leg. Manil. §. 2, 6.) “Certissima
“ populi Romani vectigalia, et maxima.” And, (§. 6,
1.) “Asia vero tam opima est et fertilis, ut et uber-
“ tate agrorum, et varietate fructuum et magni-
“ tudine pastionis, et multitudine earum rerum,
“ quæ exportantur, facile omnibus terris antecellat.”
With regard to mineral productions, we know that
the mountains of Lydia, Phrygia, and Mysia, in
ancient times, produced gold. Pontus furnished
silver, iron, and sandarach. Phrygia, Mysia, and
Caria supplied several sorts of marble highly prized
by the Romans for the beauty and variety of their
colours. In Cappadocia were to be found quarries
of alabaster, onyx, and crystal, and rich veins of
the earth called sinope. The vegetable produce
consisted in corn, millet, and every other sort of
grain, which were grown in the greatest abundance,
not only in the extensive valleys and plains, but even
on some of the elevated lands in the chain of mount
Taurus. The Hellespontine district, the islands of
Lesbos and Chios, and some parts of Ionia and
Caria, furnished wines highly esteemed by the an-
cients. Pontus, Bithynia, and Galatia abounded in
fruit-trees of different sorts; Cilicia supplied saffron
and the gum storax; and the olive and fig-tree flou-
rished in almost every part of the peninsula. The
forests of Ida, Tmolus, Olympus, and Taurus grew
timber for the construction of ships, and other pur-
poses, as well as fuel in the greatest abundance.
The rich pastures of the provinces watered by the
Halys, Thermodon, Sangarius, and Maeander, sup-
ported numerous herds and flocks. Paphlagonia
was celebrated for its mules as early as the days of
Homer; and the steeds of Cappadocia were reserved

for the royal studs of Persia and Byzantium. The fleeces of Ionia were unrivalled throughout the world for the softness of their texture; and the Persian monarchs drew from Cilicia annually a tributary supply of white horses.

If to these physical advantages we add others, presented by the great extent of coast and the number of excellent harbours it afforded, it will appear, that no country was so much favoured by nature, and so well calculated for becoming the centre of a mighty and perhaps universal empire. But the moral condition and character of its population has never kept pace with the physical resources of the country. From the earliest period, under the kings of Assyria, the dynasties of Lydia and Persia, under the empires of Rome and Byzantium, down to the present day, Asia Minor has been peopled by a race fitted, as it were, by nature for slavery and bondage. Effeminacy and luxury have been the prevailing habits of the inhabitants from the times of the soft and voluptuous Lydians to those of the indolent Turk; and this will probably always be the case as long as the softness of the climate and the fertility of the soil continue to exercise an enervating influence over the character of the people; an influence which has shewn itself so strikingly, first in the change it wrought upon the Greek colonists, who, from being brave and hardy like the parent race, became proverbially soft and effeminate; then upon their Persian conquerors; and, lastly, on the warlike and fierce Osmanlis.

There is only one short period in the history of Asia Minor during which it may be seen how the genius and energy of one man, even with such a

population as we have here described, and the resources of less than half the peninsula, could grapple with the giant strength of Rome, and even shake her power to the very centre. The noble stand made by Mithridates, though finally unsuccessful, serves at least to prove, that if Asia Minor had been united under the sole command of such a prince, it never would have remained a province of the Roman empire.

The origin of the first tribes who peopled Asia Minor, like that of almost every nation of antiquity, is a question involved in obscurity, and beset with doubts and perplexities; from which we are not likely to extricate ourselves with ease and readiness at the present day. Where history supplies no adequate information on the subject, the language of a people has always been considered as affording the best clue for discovering its primary seat and origin. Here, however, that resource is denied us; since, with the exception of a few detached words, preserved by the Greek grammarians and lexicographers, we are left in entire ignorance as to the prevailing dialects among the indigenous tribes of Asia Minor^e. I use the word *indigenous*, in contradistinction to the colonies established by the Greeks, in times which are well authenticated. It appears then that we are obliged, in this question, to glean from

^e These will be found nearly all brought together in a learned and elaborate dissertation of professor Jablonsky, entitled, *Disquisitio de Lingua Lycaonicâ*, and which has been printed in the 3d vol. of his *Opusc. Acad.* published by prof.

Te-Water, at Leyden, 1809. Other dissertations on the same subject by different learned men have been brought together in a work, entitled, *Thesaur. Nov. Dissert. ex Musæo Hasæi et Ikenii*, tom. II. p. 625—661.

history such scattered notices and hints as it has placed within our reach. Scanty and imperfect as that source is found to be, it is so far satisfactory, that it does not present us, as in the cases of Greece and Italy, with conflicting systems and opinions scarcely reconcilable with each other. It may be remarked, in the first place, that the ancients did not look upon any of the tribes of Asia Minor as autochthonous. In the next place, all those writers whose testimony is thought to have most weight, agree in deriving the origin of those tribes from two principal sources or channels, though diametrically opposed to each other, considered geographically; I mean the nations of Upper Asia and the Thracians of Europe: the former penetrating into the peninsula by the Syrian gates and the upper valleys of the Euphrates; the latter, by the straits of Byzantium. This being premised, we have now to consider by which of these two routes Asia Minor received its first settlers. Taking then the Mosaic account as the basis of our investigation, it will be seen at once that the descendants of Noah, after their dispersion in the plains of Mesopotamia, would, from their proximity to Asia Minor, have had time, not only to occupy its nearest provinces, but to spread over the whole country, before their more northern brethren could reach the Bosphorus by the slow and circuitous journey round the Palus Maeotis and the shores of the Euxine. Not to mention that the process of crossing an arm of the sea, in order to occupy a country, implies necessarily a state of things somewhat removed from a rude and primitive order of society, and supposes consequently a period much

subsequent to the primeval dissemination of mankind recorded in the book of Genesis.

Probability then alone would lead us to derive the origin of the primary settlers in Asia Minor from the plains around the Euphrates and Tigris. But this ceases to be even a matter for inquiry, when we find how strongly it is confirmed by the testimony of history. We are assured by Herodotus, that in the time of Croesus all the tract of country to the east of the Halys was occupied by a race of Syrians, whom the Greeks termed Leuco-Syri, or the White Syrians, in order to distinguish them from their more sunburnt kinsmen, who occupied the country to the S.E. of the Amanus and the shores of the Mediterranean as far as Palestine. Herodotus affirms, that the Cappadocians, a name derived from the Persians, were Syrians; and by extending their country to the shore of the Euxine, it is evident that he included the people of Paphlagonia and Pontus under the same denomination and race. (I. 72. 76.) Under the Cappadocians too we must range the inhabitants of Lycaonia and Isauria, who, though speaking a dialect of their own, are classed by Strabo with the former people. (XII. p. 533.) The Cilicians are spoken of as a nation distinct from the Cappadocians, but it is highly probable that they were only another branch of the same eastern stock. Herodotus states that they were originally called Hypachæi, but had taken the name which they then bore from Cilix, the son of Agenor, (VII.91.) which is saying, in other words, that they received a Phœnician colony. The presence of this most ancient and remarkable people in

several parts of Asia Minor, at a very remote period, is too well attested, by the direct as well as the indirect testimony of antiquity, to be called in question, even if we should not be disposed to go so far as Bochart and his followers have done in the etymological system. If we range along the southern coast of Asia Minor from Cilicia, we shall find traces of the Phœnicians in Pamphylia, though that name is certainly Greek, but indicative, at the same time, of a mixed and heterogeneous population ; we find traces of them beyond Pamphylia, in the country of the ancient Solymi, who are always spoken of as the first inhabitants of what was afterwards called Pisidia. Still further to the west, we hear of them on the coast of Caria, and in the island of Rhodes, under the names of Telchines and Heliades. There is little doubt that the Cilices of Homer, who occupied the plain of Thebe in the Troad, as well as the Dactili of mount Ida, were also Phœnicians. We have the authority of Thucydides for believing that the same people had, at a very early period, settled in several of the Greek islands. (I. 8.) Herodotus affirms, that they colonized Thasus. Other authorities speak of their establishments on the shores of the Propontis and Hellespont. And there is every reason to believe, with Bochart^f, that the worship of the Cabiri, and the Samothracian mysteries, were first introduced by them, and afterwards adopted by the Pelasgi. According to Strabo, Cadmus and his Phœnicians^g had first occupied Eubœa before they colonized Bœotia. It is also highly probable that the Carians and Pelasgi, the earliest

^f Geogr. Sacr. I. 12. p. 394. bians, (X. p. 447.) Cf. Plut.

^g Strabo calls them Ara- Thes. tom. I. p. 1

subsequent to the primeval dissemination of mankind recorded in the book of Genesis.

Probability then alone would lead us to derive the origin of the primary settlers in Asia Minor from the plains around the Euphrates and Tigris. But this ceases to be even a matter for inquiry, when we find how strongly it is confirmed by the testimony of history. We are assured by Herodotus, that in the time of Croesus all the tract of country to the east of the Halys was occupied by a race of Syrians, whom the Greeks termed Leuco-Syri, or the White Syrians, in order to distinguish them from their more sunburnt kinsmen, who occupied the country to the S.E. of the Amanus and the shores of the Mediterranean as far as Palestine. Herodotus affirms, that the Cappadocians, a name derived from the Persians, were Syrians; and by extending their country to the shore of the Euxine, it is evident that he included the people of Paphlagonia and Pontus under the same denomination and race. (I. 72. 76.) Under the Cappadocians too we must range the inhabitants of Lycaonia and Isauria, who, though speaking a dialect of their own, are classed by Strabo with the former people. (XII. p. 533.) The Cilicians are spoken of as a nation distinct from the Cappadocians, but it is highly probable that they were only another branch of the same eastern stock. Herodotus states that they were originally called Hypachæi, but had taken the name which they then bore from Cilix, the son of Agenor, (VII. 91.) which is saying, in other words, that they received a Phœnician colony. The presence of this most ancient and remarkable people in

several parts of Asia Minor, at a very remote period, is too well attested, by the direct as well as the indirect testimony of antiquity, to be called in question, even if we should not be disposed to go so far as Bochart and his followers have done in the etymological system. If we range along the southern coast of Asia Minor from Cilicia, we shall find traces of the Phœnicians in Pamphylia, though that name is certainly Greek, but indicative, at the same time, of a mixed and heterogeneous population ; we find traces of them beyond Pamphylia, in the country of the ancient Solymi, who are always spoken of as the first inhabitants of what was afterwards called Pisidia. Still further to the west, we hear of them on the coast of Caria, and in the island of Rhodes, under the names of Telchines and Heliades. There is little doubt that the Cilices of Homer, who occupied the plain of Thebe in the Troad, as well as the Dactili of mount Ida, were also Phœnicians. We have the authority of Thucydides for believing that the same people had, at a very early period, settled in several of the Greek islands. (I. 8.) Herodotus affirms, that they colonized Thasus. Other authorities speak of their establishments on the shores of the Propontis and Hellespont. And there is every reason to believe, with Bochart^f, that the worship of the Cabiri, and the Samothracian mysteries, were first introduced by them, and afterwards adopted by the Pelasgi. According to Strabo, Cadmus and his Phœnicians^g had first occupied Eubœa before they colonized Bœotia. It is also highly probable that the Carians and Pelasgi, the earliest

^f Geogr. Sacr. I. 12. p. 394. bians, (X. p. 447.) Cf. Plut.

^g Strabo calls them Ara- Thes. tom. I. p. 1

people among the Greeks who made any proficiency in nautical affairs, derived their instruction from this enterprising race.

Thus we have seen that the whole coast of Asia Minor was covered with Phœnician establishments at a period of remote antiquity, while a branch of the same people occupied, in land, the whole of the country which lies between the Halys and the Euphrates. But however the former river might have been the boundary of the Leuco-Syrians to the west, in the time of Croesus, it is not to be supposed that this had always been the limit of the Asiatic colonists of the peninsula. On the contrary, it is plain, as we have before stated, that they must have had time to spread over the whole country before the Thracian tribes had become strong and populous enough to cross the Bosphorus, and occupy the shores of the Propontis. It is probable too that the Syrians of Cappadocia and Cilicia were the last and most recent influx of Asiatic tribes, those who preceded them having become blended with the hordes which successively crossed over from Europe, and thus preserving but faint and imperfect traces of their primary origin^h.

Having thus brought forward what evidence we possess of the population of Asia Minor having been derived in the first instance from more eastern coun-

^h Most of the commentators on the book of Genesis suppose Asia Minor to have been occupied by the immediate descendants of Gomer, Askenaz, whose name is thought to bear some resemblance to that of Ascania, and Riphath and To-

garmah. Others, however, have imagined, that it was peopled by the descendants of Shem, among whom Aram would be the progenitor of the Syrians, and Lud of the Lydians. Boc-hart, Geogr. Sacr. III. 8 and 9. p. 171. II. 12. p. 83.

tries, we may pass on to consider summarily what additions were subsequently made to it from Europe. I have stated already, that according to the concurrent testimony of antiquity we must admit the European origin of several extensive tribes in Asia Minor. Of these, the earliest and most numerous appear to have been the Phrygians, who, as we learn from Herodotus, on the authority of traditions preserved by the Macedonians, once dwelt in their country under the name of Bryges; but having crossed into Asia at a period of which we cannot now form any accurate notion, they changed that appellation to the form under which it was ever after known. (I. 72.) The testimony of Herodotus is confirmed by that of Strabo, who quotes from Xanthus, the Lydian historian, and Menebrates, of Elaea, (XII. p. 572. Cf. VII. p. 295. XII. p. 550:) and Conon. (ap. Phot. Narrat. I. p. 424. Cf. Plin. V. 32.) It may be observed also, that there existed a people named Brygi in Macedonian Thrace, in the time of Herodotusⁱ, (VI. 45. VII. 185.) and the same historian alludes to traditions which represented that country as the original abode of the Phrygian Midas. (VIII. 138.) On such evidence it seems impossible to deny the fact of a migration of these Thracian Bryges into Asia at an uncertain epoch, but certainly prior to the Trojan war, since the Phrygians are clearly mentioned by Homer as a people of Asia Minor. (B. 862. Γ. 184.) As to those traditions which assign to the Phrygians a date anterior even to the formation of the Egyptian nation, (Herod. II. 2.) if any credit is due

ⁱ The word *briga* appears to have belonged to the ancient Thracians as well as to the Celts. Strabo VII.

to them, they must apply, I conceive, to that indigenous race who occupied this rich and fertile country before the Thracian migration, and became united by conquest with their successful invaders. Herodotus, too, clearly recognises an affinity between the Phrygians and the Armenians; (VII. 73.) and though I suspect that the fact is exactly the reverse of what he states, and that the Armenians were the progenitors of the Phrygians rather than descended from them, the tradition seems to strengthen the idea of what may be called an Asiatic foundation in the Phrygian stock.

Antiquity is not less positive respecting the Thracian origin of the Lydians, Carians, and Mysians, though there are many questions which render the early history of these nations intricate and perplexing; these will be considered more at length when we come to examine the origin of each people separately. At present it will be sufficient to state generally, that the three nations above mentioned acknowledged a common origin, (Herod. I. 172. Strab. XIV. p. 659.) and if it be true that the Mysi in particular were the same as the Mœsi of Thrace, and came from that country, (Strab. XII. p. 571. VII. p. 303.) it will follow, that the Carians and Lydians had also their primary seats in the same part of the European continent.

From the southern position occupied by the Carians, it is reasonable to suppose that they came first in the order of migration. Herodotus has stated, that this people occupied first of all the Cyclades, and other islands, under the name of Leleges; but that having been driven from thence by Minos, on account of their piracies, they passed over to the

Asiatic continent. The historian, however, observes, that the Carians themselves affirmed that their nation had always been possessors of the province which derived its name from them. (I. 171.) The first account, however, confirmed as it is by Thucydides, (I. 4.) and other weighty testimonies, has doubtless superior claims to our attention. Amongst these must not be forgotten that of Homer, who brings together the Carians, Leleges, Pelasgi, and Caucones, people all apparently of Thracian origin, and of wandering habits. (Il. K. 480.)

Next in order to the Carians are the Lydians, or, as they are more anciently called, the Mæones; at least it appears to have been the more general opinion among the ancients that they ought to be identified. Some writers, however, as Strabo affirms, looked upon them as two distinct nations. (XII. p. 571. XIII. p. 625.) Homer appears to have known only the name of Mæones, which, according to Herodotus, was also the more ancient appellation. (VII. 74.) It must be confessed, however, that this change of name, as well as the whole account of the Lydian dynasties, together with the celebrated tradition of the Tyrrhenian migration, recorded by that historian, are all alike unsatisfactory, and beset with great difficulties, especially in regard to chronology. These will be fully discussed when we come to treat of Lydia in particular; but I will only observe by the way, that when we find among the Lydian kings of the Heraclid dynasty the names of Ninus and Belus, it is impossible not to admit that there must have been some connexion, though Herodotus was not aware of it, between Lydia and the ancient kingdom of Assyria;

a circumstance which tends to confirm our hypothesis of an Asiatic *substratum* in the population of the entire peninsula.

The Mysi, whose Thracian origin appears least subject to dispute, if we may judge from their more northern position, settled in Asia posterior to the Mæonian migration. Indeed Herodotus affirms, that they were a colony (*ἀποικοί*) of the Lydians. (VII. 74.) This people always retained, as it should seem, a footing in the European continent; and it is to that more ancient and considerable part of the nation that we must perhaps refer that great invasion of Pæonia and Macedonia recorded by Herodotus as having taken place before the Trojan war, though it is certain that the historian expressly states that they crossed over on that occasion from Asia into Europe in conjunction with the Teucri. (VII. 20. 75.) The latter people, who are probably the ancestors of the Trojans, certainly formed settlements on the Asiatic shores of the Hellespont, with the Mysi and Dardani, at an early period; but we must look for the original seat of all these tribes in the great Pannonian and Mœsian plains, south of the Danube. It must be observed, that Herodotus himself supposes that the Pæonians were descendants of the Teucri, (V. 13.) but this could hardly be true of the Trojan Teucri. And when we find that the Dardani, who were certainly Illyrians, and contiguous to the Mœsi, boasted of having anciently been masters of all Pæonia, (Liv. XLV. 29.) it is natural to suspect that the Teucri belonged to the same European stock, whether of Thracian or Illyrian origin.

The Bithynians are another Thracian people, but

belonging apparently to a different family from that of the three important tribes we have just mentioned. Herodotus affirms, that they were originally called Strymonii, from the great Macedonian river on whose banks they were settled. But having been disturbed by the irruption of the Teucri and Mysi, they finally crossed over into Asia, and took the name of Bithyni. (VII. 75.) The Thracian origin of the Bithyni is also attested by Xenophon, (Anab. VI. 4, 1.) and Strabo, (XII. p. 511.) And I should imagine that Homer alludes to this people under the name of Hellespontine Thracians, in his account of the Trojan forces and their allies. (Il. B. 844.) To the great Thracian family belong also the Mariandyni, Bebryces, Doliones, Caucones, and other early and obscure tribes, which once had a separate political existence on the shores of the Propontis and Euxine, but became merged afterwards in the general nomenclature of Mysians and Bithynians. (Strab. XII. p. 542.) Respecting the Paphlagonians, who follow next in the same line of coast, it is not so easy to form an opinion; as the writers of antiquity seem to be silent on the question of their origin. According to Strabo, they were certainly a different people from the Cappadocians, and yet he allows that there were many words common to the two nations; whence it might be inferred, that the Paphlagonians were a mixed people, formed from the Leuco-Syri, or Cappadocians, and some other race; which, if not Thracian, came most probably from Scythia. The Amazons, who settled on the Paphlagonian coast, were believed by many to have come from that vast country, as well as the Halizones and Heneti, ranked

by Homer among the Paphlagones. (Il. B. 851. Strab. XII. p. 543.) And it is not improbable that some of the minor tribes which occupied the coasts and mountainous regions of Pontus, as far as Colchis, might trace part of their population to a Scythian source; the rest being derived, more especially in the case of the Chalybes and Chaldaei, from Armenia and Assyria.

Having thus endeavoured to analyse succinctly the probable elements of what may be called the barbarian population of Asia Minor, I shall proceed to give a brief and general history of Greek colonization in that extensive country.

If we are to allow the Pelasgi the honour of being considered the progenitors of the Hellenic race, we may then look upon their settlements in Asia Minor before the siege of Troy, as the first attempts to establish Grecian colonists in that country. Next to the Pelasgic migrations, we must place the settlements formed by Minos, who seems to have reigned, not only over Crete and the Cyclades, but to have had possessions on the coast of Caria and Lycia. In the former country, Sarpedon, his brother, is said to have founded Miletus; in the latter, the same chief established his Cretan bands, named Termilæ, after having driven from the coasts or exterminated the Milyæ and Solymi, the first possessors of the country, and descended, as appears most probable, from the Phœnicians or Syrians. But a fresh change was again introduced on the arrival of Lycaon, or Lycus, son of Pandion king of Athens, and the whole population was thenceforth designated by the name of Lycians. (Herod. I. 173. Strab. XII. p. 573.)

We must likewise place before the siege of Troy the colonization of Rhodes and Cos by the descendants of Hercules, (Il. B. 655. Strab. loc. cit.) and that of Mysia by Telephus. (Strab. XIII. p. 615.) Some of the Hellespontine towns, such as Abydos and Cyzicus, owed their foundation to Greek or Pelasgic colonists before the same era. Other cities on the coast of Pamphylia, Cilicia, and Cyprus, are supposed to be nearly coeval with the downfall of Troy. But the most numerous and important migrations from the Grecian continent were posterior to that celebrated event. The first of these was the Æolic colony, led, as we learn from Strabo and Pausanias, by some descendants of Orestes, after the death of that prince, through Thessaly and Thrace to the Hellespont; whence they crossed over into Asia, and occupied the shores of the ancient Troas, and the island of Lesbos. (Strab. XIII. p. 582. Pausan. Lacon. 2.) Other descendants of Agamemnon shortly after crossed over from Thessaly, with a fresh body of Æolian colonists, and founded Cumæ, south of the Caicus. Strabo places these events about 60 years after the fall of Troy, and not long before the return of the Heraclidæ into the Peloponnesus.

The Ionian migration was four generations later, or 1130 B.C. It was composed principally of Ionians from Attica and Ægialus, subsequently called Achaia; but Herodotus affirms, that a large portion of the colony was composed of people who had nothing in common with the Ionian name. These settled on the coast of Asia Minor, then occupied by the Carians and Leleges, whom they expelled; and having founded twelve principal cities, formed

themselves into a federal government, which held its meetings in the temple called Panionium. (I. 146. Strab. XIV. p. 633. Pausan. Achaic. 2.)

The coast of Caria, to the south of Cape Posidium, was occupied by Dorian Greeks, who migrated at different periods from Megara, Trœzene, Argos, and other cities of the mother country. The principal colonies then formed were Halicarnassus and Cnidus, with the islands of Rhodes and Cos, which together constituted the Dorian confederacy; whose meetings were held at Triopium. (Herod. I. 144.) Besides these, numerous single settlements were from time to time formed by the Greeks, both on the shores of the Euxine and those of the Cilician and Pamphylian seas. Insensibly also they spread themselves in the interior of the peninsula, as well in Lydia and Phrygia as in Galatia and Cappadocia; so that finally there was not a province, from the *Æ*gean to the Euphrates, which could not boast of possessing more than one Greek colony. It is this circumstance which gives to Asia Minor its classical character and principal historical interest, and causes it to be associated, in the mind of the scholar and the antiquary, with all that we admire in Grecian genius and taste. It is true, that the Greeks of Asia Minor, owing to the softness of the climate, and the debasing influence of a despotic government, afford us no such recollections as the glorious achievements of the sons of Hellas recall to the mind; yet it is certain, that in refinement, and the cultivation of the arts, they were at least equal, if not superior, to their European brethren. If Asia Minor cannot boast of having given birth to warriors and statesmen, she glories justly in her poets,

her historians and philosophers, her sculptors, painters, architects, and musicians. And in the three first departments she may more especially boast of having rather served as a guide to the mother country than followed in her train^k.

We learn from Herodotus, that subsequent to the establishment of the Greek colonies Asia Minor was overrun consecutively by large bodies of Cimmerians and Scythians; the former being propelled, as we often find was the case with barbarian migrations, and pursued by a more powerful horde of Scythians from the Caspian and over mount Caucasus, to the shores of Pontus, whence they afterwards penetrated into Lydia, and took Sardis. (Herod. I. 6. and 15. IV. 1. 11. 12.) But this irruption was of short duration, as the barbarians, being unable to secure a permanent footing in the country, were soon expelled by Alyattes, king of Lydia. (Herod. I. 16.) Many centuries after, another barbarian horde, coming from the west of Europe, arrived, after traversing several countries, and experiencing various vicissitudes of fortune on the Byzantine territory. These were a body of Gauls, who had left their country under the banners of Brennus; and having survived the disasters which befell their countrymen in Greece and Thrace, reached the Hellespont, whence they crossed over into Asia, at the instigation of Nicomedes, king of Bithynia, and finally settled in that part of the peninsula which took from them the name of Gallo-

^k In poetry Asia lays claim to Homer, Hesiod, Sappho, Alcæus, Anacreon, Mimnermus, Hipponax, and Nicander. In philosophy, to Thales, Py-

thagoras, Anaxagoras, Bias, and Pittacus. In history, to Hecatæus, Charon, Hellanicus, Xanthus, Herodotus, Ctesias, and Ephorus.

themselves into a federal government, which held its meetings in the temple called Panionium. (I. 146. Strab. XIV. p. 633. Pausan. Achaic. 2.)

The coast of Caria, to the south of Cape Posidium, was occupied by Dorian Greeks, who migrated at different periods from Megara, Trœzene, Argos, and other cities of the mother country. The principal colonies then formed were Halicarnassus and Cnidus, with the islands of Rhodes and Cos, which together constituted the Dorian confederacy; whose meetings were held at Triopium. (Herod. I. 144.) Besides these, numerous single settlements were from time to time formed by the Greeks, both on the shores of the Euxine and those of the Cilician and Pamphylian seas. Insensibly also they spread themselves in the interior of the peninsula, as well in Lydia and Phrygia as in Galatia and Cappadocia; so that finally there was not a province, from the Ægean to the Euphrates, which could not boast of possessing more than one Greek colony. It is this circumstance which gives to Asia Minor its classical character and principal historical interest, and causes it to be associated, in the mind of the scholar and the antiquary, with all that we admire in Grecian genius and taste. It is true, that the Greeks of Asia Minor, owing to the severity of the climate, and the debasing influence of their government, afford us no such recollection of their glorious achievements of the sons of Herakles as enter into the mind; yet it is certain, that in respect to the cultivation of the arts, they were at least, if not superior, to their European brethren. Asia Minor cannot boast of having given birth to great warriors and statesmen, she glories justly in

her historians and philosophers, her sculptors, painters, architects, and musicians. And in the three first departments she may more especially boast of having rather served as a guide to the mother country than followed in her train^k.

We learn from Herodotus, that subsequent to the establishment of the Greek colonies Asia Minor was overrun consecutively by large bodies of Cimmerians and Scythians; the former being propelled, as we often find was the case with barbarian migrations, and pursued by a more powerful horde of Scythians from the Caucasic and Asian coasts.

themselves into a federal government, which held its meetings in the temple called Panionium. (I. 146. Strab. XIV. p. 633. Pausan. Achaic. 2.)

The coast of Caria, to the south of Cape Posidium, was occupied by Dorian Greeks, who migrated at different periods from Megara, Trœzene, Argos, and other cities of the mother country. The principal colonies then formed were Halicarnassus and Cnidus, with the islands of Rhodes and Cos, which together constituted the Dorian confederacy; whose meetings were held at Triopium. (Herod. I. 144.) Besides these, numerous single settlements were from time to time formed by the Greeks, both on the shores of the Euxine and those of the Cilician and Pamphylian seas. Insensibly also they spread themselves in the interior of the peninsula, as well in Lydia and Phrygia as in Galatia and Cappadocia; so that finally there was not a province, from the Ægean to the Euphrates, which could not boast of possessing more than one Greek colony. It is this circumstance which gives to Asia Minor its classical character and principal historical interest, and causes it to be associated, in the mind of the scholar and the antiquary, with all that we admire in Grecian genius and taste. It is true, that the Greeks of Asia Minor, owing to the softness of the climate, and the debasing influence of a despotic government, afford us no such recollections as the glorious achievements of the sons of Hellas recall to the mind; yet it is certain, that in refinement, and the cultivation of the arts, they were at least equal, if not superior, to their European brethren. If Asia Minor cannot boast of having given birth to warriors and statesmen, she glories justly in her poets,

her historians and philosophers, her sculptors, painters, architects, and musicians. And in the three first departments she may more especially boast of having rather served as a guide to the mother country than followed in her train^k.

We learn from Herodotus, that subsequent to the establishment of the Greek colonies Asia Minor was overrun consecutively by large bodies of Cimmerians and Scythians; the former being propelled, as we often find was the case with barbarian migrations, and pursued by a more powerful horde of Scythians from the Caspian and over mount Caucasus, to the shores of Pontus, whence they afterwards penetrated into Lydia, and took Sardis. (Herod. I. 6. and 15. IV. 1. 11. 12.) But this irruption was of short duration, as the barbarians, being unable to secure a permanent footing in the country, were soon expelled by Alyattes, king of Lydia. (Herod. I. 16.) Many centuries after, another barbarian horde, coming from the west of Europe, arrived, after traversing several countries, and experiencing various vicissitudes of fortune on the Byzantine territory. These were a body of Gauls, who had left their country under the banners of Brennus; and having survived the disasters which befell their countrymen in Greece and Thrace, reached the Hellespont, whence they crossed over into Asia, at the instigation of Nicomedes, king of Bithynia, and finally settled in that part of the peninsula which took from them the name of Gallo-

^k In poetry Asia lays claim to Homer, Hesiod, Sappho, Alcæus, Anacreon, Mimnermus, Hipponax, and Nicander. In philosophy, to Thales, Py-

thagoras, Anaxagoras, Bias, and Pittacus. In history, to Hecatæus, Charon, Hellanicus, Xanthus, Herodotus, Ctesias, and Ephorus.

Græcia, or Galatia. (Liv. XXXVIII. 16. Strab. XII. p. 566.) This was the last important addition made to the population of Asia Minor; and on looking back to the mixed character of its inhabitants, and the many revolutions it has experienced from the earliest period, we must feel how hopeless a task it would be, even with less scanty materials than those which we possess, to trace the languages and dialects of the peninsula to a common primitive source.

In the description of Asia Minor, the geographers of antiquity appear to have adhered to no fixed plan of arrangement, but to have followed that order which accorded with their whole system. Thus Strabo begins his description with Cappadocia, and proceeds through the remaining provinces from east to west, because he had been led by his periegesis of northern Asia to Armenia. Scylax and Scymnus, of Chios, set out from Colchis, and so make the circuit of the peninsula from Pontus to Cilicia. Pomponius, Mela, and Pliny, on the contrary, begin with Cilicia, and proceed round the whole of the coast to the river Phasis. Ptolemy takes first the north coast from the Hellespont to the extremity of the Euxine, and then returns to the Hellespont to describe the western and southern coasts.

This method of description being evidently arbitrary, I have preferred adhering to that of D'Anville, as being both most simple and natural in itself, and as agreeing better with the practice I have generally observed in my other geographical works, of commencing the periegesis or periplus of a country from west to east, and from north to south. D'Anville has, with great perspicuity, divided the peninsula

into three parallel strips, each containing four sections. According to this arrangement, Asia Minor will comprise twelve principal provinces, which are as follows: 1. Mysia, including the Hellespontine district and the Troad, with the Æolian colonies. 2. Bithynia. 3. Paphlagonia. 4. Pontus. 5. Lydia, including the Ionian towns and islands. 6. Phrygia, including Lycaonia. 7. Galatia. 8. Cappadocia, together with Armenia Minor. 9. Caria, with its islands. 10. Lycia. 11. Pamphylia, including Pisidia. 12. Cilicia. The last section will be devoted to the island of Cyprus.

SECTION II.

MYSIA AND TROAS.

Origin and history of the Mysians—The Hellespont and Propontis—Interior of Mysia—The Teucri and Dardani—Ancient Ilium and the Homeric topography—The Troad—Æolian colonies—Kingdom of Pergamus—Island of Lesbos.

IT was the prevailing opinion of antiquity that the Mysians were not an indigenous people of Asia, but that they had been transplanted to its shores from the banks of the Danube, where the original race maintained itself under the name of Mœsi, by which they were known to the Romans for several centuries after the Christian era. (Strab. VII. p. 303. Artemid. ap. eund. XII. p. 571.) Nor is that opinion at variance with the tradition which looked upon this people as of a kindred race with the Carians and Lydians, since these two nations were likewise supposed to have come from Thrace; (Herod. I. 172. Strab. XIV. p. 659.) nor with another which regarded them in particular as descended from the Lydians, in whose language the word *mysos* signified *a beech*, which tree it was further observed abounded in the woods of the Mysian Olympus. Strabo, who has copied these particulars from Xanthus the Lydian and Menecrates of Elæa, states also on their authority that the Mysian dialect was a mixture of those of Phrygia and Lydia. (Strab. XII.

p. 572. Steph. Byz. v. *Mυσία*) We may collect from Herodotus that the Mysians were already a numerous and powerful people before the Trojan war, since he speaks of a vast expedition having been undertaken by them, in conjunction with the Teucri, into Europe, in the course of which they subjugated the whole of Thrace and Macedonia as far as the Peneus and the Ionian sea. (VII. 20.75.) Subsequent, however, to this period, the date of which is very remote and uncertain, it appears that the Mysi were confined in Asia Minor, within limits which correspond but little with such extensive conquests. Strabo is inclined to suppose that their primary seat in that country was the district which surrounds mount Olympus, from whence he thinks they were afterwards driven by the Phrygians, and forced to retire to the banks of the Caicus, where the Arcadian Telephus became their king. (Eurip. ap. Aristot. Rhet. III. 2. Strab. XII. p. 572. Hygin. Fab. CI.) But it appears from Herodotus that they still occupied the Olympian district in the time of Croesus, whose subjects they had become, and whose aid they requested to destroy the wild boar which ravaged their country. (I. 36.) Strabo himself also recognises the division of this people into the Mysians of mount Olympus and those of the Caicus. (XII. p. 571.) These two districts answer respectively to the Mysia Minor and Major of Ptolemy. Homer enumerates the Mysi among the allies of Priam in several passages, but he nowhere defines their territory, or even names their towns; in one place indeed he evidently assigns to them a situation among the Thracians of Europe.

Νόσφιν ἐφ' ἵπποπόλων Θρηκῶν καθοράμενος αἰαν,
Μυσῶν τ' ἀγχεμάχων, καὶ ἀγαυῶν Ἰππημολγῶν,
Γλαχτοφάγων, ἀβίων τε, δικαιοτάτων ἀνθρώπων.

IL. N. 5.

(Cf. Strab. VII. p. 303.)

The Mysians of Asia had become subject to the Lydian monarchs in the reign of Alyattes, father to Crœsus, and perhaps earlier; as appears from a passage of Nicolaus Damascenus, who reports that Crœsus had been appointed to the government of the territory of Adramyttium and the Theban plain during the reign of his father. (Creuzer. Hist. Frag. p. 203.) Strabo even affirms that Troas was already subjected in the reign of Gyges. (XIII. p. 590.) On the dissolution of the Lydian empire they passed, together with the other nations of Asia, under the Persian dominion, and formed part of the third satrapy in the division made by Darius, (Herod. III. 90. VII. 74.) After the death of Alexander, they were annexed to the Syrian empire; but on the defeat of Antiochus, the Romans rewarded the services of Eumenes, king of Pergamus, with the grant of a district, situated so conveniently with regard to his own dominions, and which he had already occupied with his forces. (Polyb. XXII. 27, 10. Liv. XXXVIII. 39.) At a later period Mysia was annexed to the Roman proconsular province; (Cic. Ep. ad Qu. Frat. I. 8.) but under the emperors it formed a separate district, and was governed by a procurator. (Athen. IX. p. 398. E.) It is to be observed also, that St. Luke, in the Acts, distinguishes Mysia from the neighbouring provinces of Bithynia and Troas. (XVI. 7. and 8.)

The Greeks have stigmatized the Mysians as a cowardly and imbecile race, who would suffer themselves to be injured and plundered by their neighbours in the most passive manner. Hence the proverbial expression *Mυσῶν λεία*, used by Demosthenes (Cor. p. 248, 23.) and Aristotle (Rhet. I. 12, 20); to which Cicero also alludes when he says, “*Quid porro in Græco sermone tam tritum atque celebratum est, quam, si quis despicatui ducitur, ut Mysorum ultimus esse dicatur.*” (Orat. pro' Flacc. c. 27.) Elsewhere the same writer describes them as a tribe of barbarians, without taste for literature and the arts of civilized life. (Orat. c. 8.)

It is extremely difficult, as Strabo had already observed, to assign to the Mysians their precise limits, since they appear to have varied continually from the time of Homer, and are very loosely marked by all the ancient geographers from Scylax to Ptolemy. Strabo conceives that the Homeric boundaries of the Lesser Mysia were the Æsepus to the west, and Bithynia to the east; (XII. p. 564.) but Scylax removes them considerably to the east of this position by placing the Mysians on the gulf of Cius. (Peripl. p. 35.) Ptolemy, on the other hand, has extended the Mysian territory to the west as far as Lampsacus, while to the east he separates it from Bithynia by the river Rhyndacus. The more eligible arrangement in this difficulty will be to look to the physical division of the coast, and to neglect distinctions which appear so variable and uncertain. I propose, therefore, to subdivide the whole extent of coast belonging to this section into three portions; the former comprising what is situated on the Propontis between the Rhyndacus and the headland of

Priapus, now *Karaboa*, where the Hellespont commences; the second, the Hellespontine shore from the last mentioned point to the promontory of Sigeum, where the strait terminates; the third and last part will include Troas and the Æolian colonies as far as the Caicus, together with the islands of Tenedos and Lesbos. In the interior we shall have to examine what belongs to the two Mysias, and we shall conclude the section with the history of Pergamus and its kingdom, and the Æolian towns near the mouth of the river Hermus.

Propontis. The Greeks gave the name of Propontis to that minor basin which lies betwixt the Ægean and the Euxine, and communicates with those seas by means of two narrow straits, the Hellespont and Bosphorus. Herodotus estimates its breadth at 500 stadia, and its length at 1400. (IV. 85.) Modern navigators reckon about 120 miles from one strait to another, while its greatest breadth from the European to the Asiatic coast does not exceed forty miles. Towards its south-eastern extremity it forms a deep bay, at the end of which was situated the ancient town and harbour of Cius; and immediately to the north of this another, formerly called Astacenus Sinus, from the port of Astacus placed on its shores. The modern appellation of *Marmara* which has been given to the Propontis is derived from the island of that name, anciently called Proconnesus ^a.

Priapus. The first town to be noticed on entering the Propontis from the Hellespont is Priapus, founded, as

^a For a description of the sea of *Marmara*, see Belon, Observations sur plusieurs singularités et choses memorables

trouvées en Grèce, Asie, &c. II. 1. Thevenot, Voyages au Levant, p. I. l. i. c. 15. Walpole's Turkey, vol. II. p. 46.

Strabo reports, by a colony from Miletus, or, as others relate, by the inhabitants of Cyzicus. The god Priapus, whom it was said a nymph had borne to Bacchus, gave his name to this town, whose territory produced excellent wine, a circumstance which sufficiently accounts for the worship paid to him there. (Strab. XIII. p. 587. Schol. Theocr. I. 21.) Thucydides speaks of Priapus as a naval station. (VIII. 107.) It surrendered to Alexander before the battle of the Granicus. (Arrian. Exp. Alex. I. 13. Cf. Strab. loc. cit. Scyl. Peripl. p. 35. Plin. V. 40. Steph. Byz. v. Πριάπος.) The modern name is *Karaboa*^b. A little to the east was a spot called Harpagium, or Harpagia, where, according to mythologists, Ganymede was snatched away by the eagle of Jove. (Strab. loc. cit. Athen. XIII. p. 601. Steph. Byz. v. Ἀρτάγια.) Thucydides notices it in conjunction with Priapus (loc. cit.) The surrounding district was known by the name of Adrastea, which is also that of a small town situated to the west of Priapus. Homer has spoken of this little tract of country in his Catalogue of the Trojan forces. (Il. B. 828.) Strabo, on the authority of Callisthenes, reports that it took its name from king Adrastus, who erected there a temple to Adrastea, or Nemesis. (XIII. p. 588. Steph. Byz. v. Ἀδράστεια.) Through the Adrasteian plain flowed the Granicus, which, according to Demetrius of Scepsis, had its source in mount Cottylus, belonging to the chain of Ida. (Strab. XIII. p. 602.) The Table Itinerary marks twenty-seven miles between its mouth and Priapus. Homer enu-

^b There are both autonomous and imperial coins of Priapus. The legend is ΠΡΙΑ. ΠΡΙΑΠ. and ΠΡΙΑΠΗΝ. Sestin. Mon. Vet. p. 73.

merates the Granicus with the other streams which descended from Ida ^c.

Δὴ τότε μητιόωντο Ποσειδάων καὶ Ἀπόλλων
Τεῖχος ἀμαλδῦναι, ποταμῶν μένος εἰσαγάγοντες,
Οστοι ἀπ' Ἰδαιῶν ὄρέων ἀλαδε πφορέουσι,
Ρῆσός θ', Ἐπτάπορος τε, Κάρησός τε, Ροδίος τε,
Γρήνικός τε, καὶ Αἴσηπος, διός τε Σχάμανδρος.

This torrent is celebrated in history on account of the signal victory gained on its banks by Alexander the Great over the Persian army 334 B. C. (Arrian. I. 13. Plut. Alex. c. 24. Diod. Sic. XVII. 19.)

Sidene.

Didymi-teiche.

Æsepus fl.

The Granicus is the river of *Dimotiko*, mentioned by Chishull ^d. “At this place,” says the traveller, “occurs a moderate river with a wooden bridge;” “and an hour beyond the town, a large one with a “fair bridge of stone.” The small river which here met the Granicus was thought by some to be the Rhesus of Homer. (Demetr. Sceps. ap. Strab. XIII. p. 602.) Strabo places on its banks an ancient city named Sidene, which once possessed an ample territory, and was governed by a prince named Glaucias; but having been taken and destroyed by Crœsus, it never rose from its ruins. (XIII. p. 587. 601.) *Dimotico*, as Chishull supposes, answers probably to a town named Didymi-teiche, which Polybius places in this part of Mysia. (V. 77.)

The Æsepus flowed also from mount Cotylus, and after a course of 500 stadia emptied itself in the Propontis, to the east of the Granicus. (Demetr. Sceps. ap. Strab. XIII. p. 602.) Strabo conceives that Homer extended the boundaries of Priam’s

^c Mannert is therefore mistaken when he says that Homer was not acquainted with the

Granicus, vol. VI. p. iii. p. 523.

^d Travels in Turkey, p. 60.

kingdom to this river, (XIII. p. 582.) It is now called *Boklu*, as appears from Chishull, who crossed it on his way from *Mihalick* to *Lampsaki*. He came, he says, “to *Bozaegee*, seated in the Adras-tian plains ; and at the same place to a large and fair river, named by the Turks *Boclew*, which “we leave on our left hand, till in two hours we cross it by a dangerous wooden bridge near *Sor-ricui^e*.” Chishull, however, mistook the Æsepus for the Rhynacus. Mons. Gosselin calls the Æsepus *Sataldere*^f. The Barenus, or Varenus, of Anna Comnena, is probably no other than the Æsepus. She describes it as flowing from a mountain named Ibibus, from whence spring also several other rivers, such as the Scamander, Angelo-Cometes, and Empe-lus. The Ibibus I take to be the Cotylus of Demetrius Scepsius. (Ann. Comm. p. 439. B.)

At the distance of eighty stadia from the mouth of Zeleia, the Æsepus, and 190 from Cyzicus, Strabo places the ancient Zeleia, the city of Pandarus.

Οἱ δὲ Ζέλειαν ἔναιον ὑπαὶ πόδα νείατον Ἰδης,
Ἄφνειοὶ, πίνοντες ὕδωρ μέλαν Αἰσήποιο,
Τρῶες· τῶν αὐτὸν ἡρχε Λυκάονος ἀγλαὸς υἱὸς,
Πάνδαρος, φέ καὶ τόξον Ἀπόλλων αὐτὸς ἔδωκεν.

IL. B. 824.

Here it may be observed that the poet describes the subjects of Pandarus as Trojans, but Strabo remarks that elsewhere he designates them as Ly-cians, alluding probably to the line

Οὐδέ τις ἐν Λυκίῃ σέογ' εὑχεται εἶναι ἄμεινων.

IL. E. 172.

^e Travels in Turkey, p. 59.

^f Note to the French Strabo, tom. IV. p. 187.

which, however, might only be meant to express, that even the archers of Lycia, a country celebrated for its bowmen, could not equal the skill of Pandarus. However, some lines above, that chief himself speaks of Lycia as his mother country;

. . . . εἰ ἐτεόν με
Ὦρσεν ἀναξ, Διὸς υἱος, ἀπορύμενον Λυκίηθεν.

IL. E. 105.

but how or when this colony came to settle on the Trojan territory, Homer has never informed us. The epithet of *'Αφνειοὶ*, given to the same people, was thought to be derived, as Strabo informs us, from the lake Aphnitis, otherwise called Dascylitis. (XIII. p. 587.) Homer elsewhere terms Zeleia “the “ sacred city.”

Οἴκαδε νοστήσας ιερῆς εἰς ἄστυ Ζελεῖης.

IL. Δ. 103.

Pirossus
mons.

Memnonis
tumulus et
vicus.

Zeleia is mentioned by Arrian as the head quarters of the Persian army prior to the battle of the Granicus; (I. 13.) and it is evident from Strabo that it still existed in that geographer's time. (Cf. Plin. V. 40. Steph. Byz. v. *Ζέλεια*.) Chishull must have passed near the site of this town between *Boxaegee* and *Sorricui*^g. Mons. Gosselin calls it *Biga*^h. Above Zeleia was a mountain named Pirossus, where the sovereigns of Lydia and the Persian monarchs had a park, for the diversion of hunting. (Strab. XIII. p. 589.) Some geographers identified it with the Terea of Homer. Not far from the mouth of the *Æsepus*, Strabo places the tomb of Memnon, son of Aurora, and near it a small town of the same name as that hero. (XIII. p. 587. Pau-

^g Travels in Turkey, p. 59.

^h French Strabo, tom. IV. p. 149. marg.

san. Phoc. c. 31, 2.) Beyond Zeleia is the river *Tarsius* fl. *Tarsius*, which, as Strabo asserts, travellers had to pass twenty times; but he does not state on what route. Chishull, who crossed it once only, describes it as "a fair and broad river, now called *Tarxa* by "the Turks." He was informed that it fell into a neighbouring lake, and afterwards into the seaⁱ.

We must now return to the coast, to speak of Cyzicus, the largest and most celebrated city on the shores of the Propontis. Its first foundation is ascribed by Conon to a colony of Pelasgi from Thessaly, under the conduct of Cyzicus, son of Apollo, and Aristides speaks of the god himself as the founder of the city. (Orat. Cyzic. I. p. 414.) In process of time the Pelasgi were expelled by the Tyrrheni, and those again made way for the Milesians, who are generally looked upon by the Greeks as the real settlers to whom its foundation is to be attributed. (Conon. Narrat. XLI. Strab. XIV. p. 635.) According to several ancient writers, the first inhabitants of the Cyzicene district were the Doliones, a Doliones. people of great antiquity and uncertain origin. (Strab. XII. p. 575. Apollod. ap. eund. XIV. p. 681.)

'Ισθμὸν δ' αὐτὸν τε Δολίονες ἀμφενέμοντο

'Ανέρες· εὐ δὲ ἡρως Αἰνῆιος νιὸς ἄνασσε

Κύξικος.

APOLLON. RHOD. I. 947.

They occupied the tract of country which lay between the Æsepus and the lake Dascylitis. (Strab. loc. cit.) They are not mentioned by Homer, nor has he spoken of Cyzicus. Herodotus informs us, that Cyzicus had become subject to the Persian empire in the reign of Darius, having surrendered to

ⁱ Travels, p. 58, 59.

Œbares, satrap of Dascylium. (VI. 33.) After the battle of Mycale, it appears to have been wrested from Xerxes, with the other Hellespontine cities, by the Grecian fleet, and with them it became afterward tributary to Athens. Having revolted from that city in consequence of the disasters of Sicily, it was recovered by her fleet after the battle of Cynossema, being then, as we learn from Thucydides, without fortifications. (VIII. 107.) Not long after, Alcibiades completely defeated the Lacedæmonian fleet under Mindarus off Cyzicus, and again entered that city which had been occupied by the Lacedæmonian admiral and Pharnabazus. Alcibiades, on this occasion, levied a heavy fine on the inhabitants. (Xen. Hell. I. 9.) After the battle of Ægospotami, Cyzicus received a Spartan harmost; (Xen. Anab. VI. 2. VII. 3.) but at the peace of Antalcidas it once more reverted to the Persians. Alexander took possession of it after his victory on the banks of the Granicus, and caused the island on which it was built to be connected with the main land by means of a bridge. (Plin. V. 32.) After the death of that prince, we find this city retaining its independence, and powerful enough to interpose its mediation between Ptolemy Philopator and Antiochus. (Polyb. V. 63, 5.) The Cyzicenes were also allied to the kings of Pergamus, and through their means secured the favour and protection of Rome. (Polyb. XXVI. 6, 13. XXXIII. 11, 2.) At this period their city was at the height of its prosperity. Florus says of it, “nobilis arce, mœnibus, portu, turribusque mar-“moreis, Asiaticæ plagæ litora illustrat.” (III. 5.) Cicero styles it, “urbem Asiæ clarissimam, nobis-“que amicissimam.” (pro Leg. Manil. 8.) Strabo

assures us that it equalled the most renowned cities of Asia in extent and beauty, as well as in the wisdom of its political institutions, and the firmness of its government in time of war or peace. The Cyzicene commonwealth resembled those of Rhodes, Marseilles, and Carthage. They elected three magistrates, who were curators of the public buildings and stores. They possessed extensive arsenals and granaries, and care was taken to preserve the wheat by mixing it with Chalcidic earth. Owing to these wise and salutary precautions, they were enabled to sustain an arduous and memorable siege against Mithridates, king of Pontus, both by sea and land. (74 B.C.) In order that the reader may be better enabled to follow the operations of the siege as they are detailed by Appian and Plutarch, it will be necessary first to give a brief chorographical description of the city and its vicinity.

Cyzicus was placed in an island which is nearly triangular, and about 500 stadia in circuit; its base being turned towards the Propontis, while the vertex advances so close to the continent, that it was easy to connect it by a double bridge. This, as Pliny reports, was accomplished by Alexander. The city was situated partly in the plain which extended to the bridges, and partly on the slope of mount Arc-ton-oros, which rose above it, towards the north. Another mountain, named Dindymus, overhung the city also in the direction of the Propontis, having on its summit a temple, said to have been erected by the Argonauts in honour of Cybele, who was worshipped by the Cyzicenes with peculiar veneration. (Strab. XII. p. 575.)

"Εστι δέ τις αἰπεῖα Προτοντίδος ἔνδοθι νῆσος,
Τυτθὸν ἀπὸ Φρυγίης πελουλητού ἡπείροιο
Εἰς ἀλα κεχλιμένη, δύσσον τ' ἐπιμύρεται ἰσθμὸς,
Χέρσω ἐπιπρηνής κατασείμενος· ἐν δὲ οἱ ἀκταὶ
Αμφίδυμοι, κείνται δ' ὑπὲρ ὕδατος Αἰσήποιο.
"Αρχτῶν μιν χαλέουσιν ὅρος περιναιετάοντες.

APOLL. RHOD. I. 936.

Terra sinu medio Pontum jacet inter et Hellen
Ceu fundo prolata maris; namque improba cæcis
Intulit arva vadis, longoque sub æquora dorso
Litus agit, tenet hinc veterem confinibus oris
Pars Phrygiam, pars discreti juga pinea montis.
Nec procul ad tenuis surgit confinia ponti
Urbs placidis demissa jugis: rex divitis agri
Cyzicus.

VAL. FLACC. II. 630.

(Cf. Ovid. Trist. I. 9. Aristid. Orat. Cyzic.)

It had two ports, which could be closed, and might contain 200 galleys. One of these harbours was called Chytus,

"Ηοῖ δ' εἰσανέβαν μέγα Δίνδυμον, ὅφρα καὶ αὐτοὶ¹
Θηήσαιντο πόρους κείης ἀλός· ἐν δ' ἄρα τοίγε²
Νῆα Χυτοῦ λιμένος προτέρου ἐξήλασαν ὅρμου.

APOLL. RHOD. I. 985.

the other Panormus, as we learn from the Scholiast. (I. 954.) The latter still retains the name of *Panormo*. The same poet names the two fountains Artacie and Cleite. (I. 958. 1068.)

Mithridates having assembled an immense force, estimated by Appian at 300,000 men, by Strabo at 150,000 infantry, with a numerous cavalry, proceeded to invest Cyzicus on the land side by occupying mount Adrastea, opposite to the town, while he blockaded it by sea with a fleet of 400 vessels. The Cyzicenes, who had lost 3000 men and ten galleys

in a naval engagement fought previously near Chalcedon, (Plut. Lucull. c. 9.) were not intimidated by these formidable preparations, but resolved to defend their city to the last extremity. The siege was then pressed with the greatest vigour, and Mithridates, having succeeded in throwing troops into the island itself, brought up his engines, and began to batter the walls and towers on ten different points. One of these machines is said to have been 100 cubits high, and this sustained another tower, from which darts and missiles of every description might be discharged. It was the work of Nicomedes, the Thessalian. But a violent wind, raised, as it was supposed, by Proserpine, in favour of the besieged, blew with such force as to hurl this huge mass, and other engines, to the ground. This loss was however soon repaired, and other machines again shook the walls; whilst secret attacks were directed against the town by means of the sap and mine. These were, nevertheless, vigorously and dexterously repelled by the besieged, who had even nearly seized Mithridates in one of the mines which he was directing in person.

Meanwhile, however, Lucullus, the Roman general, having assembled an army for the relief of the town, posted himself at a place called Thracia in the vicinity of Cyzicus, and in the rear of the enemy's camp. From thence he greatly harassed Mithridates by cutting off his supplies, and destroying whole divisions of his army, and throwing reinforcements into Cyzicus, which was plentifully supplied with provisions, whilst the besiegers were reduced to the greatest distress. Famine and disease made such ravages amongst them, that Mithridates

was finally obliged to break up his camp and raise the siege with the greatest loss and disgrace. Lucullus then entered the town, and was received with every demonstration of gratitude and joy. (Appian. Bell. Mithr. c. 73. seq. Plut. Lucull. c. 9. seq. Strab. XIII. p. 575.) The Romans, in acknowledgment of the bravery and fidelity displayed by the Cyzicenes, guaranteed to them their independence, and besides granting them several privileges and immunities, extended their territory towards Troas, and as far as the lake Dascylitis in the direction of Bithynia. (Strab. loc. cit.) Under the Roman emperors Cyzicus continued to flourish and prosper greatly. Aristides, who lived in the reign of Hadrian, has left us an Oration he composed expressly in honour of this city, from which the following passages may be selected as most illustrative of its greatness and flourishing condition. “ Its plains,” says the orator, “ would suffice, not for a city merely, but for nations: and as for rivers and lakes, and pools and dells, there are so many, that if any one chose to form settlements around them all, it would be possible to have many cities on the banks of the lakes; many too on the shore of the sea, and not a few inland.” The forum was consecrated to all the gods, and also a temple within it, which appears to have been one of the most magnificent and extensive buildings of the kind recorded in antiquity. “ The temple,” says Aristides, “ supplies the place of heights, and you alone require neither lights, nor beacons, nor watch-towers for those who arrive in your ports; but the temple, which fills the whole sight, exhibits at once to the view both the city, and the noble spirit of its inhabit-

" ants. You might say, that each of the stones of
" which it was built was equal to a temple; and
" the temple itself to the whole peribolus of such an
" edifice; the peribolus again to the circumference
" of an entire city. The parts below ground, as
" well as the upper and the middle, are worthy of
" admiration. And there are also subterraneous,
" as well as other walks, raised all round the build-
" ing, which appear, not as a sccondary object, but
" as if they alone had constituted the original plan."

From an epigram preserved in the Anthology, it appears to have been dedicated to Hadrian. Xiphilinus affirms, that it was the largest and most beautiful of all temples. The columns being four yards in thickness, and fifty cubits high, and each formed out of one piece. This magnificent edifice, according to the same writer, was destroyed by an earthquake, which caused great damage at Cyzicus, and several other towns on the Hellespont. (p. 799.)

Pliny speaks of a temple at Cyzicus in which golden threads were inserted in all the joints of the marble blocks of which it was built; which contrivance diffused a rich and soft colouring over the pictures and statues which adorned the edifice. The same writer notices a remarkable echo near the gate called Trachia. Also the fugitive stone, as it was called, from its always moving from the prytaneum, where it was kept as a curiosity, having been left by the Argonauts, who used it as an anchor. The Cyzicenes, to prevent its escaping, at last fastened it down with lead. The senate-house was a vast edifice, in the construction of which no iron had been employed, and the blocks with which it was built were so arranged, that any of them

might be removed and replaced without the use of props. (Plin. XXXVI. 15. Vitruv. IV. 10.) Great facility was afforded for the erection of these and other important public buildings, from the extensive quarries of marble with which the island of Cyzicus and that of Proconnesus abounded. (Strab. XIII. p. 589. Plin. V. 32.) The games, and other festivals celebrated at Cyzicus, were commensurate with the greatness and wealth of the city. We hear of Olympian games held every five years; of others in honour of Lucullus, to commemorate the deliverance of the town by that general; of the Hieromenia; the festival of Cybele, and others. (Aristid. Collect. Hist. Vit. Appian. Bell. Mithr. c. 76.) Cyzicus was also famous for its golden staters, which were beautifully executed, as we learn from Suidas. Xenophon often speaks of them in the *Anabasis*, and Demosthenes states that they were worth twenty-eight Attic drachmæ ^k. Under the Byzantine emperors this city continued to flourish as the metropolis of the Hellespontine province, (Hierocl. Synecl. p. 661. Jo. Mal. Chron. I. p. 364.) and its see furnished several bishops to the Christian church ^l. Having been often taken by the Turks, and recovered by the Greek emperors, it was nearly destroyed by an earthquake A. D. 943. Cyzicus gave birth to several historians, philosophers, and other writers, whose works are quoted by Ath-

^k For a full account of the gold and silver staters of Cyzicus, the reader may be referred to a special work of Sestini, (*Descrizione degli Stateri Antichi*. Firenze 1817. p. 45.) The autonomous coins are rare, but

the imperial series extends from Augustus to Justinian. Sestin. Mon. Vet. p. 72.

^l Geogr. Sacr. Car. S. Paol. p. 238. Le Quien, *Oriens Christianus*.

næus, the Scholiast to Apollonius, and Suidas; such as Agathocles, Neanthes, Deilochus, Eudoxus, and others^m. The remains of this celebrated city have been described at some length by Pocockeⁿ, and Lucas^o, and still more recently by Sestini, in a journey made there in 1779.^p Pococke points out a large area, about 100 paces broad and 400 long, with the remains of an extensive building, having a Corinthian portico and several passages underground; it is also described by Sestini; but neither of these travellers seems to have suspected that these were the ruins of the celebrated temple, the theme of Aristides' panegyric: this is however evident from the subterraneous works, and its position in the forum. The modern name of *Atraki*, which attaches to these ruins, recalls to mind the little town of Artace, spoken of by Herodotus, Scylax, and Strabo. *Artace*. The former, in relating the history of the impostor Aristæus of Proconnesus, mentions Artace as a town in the vicinity of Cyzicus. (IV. 14.) In another place he says, it was burnt by a Persian fleet, together with Proconnesus. (VI. 33.) Scylax says it was within the isthmus. (Peripl. p. 35.) But Strabo speaks of it as a mountain of the peninsula covered with thick woods, and having a little island opposite to it. (XII. p. 576.) Elsewhere, however,

^m See a full list of these Cyzicene writers in a learned and elaborate note to Thucydides VIII. 107. by Wasse, from which I have derived much information.

ⁿ T. II. p. ii. p. 114. seq.

^o Second Voyage, t. I. c. 4.

^p Viaggio per la penisola di Cizico a Nicea fatto dall' Ab-

bate Domenico Sestini Livorno, 8vo. 1789. This antiquary observes, that the island is now completely united to the land, and that there are no indications of the bridges mentioned by Strabo. The isthmus is a flat, about a mile and a half in length, and three furlongs broad. Lett. VI. p. 502. seq.

the same geographer acknowledges a town or place of that name in the Cyzicene territory, opposite to Priapus, and colonized by the Milesians. (XIII. p. 582. XIV. p. 635.) Timosthenes, a writer cited by Steph. Byz. v. Ἀρτάκη, gave this name both to a mountain of Cyzicus and a little island about one stadium from the land. The mountain bending round the shore, makes a haven capable of receiving eight ships. Sophocles alluded to Artace in a verse preserved by Steph. Byz.

Tί μέλλετ' Ἀρταχεῖς τε καὶ Περιχώσιοι;

and Demosthenes, the Bithynian poet,

Νάσσατο δὲ Ἀρταχίοισιν ἐφέστιος αἰγιαλοῖσιν.

Pliny calls the island Artacæon, and places the town in it. (V. 32.) In the time of Procopius, Artace was considered to be a suburb of Cyzicus. (Bell. Pers. I. 25.)

Melanos
promonto-
rium.

Proconne-
sus insula
et urbs.

Cape Melanos, which Strabo places in a ship's course from Cyzicus to Priapus, is probably the western extremity of the Cyzicene peninsula. More to the north, and nearly opposite to the mouth of the Æsepus, is the island called Proconnesus, or isle of stags, by the ancients, now *Marmara*, whence the modern name of the Propontis is also derived. Proconnesus was much celebrated for its marble quarries, which supplied most of the public buildings in Cyzicus with their materials. (Strab. XIII. p. 588.), as also the palace of king Mausolus. (Vitruv. II. 8.) The marble was white, with black streaks intermixed ^q. From Herodotus we collect that there was a town of the same name with the island, of

^q Blasius Caryoph. de Marm. Antiq.

which Aristeas, who wrote a poem on the Arimaspians, was a native. (IV. 14. Strab. XIII. p. 588.) This town was burnt by a Phœnician fleet, acting under the orders of Darius. (Herod. VI. 33.) Strabo distinguishes between an old and new Proconnesus ; and Scylax, besides Proconnesus, recognises another island, named Elaphonesus, with a good harbour : it was dependent on the former. (Peripl. p. 35.) ^{Elaphone-sus insula.} Pliny seems to consider Elaphonesus as a more ancient name for Proconnesus. (V. 32.) Pausanias reports that Proconnesus was conquered by the Cyzicenes, who removed from thence the statue of Dindymene. (Arcad. c. 46.) Mention is made of this island as a bishopric in the ecclesiastical historians and the Acts of the Council of Chalcedon ^{r.} Pliny names several other islets in this part of the Propontis : Ophiusa, Acanthus, Phœbe, Scopelos, Porphyrione, Halone, with a town, Delphacia, and Polydora. (V. 44.) Of these, Halone is the only one which can be identified with the modern *Alonia*, a little to the west of the peninsula of *Artaki*^s. Polydora is placed by Steph. Byz. in the vicinity of Cyzicus.

Returning to the mainland we have to mention Antigonea, a fortress belonging to the latter city, ^{Antigonea.} about fifty stadia from the sea, (Steph. Byz. v. Ἀντιγονεία,) as well as Scyrus, which the same geographer ascribes to the Doliones. (v. Σκύρμος.) Continuing along the coast from Cyzicus, we may notice Scylace and Placia, named by Herodotus among the ^{Scyrus.} Scylace.

^r Geogr. Sacr. S. Paol. p. 239. There are some few autonomous coins belonging to this island with the epigraph

ΠΡΟΚΟΝ. Sestini Mon. Vet. p. 75.

^s Pococke, tom. II. part iii. c. 22.

Placia.

few settlements belonging to the ancient race of the Pelasgi which existed in his time. The inhabitants of these towns spoke a language which was entirely different from that of the neighbouring people. (I. 57.) Scylax names only Placia. (Peripl. p. 35.) Mela and Pliny both towns. (I. 19. V. 32.)

Ariacos.

The latter notices also an obscure place called Ariacos.

Rhyndacus fl.

Further on we come to the mouth of the river Rhyndacus, which separates Mysia from Bithynia. Strabo reports that it took its source in Azanitis, a district of Phrygia ; and after receiving the waters of the Macistus, and other streams of Mysia, discharged itself into the Propontis, opposite to the little island of Besbicus. (XII. p. 576.) Pliny states that the Rhyndacus was formerly called Lycus, and took its source in the lake Artynia, near Miletopolis ; that it received the Macestus, and other rivers, and separated the province of Asia from Bithynia. (V. 32.) It is easy to see that this account is quite at variance with that of the Greek geographer. The latter, however, is confirmed by other writers, and especially by modern geographers, so that he is alone to be followed. The lake which Pliny calls Artynia is the same to which Strabo gives the name of Miletopolis, from a neighbouring town so called. (XII. p. 575.)

Artynia
sive Mile-
topolis
palus.

But there is another lake further to the east, through which the Rhyndacus flows before it reaches the Propontis. It was called Apolloniatis, from the town of

Apollonia-
tis palus.

Apollonia, situated at its northern extremity, and near the point where the river issues again from it. Hence Apollonia was usually distinguished by the denomination of ad Rhyndacum, from other towns of the

same name^t. With respect to the assertion of Pliny that the Rhyndacus was once called Lycus, I do not find that it is supported by any other authority; but all from Scylax to Ptolemy give it only the former name. Polybius, indeed, mentions a river Lycus in this vicinity, (V. 77.) which may have united with the Rhyndacus; and this might account for Pliny's mistake. The Scholiast to Apollonius Rhodius is equally in error, when he says the Rhyndacus was called, in his time, Megistus; (ad Argon. I. 1165.) for the Megistus, or Macestus, is clearly distinguished from that river by Strabo and Pliny. The former describes it as rising in the district of Abasitis, near a place called Ancyra, and after flowing through Abrettene, a part of Mysia, as uniting with the Rhyndacus. (XII. p. 576.) Polybius also mentions the Megistus in his narrative of an expedition of king Attalus into Mysia, which I shall have occasion to notice presently. (V. 77.) From the information communicated by modern travellers, it appears that the Macistus is the stream which the Turks call *Mikalick*, and which, after receiving the waters of the lake Miletopolis, now called *Minias*, joins the Rhyndacus, or river of *Lubad*, a little below that town. Chishull, on his way from Smyrna to the Hellespont, crossed this river, which he mistook for the *Æsepus*, at the village of *Mandahora*^u; and he informs us, "that he came to it again at a "place called *Susegierlick*, and that he could trace "the whole of its remaining course almost as far as " *Mikalick*, where it enters the sea :" in the latter assertion, however, his information is not correct.

^t See a description of the coins of Apollonia in Eckhel and Sestini.
^u Pag. 58. and p. 52.

Miletopo-
lis.Apollonia
ad Rhyn-
dacum.

The same traveller describes the lake of Miletopolis as being “about thirty miles in circumference, “ always full of water, and stored with plenty of “ fish. A river empties itself into this lake, from “ whence by a new channel it takes its course to “ *Mikalick*. Directly beyond this lake,” he adds, “ we then beheld the fair exalted hills of Cyzicus, “ and the peninsula Cyzicena ^x.” Miletopolis, as its name implies, must have been a colony of the Cyzicenes, who themselves came from Miletus. The earliest writer who mentions it is Apollodorus, quoted by Strabo. (XIV. p. 681. Id. XII. p. 575. Plin. V. 32.) Stephanus Byz. places it between Cyzicus and Bithynia, near the Rhyndacus. (v. Μιλητούπολις.) Mention is made of the bishops of Miletopolis in ecclesiastical writings ^y, and its coins shew that it was a place of some note ^z. In the Synecdemus of Hierocles (p. 663.) it is probable, that for Μόλις we should read Μιλητόπολις. The Table Itinerary reckons twenty miles from this place to Apollonia. Sestini says, its ruins are to be seen at a place called *Milet*, or *Melté*, by the Turks ^a. The site of the ancient Apollonia is occupied, as we are informed by modern travellers, by the Turkish town of *Abulliona*, situated in a peninsula about five miles in circuit, which advances into the lake towards its north-western extremity. Near it are scattered two or three small islands. The lake is a fine piece of water, nearly fifty miles round and ten long; it is well stocked with fish ^b. Apollonia on

^x P. 59.

from Tiberius to Otacilia.

^y Geogr. Sacr. S. Paol. p. 239.^a Viaggio per Brusa, p. 82.^z Sestini Mon. Vet. p. 73.
The imperial series extends^b Sestini Viaggio p. 86. Chi-

shull, p. 51.

the Rhynndacus is noticed by Strabo, (XII. p. 575.) Pliny, (V. 30.) Ptolemy, and Steph. Byz. (v. Ἀπολλωνία.) Plutarch reports that a division of the forces of Mithridates was defeated in this vicinity by Lucullus. (Lucull. c. 164.) The Rhynndacus is now called the river of *Ulubad*, from a Turkish town of that name, situated on its left bank a little below the point where it issues from the lake. *Ulubad* does not represent Apollonia, as Chishull imagined, but Lopadium, a Greek town of the Byzantine empire, *Lopadium*. said to have been built by one of the Comneni against the Turks of Nicæa. It is often mentioned by the historians of the lower empire, and appears to have been a bishop's see. (Nic. Chon. p. 186. Ann. Comn. p. 177. C.) The ruins of *Ulubad* consist in massive walls, with turrets placed at intervals. The Rhynndacus is navigable at this point, and ships often come up to *Ulubad* from Constantinople and the Black sea^c. Anna Comnena mentions a river called Lampes, near Lopadium, which *Lampes fl.* is either the Rhynndacus, or some branch of it. (p. 177. C.) The poet Apollonius places at the mouth of the Rhynndacus the tomb of the giant *Ægæon*, or *Briareus*.

'Αλλ' ὅτε δὴ Μυσῶν λελιημένοι ἡπείροιο,
 'Ρυνδακίδας προχοὰς μέγα τ' ἡρίον Αἰγαίωνος
 Τυτθὸν ὑπ' ἐξ Φρυγίης παρεμέτρεον εἰσορόωντες.

ARC. I. 1164.

This spot, according to Bacchylides, cited by the Scholiast, was properly called Rhynndacus. (Cf. Steph. Byz. v. Ρυνδακός.) The little island now called *Kalolimno*, situated in the Propontis, about two miles from the mouth of the river, answers to the Besbi- ^{Besbicnus} insula.

^c Sestini Viaggio, p. 83.

cus of the ancients. Pliny says it once formed part of the mainland, but that it was separated from it by an earthquake. (II. 88.) According to the same writer it is eighteen miles in circumference. (V. 32.) Other traditions relative to this island will be found in Steph. Byz. v. Βέσβικος. This part of the Propontis abounded with the zoophyte called halcyonium. (Dioscor. V. 136.)

Little is known respecting the interior of Mysia, since even the ancient geographers were but imperfectly acquainted with it, there being no towns of any importance situated in that part of the province, and the country possessing no features sufficiently attractive to deserve a particular description. The information obtained by modern travellers is almost exclusively confined to the tract which lies between *Bergamah* and *Ulubad*, the road between these two towns being the only one which appears to be frequented at present. The country to the south of Lopadium and the lake of Apollonia was mountainous and difficult, and it required three days' march to make the circuit of the latter. (Mich. Duc. p. 93.)

That portion of Mysia which lies around the sources of the river Macistus, and between it and the Rhyndacus, was called Abrettene, as we learn from Strabo, who informs us, that in the reign of Augustus it formed part of a principality granted by that emperor to Cleon of Gordiu-come, a bandit chief, who had rendered him some service in his wars against Antony. Strabo adds, that Cleon was also priest of Jupiter Abrettenus, and lord of Morene, another Mysian district, noticed by no other writer. (XII. p. 575.) The Abretteni are mentioned by Pliny. (V. 30. Cf. Steph. Byz. v. Ἀβρεττίνη. The

Abrettene regio.

road mentioned above as leading from Pergamus and along the Caicus by *Gelembé*, near the sources of that river to *Mandrakhora*, *Susugherli*, and *Ulubad*, must have traversed part of Abrettene. The country is described as wild, desolate, and mountainous by Chishull^d, Lucas^e, and Sestini^f. The only remains of antiquity which appear to have been there noticed by Chishull are at *Mandrakhora*; they consist in seven large pillars, of coarse porphyry, which support the roof of the *khan*, or inn, at that place. This may have been the Mār-Mandra. δρα ἵπποι, or Mārδρα ἵππων, of Hierocles Synecd. (p. 663.) Joannes Malala speaks of a place called Mandra, or Mandro, where Priam sent Paris to be nursed. The word Mārδρα signifies simply a stall or stable. The river which runs by *Mandrakora* is probably the Lycus of Polybius^g. It flows towards the Propontis, as Chishull, Sestini, and other travellers represent. Polybius, in describing an expedition of king Attalus into Mysia, with a large body of Gallo-Græci, or Galatæ, (V. 77.) says, that having crossed the river Lycus, he advanced to- Lycus fl. wards the settlements of the Mysians; from thence he directed his march towards Carseæ, which is probably the Caresus of Strabo, and placed by that writer in Troas. Carseæ and Didymoteiche having surrendered, the king moved onwards, and ravaged the plain of Apia. Now the plain of Apia ^{Apia cam-} is placed by Strabo above Thebe and Adramyttium, ^{pus.} and north of mount Temnus, (XIII. p. 616.) exactly where it was observed by Chishull in 1701.

^d P. 47.^e 3^{me} Voyage, tom. I. p. 133.^f Viaggi Diversi, p. 136-8.^g See the map to col. Leake's Asia Minor. It is by mistake made to fall into the Caicus.

“ In somewhat more than six hours we had passed
“ the Temnus, and enter into a rich plain, extended
“ all along the backside of Ida, now *Cordag*; at the
“ foot of which, about four miles distant from the
“ road, we descry the agreeable seat of *Balihisar*.”

Pelecas
mons.

From the Apian plain Attalus crossed over a mountain named Pelecas, and arrived on the banks of the Megistus, where the Gauls having refused to proceed further, he settled them on the Hellespont, and returned with his own forces to Pergamos. The Pelecas of Polybius is probably that continuation of mount Temnus which separates the valley of the Æsepus from that of the Megistus. This ridge appears in the Byzantine historians under the name of Lentiani colles; at least it is the only range in the vicinity of Cyzicus and Lopadium, which seems to answer to Anna Comnena's narrative of the capture of the latter city by a Turkish army, and their subsequent retreat over these hills by a defile named

Aorata sal- Aorata, in which they were attacked by Camytzes,
tus.

Pœmane-
nus.

a general who had been detached in their pursuit by the emperor Alexius. In the immediate vicinity of these hills, but nearer Cyzicus, as we learn from the same narrative, was Pœmanenus, a Mysian town of some note, and a place of great strength, ($\piολιχνιον \epsilonρυμνότατον$.) Ann. Comm. p. 440. A. Aristides also informs us, that it had a temple, sacred to Æsculapius, which was held in great veneration. (Sacr. Orat. IV. p. 569.) The orator passed through Pœmanenus on his way to the hot baths of the Æsepus, which had been recommended to him for the cure of a complaint to which he was subject. He was then coming from Hadriani, his native town, which we know to have been situated in Bithynia,

at the foot of mount Olympus, and near the Rhyn-dacus. He seems to reckon 160 stadia, or somewhat less than 20 miles, from thence to Pœmanion; but there is reason to suppose either that this number is corrupt, or that it is not reckoned from Hadriani, but from some nearer spot. At all events we shall be justified in placing Pœmanenus between the Rhyn-dacus and the Æsepus. The Table Itinerary will furnish us another indication of its position; for we find in it a place laid down on the road from Pergamus to Cyzicus, under the name of Phemenio, which, as Mannert judiciously observes, can be no other than the town in question^h. It is evident indeed, from Anna Comnena, that it was not far from Cyzicus; and Stephanus Byz. terms it expressly Χωρίον Κυζίκουⁱ, (v. Ποιμάνιον.) Hierocles calls it Pœmanentus, and enumerates it with other towns belonging to the Hellespontine province. (Synecd. p. 662. Cf. Plin. V. 32.) In the Geographer of Ravenna, (p. 761.) the name is written Pomenion, which comes nearest to the Phemenio of the Table. Mannert is inclined to identify the site of this town with some ruins on a hill observed by Pococke at a place called *Doulokui*^k, to the S. E. of Cyzicus, and on the road from that city to *Mikalitzka*. But I think it could not have been to the north of the lake of Miletopolis; I should rather look for its ruins above the *Hamanlee* of Chishull, among the hills which overhang the Tarsius.

^h Geogr. tom. VI. part. iii. p. 543.

ⁱ There are autonomous coins belonging to this town with the head of Jupiter crowned with laurel; on the reverse, a thunderbolt, and the inscription,

ΠΟΙΜΑΝΗΝΩΝ. There are others also struck in the reign of Trajan. Sestini Lett. Numism. tom. VI. p. 76.

^k Geogr. tom. VI. part. iii. p. 543.

I shall conclude this article on Pœmanenus, by reminding the reader, that according to ecclesiastical documents it was a bishopric^l, and that its church was dedicated to the archangel Michael. (Georg. Acrop. p. 19.) The Byzantine historian just quoted seems to speak of Lentiana as a tract of country about Pœmanenus and Lopadium, and between the latter and the Hellespont. (p. 6. C.) In another passage he distinctly refers to a town of the same name. (p. 15. C.) This is perhaps the same town which Hierocles calls Σκέλεντα, (Synecd. p. 662.) and which itself may be a corruption of Πελεκάντα. (Polyb. V. 77.)

The Tabula Theodosiana lays down, immediately after Pœmanenus, on the road to Pergamus, and at the distance of thirty miles from the former, and thirty-five from the latter, a station, under the name of Argiza, which Mannert is inclined to identify with the Ergasteria observed by Galen on the same route^m; but that writer reckons 440 stadia, or about fifty Roman miles, from Pergamus to Ergasterion; consequently it must have been situated fifteen miles beyond Argesæ, towards Cyzicus. (Simpl. Med. IX. 22. p. 127.) There can be little doubt that Argesæ is the Argiza of Hierocles, (Synecd. p. 663.) and that writer, by distinguishing it from Ergasterion, which he also names, throws a further obstacle in the way of Mannert's conjecture. It is not improbable that Argiza is the same town as the Erezii of Pliny, which he seems to place about Pœmanenus and Miletopolis. (V. 32.) The road from

^l Geogr. Sacr. S. Paol. p. 238. ^m Geogr. tom. VI. part. iii.
Le Quien Oriens Christ. p. 769. p. 543-4.

Pergamus to Cyzicus led probably along the valley of Tarsius, and if so, according to Strabo, must have crossed it no less than twenty times. (XIII. p. 587.) It is in this valley, which no modern traveller seems to have explored, that I would seek for Argiza or Erezii and Ergasterion ; the latter might easily be found from the scoria and other metallic appearances indicative of ancient mines noticed by Galen, (loc. cit.)

Germe, or, as Ptolemy terms it, Hiera Germe, a Germe. name which also appears on its coinsⁿ, is classed by that geographer among the towns of the Lesser Mysia, and by Stephanus Byz. is said to be near Cyzicus and the Hellespont, (v. Γέρμη. Hierocl. Syndec. p. 662.) Socrates, the ecclesiastical writer, reports, that it was in great measure destroyed by an earthquake in the reign of Valens ; but the Byzantine historians speak of it as still existing in their time ; (Georg. Pachym. p. 295.) and one of its bishops is known to have sat in the council of Chalcedon^o. From the mention of the Germian mountains in Anna Comnena, (p. 464,) we collect, that this town was situated in a hilly country, and in the vicinity of Lopadium ; and it is in this direction that Leunclavius^p, Holstenius^q, and D'Anville^r, point out a small town, named *Ghirmasti* by the Turks, as occupying the ancient site. In the same direction I would look for the remains of Oca, Oca. or Occa, a town mentioned only by later writers,

ⁿ The epigraph is sometimes ΙΕΡΑ . ΓΕΡΜΗ, and sometimes ΙΕΡΑ ΣΤΝΚΛΗΤΟC ΓΕΡΜΗΝ-ΩΝ. Sestini Mon. Vet. p. 73.

p. 239.

^p Ap. Car. S. Paol. loc. cit.

^q Annot. ad Geogr. Car. S. Paol. p. 239.

^o Geogr. Sacr. Car. S. Paol.

^r Geogr. Anc. p. 96.

Acrocon
saltus.

such as Hierocles, Synecd. (p. 662.)^s and the ecclesiastical notices, which record the fact of its being a bishopric in the reign of the emperor Leo^t. I take Oca to be the same as the Acrocon, i. e. "Ακρα 'Οκων of Anna Comnena, (p. 441. A.) from whom we collect also, that to the south of it was a defile leading to Philadelphia, in Lydia, (p. 443. A.) We may conjecture, that this pass traversed the mountains which divide the valleys of the Megistus and Rhyndacus from those of the Hermus and its tributary streams. Another pass appears to have led from Lopadium to Thyatira. (Mich. Duc. p. 45.)

Temeno-
thyritæ.
Myso-Ma-
cedones.
Pentade-
mitæ.

Ptolemy names three obscure tribes in the interior of Mysia, which are unknown, I believe, to the other geographers. Of these the Temenothyritæ occupied the west of the province, the Myso-Macedones the centre, and the Pentademitæ the south, p. 126.

HELLESPONTUS.

The narrow strait which separates the Thracian Chersonnese from the coast of Asia, and by which the waters of the Propontis are poured into the wider basin of the Ægæan, had in fabulous times received its name from the fate of Helle, daughter of Athamas, who was supposed to have perished there in her voyage to Colchis.

"Οσσον ἐπὶ στεινωπὸν ὕδωρ 'Αθαμαντίδος Ἔλλης.

DIONYS. PER. 515.

"Ενθα σφίν λαιψηρὸς ἄη νότος· ιστία δ' οὔρῳ
Στησάμενοι, κούρης 'Αθαμαντίδος αἴπα ρέεθρα
Εἰσέβαλον.

APOLL. RHOD. I. 926.

^s It should be observed, that I adopt Wesselings correction of ΟΚΗ, ΣΙΔΗΡΟΝ for Ο ΚΙΣΙ-

ΔΗΡΟΝ.

^t Geogr. Sacr. Car. S. Paol. p. 239.

(Cf. Apollod. I. 9, 1.) The tomb of Helle was placed, as Herodotus reports, on the shores of the Chersonnese, near the city of Cardia. (VII. 58.) The narrowness and length of this celebrated channel, together with the sinuosities of its shores, and the rapid and powerful current which is constantly flowing through them, are sufficient reasons to justify Homer in the epithets of Πλατὺς, which he applies to it, if we regard the epithet as bestowed upon what might be viewed rather as a mighty river than a winding arm of the sea.

**Οφραὶ ταρχύσωσι χαρηκομόσωντες Ἀχαιοῖ,
Σῆμά τέ οἱ χεύσωσιν ἐπὶ πλατεῖς Ελλησπόντῳ.*

I.L. H. 86.

(Cf. Il. P. 432. Od. Ω. 82. Æsch. Pers. 880.) It will not be necessary, therefore, to seek for an explanation of the word in the remote signification of brackishness, which has by some critics been attached to it, (Athen. II. p. 41. B.) more especially if we take into the connexion the analogous epithets of ἀγάρροος and ἀπείρων, which are elsewhere used by the poet.

**Οσσους Ελλήσποντος ἀγάρροος ἐντὸς ἔέργει.*

I.L. B. 845.

Καὶ Φρυγίη χαθύπερθε, καὶ Ελλήσποντος ἀπείρων.

I.L. Ω. 545.

It may be worth while to adduce, in confirmation, the remarkable expressions of δολερὸς καὶ ἄλμυρὸς ποτάμος, which Herodotus puts into the mouth of Xerxes, as applied to the Hellespont. (VII. 35.^u)

The straits begin properly a little to the south of cape *Karaboa*, where the ancient town of Pri-

^u See the word πλατὺς, in the glossary of Bloomfield's edition of the Persæ, v. 880.

pus stood, and terminate with cape Sigeum, now C. *Kumkalé*. Some ancient geographers, however, supposed them to commence only at Sestos and Abydos; they consequently extended the shores of the Propontis, in a south-westerly direction, to the vicinity of those towns. (Strab. XIII. p. 583. Cf. Ptol. p. 126.) When Herodotus states that the breadth of the Hellespont is seven stadia, (IV. 85.) he must be considered to mean in the narrowest part; which is between Sestos and Abydos, where Xerxes built his famous bridges. (Cf. VII. 34.) The same historian reckoned 400 stadia for the length of the strait, without however stating from what point he measured his distance. Modern measurements give about sixty miles from *Kamares*, where the straits of *Gallipoli*, or the *Dardanelles*, as they are now called, fairly commence, to the Sigeian promontory. The mean breadth seems to be not less than three miles^x.

The name of Hellespont, though properly belonging to the sea straits, in process of time was applied to the land on each side, and to the cities founded there by the Greeks. (Thuc. VIII. 86.) Not unfrequently also the Persian satrap, of whose government these cities formed a part, on the Asiatic side, was designated by the title he derived from this celebrated channel. The importance of the passage, in a political and commercial point of view, was as much felt in ancient times as at present; and the possession of it was always considered by the Athenians as indispensable to the preservation of their

^x See a particular Memoir on the Hellespont by D'Anville, inserted in the Mémoires de

l'Académie des Belles Lettres, LXXVIII. p. 318.

naval ascendency, and the security of their commerce. It was here, in fact, that the struggle between them and their enemies was long carried on with alternate success, each making the greatest efforts to drive the other from the sea, till at last the decisive battle of *Ægospotami* deprived Athens of her fleet, and, by closing the Hellespont to her ships, stripped her of her best resources, and left her no alternative but to surrender. I shall commence the Hellespontine periplus from the point where the shores of the Propontis begin to be straitened, that is, somewhat to the south-west of Priapus, which town has been considered as belonging to that sea.

Parium, founded by the Milesians, the Erythraeans, and the Parians, of Paros, (Strab. XIII. p. 588.) is mentioned for the first time by Herodotus, in the reign of Darius. (V. 117.) Under the kings of Pergamos it became a city of some extent and opulence, having been enlarged by those princes at the expense of the neighbouring towns of Adrastea and Priapus. (Strab. XIII. p. 588.) Its harbour was secure and spacious, being able to contain a fleet of more than eighty ships. (Xen. Hell. I. 1, 8.) At a later period, it was dignified by Augustus with the title of a Roman colony. (Ulpian. Digest. L. tit. 5. Plin. V. 32.^y)

The ruins of this town are pointed out by travellers at *Kamares*. “The walls of the city, which “fronted the sea, still remain, and are built of large

^y Coins and inscriptions give it the title of *Colonia Julia* and *Colonia Antonia*. The series of the former extends from Ju-

lius Cæsar to Saloninus. The autonomous coins are also very numerous. Sestin. Mon. Vet. p. 73.

" blocks of squared marble, without mortar. We
 " saw ruins of an aqueduct, reservoirs for water,
 " and the fallen architraves of a portico. There are
 " also some subterranean buildings, whose arched
 " roofs incline or dip from the horizontal level. As
 " Καμάρα means both *arch* and *aqueduct*, we can be
 " at no loss for the derivation of *Camaris*, the modern
 " name of the town. The circuit of Parium has
 " been about four miles^z."

Linum. Linum was a spot situated on the coast between Parium and Priapus, and well known for a sort of shell-fish caught there. (Strab. XIII. p. 588.) More inland was the town of Pityea and the district of Pityus, which derived its name from a hill covered with firs. The town is named by Homer, with other places in this vicinity,

Οἱ δὲ Ἀδρήστειάν τ' εἶχον καὶ δῆμον Ἀπαισοῦ,
 Καὶ Πιτύειαν ἔχον, καὶ Τηρείης ὄρος αἰπύ.
 Τῶν ἡρχὴν Ἀδρηστός τε καὶ Ἀμφιος λινοθώρηξ,
 Υἱε δύω Μέροπος Περκωσίου. ILIAD. B. 828.

and by Apollonius Rhodius, Argon. I. 933.

. . . ζαθέην τε παρήμειβον Πιτύειαν.

Some writers, however, identified Pityea with Lampsacus. (Schol. Apoll. ad loc. cit. Steph. Byz. v. Λάμψακος.)

Adrastea. Pliny was of opinion that the Adrastea of Homer had made way for Parium, (V. 32.) but Strabo expressly asserts, that it stood between the latter city and Priapus; and that it possessed a temple and

^z Walpole's Turkey, tom. I. p. 88. from Dr. Sibthorp's Papers. It appears from Anna Comnena that Parium still retained its name in her time,

p. 439. B. The bishop of Parium is named among the prelates who sat in the council of Chalcedon. Geog. Sacr. S. Paul. p. 240.

oracle of Apollo Actæus. This building was, however, afterwards demolished, and the materials were removed to Parium, and employed there in the construction of a magnificent altar. (XIII. p. 580.) In the vicinity of Parium there was said to exist a race of men, named Ophiogeneis, who were supposed to have some affinity with serpents, and to be able to cure persons who had been bit by those reptiles. (Strab. *ibid.*) Iliocolone, according to Strabo, was Iliocolone. a place situated in the Parian territory. (XIII. p. 589.)

Apæsus, or Pæsus, for Homer employs both names,

Apæsus
sive Pæsus
urbs et fl.

Oī δ' Ἀδρήστειάν τ' εἶχον καὶ δῆμον Ἀπαισοῦ.

I.L. B. 828.

Kαὶ βάλεν Ἀμφιον, Σελάγου υἱὸν, ὃς δέ τοι εὐνὴ Παισῶ

Ναῖς πολυκτήμων, πολυλήγος. I.L. E. 612.

was situated to the south of Parium, on a rivulet of the same name, now called *Beiram-dere*^a. It had been founded by the Milesians, but they afterwards deserted it for the more flourishing colony of Lampsacus. (Strab. XIII. p. 589.) Pæsus, however, existed in the time of Herodotus, who records its occupation by a Persian general at the time of the Ionian revolt excited by Histiaeus and Aristagoras (V. 117. Steph. Byz. v. Ἀπαισός.)

Lampsacus, one of the most celebrated of the Hellespontine cities, was known to have existed under the name of Pityusa before it received colonies from the Ionian towns of Phocæa and Miletus. (Strab. XIII. p. 589. Steph. Byz. v. Λάμψακος. Plut. de Virt. Mul. 18. P. Mel. I. 19.) It was situated opposite

^b Chevalier, *Voyage dans la Troade*, p. I. ch. 5.

to Callipolis, in the Thracian Chersonnese, the strait which separated the two cities being only forty stadia in breadth, and it possessed an excellent harbour.

Herodotus relates, that the first Miltiades, who settled in the Chersonnese, made war upon the Lampsacenes, who surprised him in one of his attacks, and took him prisoner. Being threatened, however, with the vengeance of Crœsus, who favoured Miltiades, they released their captive. (VI. 37.) The same historian informs us, that Lampsacus fell into the hands of the Persians during the Ionian revolt. (V. 117.) The territory of this city produced a great abundance of excellent wine, a circumstance which induced the Persian monarch to bestow it on Themistocles, when that illustrious Athenian sought refuge in his dominions, in order that his table might be furnished with that beverage from thence. (Thuc. I. 138. Athen. I. p. 29. F.) It continued, however, under the government of a native prince or tyrant, named Hippocles. His son, Æantides, married Archedice, the daughter of Pisistratus, whose tomb, with an inscription commemorative of her virtues, was to be seen at Lampsacus when Thucydides wrote. (VI. 59.) Athenæus has recorded the attempt of another citizen, named Euagon, to obtain possession of the citadel, and seize thereby the sovereign power. (XI. 508. F.) It became tributary to Athens after the battle of Mycale, and revolted on the failure of the Sicilian expedition; but, being unfortified, was easily reconquered by a small fleet under Strombichides. (Thuc. VIII. 62.) After the death of Alexander, we find the Lampsacenes defending their city against the attacks of

Antiochus, (Liv. XXXIII. 38. XXXV. 42. Polyb. XXI. 10.) voting a crown of gold to the Romans, and received by them into their alliance. (Liv. XLIII. 6.) Strabo reports that Lampsacus was yet a flourishing city in his day. It had produced several distinguished literary characters and philosophers, such as Charon the historian, Anaximenes the orator, and Metrodorus a disciple of Epicurus. That celebrated philosopher had himself resided many years there, and had reckoned some of its citizens amongst his most intimate friends. (Strab. XIII. p. 589. Diog. Laërt. Epicur.)

Lampsacus had been adorned by a remarkable statue, executed by the celebrated Lysippus, representing a prostrate lion; but it was removed by Agrippa to decorate the Campus Martius at Rome, (Strab. loc. cit.) It is well known that Priapus was worshipped with peculiar reverence in this city. (Athen. I. 30. B. Lucian. I. 275.)

Et custos furum atque avium cum falce saligna
Helleponiaci servet tutela Priapi. GEORG. IV. 110.

Et te ruricola Lampsace tuta deo. OVID. TR. I. 11.

Other passages relating to the history of Lampsacus, will be found in Xenophon. (Anab. VII. 8, 1. Polyb. V. 77. Steph. Byz. v. Λάμψακος. Polyæn. VIII. 38. Plin. V. 32. Arrian. I. 5, 16.) The name of *Lamsaki* is still attached to a small town near which Lampsacus probably stood, as *Lamsaki* itself contains no remains or vestiges of antiquity. A modern traveller assures us besides, that “its “wine, once so celebrated, is now among the worst “that is made in this part of *Anatolia* ^b.”

^b Dr. Sibthorpe, in Wallpole's Turkey, tom. I. p. 91. There are gold and silver staters of Lampsacus in different

Abarnis
promonto-
rium.

Abarnis was a promontory belonging to the Lampsacenes, as we learn from Hecatæus and Ephorus, cited by Steph. Byz. (v. *Ἄβαρνος*) and Xenophon in the Hellenics, who reports that Conon, the Athenian general, having escaped from the defeat of Ægospotami, carried off from thence the sails left there by the Lacedæmonian fleet under Lysander. (II. 1, 19.) It is also noticed by Apollonius Rhodius. (Argon. I. 932.)

*Περχώτην δὲ πὶ τῇ, καὶ Ἀβαρνίδος ἡμαθόεσσαν
Ἡῖονα—*

Stephanus Byz. ascribes it to Parium, whence we may conclude that it lay between that town and Lampsacus. Theophrastus, in a passage cited by Athenæus, says, that the truffle called “ Iton” was found there. (II. 62. C. Plin. XIX. 13.) Theophrastus also says, that there were gold mines near Lampsacus, in which a gem was found of such beauty and rarity, that the Lampsacenes presented it to Alexander. (de Lapid. Plin. XXXVII. 74.)

Colonæ.

We have yet to notice, in the territory of this city, Colonæ, a Milesian settlement, at some distance from the sea, and which must not be confounded with another town of the same name in the Troad. (Strab. XIII. p. 589. Arrian. I. 5, 16.)

Gergi-
thium.

Gergithium, a district planted with numerous vineyards, and distinct from Gergis, or Gergitha, a Trojan town, of which we shall have occasion to speak hereafter. (Strab. loc. cit.)

Myrmis-
sus
sive Mer-
messus.

Myrmissus, or Mermessus, said to be the birthplace of the Erythræan sibyl, who is also sometimes called Gergithia and Hellespontiaca, was placed by Polemo near Lampsacus. (ap. Steph. Byz.

numismatical collections. The imperial medals have been traced from Augustus to Gallienus. Sestini Mon. Vet. p. 73.

v. Μυρμισσός. Id. v. Μερμεσσός. Lactant. de Fals. Rel. I. c).

Mount Terea, the name of which occurs in the Homeric topography, was identified by some writers with a hill, distant forty stadia from Lampsacus. Hermæum, according to Polyænus, was a spot between that city and Parium, seventy stadia from the latter. (VI. 24.) Continuing along the shore of the Hellespont we come to the Practius, a small river, which has a place in the Homeric topography, together with Percote, an ancient town, situated apparently on its banks.

Oἱ δὲ ἄρα Περκώτην καὶ Πράκτιον ἀμφεγέμοντο.

IL. B. 835.

Charon of Lampsacus, cited by Strabo, (XIII. p. 583.) reckoned 300 stadia from Parium to the Practius, which he looked upon as the northern boundary of the Troad. This distance serves to identify that stream with the river of *Bergaz*, or *Bergan*, a small Turkish town situated on its left bank, and which probably represents Percote. The situation is thus described by a traveller: “A river called *Chiergee* “runs near Lampsacus, and two hours from thence “we met another winding stream, which falls into “the Hellespont at a point projecting very far to- “wards the European coast. We then passed a “village called *Beergan*, on the banks of this river. “Its situation on a sloping hill, with clumps of “trees left in picturesque spots round it, and a clear “stream running in the valley, formed a very beau- “tiful landscape. Indeed the whole of this shore “furnishes a continual succession of the richest

^c See the notes of Berkelius to Steph. Byz. v. Γέργις, and Salmasius, Exercit. Plin. p. 79.

“scenery^d.” Percote is mentioned again by Homer, (Il. O. 548.) when speaking of Menalippus, son of Priam;

. . . ὁ δὲ ὄφρα μὲν εἰλίποδας βοῦς
Βόσχ' ἐν Περκώτῃ, δητῶν ἀπονόσφιν ἔονταν.

and A. 229. from which latter passage it is apparent that Percote was on the sea, or very near it. (Cf. Xen. Hell. V. 1, 23.)

Τὰς μὲν ἔπειτ' ἐν Περκώτῃ λίπε νῆας ἔισας·
Αὐτὰρ ὁ πεζὸς ἐών, εἰς Ἰλιον εἰληλούθει.

Percote continued to exist long after the Trojan war, since it is spoken of by Herodotus, (V. 117.) Scylax, (Peripl. p. 35.) Apollonius, (Rh. I. 932.) Arrian, in his account of Alexander's expedition, (I. 13.) Pliny, (V. 32.) and Steph. Byz. (v. Περκώτη.) It was named by some writers among the towns given to Themistocles by the king of Persia. (Athen. I. 29. Plut. Themistocl. c. 30.) Somewhat further south we find Arisbe, mentioned also by Homer, together with the river Selleis.

Οἱ δὲ ἄρα Περκώτην καὶ Πράκτιον ἀμφενέμοντο,
Καὶ Σηστὸν καὶ Ἀβυδον ἔχον, καὶ διὰν Ἀρίσβην·
Τῶν αὖθ' Ὑρταχίδης ἥρχ' Ἀσιος, ὤρχαμος ἀνδρῶν,
Ἀσιος Ὑρταχίδης, ὃν Ἀρίσβην φέρον ἵπποι
Αἴθωνες, μεγάλοι, ποταμοῦ ἀπὸ Σελλήντος.

IL. B. 835.

(Cf. Z. 13. Φ. 43.) Arisbe, according to Steph. Byz., had been founded by the Mitylenæans, in whose island there was a town of the same name. Other traditions are to be found in the same lexicographer under Ἀρίσβη. It was here, according to Arrian, that Alexander stationed his army immediately after crossing the Hellespont at Abydos. (I. 12.) When the Gauls passed over into Asia, some centu-

^d Dr. Sibthorpe's Journal in Walpole's Turkey, tom. I. p. 91.

ries after, they also occupied Arisba, but were totally defeated by king Prusias. (Polyb. V. 111.) A rare coin belonging to this town shews that it still existed in the reign of Trajan^e. Pliny also names it; (V. 32.) and if it is the same as the Barispe of Hierocles, (p. 663.) we should be able to trace its history some years later. Wesselink, in his notes to that writer, quotes a passage from the Acts of St. Parthenius of Lampsacus, in which mention is made of Arisba as a place near Abydos. If Barispe again is the Bares of the ecclesiastical writers, it will follow that Arisbe was a bishop's see, under the metropolitan church of Cyzicus, about that period^f. The Selleis is probably the river called *Moussa-tchai* by the Turks, and Arisbe may have stood at *Gangerlee*, where Dr. Sibthorp observed "the ruined wall of some ancient Greek "town^g."

Further south, and on the promontory now called *Abydos*. *Nagara*, are to be seen the inconsiderable remains of the once rich and flourishing city of *Abydos*. We learn from Strabo that it had been founded by a colony of Milesians, with the consent of Gyges, king of Lydia, to whom the whole of the surrounding country was subject ; but it is evident that the name of *Abydos* had long been attached to the spot, since it occurs in Homer in conjunction with *Sestos*, with which it seems naturally united :

Kαὶ Σηστὸν καὶ Ἀβύδον ἔχον, καὶ διὰν Ἀγίσθην.

IL. B. 836.

^e Imperatorius unicus cum capite Trajani. Epigraphe APIC-BEON. ^Æ. Autonomi Epi-graphe. AP. API. ^Æ. Sestini Mon. Vet. p. 76.

^f Car. S. Paol. Geogr. Sacr. p. 239.

^g Walpole's Turkey, tom. I. p. 92.

elsewhere the poet mentions it as celebrated for its breed of horses.

'Αλλ' οὐδὲν Πριάμοιο νόθον βάλε Δημοκόωντα,
Ος οἱ Ἀβυδόθεν ἥλθε, παρ Ἰππαν ὀχειάων.

IL. Δ. 499.

After the siege of Troy, Abydos was occupied by some Thracians, and then finally by the Milesians. Strabo asserts that it was burnt by order of Darius, together with some other cities on the Hellespont, on his return from Scythia, as he feared lest the Scythians should in return be disposed to invade his dominions, and seek to effect a passage in this direction. (XIII. p. 591.) Herodotus, however, has omitted all mention of this circumstance ; and it is evident, from his subsequent history of the operations of Xerxes, that Abydos was then in a flourishing condition. But even before that, he states, that in the Ionian revolt it was taken by Daurises, a general of Darius, with other Hellespontine towns. (V. 117.) On this occasion the city, perhaps, suffered from fire, and this may have given rise to the report followed by Strabo.

It was at Abydos that Xerxes, seated on an eminence, where an ivory throne had been prepared for him, surveyed his mighty fleet which covered the Hellespont, whilst the neighbouring plains swarmed with his innumerable troops. (Herod. VII. 44.) The bridge, destined for the passage of these multitudes into the opposite continent, was placed in the narrowest part of the straits, where the breadth did not exceed seven stadia, whence it was usually called Hep-tastadium. The point immediately opposite to Abydos was called Zeugma, and that to which the bridge had been fixed, Apobathra. Sestos stood further

to the north, the distance between it and Abydos being not less than thirty stadia. (Strab. XIII. p. 591.)

Tales fama canit tumidum super æquora Xerxem
Construxisse vias, multum cum pontibus ausus,
Europamque Asiæ, Sestonque admovit Abydo.

LUCAN. II. 672.

Abydos became dependent upon Athens after the Persian war, together with Sestos, which secured to that power the passage of the Hellespont. It recovered its liberty for a short time, when the failure of the Sicilian expedition had shaken the empire of the Athenians, (Thuc. VIII. 61.) but was recovered afterwards by Alcibiades, who appears to have spent much of his time there in the midst of pleasures. (Antiph. ap. Athen. XII. p. 525. B. Cf. XIII. p. 574. E.) The Abydenes, indeed, are noted by ancient writers in general for their voluptuous and sensual habits. (Hermipp. et Aristoph. ap. Athen. loc. cit. Steph. Byz. v. *"Αβυδοι."*) The Athenians once more lost Abydos, after the battle of Ægospotami, but it was again conquered by Thrasybulus; the Lacedæmonians afterwards sent a force under Anaxibius to occupy it, but he was defeated and slain by Iphicrates. (Xen. Hell. IV. 8, 35.) Antalcidas, the Spartan admiral, having however assembled a considerable fleet, occupied Abydos, and drove the Athenians from the Hellespont, which finally brought on the peace to which he has given his name. (Hell. V. 1, 23.) Some centuries after, this city sustained a memorable siege against the forces of Philip, the son of Demetrius, king of Macedon, who, after reducing many Thracian towns, and the whole Chersonnese, summoned the inhabit-

ants to open their gates to his troops. The Abydenes, however, courageously refused, and, though unsupported by any allies, defended themselves with the greatest obstinacy, till their walls were in many places laid open. Even then they continued fighting to the last; and though the principal inhabitants agreed to surrender to the king, the people preferred to perish, with their wives and children, rather than fall into his hands. (Polyb. XVI. 30. Liv. XXXI. 16.) On the defeat of Philip at Cynoscephalæ, that prince was compelled by the Romans to evacuate Abydos, (Polyb. XVIII. 27, 4.) It was not long after occupied by Antiochus, and vainly besieged by C. Livius, commander of the Roman fleet. (Liv. XXXVII. 9—12. Appian Syr.) The defeat which Antiochus sustained at Magnesia compelled him, however, to give up the whole of Asia Minor on this side Taurus, and Abydos was ceded by the Romans, together with the other Hellespontine cities, to Eumenes, king of Pergamus. (Polyb. XXII. 27, 10.) Beyond this period it makes but little figure in history, though from its coins it is known to have flourished in the reign of the emperor Maximinus^h; and still later we can trace its existence through the Byzantine historians, to the close of the Greek empire. (Cedren. p. 699.)

Abydos has derived some celebrity from the romantic story of Hero and Leander, which cannot be said to exist merely in the fictitious poem of Musæusⁱ, since Virgil and Ovid confirm the tale;

^h Imperatorii ab Augusto usque ad Maximum Autonomi Anepigraphi Aurei et Argentei — Autonomi Inscripti AB. ABT. ABTΔ. Insignes Tetra-

drachmi argentei inscripti ABT-ΔHNΩN. Sestini Mon. Vet. p. 76.

ⁱ For an account of this poet, see Fabricius Biblioth.

(Georg. III. 260. Heroid. Epist. 18 and 19.) and Strabo speaks of an edifice near Sestos which was commonly known by the name of Hero's tower, (XIII. p. 591.) and some of the imperial medals have inscribed on them the names of the lovers ^k.

The situation of Abydos was not so advantageous, in a commercial point of view, as that of Sestos, since the latter was nearer the Propontis, and above the current which set in from that sea; whence a ship might with great facility work its way in that direction towards the Bosphorus or Euxine, and also descend with the stream into the Ægean; whereas a vessel setting out from Abydos, had great difficulty in making way against the current which set in strongly from the European shore. (Strab. XIII. p. 591. Polyb. IV. 44.)

Σηστὸς ὅπῃ καὶ Ἄβυδος ἐναντίον δρμον ἔθεντο.

DIONYS. PERIEG. 516.

Pontus et ostriferi fauces tentantur Abydi.

GEORG. I. 207.

Seston, Abydena separat urbe fretum.

OVID. TRIST. I. 9, 28.

Near Abydos, and in a plain among the mountains which rose behind the city, were some gold mines, as we learn from Xenophon, belonging to the Abydeni; the precise spot was called Cremaste. Cremaste. (Hell. IV. 8, 37.) It is probable that these mines are the same as those of Astyra, mentioned by Strabo. (XIII. p. 591.) Astyra had been once an independent and flourishing town, but in the geo-

Græc. tom. I. p. 105; also a dissertation in the Mém. de l'Academie des Belles Lettres, tom. VII. by Mons. de la Nauze.

^k Sestini loc. cit.

grapher's time it was in ruins, and its territory belonged to Abydos. (Cf. Steph. Byz. v. **Αστυρά.*)

South of cape *Nagara*, on which the ancient Abydos stood, a considerable torrent, called *Scultanie* by the Turks, and more commonly known as the river of the *Dardanelles*, empties its waters into the sea opposite to Cynossema, in the Chersonnese.

Rhodius fl. This, according to Strabo, is the Rhodius of Homer. (XIII. p. 595.)

'Ρῆσός θ', 'Επτάπορός τε, Κάρησός τε, 'Ροδίος τε.

IL. M. 20.

But Demetrius of Scepsis supposed the Rhodius to be a rivulet which rose at the back of Ida, and joined the *Aenius*; a tributary stream of the *Aesepus*. (ap. Strab. XIII. p. 603.)

DARDANIA.

We now enter upon that portion of ancient Troas to which the name of Dardania had been attached long before the existence of Troy, from Dardanus, universally acknowledged as the founder of the Trojan dynasty. This celebrated hero, whom fabulous accounts represent as the son of Jupiter and Electra, came, according to some accounts, from Arcadia, according to others, from Italy; but all agree in fixing upon Samothrace as the spot in which he had formed his first principality, before he migrated to the foot of mount Ida. (Apollod. Bibl. III. 12, 1. Strab. Epit. VII. p. 331. Virg. *AEn.* VII. 207.) We may reconcile this variety of opinions respecting the native country of Dardanus, by supposing that he was a chief of that early race, who, under the name of Pelasgi, were so widely dif-

fused, and more especially in those very countries, each of which separately claimed to be the birth-place of the Trojan prince. The epoch of the arrival of Dardanus on the coast of Asia is too remote to be ascertained at present with accuracy¹. Plato, as we learn from Strabo, (XIII. p. 592.) placed his arrival in the second epoch after the universal deluge, when mankind began to leave the summits of the mountains to which fear had driven them, and where they led a barbarous and savage life in caves and grots, like the Cyclopes of Homer. The Athenian philosopher deduced his reasoning from the passage in that poet in which Dardania, the town founded by Dardanus, is stated to have been built, at the foot of Ida.

Δάρδανον αὖ πρῶτον τέκετο νεφεληγερέτα Ζεύς·
Κτίσσε δὲ Δαρδανίην ἐπεὶ οὗπω "Ιλιος ίρη
Ἐν πεδίῳ πεπόλιστο, πόλις μερόπων ἀνθρώπων,
Ἄλλ' εἴθ' ὑπωρείας ὥκεον πολυπιδάκου "Ιδης.

IL. T. 215.

Dardanus, however, was not the first settler in the Trojan plains, since he found the country already occupied by a people whose name of Teucri was derived from that of Teucer, their king. This sovereign gave Dardanus his daughter Batieia in marriage, and ceded to him a part of his territories. (Apollod. Bibl. III. 12, 1. Steph. Byz. v. Ἀρίσβη. Eust. Il. B. 813.)

It is remarkable that Homer has never once mentioned the Teucri, who are so often identified with the Trojans by Virgil, and other Latin poets: but their existence in this part of Asia at a very early period

¹ Homer reckons five generations between Dardanus and

Priam. Il. T. 230. Cf. Apollod. Bibl. III. 12, 3.

is certified by historians of great authority. From Herodotus it appears that they were once a very numerous and powerful people, as he speaks of a great expedition undertaken by them, in conjunction with the Mysi, into Europe, before the Trojan times. (VII. 20. 43.) This is a point of history which appears particularly intricate, and seems to involve the origin of the Teucri in great obscurity. I think it much more probable that the great migration alluded to by Herodotus, and by him only, took place from the great plains around the *Danube*, where the Mysians undoubtedly had their first seat, and with whom the Teucri may have been originally connected. From thence they may have spread themselves into Macedonia and Illyria, while a portion of their wandering hordes may have crossed the Hellespont, and settled in the valleys of mount Ida. The Pæonians, as we learn from Herodotus, gave out that they were descended from the Teucri: now the Pæonian nation appears to have been one of the most ancient and widely spread of all the tribes which were to be found between Greece, properly so called, and the Danube north and south, and the Euxine and Hadriatic west and east; and it is hardly credible that this people, bearing every mark of the highest antiquity, and closely connected with the surrounding Thracian and Illyrian nations, should have owed its origin to an obscure nation occupying a small district on the coast of Asia Minor. It certainly does appear from Homer that the Pæonians of Macedonian Thrace were allied to the Trojans, and that they sent an auxiliary force to the aid of Priam; but it is nowhere said that they were the subjects of that prince. This only tends to shew

that there was a strong affinity between the tribes of Macedonia and Thrace and those of Asia, which may easily be accounted for on the supposition of their common origin. It is a curious circumstance that the Dardani, a very primitive race, apparently of Illyria, (Strab. VII. p. 316.) but who are only known to us in the latter period of the Macedonian history, claimed the sovereignty of Pæonia as their ancient right; (Liv. XLV. 29.) and I am strongly inclined to imagine that the connexion of the Dardanians and Teucrians was not formed in the valleys of Ida and the shores of the Hellespont, but in the plains of the Danube, and the Illyrian and Pæonian Alps. The Teucri probably came first into Asia, as all accounts seem to establish their greater antiquity; (Apollod. Bibl. loc. cit. Diod. Sic. IV. 75.) but they would present us with a most singular anomaly in the history of nations, if they were to be looked upon as of a different race from the Mysians, Phrygians, Bithynians, and other nations, avowedly of Thracian origin, by which they were surrounded. It was from Thrace that the tide of population was then setting very strong towards Greece, Italy, and across the Bosphorus and Hellespont into Asia, and it is very improbable that a counter current should have been formed, such as Herodotus describes, to throw back these Thracian hordes from the shores of the Hellespont and Propontis, to those countries from whence their forefathers had themselves first migrated. Upon the whole it appears probable, that though some such great migration, as Herodotus has recorded, did take place, he was misinformed as to one principal fact, namely, that it did not, as he relates, take place from Asia into Europe, but

vice versa. As the Teucri in his time were known only as an Asiatic people, it is easy to understand how he was led into the mistake, upon hearing that a very extensive migration had been formed by this people in the north of Greece, as far as Illyria and the shores of the Adriatic. When the historian wrote, Gergis, or Gergithæ, was the only city of the Troad which preserved some vestige of the ancient Teucrians. (V. 122.) This primitive appellation had first given way to that of Trojans and Troas, just as the older name of Graii, or Greeks, had been superseded by the more recent denominations of Hellenes and Achivi; and it is somewhat curious, that in both cases the older name should have been more commonly used by the Latins, whilst they were scarcely known to the Greeks.

According to the Homeric topography, the Dardani, who were subject to Anchises, and commanded by his son Æneas during the siege, occupied the small district which lies between the territory of Abydos and the promontory of Rhœteum, beyond which point the Trojan land, properly so called, and the hereditary dominions of Priam, commenced.

Δαρδανίων αὐτ' ἥρχεν, ἐνὶς παῖς Ἀγχίσαο,
Αἰνεῖας· τὸν ὑπ' Ἀγχίσῃ τέκε δῆ 'Αφροδίτη.

IL. B. 819.

Towards the mainland, Dardania extended to the summit of Ida, and beyond that chain to the territory of Zeleia, and the plains watered by the Æsepus on the north, and as far as the territories of Assus and Antandros, Æolian colonies on the Adramyttian gulf, to the south. (Strab. XIII. p. 592. 606.) It was more particularly in this inland district that the descendants of Æneas are said to have

maintained themselves as independent sovereigns after the siege of Troy ; and even during the Persian empire we read in the Hellenics of Xenophon of a Dardanian princess, named Mania, who held under the satrap Pharnabazus a principality possessed by her husband Zenis during his lifetime. On the death of this lady, by the hands of Meidias, her son-in-law, the latter seized on her fortresses and treasures, and usurped the sovereignty ; but by the interference and skilful management of Dercyllidas, the Lacedæmonian general, who then commanded a Greek force on the Hellespont, he was stripped of the possessions he had so unjustly acquired, and reduced to the rank of a private individual. The Greek towns held by Mania were then declared independent. (III. 1.) After this digression on the history of Dardanus and Dardania, we may now resume our description of the coast of the Hellespont from the mouth of the river Rhodius, where we last halted.

South of Abydos, Strabo mentions the promontory Dardanis, or Dardanium, (XIII. p. 587, 595.) which answers to the headland named *Kepoburun* by the Turks, and *Punta dei Barbieri* by the Franks. Pliny speaks of another promontory called Trapeza, between Dardanium and Abydos, eighteen miles from the former, and ten from the latter ; but these numbers are faulty. It is probable that Pliny's cape is the Dardanis of Strabo. Near it was the town of Dardanus, distant from Abydos about seventy stadia. Though of great antiquity, it was not to be identified, as Strabo remarks, with the ancient city founded by Dardanus ; since this, as we collect from Homer, was situated more inland, and at the foot of

Ida. (XIII. p. 592.) By whom the second Dardanus was built is uncertain ; we know, however, that it existed in the time of Herodotus, who mentions its capture by the Persians in the reign of Darius. (V. 117.) In the narrative of Xerxes's march he describes it as close to the sea, and conterminous with Abydos. (VII. 43.) Scylax styles it a Greek town, and places it first in his periplus of the Troad. (p. 35.) Strabo reports that the inhabitants were often compelled to change their abode by the successors of Alexander ; he reports also, that peace was concluded here between Sylla and Mithridates. (XIII. p. 595. Cf. Plut. Syll. c. 24.) Livy states that it had been declared a free city by the Romans after the defeat of Antiochus, in memory of their Trojan origin. (XXXVIII. 39. Cf. XXXVII. 9, 37. Steph. Byz. v. Δάρδανος^m. Plin. V. 32.) The ruins of Dardanus are to be found between *Kepos-Burun* and *Dervend Tchemeh Burun*. The name of *Dardanelles*, which has in the first instance been applied to the Turkish castle erected to defend the passage of the straits, and next to the straits themselves, is confessedly derived from this ancient town.

Ophry-nium.

Pteleos la-cus.

In the vicinity of Dardanus we may notice Ophry-nium, where was a grove, consecrated to Hector, on an eminence, which might be seen from all the surrounding country ; also a little lake, named Pteleos. (Strab. XIII. p. 595. Lycophr. v. 1200.) Ophrynum is mentioned by Herodotus, in his account of the march of Xerxes, (VII. 43.) and by

^m The imperial coins of Dardanus are numerous, from the reign of Augustus to that of Severus. The name of the river

Rhodius appears on a medal of Domna. Sestin. Mon. Vet. p. 76.

Xenophon, who passed through it with the 10,000 on his way from Lampsacus to Pergamus, and offered there a sacrifice of swine. (Anab. VII. 8.) Strabo is the only writer who speaks of the lake, but Steph. Byz. places a town called Pteleos in Troas.

Further south was Rhœteum, situated on a hill, Rhœteum. or promontory, (Orus ap. Steph. Byz. v. 'Ροΐτειον.) whence commences the Trojan bay, and the interesting scenery, so familiar to every one who is acquainted with the poem of Homer. At a little distance from the town, on the sea shore, might be seen the Æanteum, or tomb of Ajax, with a temple and statue erected to the memory of that hero by the Rhodians. (Plin. V. 30. Strab. XIII. p. 595.) Mention of Rhœteum occurs in Herodotus, (VII. 43.) Thucydides, (IV. 52. and VIII. 107.) and several other writers.

. . ἐνύχιοι 'Ροΐτειάδος ἔνδοθεν ἀκτῆς
Μέγρεον, Ἰδαίην ἐπὶ δεξιὰ γαῖαν ἔχοντες.
Δαρδανίην δὲ λιπόντες ἐπιπροσέβαλλον Ἀβύδῳ.

APOLL. RH. I. 929

Teucus Rhœteas primum est advectus in oras.

ÆN. III. 108.

Tunc egomet tumulum Rhœteo in litore inanem
Constitui— ID. VI. 505.

It is generally supposed that the Turkish village of *Et-Ghelme*, where there are some vestiges of antiquity, represents the town of Rhœteumⁿ, and that the Æanteum was at *Intepé*^o. The statue had been removed, and sent to Egypt, with many other

ⁿ There are some few coins extant belonging to this place. Sestini Mon. Vet. p. 76.

^o Pococke's Travels, vol. II. part ii. p. 104. Le Chevalier's

Description of the Plain of Troy, ch. 13. p. 102. Leake's Asia Minor, p. 275. Walpole's Turkey, vol. I. p. 96.

works of art, by Marc Antony; but they were all restored by Augustus to the several places from whence they had been taken. (Strab. XIII. p. 595.)

The interior of Dardania offers yet for our notice some ancient sites to which interesting recollections are attached. The first is Gergis, or Gergitha,
Gergis sive
Gergitha. which we know from Herodotus to have been a remnant of the ancient Teucri, and consequently a town of very great antiquity. (V. 122. VII. 43.) Cephalo, an early historian, who is cited by Dionysius of Halicarnassus, Athenæus, and others, as having written a history of Troy, was a native of this place. (Dion. Hal. Ant. Rom. I. p. 180. Athen. IX. p. 393. Strab. XIII. p. 589. Steph. Byz. vv. Ἀρίσβη, Γραικός.) Gergis, according to Xenophon, was a place of strength, having an acropolis and very lofty walls, and one of the chief towns held by Mania, the Dardanian princess. (Hel. III. 1, 12.) It had a temple sacred to Apollo Gergithius, and was said to have given birth to the sibyl, who is sometimes called Erythræa, from Erythræ, a small place on mount Ida, (Dion. Hal. 1. 55.) and at others Gergithia. In confirmation of this fact it was observed, that the coins of this city had the effigy of the prophetess impressed upon them. (Phlegon, ap. Steph. Byz. v. Γέργυις.^q) It appears from Strabo that Gergitha having been taken by Attalus, king of Pergamus, he removed the inhabitants to the sources of the Caicus, where he founded a new town of the same name. (XIII. p. 616.) The Romans, according to

^q Some of these coins are still extant, and accord with the testimony of Phlegon. They are thus described by numismatic writers: Caput mu-

liebre adversum laureatum cum stola ad collum R. ГЕР. Sphinx alata sedens Æ. 3. Sestini Lett. Numism. t. I. p. 88.

Livy, made over the territory of the old town to the Ilienses. (XXXVIII. 39.) Herodotus, in describing Xerxes' march along the Hellespont, states that he had the town of Dardanus on his left, and Gergitha on his right ; it is evident, therefore, that the latter must have been situated inland, and towards mount Ida. (VII. 43.) The name of Marcæum was particularly applied to that portion of the ridge which overhung Gergitha and its territory. (Steph. Byz. v. Μάρκαιον.)

Palæscepsis, so called to distinguish it from the more recent town simply known by the name of Scepsis, was a city apparently of the highest antiquity, since the latter even dated its origin from the time which immediately succeeded the Trojan war. Demetrius, a native of Scepsis, and who had written largely on the topography of the Troas, considered that city as the capital of Æneas's dominions ; and affirmed it was his son Ascanius, who, together with Scamandrius, the son of Hector, transferred the inhabitants of the old to the site of the new town, distant about sixty stadia from each other. The Dardanian princes long held sway at Scepsis ; but afterwards the government assumed the form of an oligarchy, and finally that of a democracy : the latter event dates from the union of a Milesian colony with the Scepsians ; yet the title of sovereign was still preserved by the descendants of the royal family. (Strab. XIII. p. 607. XIV. p. 635.) Scepsis, as we learn from Xenophon, was the chief city belonging to Mania, the Dardanian princess, already spoken of. After her death it was seized, together with the treasures and stores deposited there, by Meidias, who had married her daughter ; but Der-

cyllidas, having obtained admission into the town for the purpose of holding a conference with Meidias, and sacrificing in the acropolis, expelled him, and gave up the authority to the citizens. (Hell. III. 1.) Under the Macedonian kings, Scepsis underwent several vicissitudes. Antigonus transferred the inhabitants to Alexandria Troas, on account of their wars and disputes with their neighbours the Cebrenians, but Lysimachus restored to them their former abode: subsequently it became subject to the kings of Pergamus. (Strab. XIII. pp. 597. 607.) These did not prevent, however, philosophy and science from flourishing there; and Scepsis especially deserves a place in the annals of literature for the discovery of the books of Aristotle and Theophrastus, which occurred there about the time of Sylla. Strabo, who gives an interesting account of this curious circumstance, relates that Neleus of Scepsis, a disciple of Aristotle, and intimate friend of Theophrastus, having been presented by the latter with his own books, and those he had inherited from their great common master, brought them from Greece to his native town. On his death, this valuable collection came into the possession of his relations, who being illiterate persons, and unacquainted with their real worth, suffered the MSS. to remain heaped together, without any care being taken to preserve them. But what was still more to be lamented, on hearing that the king of Pergamus was busily employed in searching for rare and curious books, to add to his library, they immediately buried the MSS. of Neleus in a deep pit, where they of course sustained serious injury from damp and worms. At length, however, they were

rescued from this state, and sold to an amateur, named Apellicon, of Teos, for a considerable sum of money. This person endeavoured to supply the *lacunæ*, and make corrections; but being incompetent to execute such an undertaking, he published copies which abounded in errors. After the death of Apellicon, Sylla took possession of his books, and caused them to be removed to Rome. (XIII. p. 608.) Besides Demetrius, a distinguished writer and commentator on Homer, who is often quoted by Strabo and Athenæus, Scepsis gave birth to Metrodorus, who published also several works, and was high in favour with Mithridates, being employed by that prince in various public functions and important commissions. (Strab. loc. cit. Plut. Lucull. c. 22.) Scylax has erroneously ranked Scepsis among the maritime cities of Troas. (Peripl. p. 35.) It is evident, from Strabo and Demosthenes, (Contr. Aristocr. p. 671, 9.) that it stood at some distance from the coast. From the former it appears that Palæscepsis was situated near the source of the Æsepus, and the highest part of mount Ida and Scepsis about sixty stadia lower down. (XIII. p. 607.) In Pliny's time there existed no longer any vestige of the former; (V. 30.) but the latter is mentioned by Hierocles, (Synecd. p. 664.) and the ecclesiastical notices of bishoprics^r. According to Mannert, it still retains the name of *Eskiupschi*^s. Around Palæscepsis were several places, for the knowledge of which we are indebted to the researches of De-

^r Geogr. Sacr. p. 239. The autonomous coins have the epigraph ΣΚΗΨΙΩΝ and ΣΚΑΨΙΩΝ, sometimes with ΔΑΡΔ. for ΔΑΡΔΑΝΙΩΝ: this is more

frequently the case in the imperial money. Sestin. Mon. Vet. p. 77.

^s Geogr. tom. VI. part. iii. p. 471.

metrius the Scepsian, to illustrate the topography of the Iliad. Strabo, who has communicated them to us, places, in the upper valley of the Æsepus, Polichna, then Palæscepsis and Halizonium; the latter he supposes to be an imaginary city, brought there solely for the purpose of accounting for the Halizones, reckoned by Homer among the allies of Priam. (Il. B. 856.) Polichna is acknowledged by Steph. Byz. as a town of Troas, (v. Πολίχνα,) and also by Pliny; (V. 32.) but it must not be confounded, as some critics have done, with the Polichna mentioned by Thucydides. (VIII. 14. 23.) Beyond these the Æsepus received the waters of Caresus fl. the Caresus, which gave its name to a small town, and a rich and populous valley through which it flowed. This stream derived further celebrity from being recorded by Homer.

'Πῆσός θ', 'Ἐπτάπορός τε, Κάρησός τε, 'Ροδίος τε.

IL. M. 20.

Caresene
regio.
Caresus
urbs.

Mallus.

Ænea sive
Nea-Come.

The district of Caresus was conterminous to the territory of Zeleia; but the town was in ruins and deserted in the time of Demetrius of Scepsis, whose words to that effect are cited by Strabo. (XIII. p. 602.) It is probable, however, that the Carseæ, of which Polybius has made mention in the expedition of Attalus into Mysia, (V. 77.) is no other than the town in question. The Caresus, according to the same writer, had its source near Mallus, or Malus, a spot situated between Palæscepsis and Achæum; the latter place was opposite to the island of Tenedos. On the right bank of the Æsepus, and between Polichna and Palæscepsis, Demetrius placed Ænea, or Nea-Come, at the distance of fifty stadia from the latter site. Pliny reports, that the rain

was never observed to fall round the image of Minerva preserved in this town. (II. 96. Steph. Byz. v. Νέα.) I think it probable that the name of Aenea was first given to it in honour of Aeneas, but that it was afterwards corrupted to Nea. It has been supposed by some travellers, that the Turkish village called *Ené* occupies this ancient site; but this is too far from the Aesepus, and answers better to Neandria^t. In the vicinity of Nea were some silver mines, which in the system of Demetrius corresponded with the Alybe of Homer. (ap. Strab. XII. p. 551. XIII. p. 603.) These mines were observed by Pococke at *Eskupi*^u. It is uncertain whether the Aenius, a small river named by Strabo, without Aenius a. any indication of its course, should be connected with the Aenea or Nea of the same geographer. (XIII. p. 603.) D'Anville seems to have been of this opinion, since in his map of the country around Troy he supposes it to fall into the Aesepus.

TROJA, ET TROJANUS AGER.

I must now turn to the topography of Troy itself; a subject which will always be interesting to the classical reader, but which has been so much discussed and minutely inquired into by modern travellers and antiquaries, that no additional light can be expected to be derived from subsequent researches. To bring together all that has been said on this point by the ancients as well as the moderns, would be to form a very voluminous work in it-

^t Le Chevalier, Voyage dans la Troade, p. iii. c. 3. Chandler's Travels in Asia Minor, ch. 12. and Inscr. Ant. p. 4. Choi-

seul Gouffier supposes it to be Neandria.

^u Tom. II. part iii. p. 107.

self; and as many of the latter have only repeated what their antecessors have stated before them, and most of them agree in all the principal and material points, I shall better consult the reader's convenience by presenting him with a brief summary of what I have collected from the different authors who have expressly written on the subject; referring at the same time the student, who is desirous of investigating it more deeply, to the works enumerated at the bottom of the page^x.

This, the most classical of all lands, has been so completely trodden and examined, that it may be truly said that the ancient writers who wrote on the subject were much less acquainted with the actual topography of the Trojan plain, than our best informed modern travellers. The researches of these intelligent men have not only confirmed the great historical facts connected with the fate of Troy, which few persons indeed either in ancient or modern times have ventured to question, and those evidently for the purpose of maintaining a paradox; but they have served beautifully to illustrate the noblest poem of antiquity, and to bear witness, with due allowance for poetical exaggeration, to the truth and accuracy of Homer's local descriptions.

^x A Comparative View of the ancient and present State of the Troad, by Rob. Wood; subjoined to the essay on the Genius and Writings of Homer. Description of the Plain of Troy, by M. Chevalier, Edinburgh, 4to. 1791. Le Chevalier, Voyage dans la Troade, Paris, 8vo. 1802. Observations on the Topography of the plain of Troy, by James Rennell,

Lond. 1814. 4to. Chandler's History of Ilium, or Troy, Lond. 1802. 4to. Voyage Pittoresque de la Grece, par Choisel Gouffier, tom. II. Gell's Topography of Troy, fol. Lond. 1804. Dr. Clarke's Travels, tom. III. Col. Leake's Geogr. of Asia Minor, ch. 6., and some memoirs in Walpole's Turkey, vol. I.

They have proved, that as in every other point he was the most close and happy delineator of nature, so here he has still copied her most faithfully, and has taken his descriptions from scenes actually existing, and which must have been familiar to his eyes. In order that this may be proved to the reader's satisfaction as far as it is possible, without an actual inspection of the country, I purpose first to lay before him all the general and most striking features in the Homeric chorography, and then to illustrate them by a continued reference to modern travellers and antiquarians. It will be seen then from the Iliad that the Greeks, having arrived on the coast of the Hellespont, and effected a landing, drew up their vessels in several rows on the shore of a small bay confined between two promontories.

Πολλὸν γάρ δ' ἀπάνευθε μάχης εἰρύατο νῆσος
 Θῖν' ἐφ' ἄλὸς πολιῆς· τὰς γὰρ πρώτας πεδίονδε
 Εἴρυσαν, αὐτὰρ τεῖχος ἐπὶ πρύμνησιν ἔδειμαν.
 Οὐδὲ γάρ οὔδ', εύρύς περ ἐὰν, ἐδυνήσατο πάσας
 Αἰγιαλὸς νῆσος χαδέειν· στείνοντο δὲ λαοί.
 Τῷ δὲ προχρόσσας ἔρυσαν, καὶ πλῆσαν ἀπάσης
 Ἡιόνος στόμα μακρὸν, ὃσον συνεέργασθον ἄκραι.

IL. E. 30.

Elsewhere he states, that Achilles was posted at one extremity of the line, and Ajax at the other. (Θ. 224. Λ. 7.) He nowhere names the two promontories which enclosed the bay and the armament of the Greeks: but all writers, both ancient and modern, agree in the supposition that these are the capes Rhœteum and Sigeum, between which tradition attached to different spots the names of Nau-stathmus, the port of the Greeks, and the camp of

the Greeks. (Strab. XIII. p. 595.) According to Pliny, the distance from headland to headland was thirty stadia. (V. 33.) Strabo reckoned sixty stadia from Rhœteum to Sigeum, and the tomb of Achilles close to the latter; (*loc. cit.*^y) and these distances agree sufficiently well with actual measurements^z. Considerable changes, however, have taken place during the lapse of so many ages in the appearance of the coast. The promontories remain; but the bay has been completely filled up by the deposit of rivers and the accumulation of sand and soil, and the shore now presents scarcely any indenture between the headlands: but we are assured by Choisel Gouffier, and others, who have explored the ground, that there is satisfactory proof of the sea having advanced formerly some way into the land in this direction^a. The next great feature to be examined in the Homeric topography, is the poet's account of the rivers which flowed in the vicinity of Troy, and discharged their waters into the Hellespont. These are the Xanthus, or Scamander, and the Simois, whose junction is expressly alluded to. (Il. E. 774.)

'Αλλ' ὅτε δὴ Τροίην Ιἴον, ποταμώ τε ρέοντε,
 'Ηχι ρόας Σιμόεις συμβάλλετον ἡδὲ Σχάμανδρος,
 'Ενθ' ἵππους ἔστησε θεὰ λευκώλευος" Ήρη.

^y Le Chevalier was not correct in charging Strabo with inaccuracy in his statement of this distance. He supposes that Strabo spoke of cape Rhœteum, whereas he, no doubt, meant the town, which is some way from it.

^z Note to the French Strabo, tom. IV. p. 170.

^a Voyage Pittoresque, tom. II. p. 216. Col. Leake's Sketch to explain the supposed alteration in the coast and rivers of Troy. Asia Minor, p. 273.

And again, (Z. 2.) where it is said, that the conflict between the Greeks and Trojans took place in the plain between the two rivers.

Πολλὰ δὲ ἄρ' ἔνθα καὶ ἔνθ' θύεται μάχη πεδίοιο,
Ἄλλήλων θυνομένων χαλκῆρα δοῦρα,
Μεσσηγὸς Σιμόεντος, οὐδὲ Ξάνθοιο βοάων.

One of the first questions then to be considered, in reconciling the topography of ancient Troy with the existing state of the country, is this: Are there two streams answering to Homer's description, which unite in a plain at a short distance from the sea, and fall into it between the Rhœtean and Sigean promontories? To this question it certainly appears, from recent observations, that we must reply in the negative. There are two streams which water the plain, supposed to be that of Troy, but they do not meet, except in some marshes formed principally by the *Mendere*, the larger of the two, which seems to have no exit into the Hellespont; while the smaller river partly flows into these stagnant pools, and partly into the sea near the Sigean cape^b. It appears, however, from Strabo, or rather from Demetrius, whom he quotes, that when he wrote, the junction did take place; for he says, “The Scamander and Simois advance, the one towards Sigeum, the other towards Rhœteum, and after uniting their streams a little above New Ilium, fall into the sea near Sigeum, where they form what is called the Stomalimne.” (XIII. p. 597. Cf. p. 595.) Pliny also, when he speaks of the Palæscamander, evidently leads to the notion that the channel of that river had undergone a material alteration.

^b Choiseul Gouffier.

(V.32.) The observations of travellers afford likewise evidence of great changes having taken place in regard to the course of these streams; and it is said that the ancient common channel is yet to be traced under the name of *Mendere*, near the point of *Kum-kale*. The ancients themselves were aware of considerable alterations having taken place along the whole line of coast; for Histiæa, of Alexandria Troas, a lady who had written much on the Iliad, affirmed, that the whole distance between New Ilium and the sea, which Strabo estimates at twelve stadia, had been formed by alluvial deposit; (XIII. p. 598.) and recent researches prove that this distance is now nearly double^c. The great question, however, after all, respecting the two rivers alluded to, and on which the whole inquiry may be said to turn, is, which is the Scamander and which the Simois of Homer? If we refer for the solution of this question to Demetrius of Scepsis, who, from his knowledge of the Trojan district, appears to have been best qualified to decide upon it, we shall find, that he looked upon the river now called *Mendere* as corresponding with the Scamander of Homer, a supposition which certainly derives support from the similarity of the two names; while he considered the Simois to be the stream now called *Giumbrek-sou*, which unites with the *Mendere* near the site of *Paleo Aktshi*, supposed to represent the Pagus Iliensium, and which Demetrius himself identified with ancient Troy. But it has been rightly observed by those modern writers who have bestowed their attention on the subject, that the simi-

^c Col. Leake's Asia Minor, ch. vi. p. 295.

larity of names is not a convincing reason in itself, since they have often been known to vary; and that after all we must refer to the original account, where we find the characteristics of the two rivers described in a manner which must eventually settle the whole question, as far as regards their identity. A reference to the Iliad itself is the more necessary, as Demetrius does not appear to have satisfactorily explained, even to himself, certain doubts and difficulties which naturally arose from comparing his system of topography with that suggested by the perusal of the poet. Now it appears from more than one passage that the Simois, according to Homer, had its source in mount Ida;

"Ενθ' ἔβαλ' Ἀνθεμίωνος υἱὸν Τελαμώνιος Αἴας
 'Ηίθεον θαλερὸν, Σιμοείσιον· ὃν ποτε μῆτηρ
 "Ιδηθεν χατιοῦσα παρ' ὄχθησιν Σιμόεντος
 Γείνατ', ἐπεὶ ρά τοκεῦσιν ἄμ' ἐσπετο μῆλα ιδέσθαι.

IL. Δ. 475.

Δὴ τότε μητιόσαντο Ποσειδάων καὶ Ἀπόλλων
 Τεῖχος ἀμαλδῦναι, ποταμῶν μένος εἰσαγάγοντες,
 "Οσσοι ἀπ' Ἰδαίων δρέων ἄλαδε προρέουσι,
 'Ρῆσός θ', 'Ἐπτάπορος τε, Κάρησός τε, 'Ροδίος τε,
 Γρήνικός τε, καὶ Αἴσηπος, διός τε Σχάμανδρος,
 Καὶ Σιμόεις, ὃθι πολλὰ βιάγρια καὶ τρυφάλειαι
 Κάππεσον ἐν κονίησι, καὶ ἡμιθέων γένος ἀνδρῶν.

IL. M. 22.

and though in the latter passage the same thing is affirmed of the Scamander, it will be seen elsewhere, that the sources of that river are so plainly described as situated close to the city of Troy, that they never could be said to rise in the main chain, unless Troy itself was placed there likewise. When speaking of the pursuit of Hector by Achilles beneath its walls, he says,

τρέσε δ' Ἐκτωρ
 Τεῖχος ὑπὸ Τρώων, λαιψηρὰ δὲ γούνατ' ἐνώμα.
 Οἱ δὲ παρὰ σκοπιὴν καὶ ἔρινεὸν ἡνεμόεντα
 Τείχεος αἰὲν ὑπ' ἐκ κατ' ἀμαξιτὸν ἐστεύοντο·
 Κρουνὼ δ' ἵκανον καλλιρρόω, ἐνθα δὲ πηγαὶ
 Δοιαὶ ἀνατσσουσι Σχαμάνδρου δινήεντος.
 'Η μὲν γάρ θ' ὕδατι λιαρῷ δέει, ἀμφὶ δὲ καπνὸς
 Γίνεται ἐξ αὐτῆς, ώσεὶ πυρὸς αὐθομένοιο·
 'Η δ' ἄτέρη θέρεϊ προρέει εἰκυῖα χαλάζη,
 'Η χιόνι ψυχρῆ, ἡ ἐξ ὕδατος κρυστάλλῳ.
 'Ενθα δ' ἐπ' αὐτάων πλυνοὶ εύρεται ἐγγὺς ἔασι
 Καλοὶ, λαῖνεοι, ὅθι εἴματα σιγαλόεντα
 Πλύνεσκον Τρώων ἄλοχοι, καλαί τε θύγατρες,
 Τὸ πρὸν ἐπ' εἰρήνης, πρὸν ἐλθεῖν υἱας Ἀχαιῶν.

IL. X. 143.

These marks, which point out the double sources of the Scamander, are so peculiar and so striking, that the discovery of them would, it seems, be decisive of the question, not only as far as regards the Trojan rivers, but also, in all probability, as to the situation of Troy itself, which, according to the poet, must have stood in the immediate vicinity of the sources. It is in tracing this remarkable and most distinguishing feature of the Homeric description, that modern research and industry have been particularly conspicuous, and have enabled us to solve a question, which the ancients, from their want of similar information, could never understand. It is to Mons. Choiseul Gouffier that the merit of first discovering the springs of the Scamander undoubtedly belongs; and though the phenomena of heat and cold, described by Homer, have not been so convincingly observed by subsequent travellers as by himself, yet, by taking the positive testimony of the natives themselves, who repeatedly corroborated

the statement made by the poet, as well as the several experiments made by M. Choiseul Gouffier, and subsequently by Mons. Dubois^d, we cannot refuse to acknowledge at least that there is very sufficient foundation for the poetical picture formed of the spot by Homer. M. Choiseul describes the hot source “as one abundant stream, which gushes out “from different chinks and apertures, formed in “an ancient structure of stone work. About 400 “yards higher up are to be seen some more springs, “which fall together into a square stone basin, “supported by some long blocks of granite. These “limpid rills, after traversing a charming little “wood, unite with the first sources, and together “form the Scamander^e.” The latter, which are the cold springs of Homer, are called *Kirk Guexler*, or the *Forty Fountains*, by the Turks^f. If we besides look to the general features which ought to belong to the Scamander and the Simois of Homer, we shall find that the former agrees remarkably with the beautiful little river of *Bounarbach*, which is formed by the sources above mentioned, while the rapid Simois finds a fit representative in the impetuous *Mendere-sou*, which descends from the summits of Gargara, and fills its bed with trees torn from their roots, and huge fragments of rock. The former is described as a copious, rapid, and clear stream, whose banks are spread with flowers, and shaded with various sorts of trees.

Ἄλλ' ὅτε δὴ πόρον ἱξον εὑρέειος ποταμοῖο
Ξάνθου διηγεῖτος, ὃν ἀθάνατος τέχετο Ζεύς. IL. Φ. 1.

^d Voyage Pittoresque, p. 267,
268. Col. Leake's Asia Minor,
ch. vi. p. 283.

^e Voyage Pittoresque, p. 228.
^f Ibid. p. 268.

. ἀλλὰ Σχάμανδρος
Οἵσει δινήεις εἴσω ἀλὸς εύρεα κόλπου.

IL. Φ. 124.

"Εσταν δ' ἐν λειμῶνι Σχαμανδρίῳ ἀνθεμόεντι
Μυρίοι.

IL. B. 467.

Καίοντο πτελέαι τε, καὶ ἵτεαι, ἡδὲ μυρῖκαι,
Καίετο δὲ λωτός τ', ἡδὲ θρύον, ἡδὲ χύπειρον,
Τὰ περὶ καλὰ ρέεθρα ἄλις ποταμοῖο πεφύκει.

IL. Φ. 350.

According to Mr. Chevalier, the river of *Bounarbachî* "is never subject to any increase or diminution ; its waters are as pure and pellucid as crystal ; its borders are covered with flowers ; the same sort of trees and plants which grew near it when it was attacked by Vulcan, grow there still ; willows, lote-trees, ash-trees, and reeds, are yet to be seen on its banks, and eels are still caught in itg." It was doubtless on account of the beauty and copiousness of its stream that divine honours were paid to the Scamander by the Trojans. (Il. E. 77. Cf. Aeschin. Epist. X. p. 680.)

The Simois, on the contrary, bears all the marks of a mighty torrent, rushing down from the mountains with furious haste and resistless force. This is evident from the address of the Scamander to his brother god, invoking his aid against Achilles ;

Φίλε κασίγνητε, σθένος ἀνέρος ἀμφότεροί περ
Σχῶμεν, ἐπεὶ τάχα ἀστυ μέγα Ποιάμοιο ἄνακτος
'Εχπέρσει, Τρῶες δὲ κατὰ μόθον οὐ μενέουσιν.
'Αλλ' ἐπάμυνε τάχιστα, καὶ ἐμπίπληθι ρέεθρα
"Τδατος ἐκ πηγέων, πάντας δ' ὀρόθυνον ἐναύλους.

^g Description of the Plain of Troy, p. 83. See also Voyage Pittoresque, tom. II. p. 228.

"Ιστη δὲ μέγα κῦμα· πολὺν δὲ ὀρυμαγδὸν ὄρινε
Φιτρῶν καὶ λάσων, οὐα παισομεν ἄγριον ἄνδρα.

IL. Φ. 308.

and all modern travellers and topographers concur in allowing that this is precisely the character of the *Mendere*, which takes its rise in a deep cave below the highest summit of mount Ida, and, after a tortuous course between steep and craggy banks, of nearly thirty miles, in a rugged bed, which is nearly dry in summer, finds its way into the plain of *Bounarbachi*. It is true, that when Demetrius of Scepsis wrote, which is some years after the defeat of Antiochus by the Romans, (Strab. XIII. p. 593.) the *Mendere* certainly bore the name of Scamander, for he describes the source of that river in mount Ida very accurately, (ap. Strab. XIII. p. 602.) I should admit also, that the Scamander, which, according to Herodotus, was drained by the army of Xerxes, (VII. 42.) is the *Mendere*: Hellanicus likewise was of this opinion, (ap. Schol. Il. Φ. 242.) But this objection may be fairly disposed of, by supposing, that the name of Scamander, which is certainly much oftener mentioned in Homer, had in process of time been transferred to the river whose course was longer, and body of water more considerable; whereas it is impossible, I conceive, to get over the difficulty presented by Homer's description of the double sources of the Scamander. The question may be fairly summed up in this way: either we must allow that Homer drew his local descriptions from real scenes, or that he only applied historical names to fanciful and ideal localities; in the latter case, all our interest in the comparative topography of Troy ceases, and it is a fruitless task to look for

an application of the imagery traced by the poet to the actual face of things. But if a striking resemblance does present itself, we are bound, in justice to the poet, to take our stand on that ground, and, without regarding any hypothesis or system which may have been advanced or framed in ancient times, to seek for an application of the remaining local features traced in the Iliad in the immediate vicinity of the sources of *Bounarbachî*. Here then travellers have observed, a little above these springs and the village of the same name, a hill rising from the plain, generally well calculated for the site of a large town, and in particular satisfying many of the local requisites which the Homeric Troy must have possessed; such as a sufficient distance from the sea, and an elevated and commanding situation. This is evident from the epithets of ἡγεμόνεσσα, αἰπεινὴ, and ὁφρύονεσσα, which are so constantly applied to it. If we besides have a rock behind the town, answering the purpose of such a citadel as the Pergamus of Troy is described to have been, “Πέργα-“ μος ἄκρη,” rising precipitously above the city, and presenting a situation of great strength, we shall have all that the nature of the poem, even in its historical character, ought to lead us to expect^h. With respect to minor objects alluded to by Homer in the course of his poem, such as the tombs or mounds of Illus, Æsyetes, and Myrina, the Scopie and Erineus, or grove of wild fig-trees, it is perhaps too much to seek to identify them, as the French topographers have somewhat fancifully

^h For a detailed description of the heights of *Bounarbachî*, I would refer the reader to the

Voyage Pittoresque, tom II. p. 238, where an accurate plan is given.

done, with present appearancesⁱ. It is certain that such indications cannot be relied upon, since the inhabitants of New Ilium, who also pretended that their town stood on the site of ancient Troy, boasted that they could shew, close to their walls, these dubious vestiges of antiquity. (Strab. XIII. p. 599.) With respect to the objection which may be brought against the situation here assigned to ancient Troy, that it would not have been possible for the flight of Hector to have taken place round the walls, as the poet has represented it, since the heights of *Bounarbachî* are skirted to the N. E. by the deep and narrow gorge of the *Mendere*, which leaves no room even for a narrow footpath along its banks ; I agree with those commentators and critics who are of opinion that we ought not to take the words of the poet in the sense which has commonly been assigned to them, but that it is better to suppose, that Hector and Achilles ran only round that portion of the city which fronts the plain from the Scæan gates to the sources of the Scamander, and back again^k. The difficulty in that case will be satisfactorily removed, and there will then remain, I conceive, no valid objection to the system which recognises the hill of *Bounarbachî* as the representative of the ancient city of Priam, and which has been almost universally embraced by modern travellers and scholars.

There remain only two or three sites to be noticed, in order to complete this short view of the

ⁱ I allude to Messrs. Choiseul Gouffier and Le Chevalier.

^k Choiseul Gouffier, Voyage Pittoresque, tom. II. p. 238—

240; Le Chevalier's Description of the Plain of Troy, p. 135; Leake's Asia Minor, ch. vi. p. 304.

Homerical topography of the plain of Troy. The hill called Throsmos by the poet, and which was a favourite station of the Trojan army in advance of their city towards the Grecian camp, is supposed to correspond with some rising ground on the left bank of the Scamander. That of Callicolone, on the other hand, where Mars took his stand, for the purpose of encouraging the Trojan troops, was near the Simois, and towards the left of the Greek encampment.

Ἄντις δ' Ἀρης ἐτέρωθεν, ἀρεμνῆ λαίλαπι ίσος,
 'Οξὺ κατ' ἀκροτάτης πόλιος Τρώεσσι κελεύων,
 'Αλλοτε πὰρ Σιμόεντι θέων ἐπὶ Καλλιχολώνῃ. IL. Τ. 51.

According to Strabo, who probably copies Demetrius, Callicolone was ten stadia from the Pagus Iliensium, and five from the Simois. From whence it appears to answer to a hill near the site called *Eski Aktchi-kevi*; (XIII. p. 597.) but, as this arrangement is entirely deduced from the hypothesis which Demetrius had adopted with respect to the Simois and Scamander, it has not been adhered to by modern critics, who place Callicolone on the left bank of the *Mendere* or Simois; some opposite to the heights of *Bounarbach*, others nearer the sea. Demetrius, in placing ancient Troy on the site of the Pagus Iliensium, said to have been built by Ilus, (Strab. XIII. p. 593.) was obliged to seek for a representative of the Simois in one of those small streams which, flowing from east to west, fall into the *Mendere* on the right bank of that river. And if we fix the Pagus of Demetrius at *Eski Aktchi-kevi*, as most modern critics have done, his Simois will be the *Kamar-sou*, the most considerable of the streams alluded to, and which joins the *Mendere*

Pagus Ili-
ensium.

about three miles below *Bounarbachı*: the plain situated between the two rivers would also seem to be the Simoisius campus of the same ancient writer. But according to the modern system, the *Kamarasou* is the river Thymbrius, and the plain that of Thymbra, alluded to by Homer, in the account of Thymbra. the Trojan forces, and their different positions, supposed to be disclosed by Dolon :

Πρὸς Θύμβρης δὲ ἔλαχον Λύκιοι, Μυσοὶ τὸν ἀγέρωχον,
Καὶ Φρύγες ἵπποδάμοι, καὶ Μήονες ἵπποχορυσταί.

IL. K. 430.

There is another river, however, which now falls into the Hellespont, near the tomb of Ajax, but which appears formerly to have joined the *Mendere*, and, from the name of *Tumbrek*, which it bears, may be thought to have a better claim to be considered as the Thymbrius of Strabo, though not that of Homer; for it must not be forgotten, that in the geographer's time the inhabitants of New Ilium had confounded all the Homeric topography by adapting the names of places mentioned in the Iliad to the localities of their own district and city. Apollo had a temple at Thymbra, as we further learn from Strabo, which accounts for the epithet of Thymbræus applied to that god by Virgil :

Da propriam, Thymbræe, domum : da moenia fassis.

ÆN. III. 85.

and before him by the author of Rhesus, v. 224.

Θυμβαῖς καὶ Δάλις, καὶ Λυκίας
Ναὸν ἐμβατεύων
Ἄπολλον.

It was in this temple that Achilles is said to have been mortally wounded by Paris. (Eustath. ad

Il. K. 433. Serv. ad AEn. loc. cit. Steph. Byz. v. Θύμηβρα.)

Ilium No-
vum.

Whatever traces might remain of the ruins of the city of Priam, after it had been sacked and burnt by the Greeks, these soon disappeared, as Strabo assures us, by their being employed in the construction of Sigeum, and other towns founded by the Æolians, who came from Lesbos, and occupied nearly the whole of Troas. On their arrival in that country, they had found it possessed by the Treres, a barbarian tribe of Thracian origin, who are supposed to have come into Asia with the Cimmerians. (XIII. p. 599. XII. p. 573.) The first attempt to restore the town of Troy was made by some Astypalæans, who, having first settled at Rhœteum, built, near the Simois, a town they called Polium, but which subsisted only a short time; the spot, however, still retained the name of Polisma when Strabo wrote. Some time after, a more advantageous site was selected in the neighbourhood, and a town, consisting at first of a few habitations and a temple, was built under the protection of the kings of Lydia, the then sovereigns of the country. This became a rising place; and in order to ensure the prosperity of the colony, and to enhance its celebrity, the inhabitants boldly affirmed that their town actually stood on the site of ancient Troy, that city having never been actually destroyed by the Greeks. There were not wanting writers who propagated this falsehood, in order to flatter the vanity of the citizens, (Strab. XIII. p. 601.) and when Xerxes passed through Troas, on his way to the Hellespont, the pretensions of New Ilium were so firmly established, that the Persian monarch, when he visited their acro-

polis, and offered there an immense sacrifice to Minerva, actually thought that he had seen and honoured the far-famed city of Priam. (Herod. VII. 42.) In the treaty made with the successor of Xerxes, Ilium was recognised as a Greek city, and its independence was secured ; but the peace of Antalcidas restored it again to Persia. Some years after, it was momentarily in the hands of Charidemus, a Greek partisan, at the head of some mercenary troops hired by Artabazus, satrap of the Hellespont, to defend himself against the attack of Autophradates, governor of Lydia. Charidemus obtained possession of the town and citadel by a stratagem, but being besieged by the forces of the victorious Autophradates was unable to hold out, and obtained permission to withdraw. (Demosth. in Aristocr. p. 671. *Aen. Tact.* c. 24. *Polyæn. Stratag.* III. 14.)

On the arrival of Alexander in Asia Minor, (Arrian. *Exp. Alex.* I. 11, 12,) or, as some say, after the battle of the Granicus, (Strab. XIII. p. 593.) that prince visited Ilium, and after offering a sacrifice to Minerva in the citadel, deposited his arms there, and received others, said to have been preserved in the temple from the time of the siege of Troy. He further granted several rights and privileges to the Ilienses, and promised to erect a more splendid edifice, and to institute games in honour of Minerva ; but death prevented the execution of these designs. (Arrian. loc. cit. Strab. loc. cit. Diod. Sic. XVIII. p. 589.) Lysimachus, however, to whose share Troas fell on the division of Alexander's empire, undertook to execute what had been planned

by the deceased monarch. He enclosed the city within a wall, which was forty stadia in circumference; he also increased the population by removing thither the inhabitants of several neighbouring towns. (Strab. XIII. p. 593.) At a subsequent period Ilium further experienced the favour and protection of the kings of Pergamus; and the Romans, on achieving the conquest of Asia Minor, sought to extend their popularity by securing the independence of a city from which they pretended to derive their origin, and added to its territory the towns of Rhœteum and Gergitha. (Liv. XXXVII. 37. XXXVIII. 39.) And yet it would appear, that at that time Ilium was far from being a flourishing city, since Demetrius of Scepsis, who visited it about the same period, affirmed that it was in a ruinous state, many of the houses having fallen into decay for want of tiling. (ap. Strab. loc. cit.) During the civil wars between Sylla and Cinna, Ilium was besieged and taken by assault by Fimbria, a partisan of the latter. This general gave it up to plunder, butchered the inhabitants, and finally destroyed it by fire. Not long after, however, Sylla arrived in Asia, and having defeated Fimbria, who fell by his own hand, restored Ilium to the surviving inhabitants, reinstated them in their possessions, and restored the walls and public edifices. (Appian. Bell. Mithr. c. 53. Plut. Vit. Syll. Strab. XIII. p. 594.) The Ilienses received Lucullus in their city when that general had compelled Mithridates to raise the siege of Cyzicus, and paid him distinguished honours. (Plut. Vit. Lucull.) After the battle of Pharsalus, Ilium was visited by Julius Cæsar, who

explored, if we may believe Lucan, all the monuments and localities which claimed any interest from their connexion with the poem of Homer.

Sigeasque petit, famæ mirator, arenas,
 Et Simoëntis aquas, et Graio nobile busto
 Rhœtion, et multum debentes vatibus umbras.
 Circuit exustæ nomen memorabile Trojæ,
 Magnaque Phœbei quærit vestigia muri.
 Jam silvæ steriles, et putres robore truncæ
 Assaraci pressêre domos, et templa deorum
 Jam lassâ radice tenent: ac tota teguntur
 Pergama dumetis: et jam periœre ruinæ:
 Adspicit Hesiones scopulos, silvasque, latentes
 Anchisæ thalamos; quo judex sederit antro;
 Unde puer raptus cœlo; quo vertice Naïs
 Luxerit Ænone: nullum est sine nomine saxum.
 Inscius in sicco serpentem pulvere rivum
 Transierat, qui Xanthus erat: securus in alto
 Gramine ponebat gressus; Phryx incola manes
 Hectoreos calcare vetat. Discussa jacebant
 Saxa, nec ullius faciem servantia sacri;
 Herceas, monstrator ait, non respicis aras?

PHARS. IX. 961.

Cæsar, in consequence of this visit, and his pretended descent from Iulus, conceded fresh grants to the Ilienses, and added Sigeum, Dardanus, and other towns, to their territory; he likewise instituted those games which Virgil has alluded to in the *Aeneid*, and which the Romans called “Ludi Tro-“jani.” (*Æn.* V. 602. *Suet.* Cæs. 39. *Dio.* Cass. XLIII. 23.) We hear of the Ilienses having been fined by Agrippa for not paying proper respect to Julia, when that princess visited their city; but the fine was remitted, owing to the intercession of Herod, king of Judæa. (*Nicol. Damasc. Exc.* p. 418.) We

further trace the history of Ilium through the reign of Tiberius, when it was visited by Germanicus, but refused permission to erect a temple to the emperor. (Tacit. Ann. II. 54. IV. 55.) It preserved its privileges and freedom under Trajan, as we learn from Pliny, who styles it, “Ilium immune, unde “omnis claritas.” (V. 30.) It subsisted under Diocletian, and it is even said that Constantine had entertained serious thoughts of transferring thither the seat of empire. (Sozom. Hist. Eccl. II. 3. Zosim. II. 34.) The last records we have of its existence are derived from Hierocles, (Synecd. p. 663.) the Itineraries, and the Notices of Greek bishops under the Byzantine empire. It became afterwards exposed to the ravages of the Saracens, and other barbarians, who depopulated the Hellespont and Troad: it sunk beneath their repeated attacks, and became a heap of ruins. The surrounding villages are yet filled with inscriptions, and fragments of buildings and monuments, which attest its former splendour and magnificence. According to the account of a modern traveller, who has minutely explored the whole of Troas, New Ilium occupied a gently rising hill about seventy feet high, above the adjacent plain, in which the waters of the *Tumbrek-tchai* and *Kamar-sou* form some marshes. On the south side are to be seen the foundations of the acropolis, and the lines of the walls may be traced along the whole of their circuit, though the Turks have removed the stones to construct their habitations. They call the site *Hissardjick*, or *Eski Kalafatli*¹.

¹ Choiseul Gouffier, tom. II. part iii. p. 381. Barker Webb, Osservazioni intorno l'Agro Trojano Bibl. Ital. No. 67. Luglio, 1821.

New Ilium was twenty-one miles from Abydos, or 170 stadia, (Strab. XIII. p. 591.) and about eleven miles from Dardanus. (Itiner. Anton. p. 334.) According to Strabo, New Ilium was not more than twelve stadia from the Portus Achæorum, and twenty from the mouth of the Scamander. (XIII. p. 598.) Pliny reckons a mile and a half. (V. 30.) It is uncertain where we should place the small town of Scamandria, mentioned by the latter author, and also by Hierocles, who calls it Σκάμανδρος. (Synecd. p. 663.) An inscription has been discovered, recording a treaty for the sale of corn between the Ilienses and Scamandrians^m.

Sigeum was founded posterior to the siege of Troy by an Æolian colony, headed by Archæanax of Mytilene. He is said to have employed the stones of ancient Ilium in the construction of his town. The Athenians, some years afterwards, sent a body of troops there headed by Phrynon, a victor at the Olympic games, and expelled the Lesbians. This act of aggression led to a war between the two states, which was long waged with alternate success. Pittacus, one of the seven sages, who commanded the Mityleneans, is said to have slain Phrynon, the Athenian leader, in single fight. The poet Alcæus was engaged in one of the actions that took place, and, by his own confession, fled from the field, leaving his arms to the enemy. At length both parties agreed to refer their dispute to Periander of Corinth, who decided in favour of the Athenians. (Strabo XIII. p. 599. Herod. V. 95. Diog. Laert. I. 74.) The latter people, or rather the Pisistratidæ, remained then in possession of Sigeum,

^m Voyage Pittoresque, tom. II. p. 288.

and Hippias, after being expelled from Athens, is known to have retired there, together with his family. (Herod. V. 65.)

Sigeum
promonto-
rium.

The town of Sigeum no longer existed when Strabo wrote, having been destroyed by the citizens of New Ilium. (XIII. p. 600. Plin. V. 30.) The promontory was especially celebrated in antiquity, as the spot on which the ashes of Achilles had been interred; and such was the reverence with which Achilleum. it was regarded, that a small town, named Achilleum, appears to have grown up around the tomb, as early as the time of Herodotus. (V. 94.) Strabo, on the authority of Demetrius of Scepsis, reports that it was fortified by the Mitylenians in their war with Athens. (XIII. p. 600.) The tomb of Achilles was successively visited by Alexander, (Arrian. Exp. Alex. I. 12. Cic. pro Arch. c. 10.) Julius Cæsar, and Germanicus; and the mound which overtops it is still visible at the present day, together with those of Patroclus and Antilochus ⁿ.

'Εν τῷ τοι κεῖται λεύκ' ὀστέα, φαῖδιμ' Ἀχιλλεῦ,
Μίγδα δὲ, Πατρόχλοιο Μενοιτιάδαο θανόντος.
Χωρὶς δ', Ἀυτιλόχοιο· τὸν ἔξοχα τῖες ἀπάντων
Τῶν ἄλλων ἐτάρων, μετὰ Πάτροχλόν γε θανόντα.
Αμφ' αὐτοῖσι δ' ἔπειτα μέγαν καὶ ἀμύμονα τύμβον
Χεύαμεν Ἀργείων ιερὸς στρατὸς αἰχμητάων,
Ἀκτῇ ἐπὶ προύχούσῃ, ἐπὶ πλατεῖ Ἐλλησπόντῳ.
Ως κεν τηλεφανῆς ἐκ ποντόφιν ἀνδράσιν εἴη
Τοῖς, οἵ νῦν γεγάσσι, καὶ οἱ μετόπισθεν ἔσονται.

Od. Ω. 76.

The cape of Sigeum is now called *Yeni-cher*. A little to the south of it is another headland, with some ruins, which may possibly belong to the little

ⁿ Chevalier, Descr. of the Plain of Troy, chap. xxi. p. 142. Voyage Pittoresque, tom. II. p. 330.

town of Agamia^o, said to have been so called from Agamia, the adventure of Hesione, who was there exposed to the sea-monster, and delivered by Hercules. (Steph. Byz. v. Ἀγάμεια. Cf. Hesych. ead. v.) In Hierocles it is not unlikely that for Ἀρτέμεια we ought to read Ἀγάμεια. (Synecd. p. 663.) Opposite to the headland are some little islands, or rocks, which may be the Lagussæ of Pliny; (V. 38. Cf. Eustath. Il. B. ^{Lagussæ}_{insulæ}. p. 306.) but this is uncertain, as the same geographer enumerates with those on the coast of Troas several others; Ascaniæ, Plateæ III., Lamiæ, Pli-taniæ II., Plate, Scopelos, Getone, Arthedon, Cœlæ, Didymæ. The largest of these islets is now called *Taushan*. Somewhat to the south is the more conspicuous and celebrated island of Tenedos, whither the Greeks retired, as Virgil relates, in order to surprise the Trojans.

Est in conspectu Tenedos, notissima fama
Insula, dives opum, Priami dum regna manebant;
Nunc tantum sinus, et statio male fida carinis;
Huc se provecti deserto in littore condunt.

ÆN. II. 21.

Et jam Argiva phalanx instructis navibus ibat
A Tenedo, tacitæ per amica silentia lunæ,
Littora nota petens. IBID. 254.

This island was formerly called Leucophrys, from its white cliffs; (Eustath. Il. A. p. 33. Lycophr. 346.)

Toῖς εἰς στενὴν Λεύκοφρυν ἐκπεπλευχόσι.

and it took the name of Tenedos from Tennes, the son of Cycnus, whose adventures are related at length by Heraclides Ponticus, (Polit. p. 209.) Strabo, (VIII. p. 380. XIII. p. 604.) Pausanias, (Phoc.

^o Voyage Pittoresque, tom. II. p. 331.

14.) Conon. (Narrat. pp. 24. 130.) Tenedos received a colony of Æolians, (Herod. I. 149. Thuc. VII. 57.) which flourished for many years, and became celebrated for the wisdom of its laws and civil institutions. This we collect from an ode of Pindar inscribed to Aristagoras, prytanis or chief magistrate of the island. (Nem. XI.) Aristotle is known to have written on the polity of Tenedos. (Steph. Byz. v. Τένεδος.) Apollo was the principal deity worshipped in the island, as we know from Homer. (Il. A. 37.)

Κλῦθι μου, Ἀργυρότοξὸν χρύσην ἀμφιβέβηκας,
Κίλλαν τε γαθένην, Τενέδοιό τε ἱρὶ ἀνάσσεις,
Σμινθεῦ—

According to the same poet, Tenedos was taken by Achilles during the siege of Troy. (Il. A. 624.) When the prosperity of Tenedos was on the decline, the inhabitants placed themselves under the protection of the flourishing city of Alexandria Troas. (Pausan. Phoc. 14.) At a still later period it derived again some importance from the granaries which Justinian caused to be erected there, for the purpose of housing the cargoes of corn brought from Egypt and intended for Constantinople, but which were frequently delayed by contrary winds blowing from the Hellespont. (Procop. AEd. Justin. V. 1.) Strabo estimates the circuit of Tenedos at eighty stadia, and its distance from the mainland at forty, which is pretty correct; but the little islands called Calydnae, which the same geographer places between cape Lectum and Tenedos, are not to be found in that direction. (XIII. p. 603.) In Choiseul Gouffier's map, they are laid down between Tenedos and Sigeum. There were several proverbs con-

nected with the history of Tenedos which may be found in Steph. Byz. (v. Τένεδος.) It may be worth while to remark, that Nymphodorus, a geographical writer quoted by Athenæus, affirmed that the women of Tenedos were of surpassing beauty. (XIII. p. 60.) When Chandler visited this island, which retains its ancient name, “ he found there but few remains of “ antiquity worthy of notice; in the streets, the walls “ and burying-grounds, were pieces of marble and “ fragments of pillars, with a few inscriptions P.” Homer places between Imbros and Tenedos the submarine cave, in which Neptune rested his horses while he proceeded to aid the Greeks.

Ἐστι δέ τι σπέσις εύρù βαθείης βένθος λίμνης,
Μεσσηγὺς Τενέδοιο καὶ Ἰμβρου παιταλοέσσης.
Ἐνθ' ἵππους ἔστησε Ποσειδάων ἐνοστίχθων. IL. N. 32.

Opposite to Tenedos, on the Trojan coast, was a spot named Achæum, (Strab. XIII. p. 603, 4.) and Achæum. immediately after followed Larissa and Colonæ, two towns of great antiquity, but which made way, together with several others, for the rising city of Alexandria Troas. Colonæ was the city of Cycnus, Colonæ. already mentioned as the father of Tennes, and stood at a distance of 140 stadia from Ilium. (Strab. XIII. p. 589. Pausan. Phoc. 14. Xen. Hell. III. 1, 10.) Larissa, a name always indicative of a Pelasgic origin, had probably been founded by one of those wandering tribes, which settled in different parts of the Asiatic coast before the siege of Troy; but Strabo is of opinion, and apparently on good grounds, that this was not the Larissa spoken of by Homer, (Il. P. 301.) as that is expressly said to have been far from Troy. (Strab. XIII. p. 620.) This

P Travels in Asia Minor, p. 22. Inscr. Ant. pp. 3, 4.

town is alluded to by Thucydides (VIII. 101.) and Xenophon (III. 1, 10.) Cf. Scyl. p. 36. But Stephanus Byz. looks upon it as the Homeric town. (v. Λάρισσα.) Athenæus mentions some hot springs near Larissa in Troas, (II. p. 43.) which are still known to exist a little above the site of Alexandria Troas.

Alexandria Troas^q. The latter city, which was so called by Lysimachus, had been first named Antigonia, from Antigonus, another of Alexander's generals, who was its first founder. Antigonus had already increased its population by sending thither the inhabitants of Cebrene, Neandria, and other towns; and it received a further increase under the auspices of Lysimachus: under the Romans it acquired still greater prosperity, and became one of the most flourishing of their Asiatic colonies. (Strab. XIII. pp. 593, 604. Cf. Plin. V. 30.) It was thus distinguished by the Romans on account of the fidelity it had displayed in the war which they waged against Antiochus. (Liv. XXXV. 42. Polyb. XXI. 10, 3. Cf. V. 78, 6. 111, 3.) In the Acts of the Apostles it is simply called Troas, and it was from its port that St. Paul and St. Luke set sail for Macedonia, (xvi. 11.) and it was there, on his return from Macedonia, that the apostle restored to life Eutychus, who had been killed by a fall from an upper story whilst asleep. (xx. 9.) Of this town were Hegesianax and Hestiae, who wrote commentaries on Homer, and Hegemon, an epic poet. (Strab. XIII. p. 599. Steph. Byz. vv. Τρωϊας et Ἀλεξάνδρεια. Athen. IX. p. 393.) The site of Alexandria is called *Eski Stamboul*, and numerous ruins attest its former magnificence. According to Chandler, "it

^q Voyage Pittoresque, tom. II. p. 438.

" was seated on a hill sloping toward the sea, and
 " divided from mount Ida by a deep valley. On
 " each side is an extensive plain, with water courses.
 " The city wall is standing, but with gaps, and the
 " battlements ruined. It was thick and solid, had
 " square towers at regular distances, and was seve-
 " ral miles in circumference. Besides houses, it has
 " enclosed many magnificent structures; but now
 " appears as the boundary of a forest or neglected
 " park." The principal buildings, according to the
 same diligent and learned traveller, were a public
 gymnasium, or stadium, a theatre and odeum, se-
 veral temples, and a magnificent aqueduct built by
 Herodes Atticus. There are also some vestiges of
 the port and mole ^r.

Strabo affirms, that the site on which this city was built had borne the name of Sigia. (XIII. p. 604.) More to the south was the town of Chrysa, sur-^{Chryssa}
 named Dia, and celebrated for the worship of Apollo ^{qusæ et Dia.} Sminthius, so called from *σμίνθος*, which in the Æolic dialect signifies a *rat*. Tradition ascribed the origin of the name to the circumstance of this animal's having appeared in great numbers, when the Teucrians landed in Troas from Crete, and having gnawed the leather of their arms and utensils. Various other fabulous tales respecting these rats are to be found in Strabo, who observes, that there were numerous spots on this coast to which the name of Sminthia was attached. The temple itself was called

^r Chandler's Travels in Asia Minor, p. 32. The reader will find also a detailed account of the ruins of Alexandria, together with a plan of them, in the splendid work of Choiseul

Gouffier, so often referred to. tom. II. p. 434. The coins of Alexander Troas are to be found in almost every collection. The earliest bear the name of Antigonia. Sestin. Mon. Vet. p. 76.

Sminthi-
um. Sminthium. He does not however allow, as Scylax does, (p. 36.) that this edifice, or the Chrysa here mentioned, were those to which Homer has alluded in the first book of the Iliad, as the abode of Chryses, the priest of Apollo. He places these more to the south, and on the Adramyttian gulf. (XIII. pp. 604, 612.)

Halesium. Continuing along the coast, we find a plain of Halesium, some extent, anciently called Halesium, from the salt springs with which it abounded. These furnished a great supply of salt from works established in the spot called Tragaseæ. And it was affirmed, that when Lysimachus had laid a duty on this article, the springs suddenly failed, but reappeared on the tax being withdrawn. (Athen. III. p. 73. Strab. XIII. p. 605. Steph. Byz. vv. Ἀλήσιος, Τράγασσαι.) The salt of Tragaseæ is mentioned by Galen, (de Temp. Medic. Simpl. t. II. p. 151.) Hesychius, (v. Τράγασσαιοι,) and others. The works are still in existence, and are known to the Turks by the name of *Tuzla*, which precisely corresponds with the Latin *Salinæ*^s. Near these works we must look for the ruins of Hamaxitus, an ancient town, probably of Æolic origin, noticed by Scylax, (p. 36.) Thucydides, (VIII. 101.) and Strabo, (XIII. p. 605.) as situated on the Trojan coast. (Cf. Plin. V. 33. Apollod. ap. Steph. Byz. v. Ἀμαξίτος.) The promontory of Lectum was the southernmost point of Troas, the towns situated beyond it, on the Adramyttian gulf, being considered as belonging to Æolis. (Strab. XIII. p. 605. Plin. V. 32.) Homer, in

Hamaxi-
tus.
Lectum
promonto-
rium.

^s Le Chevalier, Voyage dans la Troade, tom. I. ch. 2. Col. Leake states, that the neigh-

bouring hills are composed of rock salt. Asia Minor, ch. vi. p. 274.

his account of the deceit practised upon Jupiter by Juno, makes it part of the chain of Ida, and the spot where the goddess landed, together with her auxiliary the god of sleep :

Τὼ βήτην, Λήμνου τε καὶ Ἰμβρου ἄστυ λιπόντε,
 'Ηέρα ἐσσαμένω, ρίμφα πρήσσοντε κέλευθον·
 "Ιδην δ' ιχέσθην πολυπίδακα, μητέρα θηρῶν,
 Λεχτὸν, οὗ πρῶτον λιπέτην ἄλα· τὼ δὲ ἐπὶ χέρσου
 Βήτην· ἀκροτάτη δὲ ποδῶν ὑπ' ἐσείστο ὕλη.

IL. Ξ. 281.

Herodotus relates, that after the battle of Mycale the Greek fleet took up their station near Lectum, on their way to the Hellespont, the wind being adverse. (IX. 114.) It is also alluded to by Thucydides, (VIII. 101.) Livy, (XXXVII. 37.) and Plutarch, in the life of Lucullus. Athenæus reports, that the purple shellfish was found here, as well as near Sigeum, and of a large size. (III. p. 88.) The modern name is Cape *Baba*.

In the interior of Troas there remain yet a few places to be pointed out. Among these, Neandria is Neandria frequently mentioned in history as an Æolian colony of some note. (Scyl. p. 36.) Its territory appears from Strabo to have included a fertile and extensive plain, named Samonium ; (II. p. 106. XI. p. 472.) Samonius Campus. and the same geographer affirms that it was situated between Hamaxitus and New Ilium, at a distance of 130 stadia from the latter. These circumstances concur in fixing the site of this ancient town near the modern village of *Enai*, or *Ene*, where there are many vestiges of antiquity, and above which the valley of the *Mendere*, or Simois, opens into a broad and well cultivated plain, now called *Baira-*

misch^t. Neandria, as we learn from Xenophon, had belonged to the Dardanian princess Mania ; but on her death it was declared independent by Der-cyllidas. (Hell. III. 1, 13.) After the dissolution of Alexander's great empire, Antigonus obtained for a short time possession of Troas, and Neandria and other small towns were destroyed, to make way for the city which that general founded on this coast under the name of Antigonia, but which afterwards was called Alexandria Troas. (Strab. XIII. p. 604. Cf. Steph. Byz. v. Νεάδρεια. Antigon. Caryst. c. 187. Cedren. Compend. p. 126. Plin. V. 30.) A little to the south of *Ene*, and between it and *Eski Stam-boul*, or Alexandria, a small place named *Kutchu-Cocylum*. *lan*^u is thought to represent Cocylia, or Cocylum, a Greek town mentioned by Xenophon, in connexion with Ilium and Neandria, in the passage above referred to. In Pliny's time it no longer existed. (V. 33.)

On the left bank of the *Mendere*, and to the south of *Ene*, or Neandria, is a ruined fortress called *Tchigri* by the natives ; this may have been Cenchreæ. Cenchreæ, a town of Troas, where Homer was said to have resided some time, to make himself acquainted with the Trojan topography. (Steph. Byz. v. Κεγχρέαι.) Some even pretended that the poet was born there. (Suid. v. Ὄμηρος.) Under the Greek emperors, Cenchreæ is mentioned as a fortress in which state prisoners were confined. (Pachymer.

^t Voyage Pittoresque, tom. II. p. 285. Leake, Asia Minor, ch. vi. p. 274. Some topographers have identified *Enai* with Nea or Neacome, but this was near the *Aesepus*. There are

some few coins of Neandria, with the legend NEAN. Sestini, p. 77.

^u Voyage Pittoresque, Carte de la Troade, tom. II. p. 201.

tom. I. p. 331.) It was besieged and taken by the Turks in the fourteenth century. (Pach. tom. II. p. 334.) According to Choiseul Gouffier, the walls and gates of this town are yet standing^x. Higher up the river *Mendere*, and not far from its source in mount Ida, are some extensive ruins denoting an ancient town of importance. The site is called *Kutchulan-tepe*, and its topographical situation agrees with that which ancient writers assign to Cebrene, Cebrene capital of a small district named from it Cebrenia.^{Cebrenia regio.} But it was affirmed by some, that the name was derived from Cebriones, the natural son of Priam, and charioteer of Hector. Strabo reports, that the district of Cebrenia was separated by the Scamander (the Simois of Homer) from the territory of Scepsis, with which town the Cebrenians were almost constantly at war. This state of discord was at length put an end to by Antigonus, who removed the inhabitants of both towns to Antigonia, afterwards Alexandria Troas. (XIII. p. 597.) According to Ephorus, Cebrene had received a colony from the Æolian Cyme. (ap. Harpocr. v. Κέβρηνα. Cf. Scyl. Peripl. p. 36.) Xenophon affirms that it was a place of great strength. It resisted for some time the attack of Dercyllidas, the Lacedæmonian commander, but at length submitted to his authority. (Hell. III. 1, 14.) Cebrene is also noticed by Demosthenes. (contr. Aristocr. p. 671.) We learn from Apollodorus that there was a river named Cebren, which probably flowed near the town. (Biblioth. III. 5, 6. Steph. Byz. v. Κέβρηνα.) It is now called *Kazdagħ-tħai*, and falls into the *Mendere* a little above the ruins of *Kutchunlu-tepe*^y.

^x Voyage Pittoresque, tom. II. p. 201.

^y Ibid. p. 284.

The *Mendere* receives on its right bank, some miles below, a larger torrent, called *Lidjick-Deressi-Andrius f. tchai*, which is probably the river Andrius, which, according to Strabo, flowed from Caresene. (XII. p. 602.) It was from the number of the streams which descend from its sides into the Hellespont and Propontis that Homer gives to mount Ida the epithet of πολυπίδαξ; and, according to modern travellers, it still preserves that feature, as well as the accompanying one, of being the haunt of numerous beasts, expressed by the poet in the same line :

*Ιδην δὲ ἵκανεν πολυπίδαχα, μητέρα θηρῶν. IL. Θ. 47.

Strabo compares the whole chain to a scolopendra, on account of the great number of subordinate hills which branched off from it in various directions. Of these, the highlands about Zeleia were the most northern; while the headland of Lectum formed the extreme point to the south-west. Two other subordinate ranges, parting from the principal summit, and terminating, the one at cape Rhœteum, the other at the Sigean promontory, might be said to enclose the territory of Troy in a crescent; while another central ridge betwixt the two, separating the valley of the Scamander from that of the Simois, gave to the whole the form of the Greek letter ε. (Demetr. ap. Strab. XIII. p. 597.) The highest summit, which Homer calls Gargara, is now called *Kax-dagh*. Its elevation has been ascertained to be 775 toises, or about 5000 English feet, above the level of the sea. Those travellers who have ascended this lofty mountain give an animated description of the extensive prospect over the Hellespont, Propontis, and the whole surrounding country, which they

enjoyed from it^z, and which fully justifies the expressions of the poet :

"Ιδην δὲ ἵκανεν πολυπίδαχα, μητέρα θηρῶν,
Γάργαρον, ἐνθα δέ οἱ τέμενος, βωμός τε θύσεις."
"Ενθ' ἴππους ἔστησε πατὴρ ἀνδρῶν τε θεῶν τε,
Λύσας εἰς ὄχέων, κατὰ δὲ ήρα πουλὺν ἔχευεν.
Αὐτὸς δὲ ἐν κορυφῇσι καθέζετο κύδει γαιῶν,
Εἰσορόων Τρώων τε πόλιν καὶ νῆας Ἀχαιῶν. I.L. Θ. 47.

Several ancient writers have spoken of a remarkable coruscation of light which was to be observed before sunrise around this elevated summit :

Quod genus Idæis fama est e montibus altis
Dispersos igneis orienti lumine cerni :
Inde coire globum quasi in unum, et conficere orbem.

LUCRET. V. 662.

(Cf. Diod. Sic. XVII. 7. Pomp. Mel. I. 18.) Various explanations of this phenomenon have been suggested by modern naturalists, which will be found in Choiseul. The sources of the *Mendere* are to be seen in a remarkable cavern above the village of *Audgelar*, at the foot of the mountain. Besides Gargara, we hear of three other summits ; Cotylus, which has already been mentioned, Pytna, and Dicte, in the territory of Scepsis. (Strab. XIII. p. 472.) Other passages relating to this celebrated mountain will be found in Homer's Hymn to Venus ; Ovid's Epistles, XVI. 53 ; Dionys. Perieg. 814.

On rounding cape Lectum, the coast is seen to stretch far to the east, when it again bends to the south-west, so as to form a deep bay, which took its name from the once flourishing city of Adramyt-

Adramyt-
tenus Si-
nus.

^z Voyage Pittoresque, tom. II. p. 281. Clarke's Travels, tom. II. p. 134. Dr. Hunt's Journal, in Walpole's Turkey, tom. I. p. 120.

tium, situated at the head of it, at a little distance from the coast. The shores of this beautiful gulf had at an early period been peopled by those wandering tribes who, under the name of Leleges, are so often mentioned in the barbarous age of Grecian history. Homer enumerates them among the Trojan forces, (Il. K. 432.) and assigns to them the town of **Pedasus**, on the river **Satnioeis**:

Ἄλτεω, ὃς Λελέγεσσοι φιλοπτολέμοισιν ἀνάσσει,
Πήδασον αἰπήσσαν ἔχων ὑπὸ Σατνιόεντι. Il. Φ. 86.

Ναῖς δὲ, Σατνιόεντος ἐύρρετας παρ' ὄχθας,
Πήδασον αἰπεινήν. Il. Z. 34.

The situation of this Homeric town remains undefined; it appears indeed from Pliny, that some authors identified it with Adramyttium. (V. 32.) There was another Pedasus in Caria, which must Satnioeis fl. not be confounded with it. The Satnioeis is generally supposed to be a small stream which falls into the Ægean sea, some miles to the north of cape Lectum, and near the salt works of *Tuzla*, from whence it derives its present name^a. Strabo informs us, that some critics wrote the word Saphnicioeis. (XIII. p. 605.) The first city of note to the east of cape Lectum is Assus, founded, according to Myrsilus and Hellanicus, the Lesbian historians, by a colony from that island. (Ap. Strab. XIII. p. 610.) It is celebrated in the annals of Grecian philosophy as the birthplace of Cleanthes the Stoic, the successor of Zeno. Aristotle resided also some time at Assus, having married, it is said, the niece of Hermias, a eunuch, who had made himself tyrant of the city. Hermias, however, having fallen into the

^a Choiseul Gouffier, tom. II. p. 438. Leake's Asia Minor, p. 273.

hands of Memnon, the Persian general, was put to death, and Assus was taken possession of by the Persian forces. (Strab. XIII. p. 610. Cf. Diog. Laert. V. 3.) Assus occupied a commanding situation, at some distance from the coast, and was fortified with strong walls ; but the road which led to it from the port was so steep, that Stratonicus the musician humorously applied to it this verse of Homer ;

"Ασσον ἵθι, ὡς κεν θᾶσσον ὀλέθρου πείραθ' ἔχηαι."

I.L. Z. 144.

The port was chiefly formed by a great mole. We learn from the Acts of the Apostles that St. Luke, and the other companions of St. Paul, here rejoined with their ship the apostle, who had left them at Alexandria Troas, and had crossed on foot from that city to Assos : (xx. 13.) “ And we went before “ to ship, and sailed unto Assos, there intending to “ take in Paul : for so had he appointed, minding “ himself to go afoot. And when he met with us at “ Assos, we took him in, and came to Mitylene.”

Pliny seems to say Assus was once called Apollonia. (V. 32.) The same writer informs us, that a stone was found in the territory of this city which had the peculiar property of wasting the flesh of bodies entombed in it ; hence it was called “ sarcophagus.” (XXXVI. 17. Vid. Salmas. Cf. Steph. Byz. v. *"Ασσος."*) Col. Leake, who visited the remains of this ancient city, on the site now called *Beriam Kalesi*, observes, “ that they are extremely curious. There “ is a theatre in very perfect preservation ; and the “ remains of several temples lying in confused heaps “ upon the ground. On the western side of the “ city, the remains of the walls and towers, with a

Polyme-
dium.

Gargara.

" gate, are in complete preservation; and without
 " the walls is seen the cemetery, with numerous
 " sarcophagi still standing in their places, and an
 " ancient causeway leading through them to the
 " gate. Some of these sarcopahgi are of gigantic
 " dimensions. The whole gives perhaps the most
 " perfect idea of a Greek city that any where ex-
 " ists ^b." Strabo places between Assus and cape
 Lectum, at forty stadia from either, a fortress named
Polymedium; (XIII. p. 606.) but Pliny perplexes
 us by naming in this vicinity **Palamedium** and **Polymedia**: his text is probably not without error.
 (V. 32.) Sixty stadia beyond Assus, and 140 from
 cape Lectum, we must place **Gargara**, a colony of
 the former, and situated on a cape which probably
 took its name from the celebrated summit of mount
 Ida. It was from this cape that the Adramyttian
 gulf, called also by some the bay of Ida, properly
 commenced. (Strab. XIII. p. 606.) Gargara had
 been an *Æolian* colony, but it afterwards received
 an increase of inhabitants from the town of Mileto-
 polis, so that the town lost much of its Greek cha-
 racter, as Demetrius of Scepsis affirmed. (Strab.
 XIII. p. 610. Mel. I. 18.) The territory of Gar-
 gara, situated at the foot of mount Ida, is much
 celebrated by the writers of antiquity for its great
 richness and fertility, especially in corn.

. . . nullo tantum se Mysia cultu
 Jactat, et ipsa suas mirantur Gargara messes.

VIRG. GEORG. I. 102.

^b Asia Minor, p. 128. The autonomous coins of Assus, with the epigraph ΑΣΣΙΩΝ, are rare. The imperial money ex-

hibits a series from Augustus to Alexander Severus. Sestin. p. 72.

Hinc grata Cereri Gargara, et dives solum,
Quod Xanthus ambit nivibus Idæis tumens.

SENEC. PHÆN. ACT. IV. V. 608.

(Cf. Steph. Byz. v. Γάργαρον. Plin. V. 32. Macrob. Saturn. V. 20. Etym. Magn. v. Γάργαρα.) Gargara must be sought for near the headland on which is now situated the village of *Iné*^c. In the same vicinity stood Lamponia, or Lamponium, an Aeolian city, named by Hecatæus and Hellanicus. (Ap. Steph. Byz. v. Λαμπώνεια.) Herodotus reports, that it was annexed to the Persian empire by the satrap Otanes, in the reign of Darius, son of Hystaspes. (V. 26.) Somewhat further from the coast were the towns of Andeira and Ponia. The territory of the Andeira. former was productive of a mineral substance, which, by different processes, became zinc, or the metal called orichalcum. (Strab. XIII. p. 610. Steph. Byz. v. Ἀνδείρα.) Ponia is mentioned by Pliny; (V. 32.) Ponia. and the Ecclesiastical Notices name it as a bishopric of the Hellespontine province^d. (Hierocl. Synecd. p. 663.) Near Andeira was to be seen a remarkable subterraneous passage, which was said to extend underground as far as Palæa, a village distant 130 stadia from Andeira. It was accidentally discovered by a goatherd, who found there one of his goats, which had strayed into the cavern. A temple was dedicated here to the goddess Cybele. (Strab. XIII. p. 614.)

Antandrus, the foundation of which seems to be ascribed by Herodotus to the Pelasgi, (VII. 42.) is

^c Note to the French Strabo, tom. IV. p. 198. The coins of Gargara have the inscription ΓΑΡ. and ΓΑΡΓΑΡΕΩΝ. Sestini, p. 72.

^d There are some few coins belonging to Ponia, with the legend ΠΙΟΝΙΤΩΝ. Sestini, p. 75.

mentioned as an Æolian colony by Thucydides. (VIII. 108.) It seems also to have been occupied at an early period by the Cimmerians and Edonian Thracians, as appears from the epithets of Cimmeris and Edonis applied to it by Pliny. (V. 32.) Aristotle, indeed, who is quoted by Steph. Byz., (v. *Ἀντανδρός*, affirmed, that the Cimmerians retained possession of it for 100 years. Antandrus was advantageously situated on the coast, at the foot of mount Alexandra, one of the summits of Ida; so called, as it was said, from the judgment of Paris. The forests of this mountain supplied the Antandrians with timber for building ships; they also exported it in large quantities. The spot to which it was carried down from Ida bore the name of Aspaneus. (Strab. XIII. p. 607.)

. . . . classemque sub ipsa
Antandro et Phrygiæ molimur montibus Idæ.

VIRG. ÆN. III. 5.

In the eighth year of the Peloponnesian war, some Lesbian exiles, aided by the Spartans, seized upon Antandrus, and made war from thence upon the Athenians and Mitylenians; (Thuc. IV. 52.) but the former people, having defeated them in an engagement, retook the town. (IV. 75.) After the Sicilian expedition, Antandrus fell into the hands of the Persians, but the inhabitants, exasperated by the conduct of Arsaces, the lieutenant of Tissaphernes, attacked his troops, and drove them from their city. (VIII. 108. Cf. Herod. V. 26. Xen. Anab. VIII. 4. Mel. I. 18. Scyl. Peripl. p. 36.)^e The site once occupied by this ancient city still retains the

^e There are both autonomous and imperial coins of Antandrus, but the former are scarce. Sestini, p. 71.

name of *Antandro*. The Antonine Itinerary reckons thirty-one miles from Antandrus to Adramyttium; the Table, more correctly, only sixteen. Strabo places between Gargara and Antandrus a mountain named Cillæum. (XIII. p. 612.) Adramyttium, ^{Adramyt-}_{tium.} which gave its name to the extensive bay on which it stood, is said by Strabo to have been colonized by the Athenians; (XIII. p. 606.) but the foundation of the city is ascribed by Aristotle to Adramys, a brother of Crœsus. (Steph. Byz. v. Ἀδραμύττειον.) Strabo also mentions, that several writers ascribed its origin to the Lydians. (XIII. p. 613.) But, if we are to believe Eustathius, and other commentators, Adramyttium already existed before the Trojan war. Pliny indeed affirms, that it was no other than the Pedasus of Homer. (V. 32.) The writer of the Not. Eccles. (p. 27.) identifies it with Lyrnessus. However this may be, it is certain that Adramyttium, from its advantageous situation, had early become a flourishing city. (Herod. VII. 42. Strab. loc. cit. Scyl. Peripl. p. 36.) The Athenians had settled there the inhabitants of Delos, whom they had removed from their island when it was purified; but these unfortunate exiles were afterwards cruelly massacred by Arsaces, the Persian general, who commanded under Tissaphernes. (Thuc. VIII. 108. Pausan. Messen. c. 27.) After the defeat of Antiochus, Adramyttium was ceded by the Romans to the kings of Pergamus, under whom it continued to prosper; but it suffered greatly during the war with Mithridates, the whole senate, and several of the principal inhabitants, having been put to death by order of Diodorus, a partisan of that monarch. (Strab. XIII. p. 614.) Appian, on

the other hand, accuses the Adramytteni of having butchered many Roman citizens, to gratify Mithridates. (Bell. Mithrid. 23.) Xenocles, a celebrated orator of Adramyttium, was sent to Rome to plead the cause of his native city, and the whole province of Asia, suspected of having favoured the king of Pontus. (Strab. XIII. p. 614.) It was in a ship of Adramyttium that the apostle Paul commenced his voyage from Cæsarea to Italy, as a prisoner, to appear before the Roman emperor. (Acts xxvii. 2.) It is evident from Pliny's account, that Adramyttium was the most considerable of all the towns in this vicinity, since it was the seat of a *conventus*, in which all the causes of the neighbouring places were tried. (V. 32.) We find Adramyttium often mentioned by the Byzantine historians, and the ancient name is even now but little changed in that of *Adramiti*^f.

Astyra. Between this city and Antandrus, Strabo places Astyra, a small town, with a celebrated temple and grove sacred to Diana. These belonged to the Antandrians. (XIII. p. 614. Scyl. Per. p. 36.) This Astyra must not be confounded with the place of the same name near Abydos. Not far from thence was a small lake, called Sapra, full of deep holes, and which communicated with the sea. (Strab. loc. cit.) Pausanias speaks of some warm baths at Astyra, the water of which was black. (IV. 35.) Pliny mentions several obscure streams which apparently discharged themselves in the gulf of Adra-

Sapra la-
cus.

^f The coins of Adramyttium have the legend ΑΔΡΑΜΥΤΤΗΝΩΝ; they attest the alliance of that town with several im-

portant cities, such as Mitylene, Ephesus, Laodicea. Sestini, p. 71.

myttium from Ida, such as the Astron, Cormalus, Eryannus, Alabastius, Hierus. (V. 82.)

The whole of the surrounding district, according to Homer, was once occupied by a colony of Cilicians, who were governed by Eetion, father of Andromache, at the time of the Greek invasion. His capital was Thebe, surnamed Hypoplacia, from being Thebe situated under a hill called Placos.

Placos
mons.

*'Ητοι γὰρ πατέρ' ἀμὸν ἀπέκτανε δῖος Ἀχιλλεὺς,
'Εx δὲ πόλιν πέρσεν Κιλίκων εύναιετάωσαν,
Θήβην ὑψίπυλον· κατὰ δὲ ἔκτανεν Ἡετίωνα,
· · · · ·
Μητέρα δὲ, ἡ βασίλευεν ὑπὸ Πλάκωνος ὑληέσση,*

I.L. Z. 414.

*'Ἡετίων, δὲς ἔναιεν ὑπὸ Πλάκωνος ὑληέσση,
Θήβη 'Υποπλακίη Κιλίκεστος' ἀνδρεσσιν ἀνάσσων.*

Thebe, destroyed by Achilles, did not rise from Thebes its ruins; but the name remained throughout antiquity attached to the surrounding plains, famed for their fertility, and often ravaged and plundered by the different armies whom the events of war brought into this part of Asia. (Xen. Anab. VII. 8, 4. Polyb. XVI. 1, 7. XXI. 8, 13. Liv. XXXVII. 19. Pomp. Mel. I. 18.)

Lyrnessus, another Homeric city, disappeared also with Thebe, and left no trace of its existence beyond the celebrity which the Iliad has conferred upon it. Pliny asserts that it stood on the banks of the little river Evenus, whence, as we learn from Strabo, the Adramytteni derived their supply of water. (XIII. p. 614. Plin. V. 32.) In Strabo's time, the vestiges of both Thebe and Lyrnessus were still pointed out to travellers; the one at a distance of sixty stadia to the north, the other, eighty stadia

to the south of Adramyttium. (XIII. p. 612.) The same geographer informs us, that Chrysa and Cilla, both celebrated in the Iliad, were also situated in the immediate vicinity of Adramyttium. Other writers, however, identified Chrysa with the town of that name, already noticed in the territory of Alexandria Troas; but the geographer observes that the latter had no port, and was besides too far from Thebe, to which the city of Chryseis belonged, as appears from Il. A. (366.): he however supposes that the Alexandrian Chrysa was a colony of the Cilician town. Cilla stood on the side of Antandrus, and was still famed for the worship of Apollo Cillæus.

Κλῦθι μεν Ἀγυρότοξὸς Χρύσην ἀμφιβέβηκας,
Κίλλαν τε ζαθέην, Τενέδοιό τε ἱφι ἀνάσσεις.

IL. A. 37.

Cillæus flu-
vius. There was also a small stream named Cillæus, which descended from mount Ida, and flowed near the sacred edifice. (XIII. p. 612.) The modern name of this river is *Zikeli*. Chrysa was twenty stadia from Astyra and fifty from Thebe, which was consequently seventy from the latter. Andeira was sixty stadia from Thebe. Before we leave the Trojan Cilicians, I would just observe that the name of their chief city naturally induces a suspicion that they were really Syro-Phœnicians, who had been transplanted thither from the coast of Cilicia. The form of the word Lyrnessus corresponds too with the names of cities, which are so commonly met with on the shores of the Lycian and Pamphylian seas; such as Telmissus, Termessus, Pindensis-sus, &c.

North of Adramyttium, Strabo points out a few

localities, of which we must not omit to speak. He seems to derive his information, with respect to these points of detail, from the researches of Demetrius the Scepsian. Speaking of the little river Hep-taporus of Homer, but called also Polyporus, he observes, that a traveller would cross it seven times in journeying from the Beautiful pine to the little town of Celænæ and the temple of Aesculapius, founded by Lysimachus. He proceeds to report, that this remarkable tree, from the account given of it by king Attalus, was twenty-four feet in circumference, and that its stem, after rising to the height of sixty-seven feet, was formed into three ramifications, which reunited near the summit. The entire height was two plethra and fifteen cubits, or about 220 feet. It was 180 stadia from Adramyt-tium. Sixty stadia further were two places named Cleandria and Gordus, situated near the source of the Rhodius, also mentioned by Homer; but other commentators of the poet, as we have seen^g, supposed this river to flow into the Hellespont, whereas Demetrius asserted that it joined the Aenius, one of the tributary streams of the Aesepus. (Strab. XIII. p. 603.) In another passage, Strabo, still copying from Demetrius, speaks of Corybissa, a small district near Scepsis, and close to a rivulet called Eureis fl. et vicus. reis and a village of the same name, and the torrent Aethaloeis. (X. p. 473.) The latter is perhaps the same which Pliny calls Etheleus. (V. 32.) Strabo names also Hippocorona as a spot near Adramyt-tium, and Corybantium in the vicinity of Hamaxitus. (loc. cit.)

The promontory of Pyrrha closes the gulf of Pyrrha
g P. 76. promonto-
rium.

Adramyttium, properly so called, to the south ; it answers to the cape called *Karatepe-bouroun* by the Turks, *S. Nicolo* by the Franks. Strabo reckons 120 stadia from this headland to the opposite cape of Gargara. A temple of Venus was seated on the summit. (XIII. p. 606.) Beyond this point the same geographer places Cisthene, once a flourishing town and port, but deserted in his time ; (XIII. p. 607. Pomp. Mel. I. 18. Plin. V. 32.) and somewhat inland some copper mines, and the towns of Perperene and Trarium. The former of these was the see of a bishop in the time of the Byzantine empire, (Eccles. Not. p. 43.) and appears also to have been called Theodosiopolis^h. The line of coast which next follows was at one time known by the name of Acte, or coast of the Mitylenians, because that people had founded there several small towns. (Strab. XIII. p. 605 and 607.) Thucydides alludes to them under the name of Ἀκταῖαι πόλεις. Heraclea. (IV. 52.) Strabo names two of them, Heraclea and Coryphantis ; (XIII. p. 607.) Pliny, “ Heracleotes ” tractus, Coryphas oppidum.” (V. 32.) The name of the latter place is corruptly written Corifanio in the Table Itinerary. Pliny points out in the same vicinity, the two little rivers Grylius and Olius, and the district of Aphrodisias. Next follows Attæa, only known to Strabo, unless it is the same as the Attalia of the Table. (Strab. loc. cit.) Atarneus is oftener mentioned by the classical writers. Herodotus says it was a town of Mysia, opposite to Lesbos, and that it was ceded to the Chians by the

Grylius fl.
Olius fl.
Aphrodi-
sias regio.
Attæa.

Atarneus.

^h Several coins of the Roman empire from Nero downwards attest also the existence

of this town. The epigraph is ΠΕΡΠΕΡΗΝΙΩΝ. Sestini, p. 75.

Persians in the reign of Cyrus, for having delivered into their hands the Lydian Pactyas. (I. 160.) Scylax also says, Atarneus belonged to the Chians. (p. 36. Cf. Pausan. IV. 35.) The land around Atarneus was rich, and productive in corn. Histiaeus was defeated and taken in an engagement with the Persian forces at Malene, a spot not far ^{Malene.} from this town. (Herod. VI. 28, 29.) Xenophon places it between Adramyttium and the Caicus. (Anab. VII. 8, 4.) Strabo reports that Atarneus was for some time the residence of Hermias, tyrant of Assus. (XIII. p. 614. Cf. Pausan. VII. 2. Isocr. Paneg. p. 70. Steph. Xen. Hell. III. 2, 9. Aristot. Polit. II. 7. Plin. V. 32. Steph. Byz. v. Ἀτάρνεα.) The ruins of Atarneus are to be seen near the modern village of *Dikheli*ⁱ.

Herodotus names Carine as a town of Mysia in Carine. the neighbourhood of Atarneus, through which the army of Xerxes passed on its march to the Hellespont: it appears to have been situated between Atarneus and Adramyttium. (VII. 42. Cf. Steph. Byz. v. Καρίνη. Ephor. ap. eund. v. Βένα. Plin. V. 32.) It is not improbable that in Xenophon (Anab. VII. 8, 4.) we should read Καρίνης, instead of Κερτο-^{Certo-}_{nium.} οὐον, as the situation of this latter place, mentioned by no other author, agrees very well with that assigned to Carine. The MSS., however, it must be confessed, do not favour such an alteration; and it may be further observed that Theopompos, quoted by Steph. Byz., speaks of a Mysian town named Cytonium. (v. Κυτώνιον.) Carene may perhaps correspond with *Chirin-Kevi*, a small place near the

ⁱ There are some very scarce autonomous coins belonging to

Atarneus, with the legend ATA. and ATAP.

coast; and Cytonium, or Certonium, perhaps answers to *Kidonia*, a town somewhat to the south of it.

Pitane. Pitane, an Æolian city of some note, possessed two harbours, and was situated near the mouth of Evenus fl. the Evenus, now called *Tchandeli*: an aqueduct carried water from this river, probably near its source, as far as Adramyttium. (Strab. XIII. p. 614. Cf. Scyl. Peripl. p. 37.)

Æoliam Pitanen a læva parte relinquit.

OVID. METAM. VII. 357.

Canaius fl. Pliny places Pitane near the river Canaius, which no other writer notices. (V. 32.) This town was the birthplace of Arcesilas the philosopher, founder of the middle academy. (Strab. loc. cit. Diog. Laert. Vit. Arces. Cf. Steph. Byz. v. Πιτάνη. Hierocl. Synecd. p. 661.) Near Pitane was a spot called

Atarneus sub Pitane. Atarneus under Pitane, to distinguish it from the town of the same name already mentioned. It was opposite the island of Elæussa. (Strab. XIII. p. 614.) The bricks made at Pitane were said to be so light as to float in the water. (Strab. ibid.) Pitane is supposed to occupy the site now called *Tchandeli*. The gulf of Adramyttium, taken in its widest extent, is closed here to the south-west by the pro-

Cane pro-
monto-
rium et
mons. montory of Cane, now *C. Coloni*. Strabo says it was also called Ægan, and affirms that it was on the south of the river Caicus, and 100 stadia from Eleæ, the port of Pergamus; (XIII. p. 615.) whereas Herodotus, speaking of the march of the Persian army under Xerxes, distinctly states, that having crossed the Caicus they proceeded northwards, having the mountain of Cane on their left. (VII. 42.) Mela also places Cane north of the Caicus, (I. 18.) as well

as Pliny. (V. 32.) Strabo, in another place, describes mount Cane as surrounded on the south and west by the sea, on the east by the plain of the Caicus, on the north by the district of Elaea, which sufficiently characterises *Cape Coloni*. There was also a small town named Canæ, opposite to the southernmost point of the isle of Lesbos. It was founded by a colony of Locrians, who came from Cynus. (Strab. XIII. p. 615. Steph. Byz. v. Κάνας. Plin. V. 32.) The ruins of this town are to be sought for near *Coloni*^k.

The Caicus, the most considerable of the Mysian Caicus fl. streams, discharges its waters into a bay which took its name from the port of Elaea, about thirty stadia to the south-east of the town of Pitane. It rises at the foot of the eastern extremity of that chain which was known to the ancients by the name of mount Temnus, and extends from mount Ida to the borders of Phrygia and Bithynia. Another stream named Mysius, rising in the same chain, but more to Mysius fl. the west, mingled its waters with the Caicus. (Æsch. ap. Strab. XIII. p. 616.)

'Ιὸς Καϊκες Μύσιαι τ' ἐπιφόροι.

Saxosumque sonans Hypanis, Mysusque Caicus.

GEORG. IV. 370.

Et Mysum capitisque sui ripæque prioris
Pœnituisse ferunt, alia nunc ire, Caicum.

OVID. METAM. XV. 277.

The plains watered by the Caicus bore at a very Teuthra-
early period the name of Teuthrania, from Teu-<sup>nia regio
et urbs.</sup>

^k D'Anville has erroneously placed Canæ south of the Caicus. Numismatic writers assign to Canæ coins which bear the epigraph ΚΑΜΗΝΩΝ, without

however accounting for the change which it implies in the name of the town. Sestini, p. 72.

Ceteii.

Perga-
mum.

thras, a king of Mysia, who is said to have adopted Telephus, the son of Hercules and Auge. (Eurip. ap. Strab. XIII. p. 615.) According to Strabo there was a town as well as district named Teuthrания, distant about seventy stadia from Elaea, Pitane, Atarnaeus, and Pergamus. (Cf. Xen. Anab. VII. 8, 10. Hell. III. 1, 4.) The subjects of Eurypylus, son of Telephus, are called Ceteii by Homer ; (Odyss. A. 520.) a name which has much perplexed commentators, though it is generally allowed that it must apply to the Mysians. Strabo observes, that there was a small river named Ceteius which fell into the Caicus, and therefore tended to establish still further the supposed connexion between the people mentioned by Homer and the Mysians. (XIII. p. 616.) The Caicus derives its modern name from *Bergamo*, the ancient Pergamum. This celebrated city is mentioned for the first time, I believe, in the Anabasis. (VII. 8, 4.) Xenophon remained here for some time as the guest of Gorgion and Gongylus, two brothers, who appear to have been the possessors of the place. (Cf. Hell. III. 1, 4.) Xenophon made from thence a predatory excursion against a Persian nobleman named Asidates, whom he captured, with all his family. (Anab. loc. cit.) It was apparently a fortress of considerable natural strength, being situated on the summit of a conical hill, and was in consequence selected by Lysimachus, Alexander's general, as a place of security for the reception and preservation of his great wealth, said to amount to the enormous sum of 9000 talents. The care of this treasure was confided to Philetærus of Tium in Bithynia, an eunuch from his earliest infancy, and a person in whom he placed the greatest

confidence. Philetærus remained for a long time faithful to his charge; but having been injuriously treated by Arsinoe, the wife of Lysimachus, who sought to prejudice the mind of her husband against him, he was induced to withdraw his allegiance from that prince, and declare himself independent. The misfortunes of Lysimachus prevented him from taking vengeance on the offender, and thus Philetærus remained in undisturbed possession of the town and treasure for twenty years, having contrived, by dexterous management and wise measures, to remain at peace with all the neighbouring powers. He transmitted the possession of his principality to Eumenes, his nephew, who added much to the territory he inherited from his uncle, and even gained a victory near Sardes over Antiochus, son of Seleucus. After a reign of twenty-two years, he was succeeded by his cousin Attalus, whose father Attalus was the younger brother of Philetærus. This prince was first proclaimed king of Pergamum, after a signal victory obtained by him over the Gallo-Græci, or Galatæ, and by his talents, and the soundness of his policy, deserves a distinguished place among the sovereigns of antiquity. (Polyb. XVIII. 24. Liv. XXXIII. 21. Strab. XIII. p. 624.) He early espoused the interests of Rome against Philip, king of Macedon, and, in conjunction with the Rhodian fleet, rendered important services to the former power. His wealth was so great as to become proverbial. (Hor. Od. I. 1, 12.) He had married Apollonias, a lady of Cyzicus, of obscure birth, but great merit and virtue: by her he had four sons, Eumenes, Attalus, Philetærus, and Athænæus. Eumenes ascended the throne on his father's

death, which took place at an advanced age, after a prosperous reign of forty-three or forty-four years. (Polyb. Liv. et Strab. loc. cit.) The new sovereign, continuing to tread in his father's steps, and adhering to his policy, remained the firm friend of the Romans during all their wars against Antiochus and the kings of Macedonia, and received from them in recompense of his fidelity and valuable assistance all the territory conquered from Antiochus on this side of mount Taurus. Prior to this period, the territory of Pergamum did not extend beyond the gulfs of Elaea and Adramyttium. (Strabo loc. cit. Liv. XXXVIII. 39.) Waylaid by the hired assassins of Perseus, king of Macedon, he had nearly perished at Delphi; (XLII. 14. et seq.) and yet he is represented by the Roman historian as subsequently favouring the cause of the man who sought to destroy him, and of having thereby incurred the ill-will and anger of the Roman people. (XLIV. 13. 20. XLVI. 1—9.) With that arrogant nation, past services were reckoned as nothing, if they were not accompanied by the most abject and slavish dependence; and the uniform ingratitude with which they treated their allies who maintained some show of freedom, as in the case of the Ætolians, Rhodians, and Achæans, favours strongly the supposition that their conduct towards Eunenes was dictated by the same overbearing spirit. The king of Pergamum employed himself, during the leisure which a profound peace now afforded him, in embellishing his capital, and patronising the arts and sciences. He decorated the Nicephorium, a public building which Pergamum already owed to the munificence of Attalus, (Polyb. XVIII. 24. Liv. XXXIII. 21.) with

walks and plantations, and built himself several other edifices. But the most lasting monument of his liberality, as well as his fame, was the great library which he founded, and which yielded only to that of Alexandria in extent and value. (Strab. XIII. p. 624. Athen. I. 3.) It was from their being first used for writing in this library that parchment skins were called “*Pergamenæ chartæ.*” (Varr. ap. Plin. XIII. 11.) Plutarch informs us that this vast collection, which consisted of no less than 200,000 volumes, was given by Antony to Cleopatra. (Vit. Anton. p. 943.) Eumenes reigned forty-nine years, leaving an infant son under the care of his brother Attalus, who administered affairs as regent for twenty-one years with great success and renown. In conjunction with Alexander, son of Antiochus, he defeated Demetrius, son of Seleucus. Allied with the Romans, he assisted them in their war against the Pseudo-Philip. He likewise defeated Diegylis, king of the Thracian Cæni, and caused the overthrow and death of Prusias, king of Bithynia, by inducing his son Nicomedes to revolt against him. He was succeeded by his nephew Attalus, surnamed Philometor. This prince died after a reign of only five years, and left his dominions by will to the Romans. Aristonicus, a natural son of Eumenes, opposed this arrangement, and endeavoured to establish himself on the throne; but was vanquished and taken prisoner; and the Romans finally took possession of the kingdom, which from henceforth became a province of the empire under the name of Asia. (Strab. XIII. p. 624. XIV. p. 646.) Pergamum continued to flourish and prosper as a Roman city, so that Pliny

does not scruple to style it “longe clarissimum” “Asiæ Pergamum.” (V. 32.) To the Christian the history of Pergamum affords an additional interest, since it is one of the seven churches of Asia mentioned in the book of Revelations¹. Though condemnation is passed upon it as one of the churches infected by the Nicolaitan heresy, its faithful servants, more especially the martyr Antipas, are noticed as holding fast the name of Christ. (Rev. ii. 12. et seq.) The town was situated in a plain, watered by two small rivers or torrents flowing from mount Pindasus, and named Selinus and Cetius; these joined afterwards the Caicus. The citadel was placed on the conical hill mentioned by Strabo. (XIII. p. 623.) The modern town retains the name of *Bergamah*, and yet presents to the eye several extensive ruins, and other vestiges of its former magnificence^m. Dallaway, who has accurately described the ruins of Pergamumⁿ, mentions “a wall, facing the south-east of the acropolis, of hewn granite, at least a hundred feet deep, engrafted into the rock, and above that, a course of large substructions, forming a spacious area, upon which once rose a temple unrivalled in sublimity of situation, being visible from the vast plain, and

Pindasus
mons.
Selinus fl.
Cetius fl.

¹ Our translators of the New Testament do not appear quite accurate in rendering the name of this city Pergamos; it should be Pergamum: the Greek being almost always τὸ Πέργαμον. It is true, that Steph. Byz. writes Πέργαμος, but he gives no authority for that form.

^m The reader will find these described in Smith's Account

of the Seven Churches of Asia, and still more recently in Mr. Arundell's Visit to the Seven Churches of Asia. The coins of Pergamum are very numerous, as may be seen from Eckhel, Sestini, and other numismatical writers.

ⁿ Constantinople, Ancient and Modern, &c. p. 303.

“the Ægean sea.” He supposes it to have been erected in honour of Trajan. The same antiquary describes a great aqueduct, of one row of lofty arches over the Selinus, and a massive pile of building which formed the front and grand entrance into the Naumachia, which he considers as the most complete edifice of the kind in Asia Minor. At the western extremity of the hill are the remains of a theatre. Near the cemetery stood probably the celebrated temple and sanctuary of Æsculapius. (Appian. Bell. Mithr. c. 60. Tacit. Ann. III. 63.) Besides these, there are some massive remains of the great church, dedicated to St. John the Evangelist. The Selinus is called by the Turks *Tabaklar-tchay*, the Cetius *Barmakpatras-tchay*, the Caicus *Aksou*, or *Bakir-tchay*^o. In the plains watered by the Caicus, and in the vicinity of Pergamum, there yet remain to be noticed some few towns, such as Alisarna, mentioned by Xenophon; (Hell. III. 1, 4. and Anab. VII. 8, 10.) in the latter passage it is called Elisarne. Pliny writes it Haliserne. (V. 32. *Alisarna*. Cf. Steph. Byz. v. Ἀλίσαρνα.) Comania, an obscure town, noticed only by Xenophon. (Anab. VII. 8, 8.) Parthenium, for the knowledge of which we are also indebted to the Anabasis, (loc. cit. and VII. 8, 12.) and Pliny. (V. 32.) Apollonia, which, according to Strabo, was to the east of Pergamum on the way to Sardes. (XIII. p. 625. Xen. Anab. loc. cit. Plin. V. 32. Steph. Byz. v. Ἀπολλωνία.) Pliny names also Cale, perhaps the same as the Calse of the Not. Cale. Eccl. (Prov. As. p. 43.) Conisium, written Κονιοσίνη Conisium. in the same document. Balcea, which Steph. Byz. places near the Propontis, (v. Βαλκεία) is perhaps

^o Arundell's Visit, &c. p. 282. and 278.

Tegium.
Tiare.
Sarnaca.
Lycide.
Thymbre.
Oxyopum.
Lygda-
mum.
Hadriano-
theræ.

Bali-kesri. Tegium, Tiare, Sarnaca, Lycide, Thymbre, Oxyopum, Lygdainum, are unknown. Hadrianotheræ, a place so called from its having been a favourite hunting-seat of the emperor Hadrian, (Dio. Cass. LXIX. 10. Spart. Vit. Hadr. c. 20.) is placed in the Table Itinerary, where the name is corruptly written Hadreanuteba, at the distance of eight miles from Pergamum, and thirty-three from Miletopolis. We know from Aristides that it stood on the road from the latter town to Hadriani, his native city, situated in Bithynia. (I. 500.) It appears from its coins, which are numerous, to have been a place of some note, as it possessed a senate^p. In the Ecclesiastical Notices it is enumerated among the sees of the Hellespontine province. (Hierocl. Synecd. p. 6.) Sestini is inclined to place Hadrianotheræ at *Trikala*, a village distant an hour and a half from *Soma*, which is eight hours from Pergamum : he obtained there a medal of Antinous, struck in that town^q. In that case the distance from Pergamum marked in the Table must be wrong ; it is indeed certain that the distance between that town and Miletopolis is too small^r.

ÆOLIS.

In the course of the description which has just terminated of Mysia and Troas, we have had occasion to speak of several towns which undoubtedly lay just claim to an Æolian origin. It has been already indeed stated, in the introductory section,

^p The epigraph is IEPA ΣΤΝΚΛΗΤΟΣ ΑΔΡΙΑΝΟΘΗΡΙΤΩΝ. Sestini, p. 68. This antiquary, it should be observed, falsely ascribes Hadrianotheræ

to Bithynia.

^q Viaggi diversi, p. 135.

^r Col. Leake's Asia Minor, p. 271.

that the Æolians, who were the first great body of Grecian colonists that settled in Asia Minor, had not long after the Trojan war founded several towns on different points of the Asiatic coast, from Cyzicus to the river Hermus; but it was more especially in Lesbos, which has a right to be considered as the seat of their power, and along the neighbouring shores of the gulf of Elæa, that they finally concentrated their principal cities, and formed a federal union, called the Æolian league, consisting of twelve states, with several inferior towns to the number of thirty. The description of Æolis will naturally connect itself with that of Mysia, though the latter terminates with the Caicus, and will bring us from that river along the shores of the Eleatic gulf to the vicinity of the Hermus, where the Ionian confederacy, which will be more conveniently brought under the head of Lydia, commences. Herodotus, who ascribes to the Æolians a Pelasgic origin, informs us that they occupied at first the plains of Thessaly, then called Æolis; but being driven from thence by the Thessali, who came from Thesprotia, they migrated to Bœotia and Attica, and other parts of Greece. (VII. 176. Cf. Pausan. X. 8.) The Æolian name does not appear however to have been in use before the Trojan war, at least it never occurs in Homer, though he speaks of Æolus and his immediate descendants. The Æolian colonies, according to Strabo, were anterior to the Ionian migrations by four generations. He states that Orestes had himself designed to head the first; but his death preventing the execution of the measure, it was prosecuted by his son Pentilus, who advanced with his followers as far as Thrace. This movement was

contemporary with the return of the Heraclidæ into Peloponnesus, and most probably was occasioned by it^s. After the decease of Pentillus, Archelaus, or Echelatus, his son, crossed over with the colonies into the territory of Cyzicus, and settled in the vicinity of Dascylium. Gras, his youngest son, subsequently advanced with a detachment as far as the Granicus, and not long after crossed over to the island of Lesbos, of which he took possession. Some years after these events, another body of adventurers crossed over from Locris, under the conduct of Clevas and Malaus, two chiefs descended from Agamemnon, and founded Cyme, and other towns on the gulf of Elæa : they also took possession of Smyrna, which became one of the twelve states of the league ; but this city having been wrested from them by the Ionians, the number was reduced to eleven in the time of Herodotus. These, according to that historian, were Cyme, Larissa, Neontichos, Temnus, Cilla, Notium, Ægiroessa, Pitane, Ægææ, Myrina, Grynea. (I. 149.) We learn from the same writer that the Æolians, in common with the other Greek colonists of Asia, had become subject to Crœsus ; but on the defeat of the Lydian monarch by Cyrus they submitted to the conqueror, and from thenceforth were annexed to the Persian empire. (I. 6, 28. II. 90.) They contributed sixty ships to the fleet of Xerxes. (VII. 95.) Herodotus observes of Æolis that its soil was more fertile than that of Ionia, but the climate inferior. (I. 149.) In the time of Xenophon, Æolis formed part of the Hellespontine satrapy held by Pharnabazus, and it appears to have comprised a considerable portion of

^s See Larcher, Chronologie d'Hérodote, tom. VII. p. 417.

the country already described under the head of Troas. (Hell. III. 1, 8.) Wrested by the Romans from Antiochus, it was annexed to the dominions of Eumenes. (Liv. XXXIII. 38. XXXVII. 8. XXXVIII. 39.)

The first town which occurs on the coast after crossing the Caicus is Elæa, the port and naval arsenal of Pergamum. According to some traditions it had been founded after the siege of Troy by the Athenians under the command of Menestheus. (Strab. XIII. p. 622.) Elæa was distant twelve stadia from the mouth of the Caicus, and 120 from Pergamum. (XIII. p. 615.) It gave the name of Elæaticus to the bay in which it stood, and which is also known by that of Cumæus ^{Elæaticus} _{sinus.} now gulf of *Tchandeli*. Strabo estimates the width of the bay at eighty stadia between cape Harmatus, which terminates it to the north, and that of Hydra to the south. (XIII. p. 622.) Harmatus would seem from thence to be a point of land between the mouth of the Evenus and that of the Caicus; but, according to Thucydides, it was situated to the north of the Arginusæ and opposite to Methymna, i. e. I conceive, the territory of that city. (VIII. 101.) The earliest author who mentions Elæa is Scylax; (Per. p. 37.) subsequently it is frequently alluded to in the account of the wars between the kings of Pergamum and those of Macedonia and Syria. (Polyb. XVI. 41, 5. XXI. 8. Liv. XXXVI. 43. XXXVII. 18.) It was besieged in vain by Prusias, king of Bithynia. (Polyb. XXXII. 25, 9. Cf. Artemid. ap. Strab. XIII. p. 622. Plin. V. 32. Ptol. p. 118.) Steph. Byz. asserts that Elæa was formerly called Cidænis. (v. 'Ελαια.) The ruins of this town exist pro-

Grynum
sive Gry-
nea.

bably not far from the village of *Clisiakevi*, on the road from Smyrna to *Bergamah*^a. Next follows Grynium, or Grynea, one of the twelve Æolian cities, (Herod. I. 149.) and celebrated for the worship of Apollo, who derived from thence the surname of Gryneus :

His tibi Grynei nemoris dicatur origo :
Ne quis sit lucus, quo se plus jactet Apollo.

VIRG. ECL. VI. 72.

Sed nunc Italiam magnam Gryneus Apollo,
Italiam Lyciae jussere capessere sortes.

ÆN. IV. 345.

Strabo remarks, that the town belonged in his time to the Myrinaeans ; from whence we must infer that it had much declined from its former prosperity and fame. The temple and oracle, however, still subsisted, at a distance of forty stadia from Myrina. The edifice was remarkable for its size, and the beauty of the white marble of which it was built. (XIII. p. 622.) Grynium is noticed by Scylax, (Per. p. 37.) Xenophon, (Hell. III. 1, 4.) Diodorus, who reports that it was taken by Parmenio, (XVII. 7.) Pliny, (V. 32.) and Steph. Byz. (v. Γρύνιοι.) Beyond was a haven, called the Port of the Greeks, where was an altar erected in honour of the twelve gods. (Strab. XIII. p. 622. Cf. Scyl. Per. p. 37.) Myrina, according to Strabo, was a maritime city, distant forty stadia from Grynium, and eighty from Elæa. (XIII. p. 622.) The Table Itinerary reckons twelve miles from the latter city. Myrina, reckoned by Herodotus among the twelve states of Æolis, (I. 149.) is stated by Mela to have been founded by Myrinus before the others. (I. 18.) We are informed by

Portus
Achivo-
rum.

Myrina.

^a Smith's Account of the Seven Churches of Asia, p. 7.

Xenophon, that it was ceded, together with Grynea, by Artaxerxes to Gongylus, an Eretrian, who had been banished from his native city for favouring the interests of Persia. (Hell. III. 1, 4.) Myrina, as we find from Polybius and Livy, was occupied for some time by Philip, son of Demetrius; but being vanquished by the Romans, he was compelled by that people to evacuate the place. (Polyb. XVIII. 27, 4. Liv. XXXIII. 30.) Mention is made of this town in Cicero's Letters; (ad Fam. V. 20.) and we learn from Tacitus, that it received a remission of imposts, in the reign of Tiberius, on account of the damage it had sustained from an earthquake. (Ann. II. 47.) It appears from Pliny to have subsequently assumed the name of Sebastopolis. (V. 32.) Martial pronounces the penultimate long: (IX. Ep. 42.)^b

Campis dives Apollo sic Myrinis.

But the most considerable of the Æolian cities was Cyme, surnamed Phriconis, because its first founders had settled for some time around mount Phricium in Locris, previous to crossing over into Asia. On their arrival in Æolis, they found that country in the possession of the Pelasgi; but the latter, who had sustained great losses during the Trojan war, were unable to offer any resistance to the invaders, who successively founded Neontichos, and afterwards Cyme, though, according to some traditions, there existed already a place of that name, so called from Cyme, one of the Amazons. (Strab. XIII. p. 628.) Mel. I, 18. Steph. Byz. v. Κύμην.) Cyme was one among the many cities which laid claim to the honour of having given birth to Homer; and if the

^b The coins of this town have the name written two ways, ΜΥΡΙΝΑ and ΜΥΡΕΙΝΑ. Sestini, p. 78.

writer of the life of that poet, which some have ascribed to Herodotus, is to be credited, the ancestors of the great bard were certainly natives of the town to which our attention is now drawn. It is also added, that he received the name of "Ομηρος during his residence there; that word in the Cymæan dialect signifying "one blind." (c. 14.) Whatever may be thought of the pretensions of the Cymæans to be considered as the countrymen of Homer, their right to another great Greek poet is indisputable; I mean Hesiod, whose father, by his own account, was born in Cyme, though he quitted it to reside at Ascra in Bœotia:

"Ος ποτε καὶ τῆδ' ἥλθε, πολὺν διὰ πόντον ἀνύσσεις
Κύμην Αἰολίδα προλιπών, ἐν νη̄ μελαινῃ̄.

OP. ET DI. 634.

Ephorus, one of the most distinguished historians of Greece, but whose works are unfortunately lost to us, was another illustrious native of Cyme. That city, however, notwithstanding the celebrity it derived from the birth of such talented individuals, was by no means generally famed for the genius and wit of its citizens. On the contrary, they were proverbially taxed with stupidity and slowness of apprehension. (Strab. XIII. p. 622. Suid. *"Ονος εἰς Κυμαῖς.* Plut. Vit. Cæs. §. 61.) Herodotus relates, to the honour of the Cymæans, that when Pactyas the Lydian had taken refuge in their city, to escape from the vengeance of the Persians, they would not surrender him up to the officer sent by Cyrus to demand him, but allowed him to escape to Mitylene. (I. 157 seq.) We learn from the same authority, that, under the reign of Darius, the Cymæans, like most of the Greek cities tributary to Persia, were go-

verned by a chief or tyrant possessed of absolute power. When the revolution excited by Aristagoras of Miletus broke out, the Cymæans, satisfied with obtaining their independence, deposed their prince without committing any act of violence against him. (IV. 138. V. 38.) They were, however, quickly reduced to subjection by the Persian forces commanded by Artaphernes, satrap of Lydia. (V. 123.) The remnant of Xerxes' fleet wintered in the harbour of Cyme, after the disastrous engagement off Salamis. (VIII. 130.) Successively held by the Persians, the kings of Syria, and of Pergamum, it was finally annexed to the latter empire by the Romans, at the same time that it was declared free from all taxes. (Corn. Nep. Alcib. c. 7. Polyb. V. 77, 4. XXII. 27, 4. XXXIII. 11, 8. Liv. XXXVII. 11. XXXVIII. 39.) In the reign of Tiberius, Cyme suffered, in common with other cities of Asia, from the terrible earthquake which desolated that province. (Tacit. Ann. II. 47. It still subsisted in the time of Pliny. (V. 32.) And ecclesiastical writings, much posterior to that author, attest its existence as the see of a bishop under the Byzantine emperors^c. Cyme, according to the Itineraries, was nine miles from Myrina, but Strabo reckons only forty stadia. (XIII. p. 622.) Modern writers on comparative geography have generally placed its ruins near the Turkish village of *Sanderli*. "At the edge of the gulf of *Sanderly*, on the right, are seen towers of a wall or castle," says Dallaway, "nearly upon the site of the ancient Cyme. In a large vineyard we were shewn many marble columns of the Ionic

^c Geogr. Sacr. Car. S. Paul. p. 238.

"order ^{d.}." Near the town was a small stream or Xanthus ^{f.} fountain called Xanthus ^{e.} The Hermus flowed a little to the south-east of Cyme, and a mountain which rose between that river and the city bore the name of Sardene, as we learn from the writer of Homer's Life, who quotes these lines as from that poet :

Sardene
mons.

Αἰδεῖσθε ξενίων χεχρημένον ἡδὲ δόμοιο
οἱ πόλιν αἰτεινὴν Κύμην Ἐριώπιδα κούρην
ναιετε, Σαρδήνης πόδα νείατον ὑψικόμοιο.
ἀμβρόσιον πίνοντες ὕδωρ θείου ποταμοῖο
"Ἐρμου δινήεντος, ὃν ἀθάνατος τέκετο Ζεύς.

Adæ.

Larissa
Phriconis.

Adæ, a place pointed out by Strabo, (XIII. p. 622.) on the authority of Artemidorus, between Cyme and cape Hydra, at the distance of forty stadia from the latter, is unknown to other writers. Larissa, sur-named Phriconis, as well as Cyme, and for the same cause, had been, as its name sufficiently attests, a Pelasgic settlement, before the arrival of the Æolian colony in this part of Asia; and Strabo conceives, with reason, that it is the city to which Homer alludes when he says,

'Ιππόθοος δ' ἄγε φῦλα Πελασγῶν ἐγχεσιμώρων,
Τῶν οἱ Λάρισσαν ἐριβώλαχα ναιετάασκον. IL. B. 840.

When the Æolians had occupied the country, they transferred the Pelasgi to their new city of Cyme : Larissa, however, was not abandoned, since Herodotus reckons it among the twelve cities of Æolis. (I. 149. Strab. XIII. p. 621.) The author of Homer's Life states, that the poet, in going from the Hermus

^d Constantinople, p. 290. Mannert, tom. VI. p. 390. D'Anville assigns to it the site of Nemourt, but this is more probably Myrina. Geogr. Anc. p.

102. fol.

^e As appears from the coins of Cyme, which are numerous. Sestini, p. 78.

to Cyme, passed by Neontichos and Larissa. (§. 11, 12.) In the Hellenics, Xenophon, to distinguish this city from others of the same name, styles it the Egyptian Larissa, because the elder Cyrus had established there a colony of Egyptian soldiers. (Hell. III. 1, 5. Cyrop. VII. 1, 21.) Larissa appears from the same historian to have been a place of great strength, as it was besieged in vain by Thimbron. (Hell. loc. cit.) Strabo remarks, that it was deserted in his time. (XIII. loc. cit. Cf. Plin. V. 32. Steph. Byz. v. Λάρισσα^f.)

Neontichos, founded by the Æolians as a temporary fortress, on their first arrival in the country from Locris, was, according to Strabo, thirty stadia from Larissa. Pliny leads us to suppose it was not on the coast, but somewhat removed from it; and we collect from a passage in the Life of Homer, already quoted with reference to Larissa, that it was situated between that town and the Hermus. Herodotus names Neontichos among the leading cities of Æolis. (I. 149.) In Homer's Life it is stated, contrary to Strabo's authority, that Neontichos was founded eight years later than Cyme. (§. 9. Cf. Steph. Byz. v. Νέοντιχος.) The ruins of this town should be sought for on the right bank of the Hermus, and above *Giuzel-hissar*, on the road from Smyrna to *Bergamah*.

Temnus, another Æolian town frequently mentioned by Greek writers, was situated apparently on the opposite bank of the river, in a commanding situation overlooking the plains of Cyme, Phocæa,

^f Sestini assigns doubtfully to the Æolian Larissa some brass medals, with the legend ΛΑ and ΛΑΠΙ. p. 78.

and Smyrna. (Strab. XIII. p. 622.) I say apparently, because there is a passage in Pausanias which would lead us to suppose it stood on the northern side of the Hermus, opposed to mount Sipylus. (Eliac. I. 13.) If, however, the Table Itinerary is correct in estimating the distance between Cyme and Temnus at thirty-three miles, there could be no doubt as to the southern situation of the latter town with reference to the Hermus; but this number of miles exceeds even the real distance from Cyme to Smyrna, which, by the best maps, does not appear to equal thirty. Most antiquaries are inclined to place Temnus at *Menimen*, a large village to the north of Smyrna. Chandler states, that “it is situated on a rising ground by the Hermus, “and appears as a considerable place, with old cas-“tles^{g.}” It seems, from the account of the same traveller, that “the river has, during the lapse of “ages, undergone great changes in its course. The “mouth especially has been continually shifting and “changing place, in consequence of the encroach-“ments made on the sea.” Pliny states that Temnus, which was once situated at the mouth of the Hermus, no longer existed in his day. (V. 31.) Xenophon speaks of it as a small town. (Hell. IV. 8, 5. Cf. Herod. I. 149.) Polybius states that the town of Temnus, after being subject to Achæus, surrendered to Attalus, when that prince invaded Æolis. (V. 77, 4.) The same historian informs us, that near the city there was a temple sacred to Apollo Cynius, which was plundered and burnt by Prusias, king of Bithynia. (XXII. 25, 12. Cf. Cic.

^g Asia Minor, p. 93.

pro Flac. §. 18, 20, 21. Tacit. Ann. II. 47. Steph. Byz. v. Τῆμνος^b.)

Ægæ was situated on the same range of hills as *Ega*. Temnus, (Strab. loc. cit.) but more inland. (Scyl. Peripl. p. 38. Plin. V. 32.) Herodotus calls it *Aiyaiā*, and the inhabitants *Aiyaeis*. (I. 149. V. 67.) Xenophon, *Aiyēis*ⁱ. (Hell. IV. 8, 5. Polyb. V. 77, 4. Tacit. Ann. II. 47.) In Ptolemy, the name of this town is corruptly written *Ægara*. The Ecclesiastical Notices enumerate it among the bishoprics of the Hellespontine province. (Hierocl. Syn. p. 660^k.)

Ægiroessa, one of the twelve Æolian cities, as *Ægiroessa*. Herodotus reports, does not occur in any other historian or geographer; but it is not unlikely that the name was subsequently changed; and, in the absence of better information, we may conjecture that the Attalia Agroira, which Stephanus assigns Attalia to Lydia, (v. Ἀττάλεια,) but Pliny to Æolis, (V. 32.) Agroira. is no other than the town alluded to by the father of history.

Posidea, mentioned by Pliny together with Attalia Posidea. Posidea, has escaped the observation of other geographers.

Another Æolian town of uncertain position is Parparon, called by some also Perine, where it is reported that Thucydides ended his days. (Steph. Parparon sive Perine. Byz. v. Παρπάρων.) The same geographer ascribes to Æolis a river and island named Potamosacon. Potamosacon. (v. Ποταμοσάκων.) Pliny assigns to the "jurisdictio con. "Pergamena," the Begmenteni, Hieracometæ, Per-

^b The legend on the coins of Temnos is ΤΗΜΝΟΣ and ΤΗΜ-ΝΕΙΤΩΝ. Sestini, p. 78.

ⁱ The coins of Ægæ acknow-

ledge both forms, and also that of *Aiyaeis*, which indeed is more frequent. Sestini, p. 77.

^k Geogr. Sacr. Car. S. Paul.

pereni, Tiareni, Hierolophienses, Attalenses, Pantenses, and others.

Lesbos
insula.

Having terminated the periplus of the Æolian coast, we will conclude this section with some account of Lesbos, which, both from its position and historical associations, naturally finds a place here as one of the most celebrated and flourishing establishments formed by the Æolians.

According to Strabo, the circuit of the island was 1100 stadia, (XIII. p. 616.) in which number he agrees with Agathemerus. (p. 17.) But Pliny reckons 195, and Isidorus 168 miles; both of which computations considerably exceed the number given by Strabo. It is probable that the latter geographer measured his distances only from cape to cape, and neglected the windings of the coast. The same writer reckons 560 stadia from the promontory of Sigrium to that of Malea, the two extreme points of the island from north to south; this is therefore to be considered as its greatest length: its breadth was most considerable between cape Sigrium and the headland opposite to the little island of Leuce, and not far from the town of Methymna, distant, according to Strabo, 210 stadia from cape Sigrium. The narrowest part of the island lay between Pyrrha and Ægireus, the former being situated in a bay deeply indenting the western coast. (Strab. loc. cit.)

The earliest inhabitants of this large and fertile isle appear to have been of Pelasgic origin, as may be collected from the account of Strabo, and the appellation of Pelasgia given to it by Diodorus (V. 80.) and Pliny. (V. 39. Cf. Steph. Byz. v. Μέταον.) It is said to have derived from Lesbus, a grandson of

Æolus, (Diod. Sic. loc. cit.) the name by which it is best known in history, and which, according to Homer, was attached to it in the time of which his poem treats :

Δώσω δὲ ἐπτὰ γυναικας ἀμύμονας, ἔργ' εἰδυίας,
Λεσβίδας· ἄς, ὅτε Λέσβον ἐϋκτιμένην ἔλεγ αὐτὸς,
Ἐξελόμην, αἱ κάλλει ἐνίκων φῦλα γυναικῶν.

IL. I. 128.

Καὶ σε, γέρον, τὸ πρὸν μὲν ἀκούομεν ὄλβιον εἶναι,
Οσσον Λέσβος ἄνω, Μάχαρος ἔδος, ἐντὸς ἐέργει,
Καὶ Φρυγή καθύπερθε, καὶ Ἐλλήσποντος ἀπείρων.

IL. Ω. 543.

Though the poet does not name any of the Lesbian cities, it is clear from the epithet of *ἐϋκτιμένη* that they were numerous and flourishing ; the last quotation is also calculated to give a very favourable idea of the fertility and commerce of the island in this early age. The first Greek colony, according to Strabo, was led into the island by Gras, son of Archelaus, and great grandson of Orestes, who had already formed settlements in Mysia and Troas. (XIII. p. 582. Cf. Pausan. III. 2. Hom. Vit. §. 38.) So prosperous was the condition of the Lesbians, that Strabo does not scruple to consider them as the head of the Æolian states. (XIII. p. 616.) This was especially the case after the cities of the continent had been subjugated by Croesus and the Persians. For though they sustained a severe defeat by sea from the Samians under Polycrates, (Herod. III. 39.) they continued to hold a distinguished place among the maritime powers of Greece. Having taken an active part in the revolt of Aristagoras, (Herod. VI. 5, 8.) they became exposed to the vengeance of Darius, who sent a fleet against

their island, after the defeat of Lade, and reduced all the male population to slavery. (VI. 31.) Delivered from the Persian yoke by the victories of Salamis and Mycale, the Lesbians readily joined the combined fleets, and contributed with zeal to the exigencies of the war. Athens having at this time acquired a marked ascendancy over the confederate states, the Lesbians found themselves no longer in the same situation ; for though the Athenians affected to treat them with deference as allies, it was apparent that they were in reality only dependents and subjects. (Thuc. III. 10.) Galled by the yoke, which began to press heavily upon them, and urged by the Bœotians, who were of kindred Æolian origin, the whole island, with the exception of Methymna, seized the opportunity offered by the Peloponnesian war for joining the Spartan alliance, and revolting from Athens. Unhappily for the Lesbians, the energy and promptitude of that power were met only by dilatoriness and indecision on the part of the Lacedæmonians, and the revolt was soon crushed by the capture of Mitylene, the capital of the island, and the chief seat of the rebellion. (Thuc. III. 50.) The Lesbians made another attempt to emancipate themselves from Athenian subjection after the disasters experienced by that people in Sicily ; (VIII. 5.) but it was not till the siege and downfall of Athens ensued, that they succeeded in obtaining that freedom which they had so long wished for. So much of the history of this celebrated island is comprised in that of Mitylene, that it will be better to proceed at once to give some account of that city, and to commence from thence our circuit of the Lesbian coast.

Mitylene, or Mytilene, for the name is written Mitylene. both ways, is said to have been so called from Mitylene, daughter of Macareus. (Steph. Byz. v. Μυτιλήνη. Diod. Sic. V. 80.) Whoever was its founder, we can have no doubt, from the superior advantage of its maritime situation, that it was occupied in preference to any other locality by the Æolian colonists, since it possessed two harbours; one, turned towards the south, capable of being closed, and fit for the reception of triremes, with docks for fifty ships; the other, still more extensive and deep, and defended by a mole. A small island, on which part of the town was built, added still further to the security of the harbour off which it lay. (Strab. XIII. p. 617. Pausan. VIII. 30.) Besides these natural advantages, Mitylene was greatly adorned and beautified by art; so that it not only became the seat of commerce, but presented attractions which few other spots could equal. It could boast of having given birth to Sappho and Alcæus, and to the historians Myrsilus and Hellanicus. Pittacus, one of the seven sages of Greece, long presided over her counsels, and directed her affairs; and though he was invested with unlimited power, he only used it to put down faction, and to favour the ends of benevolence and justice. (Strab. XIII. p. 617. Plut. tom. IX. p. 265, 405. Diog. Laert. I. 75.) During his administration, Mitylene became engaged in a contest with the Athenians, then governed by Pisistratus, for the possession of Sigeum, on the coast of Troas. The war was put an end to by the mediation of Periander of Corinth. (Herod. V. 94.) Mitylene was at that time the most flourishing of the Æolian states; it enjoyed a profitable trade with Egypt, (Herod.

II. 178.) and possessed several dependencies on the Asiatic coast. (Strab. XIII. p. 317.) In the reign of Darius, the Mitylenians were for a time subject to the authority of Coes, one of their citizens, who had obtained the sovereignty from the Persian monarch, in reward for an important service he had rendered that prince during the Scythian expedition, (V. 11.) but on the breaking out of the Ionian revolt they deposed Coes, and put him to death. (V. 38.)

In the beginning of the Peloponnesian war, we find the Mitylenians taking the lead in the formation of a plan for revolting from Athens, and sending deputies to the Peloponnesian assembly to demand immediate assistance. Had the Spartans displayed the same zeal and activity in supporting their new allies, which the latter did in resisting the Athenians, Lesbos must have been delivered, and all the dependencies of Athens probably wrested from her grasp. But on the first news of the revolt, a considerable squadron, under the command of Paches, was despatched to Lesbos, and the Mitylenians, after an unsuccessful action, were blockaded in their harbour; and the town was soon besieged by sea and land. The citizens, however, resolutely defended themselves, and had they been adequately supported, would ultimately have triumphed over the enemy. But the injudicious advice of Salæthus, the Spartan emissary, who recommended that arms should be given to the populace, proved fatal to their cause, since the people once armed, prevailed over the civic body, and opened the town to the Athenians. The folly of the Mitylenians in this respect is only surpassed by the cruelty of their

enemies; and we shudder on reading Thucydides, to think how nearly a whole population had been swept away, to satisfy the vengeance of a mob, inflamed by the arts of a worthless demagogue. (Thuc. III. 2—50.) After this unsuccessful attempt to cast off their chains, the Mitylenians remained in passive subjection, till the losses experienced by Athens in Sicily once more induced them to revolt. The attempt was however feeble and premature, and was soon put down. (VIII. 22, 23.) Towards the close of the Peloponnesian war, we see Conon, the Athenian general, defeated off Mitylene by the Spartan Callicratidas, and blockaded in the harbour. He was soon however delivered, by the total defeat of the Peloponnesian fleet off the islands of Arginusæ. (Xen. Hell. I. 6, 10. et seq.) After these events, a long interval elapses before our attention is drawn to the affairs of Mitylene by any remarkable occurrence. The citizens of that town having favoured the cause of Mithridates against the Romans, were severely punished, first, by Lucullus, who slew a great number of them in an engagement, (Plut. Lucull.) and again, by M. Thermus, who besieged their city, and having taken it by assault, gave it up to be plundered and destroyed. (Liv. Epist. LXXXIX. 36.)

The friendship which Pompey felt for the historian Theophanes, a native of Mitylene, proved afterwards highly beneficial to his country; since by his influence it was not only raised from ruin, and restored to liberty, but rendered more prosperous and flourishing than before. The son of Theophanes, named Marcus Pompeius after his father's patron, succeeded also in conciliating the favour of Augustus and Tiberius for his countrymen. During their

reigns, Mitylene held a distinguished rank among the first cities of the empire. (Strab. XIII. p. 617. Plut. Pomp. Vell. Patrc. II. 18.)

Laudabunt alii claram Rhodon, aut Mitylenen.

HOR. OD. I. 7.

Pliny styles it “libera Mitylene, annis MD potens.” (V. 39¹.) The history of this city may be further illustrated by a reference to Polyb. XI. 5, 1. Cic. Ep. ad Fam. IV. 7. Senec. ad Helv. c. 9. Athenæus praises its shell-fish and wine, (III. 86. E. 92. D. I. 30. B.) *Metelin*, as it is now called, is still a considerable place, and gives its name to the whole island^m.

Methymna. Next in importance to Mitylene was Methymna, an Æolian colony, (Herod. I. 151. Scyl. p. 36.) situated near the northernmost point of the island, and distant sixty stadia from the coast of Troas, lying between Polymedium and Assus. (Strab. XIII. p. 616.) It was the birthplace of Arion, the celebrated musician, whose adventure with the dolphin is related by Herodotus, (I. 23.) Strab. (loc. cit.) and of the historian Myrsilus, (Steph. Byz. v. Μῆθυμνα.) The territory of this town was contiguous to that of Mitylene, a circumstance which appears to have created a considerable degree of rivalry between them, and probably induced the Methymnæans to adhere to the Athenians, while their neighbours were bent on detaching themselves from that power. (Thuc. III. 2, 18.) As a reward for their fidelity,

¹ The imperial coins of Mitylene exhibit an uninterrupted series, from Augustus to Valerian. The epigraph is invariably, I believe, ΜΤΙΛΗΝΑΙΩΝ, and not ΜΙΤΤΛΗΝΑΙΩΝ. Ses-

tini, p. 79.

^m For an account of its present state, see Tournefort, p. 149. and Le Bruyn, Voyage au Levant.

the Methymnæans were exempted from contributions in money, (VI. 85. VII. 57.) Towards the close of the Peloponnesian war, Methymna fell into the power of the Spartan commander, Callicratidas, who, though urged to treat the citizens with severity, and to sell them as slaves, refused to comply with the advice, declaring, that as long as he was admiral, no Greek, as far as lay in his power, should be enslaved. (Xen. Hell. I. 6, 8.) Theopompus, who is quoted by Athenæus, (X. 442. F.) speaks of a tyrant of Methymna, named Cleomenes, who was at some pains to reform the licentious manners of his subjects. The wine of Methymna was held in great estimation;

Gargara quot segetes, quot habet Methymna racemos.

OVID. ART. AM. I. 57.

hence Bacchus was frequently called the god of Methymna, (Athen. VIII. 363. B. Cf. Pausan. X. 19.) Further mention of this city is made in Polybius, (XXXIII. 11.) Livy, (XLV. 31.) Diod. Sic. (XIII. 76.) Pliny, (V. 39.ⁿ) The remains of Methymna are to be seen near the village of *Molivo*, at the northern extremity of the island, where Ptolemy has placed it. To the south of this place is a range of hills, called *Leptimo*, which probably answers to the Mons Lepetymnus of Pliny and others. (Antig. Caryst. c. 17.) The same geographer names along with it Ordymnus, Macistus, Creon, and Olympus, (V. 39.) Mount Ordymnus is called Ordynus by Theophrastus. (H. Pl. III. 18.) Ægireus was a small place belonging to Methymna, and situated,

^a In the autonomous and imperial coins of Methymna, the inscription is both MAΩTMNAI-

ΩN and MEΩTMNAIΩN; in the more recent ones, only MH-ΩTMNAIΩN. Sestini, p. 79.

as Strabo reports, on the eastern coast of Lesbos, where that island is only twenty stadia broad. (XIII. p. 616.)

Sigrium
prom.

Antissa.

Cape Sigrium forms the extreme point of the island to the north west. (Strab. loc. cit.) It retains the name of *Sigri*. Near this headland was situated the ancient town of Antissa, (Herod. I. 151. Scyl. p. 36.) the birthplace of Terpander, the celebrated musician and poet, who is said to have first used the lyre with seven strings^o. (Clem. Alex. Strom. I. p. 308. Strab. loc. cit. Steph. Byz. v. Ἀντίσσα.) This place joined the Mitylenians in their revolt against Athens, and was in consequence attacked by the Methymnæans; but they were repulsed with loss by the inhabitants. (Thuc. III. 18.) On the reduction, however, of Mitylene, Antissa submitted to the Athenian forces. (III. 28.) Some centuries later, this town having sided with Antiochus against the Romans, was destroyed by the latter, and the lands were given up to Methymna. (Liv. XLV. 31. Plin. V. 39.) The ruins of this town were observed by Pococke, a little to the north of *Cape Sigri*, on the site called *Calas Limneonas*^p.

Eressus.

Eressus was situated on a hill, at a distance of twenty-eight stadia from C. Sigrium. It derives celebrity from having given birth to Theophrastus. The real name of this distinguished naturalist and philosopher was Tyrtamus; that of Theophrastus having been bestowed upon him by his master, Aristotle, on account of his superior eloquence. Phanias, another disciple of the great Stagirite, was likewise

^o The head of a musician engraved on the coins of Antissa is that of Terpander, and not of Orpheus, as Sestini supposes,

p. 79.

^p Travels in the East, tom. I. b. 3. c. 4.

a native of Eressus. (Strab. loc. cit. Steph. Byz. v. Ἔρεσσος.) Eressus revolted from Athens, together with Mitylene, but was reduced by Paches. (Thuc. III. 18. 35. It again revolted towards the end of the war, when it was besieged by an Athenian force, under Thrasybulus, but he was called away from thence, by the sailing of the Peloponnesian fleet into the Hellespont. (Thuc. VIII. 100. Diod. Sic. XIV. 94.) According to Archestratus, quoted by Athenæus, Eressus was famous for the excellence of its wheaten flour.

εύχάρπου χριθῆς καθαρῶς ἡσκημένα πάντα
ἐν Λέσβῳ, κλεινῆς Ἐρέσου περικύμονι μαστῷ
λευκότερ' αἰθερίας χιόνος. θεοὶ εἶπερ ἔδουσιν
ἄλφιτ' ἐκεῖθεν ἵων Ἐρεμῆς αὐτοῖς ἀγοράζει.

This town is mentioned by Herodotus, (I. 151.) Scylax, (p. 36.) Pliny, (V. 39.) P. Mela, (I. 18.) and Ptolemy. The site yet preserves the name of *Eresso*^q.

Pyrrha was situated in a deep bay, with a narrow Pyrrha. inlet, called from thence the Euripus of Pyrrha, (Aristot. ap. Athen. III. 88. C. Strab. XIII. p. 617.) and which answers to the Port *Caloni*. It sided with Mitylene in the Lesbian revolt, but was reconquered by Paches. (Thuc. III. 18, 25, 35. Cf. Scyl. p. 36. Steph. Byz. v. Πύρρα.) Strabo reports, that in his time the town no longer existed, but the suburbs and port were still inhabited; the latter was eighty stadia from Mitylene. (XIII. p. 618.) Pliny states that the town was destroyed by the sea. (V. 39.) Agamede, a place situated near Pyrrha, had like- Agamede. wise disappeared in that writer's day. (Cf. Steph.

^q Pococke, Travels in the East, tom. I. b. 3. c. 4. Mannert, Geogr. tom. VI. p. 444. On its

coins the name of this town is always written with one Σ. ΕΠΕΣΙΩΝ. Sestini, p. 79.

Hiera. Byz. v. Ἀγαμῆδη.) Hiera, though no longer existing when Pliny wrote, seems to have left its name to the gulf of *Jero*, called also *Olivieri* by the Franks^r.

Malea pro- (Plin. V. 39.) Our periplus of Lesbos closes with
monto- Cape Malea, the extreme point of the island to the
rium. south east, and nearly opposite to the promontory of
Cane, in Æolis. Strabo states that it waⁿt seventy
stadia from Mitylene, and 100 from Pyrrha. (XIII,

Malea lo- p. 617.) Mention is made of Malea in Thucydides,
cus. (III. 4.) where he seems to place it to the north of
Mitylene; if there is no error in the text, this must
apply to a place or station near the last mentioned
town, where perhaps the temple of Apollo Maloeis,
held in great veneration by the inhabitants, was
situated. (Thuc. III. 3.) The cape also, it should
be observed, would have been a bad station for the
Athenian fleet and camp, nor could they have been
joined there easily by the Methymnæan forces.
(Thuc. III. 4.) Xenophon distinctly mentions Cape
Malea as the station occupied by the fleet of Calli-
cratidas, before the sea-fight off Arginusæ; but
when he adds, that it is ἀντίον τῆς Μυτιλήνης, he
means probably over against, and in a line with
Mitylene. (Hell. I. 6, 19.) Its modern name is
Cape *Maria*.

Arisba. To complete our nomenclature of the Lesbian
cities, we may add the names of Arisba, destroyed,
as Pliny reports, by an earthquake. (V. 39.) Herodotus states, that it was conquered by the people of
Methymna. (I. 151. Cf. Steph. Byz. v. Ἀρίσβη.
Geren. Strab. XIII. p. 590.) Geren, a town or village so
called from Geren, the son of Neptune. (Steph. Byz.
Issa. v. Γέρην.) Issa, named also Himera. (Id. v. Ἰσσα.)

^r Pococke, tom. I. b. 3. c. 4.

Metaum, founded by Metas, a Tyrrhenian chief. Metaum. (Id. v. Μέταυ.) Nape, a spot situated in the plain country near Methymna. (Strab. IX. p. 426. Steph. Byz. v. Νάπη.) Xanthus, a town of Lesbos. (Id. v. Ξάνθος.) Penthile. (Id. v. Πενθίλη.) Polium, a spot with a chapel (*ἱρῷον*) sacred to Tantalus. (Id. v. Πόλιον.) There was also a mountain of the same name with that hero. (Id. v. Τάνταλος.) Brisa, a promontory where was a temple of Bacchus. (Id. v. Βρίσα. Androt. ap. Etym. M.) Hyperdexion, a spot where stood the shrines of Jupiter Hyperdexius and Mi-^{Hyper-}nerva Hyperdexia. (Id. v. Τύπερδέξιον.)

Between Lesbos and the continent of Asia are several islets noticed by ancient geographers. Strabo reckons twenty, and observes that the name of Hecatonnesi was applied to the group, from Hecatus, or Apollo, the deity most revered throughout the adjoining country. (XIII. p. 618.) Herodotus, however, writes the name 'Εκατὸν Νῆσοι, (I. 151.) as if it was formed from the numerical adjective; and this derivation is more simple and probable than that of Strabo. (Cf. Steph. Byz. v. Εκατόνησοι.) The modern appellation of these islets is *Musco-nisi*^s. The largest of these contained a city of Æolian origin, according to Herodotus, who does not however mention it by name. (I. 151.) But from other writers we learn that it was called Pordoselene, or Porose-^{Pordose-}lene; the latter form being adopted, as Strabo con-^{lēne, sīv}tends, by those who wished to avoid the indelicate allusion presented by the former^t. Scylax writes Pordoselene, (Peripl. p. 36.) as well as Steph. Byz. and Hesychius. Pliny, who erroneously places it

^s Note to the French Strabo. πορδὴ, "crepitus ventris," tom.

^t This being formed from III. p. 277.

near Ephesus, (V. 38.) and Ptolemy, (p. 136.) Poroselene ^u. This town is known to us as a bishop's see in the seventh century. (Hierocl. p. 686.) Pliny names besides the following islets, Sandaleon, Leucæ, a group of five; Cydonea, one of them, was remarkable for a hot source. (V. 39.)

Sandaleon
insula.

Leucæ in-
sulæ.

Cydonea
insula.

Arginusæ.

The Arginusæ, so celebrated in Grecian history for the naval victory gained by the ten Athenian generals over the Spartan fleet, but so barbarously and ungratefully turned against them by their own countrymen, are three small islands, situated close to the promontory of Cane, and about 120 stadia from Mitylene. Thucydides leads us to infer there was a spot of the same name on the neighbouring coast of Æolis. (VIII. 101. Diod. Sic. XIII. 98. Cf. Xen. Hell. I. 6, 19. seq. Plin. V. 39. Harpocr. v. Ἀργινοῦσαι.)

^u The coins of this town invariably, I believe, exhibit the latter form, ΠΟΡΟΣΕΛΗΝΕΙΤΩΝ. Sestini, p. 75.

SECTION III.

BITHYNIA.

Origin and history of the Bithynians—Boundaries of the province under the Roman empire—Description of the coast on the Propontis—Interior of the country around mount Olympus and the lake Ascanius—Nicea and Nicomedia, with the adjoining bays—Chalcedon and the Thracian Bosphorus—The Euxine—Coast of that sea as far as the Sangarius—The Ma-riandyni and Caucones—Interior of eastern Bithynia.

THE early revolutions which Asia Minor seems to have experienced in regard to its population, both before the Trojan war and immediately after that period, render it, as Strabo justly observes, a matter of no small intricacy to assign to contiguous nations their distinctive limits and proper territories. The Greek geographer has felt this to be peculiarly the case with the province of Bithynia, which appears to have been successively occupied, with varying boundaries, by the Phrygians, Mysians, and Bithynians. The latter people, as their name sufficiently attests, became the permanent possessors of the country; but this event cannot be considered as prior to the siege of Troy, since Homer nowhere mentions the Bithynians, but invariably designates the people of that country by the name of Mysians and Phrygians. (Il. B. 862. N. 792. Strab. XII. p. 565.) Strabo has also proved that the Mysians not only

occupied the shores of the lake Ascanius and the plains of Nicæa, but that they extended as far as Chalcedon and the Thracian Bosphorus. (XII. p. 566.) Though we cannot precisely fix the period at which the Bithyni settled in the fertile district to which they communicated their name, we can have no doubt as to the country from whence they came, since the testimony of antiquity is unanimous in ascribing to them a Thracian origin. Herodotus in particular asserts, that according to their own traditions they came from the banks of the Strymon, and having been driven from their country by the Teucri and Mysi, crossed over into Asia. (VII. 75.) Thucydides also and Xenophon expressly term them Bithynian Thracians. (Thuc. IV. 75. Xen. Hell. I. 3, 2. III. 2, 2.) The latter writer traversed their country on his return into Greece with the ten thousand, and had ample opportunities of knowing, both from their customs and language, that they were of the same great family with the Thracians of Europe. (Anab. VI. 4, 1.) Some geographers have noticed a distinction to be observed in regard to this people, namely, that the appellation of Bithyni was properly applicable to the inland population, while that of the coast took the name of Thyni. (Apoll. Rhod. II. 462. Eustath. ad Dionys. Perieg. 793. Plin. V. 32.) But historically speaking, it is of little value, and may therefore safely be neglected. The Bithynians, as Herodotus informs us, were first subjected by Croesus. (I. 28.) On the dissolution of the Lydian empire they passed under that of Persia, and their country became the seat of a satrapy, sometimes known in history by the title of Dascylium, sometimes of the Hellespont,

but more commonly of Bithynia. The people lived principally in villages; the only considerable towns being situated on the coast, and inhabited by Greek colonists. This state of things lasted till the death of Alexander, who had taken military possession of the country after the defeat and expulsion of the Persian troops from the peninsula.

On the decease of the king of Macedon we find Botirus, the son of Dydalsus, a Thracian chief, seizing upon Astacus, a Greek town on the sea-coast, and after defeating Calantus, the officer who commanded the Macedonian forces in the country, establishing an independent principality which he transmitted, through his lineal descendants Bas and Xipœtes, to Nicomedes, son of the latter, who after the death of Lysimachus first assumed the title of king of Bithynia. (Memn. Exc. ap. Phot. p. 720. seq.) He gave his name to the city of Astacus, which from henceforth was called Nicomedia, and became the capital of the new kingdom. (Pausan. V. 12.) Nicomedes was succeeded by his son Prusias, surnamed Zeilas^a, (Polyb. XXXVII. 2, 1.) and he again by Prusias, the Hunter, who was long engaged in war with Attalus, king of Pergamum, and is well known in history for having abandoned Hannibal to his pursuers, when that great man sought refuge at his court from the animosity and vindictiveness of the Romans. (Liv. XXXIX. 46—51.) This sovereign had extended considerably the limits of the Bithynian empire by the accession of some important towns conceded to him by his ally, Philip of Macedon, (Strab. XII. p. 563. Liv. XXXII. 34.) and several advantages gained over the Byzantians and king

^a See Schweighæuser's note to this fragment.

Attalus; but the latter was finally able to overcome his antagonist, by stirring up against him his own son Nicomedes, who, after drawing the troops from their allegiance to his father, caused him to be assassinated. (Liv. Epit. L. Justin. XXXIV. 4.) Nicomedes, after this unnatural crime, ascended the vacant throne, and reigned for several years. He was succeeded by his son Nicomedes Philopator, who found himself engaged not long after his accession in a war with Mithridates; and though he was supported by the Roman forces, he was compelled, after sustaining repeated defeats, to fly from his dominions, and abandon them to his victorious enemy. (Appian. Bell. Mithr. c. 7—20.) On his death, which occurred soon after these events, he bequeathed his kingdom to the Roman people, and, in pursuance of this arrangement, Bithynia, after the overthrow of Mithridates, was annexed to the empire. (Liv. Epit. XCIII. Plut. Cæs. §. 3.) Like other Asiatic sovereigns, the kings of Bithynia are said to have been sensual and effeminate. (Polyb. XXXVII. 2. Cic. Verr. V. 11.) The interior of the country was mountainous and woody; (Xen. Anab. VI. 5. Nicet. Chon. p. 128.) but near the sea it was covered with rich and fertile plains, thickly spread with towns and villages. The produce consisted in grain of every sort; wine, cheese, figs, and various kinds of wood. (Xen. Anab. VI. 4, 4. Strab. XII. p. 565. Plin. XI. 42.)

Bithynia, properly so called, is confined to the west by the Rhindacus, which separates it from Mysia, and to the east by the river Sangarius; but if we include within its limits, as most geographers have done for the sake of convenience, the districts

of the Caucones and Mariandyni, we shall remove the boundary on that side to the river Parthenius, where Paphlagonia commences. On the north it is bounded by the Propontis and the Euxine, and on the south it is contiguous to the provinces of Phrygia and Galatia: the boundary on that side being formed apparently by the chain of the Bithynian Olympus, which runs nearly parallel with the Euxine, and extends its ramifications beyond Paphlagonia as far as Pontus and the river Halys. The western portion of Bithynia has received from the Turks the name of *Khodavendkhiar*; and that situated on the Euxine and around the Bosphorus they call *Kodjaili*.

Commencing our survey of the Bithynian coast from the Rhyndacus, where that of Mysia terminates, and travelling eastward, the first place which we arrive at is Dascylum, which was once of sufficient note to give its name to the Persian satrapy, under which Mysia and Bithynia were comprehended. (Herod. III. 120, 126. VI. 33.) Alexander sent Parmenio to occupy this town after the battle of the Granicus. (Arrian. I. 17.) Strabo informs us it gave its name to the Palus Dascylitis, near which it stood; (XII. p. 575.) and Stephanus Byz. also acknowledges this lake; (v. Δασκύλιον,) but Eustathius confounds it with the Aphnitis of Strabo; (ad Il. B. 824.) and in this respect he seems only to follow that geographer himself. (XII. p. 587.) Dionysius of Halicarnassus, on the other hand, seems to suppose that the lake of Dascylum is the same as the Palus Ascania; (Ant. Rom. I.) but this is likewise an error; for modern researches establish the existence of a large piece of water on

the right bank of the Rhyndacus, and not far from the mouth of that river, in a tract of country to which the name of *Diaskilo* is still attached ^b. P. Mela (I. 19.) and Pliny (V. 32.) write Dascylos. A bishop of Dascylia in Bithynia is mentioned in Ecclesiastical History. (Conc. Quin. p. 1194.) From Xenophon we learn that Pharnabazus, the satrap of Bithynia and the Hellespont, had his principal seat and estate at Dascylum. He represents it as situated in a rich and plentiful country, thickly studded with large villages. The parks were beautifully laid out, and abounded in animals for the chase. A river well stocked with fish ran through the grounds, and the woods supplied every sort of feathered game. This fine estate was completely ruined and devastated by the troops of Agesilaus, during the war he carried on against Pharnabazus in Asia. (Xen. Hell. IV. 1, 8, et seq.) The river here mentioned by Xenophon is probably that stream which flows from mount Olympus, near *Broussa*, and, after forming the lake which took its name from Dascylum, joins the Rhyndacus near its exit into the Propontis. The Turks call this river *Oufersou*, or *Niloufer*, and I imagine it answers to the

Odrysses ^{fl.} cited by Strabo. (XII. p. 551.)

Speaking of the Halizones, or Alazones, a people mentioned by Homer, this ancient writer, in his Periegesis, stated, “that Alazia, their principal town, “ was near the Odrysses, which flowed from the “ west, from the lake Dascylitis, and after travers-“ ing the Mygdonian plain joined the Rhyndacus. “ Alazia is now deserted, but there are several small “ towns inhabited by the Alazones, whose country

^b Note to the French Strabo, tom. IV. b. xii. p. 115.

" is traversed by the Odrysses. Apollo is especially revered there, particularly in those parts which border on the territory of Cyzicus." This description, as may be seen from the map, agrees very well with the *Niloufer*, except in one circumstance, which, it must be confessed, is a very material one. That river, instead of flowing, as the Odrysses of Hecataeus, from west to east, runs in the opposite direction. The Macestus is the only river which would fulfil the condition of falling into the Rhynacus from the west, but it comes from the lake of Miletopolis, not the Dascylitis. Again, it may be observed, that Menecrates of Elaea placed the Halizones in the mountains above the coast of Myrlæa, which agrees very well with the topography of Hecataeus and the course of the *Niloufer*. (Strab. loc. cit.) Pliny also favours our supposition by the mention of a river Horisius, which he connects with the Rhynacus, and which can scarcely be identified with any other stream than the Odrys-
ses of Hecataeus, and the modern *Niloufer*. To the east of Dascylum follows the Gebes, or Gelbes,
Gebes, sive
Gelbes fl. an obscure river unknown to every geographer but Pliny. (V. 32.) The same author places inland, and on the banks of this river, the town of Helgas,
Helgas, sive
Booscœte, or Booscoete, *Boὸς κοίτη*, afterwards called Germani-
postea Ger-
manicopo-
lis. copolis. Mannert is inclined to identify this place with the Cæsarea of Ptolemy (p. 118.) and Hiero-
Cæsarea. cles. (p. 693.) Dio Chrysostom also mentions a small town of that name very near Prusa. (Orat. XLVII. p. 526.)

Myrlea, at some little distance from the coast, according to Pliny, was a colony of Colophon. (Cf. postea Apamea. Mel. I. 19.) It flourished as an independent city

for several years, (Scyl. p. 35.) till it was taken and destroyed by Philip, son of Demetrius, king of Macedon, who ceded the territory to Prusias, sovereign of Bithynia, his ally. This prince rebuilt the town, and called it Apamea, after his queen. (Strab. XII. p. 563.) Stephanus Byz. is less correct in referring this to Nicomedes. (v. Μύρλεια.) From the latter

Myrleanus Sinus. geographer we collect, that the name of Myrleanus Sinus was sometimes applied to the gulf on which Myrlea stood, but which is more generally known by that of Cianus. Apamea received a Roman colony under the auspices of Julius Cæsar, as appears from the title of *Colonia Julia Concordia Apamea* on its coins^c. It is mentioned as a flourishing town by Pliny the younger. (Epist. X. 56.) Asclepiades of Myrlea is a grammarian frequently cited by Athenæus and the Scholiasts. The ruins of Apamea have been observed by various travellers near the site now called *Modania*, about six hours north of *Broussa*^d.

The deep bay whose southern shore we are now following took the name of Cianus from the ancient city of Cius, situated at the vertex of the angle made by its two sides. (Scyl. Per. p. 35.) It had been founded originally by a colony of Milesians, and was advantageously placed at the mouth of the river Ascanius, which discharged into the Propontis the waters of the Ascanian lake; and being navigable, rendered Cius the emporium of a large tract of surrounding country, and many inland towns of

^c Sestini, p. 66. Some earlier coins exhibit the epigraph ΑΠΑΜΕΩΝ ΜΥΡΛΕΑΝΩΝ.

^d Wheeler, tom. I. p. 209.

Pococke, tom. III. b. ii. c. 25.
P. Lucas, Third Voyage, tom. I. p. 128.

Bithynia and Phrygia. (Plin. V. 32. Aristot. ap. Schol. Apoll. Argon. I. 1177.) It was more particularly the port of Nicæa, the chief town of the former province; and as late as towards the close of the Byzantine empire, travellers coming from Europe by sea landed at Cius, and having crossed over land to the Ascanian lake, sailed to Nicæa. (G. Pachym. p. 287.) Herodotus calls it a town of Mysia. (V. 122.) Strabo informs us, that Philip, son of Demetrius, having ruined Cius together with Myrlea, in conjunction with Prusias, gave them up to that sovereign, who founded a new town on the site of the former, which he called Prusias. (XII. p. 563.) This town appears to have been termed the maritime Prusias, to distinguish it from another Bithynian town, named Prusias ad Hypium. (Memnon ap. Phot. Cod. CCXXIV.^e) It is evident, however, that Cius either still subsisted as a separate town from Prusias, or recovered its original appellation, since it is mentioned under that name by several authors much posterior to the event alluded to by Strabo. (P. M. I. 19. Plin. V. 32. Zosim. I. 35. Hierocl. Synecd. Anna Comm. p. 172, C. Nicet. Chon. p. 233, C. and many others^f.) The site on which it was built still retains the name of *Kio*. The river Cius mentioned by Apollonius Rhodius (I. 1178.) is probably that which has been already mentioned as flowing from the Ascanian lake into the bay of Cius, though it must be admitted that

^e This distinction is further observable in the coins of Prusias; the inscription is ΠΡΟΤ-
CIEΩΝ ΤΩΝ ΠΡΟΣ ΘΑΛΑΣΣΑΝ.

^f There are also coins, with the epigraph KIANΩΝ, of the

reigns of Claudius, Hadrian, and Severus. Sestin. p. 67. There are, I believe, no imperial medals of Prusias on the sea.

Hylas flu-
vius.

Arganthonius mons.

Posidium
promonto-
rium.

Prusa ad
Olympum.

Pliny makes the Ascanius and Cius two different streams. (V. 32.) The Hylas of the same geographer was supposed by mythological writers to be the fountain where the youth of that name was carried away by the Naiads. (Apoll. Arg. I. 1353.) Strabo reports, that in his time the inhabitants of Prusias celebrated a festival called Oribasia in commemoration of that event. (XII. p. 564.) The little stream in question flowed probably from mount Arganthonius, which tradition has connected with the story of Hylas :

Τῆμος ἄρ' οἶγ' ἀφίκοντο Κιανίδος ἡθεα γαιῆς
'Αμφ' Ἀργανθώνειον ὅρος προχοάς τε Κίοιο.

APOLL. RH. I. 1177.

Strabo says it rose above Prusias. (loc. cit.) In the Argonautics ascribed to Orpheus (v. 641.) it is called Arganthus ; in Steph. Byz. Ἀργανθώνις. This mountain terminates in a cape which forms the extreme point of the northern shore of the Cianus Sinus. Ptolemy names it Posidium promontorium ; the modern appellation is *Bozburun*. Near Cius was a place called Bryllium, and a small tract of country to which it gave the name of Bryllis. (Steph. Byz. v. Βρύλλιον. Plin. V. 32.)

Before we quit the shores of the Propontis for those of the Bosphorus, it will be proper to speak of some few towns which are to be found in that part of Bithynia which is situated between the coast and the Mysian and Phrygian mountains. The most important of these is Prusa ad Olympum, so called from being placed at the foot of mount Olympus, commonly termed the Mysian, to distinguish it from the Thessalian chain. Pliny asserts, without naming his authority, that this town was founded by

Hannibal. (V. 32.) By which expression we are probably to understand that it was built at the instigation of this great general, when he resided at the court of Prusias, from whom the name of the city seems evidently derived. But Strabo, following a still more remote tradition, affirms that it was founded by Prusias who made war against Croesus. (XII. p. 564.) In Stephanus, who copies Strabo, the latter name is altered to Cyrus. (v. Προῦσα.) But it is probable that both readings are faulty, though it is not easy to see what substitution should be made^g. Dio Chrysostom, who was a native of Prusa^h, did not favour the tradition which ascribed to it so early an origin as that authorized by the reading in Strabo, since he says of it, (Orat. XLIII. p. 585.) Εὗ γὰρ ἵστε ὅτι οὐ μεγίστη τῶν πόλεων ἐστὶ, οὐδὲ πλεῖστον χρόνον οἰκουμένη. Stephanus Byz. remarks that Prusa was but a small town. Strabo, however, informs us that it enjoyed a good government. (loc. cit.) It continued to flourish under the Roman empire, as may be seen from Pliny the Younger; (Ep. X. 85.) but under the Greek emperors it suffered much from the wars carried on against the Turks. (Nicet. Chon. p. 186, D. p. 389, A.) It finally remained in the hands of the descendants of Osman, who made it the capital of their empire, under the corrupted name of *Brusa* or *Broussa*. It is still one of the most flourishing towns possessed by the Infidels in *Anatolia*ⁱ.

^g See the various emendations proposed in a note to the French Strabo, tom. IV. lib. xii. p. 82.

^h There are autonomous and imperial coins of Prusa. The name of the people on these

monuments is ΠΡΟΤΣΑΕΙΣ. Sestini, p. 70.

ⁱ For a good account of *Broussa* and its vicinity, see Browne's Travels in Walpole's Turkey, tom. II. p. 108.

Olympus
mona.

The warm baths of Prusa, which are still held in great repute^k, were known to the ancients. Atheneus says they were commonly called the royal waters. (II. p. 43, A. Steph. Byz. v. Θερμά.) Mount Olympus, which rose above Prusa, was one of the highest summits of Asia Minor, being covered with snow during great part of the year^l. The lower parts, and the plains at the foot, especially on the western side, had from the earliest period been occupied by the Mysians, whence it was generally denominated the Mysian Olympus. (Plin. V. 32.) Its sides were covered with vast forests, which afforded shelter to wild beasts, and not unfrequently to robbers, who erected castles there, and other strong holds. (Strab. XII. p. 574.) We read in Herodotus, that in the time of Croesus an immense wild boar, issuing from the woods of Olympus, laid waste the Mysian lands, and became so formidable, that the inhabitants were obliged to send a deputation to the Lydian monarch, to request his aid for delivering their country from the monster. (I. 36.) The lower regions of this great mountain are still covered with extensive forests, but the summit is rocky, and destitute of vegetation^m. The Turks call it *Anadoli dagh*. In the Byzantine historians mention is made of several fortresses which defended the passes of Olympus; such as Pytheca, (Nicet. Chon. p. 35, B. Cinnam. p. 21.) Acrunum, and Calogrœa, (Cinnam. ibid. Melangia Cedren. p. 553. Ann. Comm. p. 441.) More to the west, and near the sources of the Rhyndacus, a village now called

^k Browne describes them minutely, p. 109.

^l Ibid. p. 112.

^m Sestini Viaggio da Cizico a Broussa.

Edrenos naturally suggests the idea of its being on the site of Hadriani, a Bithynian town of some note, and the native place of Aristides the rhetorician, who often alludes to it in his Orations. We collect from his account that it was near a river, which is doubtless the Rhyndacusⁿ, and on the borders of Mysia, two days' journey from Cyzicus, 160 stadia from Pæmanenum, and more than one day's journey from Hadrianotheræ, on the road to Pergamum. (tom. I. p. 596.) Hadriani is known to the ecclesiastical writers as a bishopric in the Hellen-pontine province. (Socrat. Eccl. Hist. VII. 25. Hierocl. Syncd. p. 693.) Sestini observes that *Edrenos* is a large and flourishing village, about eight hours from *Broussa*, on the south side of mount Olympus^o. Returning to Prusa, and advancing from thence to the north-east, we shall reach the banks of the Ascanian lake, already noticed under ^{Ascanius} the head of Cius. The country situated around this ^{lacus.} expanse of water is thought by Strabo to be the Ascania of Homer, though that poet places it in ^{Ascania} regio. Phrygia :

Φόρκυς αὐτὸν Φρύγας ἡγε, καὶ Ἀσκάνιος θεοειδῆς,
Τῇλ' ἐξ Ἀσκανίης. IL. B. 862.

Πάλμων τ', Ἀσκάνιον τε, Μόρυν θ' υἱὸν Ἰπποτίωνος.
Οἵ δ' ἐξ Ἀσκανίης ἐριβώλαχος ἥλθον ἀμοιβοί.

IL. N. 792.

Subsequent writers, however, have assigned it to Mysia, as Euphorion, quoted by Strabo, (XII. p. 566.)

ⁿ The emblem of a river is also found on the coins of Hadriani, and sometimes allusion is made to the vicinity of Olympus, as in the epigraph ΑΔΡΙΑ-

ΝΕΩΝ ΠΡΟΣ ΟΛΥΜΠΟΝ. Sestini, Lettere Numism. tom. VIII. p. 16.

^o Ibid. p. 14.

. . . Μυσοῖς παρ' ὅδασιν Ἀσκανίοιο :
and Alexander the Ætolian :

Oἱ καὶ ἡπ' Ἀσκανίων δωματ' ἔχουσι ρόῶν
Λίμνης Ἀσκανίης ἐπὶ χείλεσιν ἐνθα Δολίων
Τὸς Σιληνοῦ νάσσατο καὶ, Μελίης.

According to Apollodorus, there was a place called Ascania on the shore of the lake. (Ap. Strab. XIV.

Ascania
pagus.

p. 681.) Aristotle observes, that the waters of the Palus Ascania are so impregnated with nitre as to cleanse the clothes dipped in them. (Mirab. Ausc. c. 54. Cf. Plin. XXXI. 10.) Col. Leake describes the Ascanian lake as “about ten miles long, and “four wide, surrounded on three sides by steep “woody slopes, behind which rise the snowy sum-

Nicæa.

“mits of the Olympus range P.” Nicæa, the capital of Bithynia, according to Strabo, was situated on the eastern shore, in a wide and fertile plain, though somewhat unhealthy in summer. Stephanus states that it was first colonized by the Bottiæi, and was called Anchore. (v. Νίκαια.) Strabo mentions neither of these circumstances, but states that it was founded by Antigonus, son of Philip, who called it Antigonia; it subsequently received that of Nicæa from Lysimachus, in honour of his wife, daughter of Antipater. The circumference of the town, which was built in the form of a square, measured sixteen stadia, and the streets were drawn at right angles to each other, so that from a monument which stood near the gymnasium it was possible to see the four gates. (XII. p. 565.) Pliny the Younger, in his Letters, makes frequent mention of Nicæa and its public buildings, which he had undertaken to restore, being at that time governor of Bithynia. (X. 40, 48,

et seq.) It was the birthplace of Hipparchus the astronomer, (Suid. v. "Ιππαρχος.") and Dio Cassius. Nicæa is also spoken of by Cicero, (pro Deiot. §. 9. Epist. Fam. XIII. 61.) Dio Chrys. (Or. XXXVIII.) Memnon, (ap. Phot. Cod. CCXXIV. p. 383.) and others. Under the Byzantine emperors it was often taken and retaken during their wars with the Turks. Nicetas states, that at this time the walls were built of brick. (p. 181.) The present town of *Isnik*, as it is called by the Turks, has taken the place of the Bithynian city, but “the ancient walls, towers, “and gates are in tolerably good preservation. In “most places they are formed of alternate courses “of Roman tiles and of large square stones, joined “by a cement of great thickness. The Turkish “town never was so large as the Grecian Nicæa, “and it seems to have been almost entirely con-“structed of the remains of that city^{q.}” Nicæa is celebrated in the ecclesiastical annals for the council held there against the Arian heresy, A. D. 325; whence the creed drawn up by the prelates assembled on that occasion is called Nicene.

Pliny reckons twenty-five miles from Prusa to Nicæa. (V. 32.) On the Ascanian lake, and 120 stadia from Cius, was a place rendered remarkable by some springs which were observed to fail in winter, but to overflow in summer. In Antigonus of Carystus (c. 188.) this spot is named Mythopolis, and in the treatise de Mir. Ausc. (c. 55.) Mythepon^{Mythopolis sive potius} Pythopolis; but I should apprehend that the real name of Pythopolis.

^q Leake's Asia Minor, p. 10, 11. Walpole's Turkey, tom. II. p. 146. from Browne's Memoir. The coins of Nicæa, both under the Bithynian sovereigns

and the Roman emperors, from Augustus to Gallienus, abound in collections; the epigraph is NEIKAIEΩΝ. Sestini, p. 69.

the place is Pythopolis, as we find it written in Pliny (V. 32.) and Steph. Byz., who assigns it to Mysia, (v. Πυθόπολις.) Plutarch quotes a story related by Menecrates, in his account of Nicæa, to prove that this town had been founded by Theseus.

Soloon f. The neighbouring brook received the name of Soloon from one of the hero's companions. (Thes. p. 12.) Stephanus places near the bay of Astacus a spot called Pythium; (vv. Πύθιον, Θερμά.) and Procopius speaks of some baths, and a church of St. Michael, repaired by the emperor Justinian. These possibly may all be referred to Pythopolis. (Procop. de AEdif. V. 1.) The Byzantine historians notice several small towns or fortresses in the district of Nicæa, which serve at least to shew how populous it was then. Basilea, a place forty stadia distant from Nicæa, (Niceph. Bryen. II. p. 52.) is probably to be identified with the Basilionopolis of Hierocles, and the councils, and the Basinopolis of Synesius. (Epist. 66.) G. Pachymeres speaks of Belocome, a place of great strength, (p. 288.) also Angelocome, Anagurdes, Platanea, Melangea, (p. 286.) Crulla, Catœcia, (Κατοικία,) Heracleum, and Nemicome: (p. 287.) he observes, that the road from these two last places to Cius passed through a woody country.

Heracleum. Heracleum answers doubtless to the village of *Era-klî* observed by Lucas on his way from Nicomedia to Nicæa^r. Frequent mention is also made of Georgii Castellum: (Ann. Comn. p. 313, B.) near it were Rhodomerus, Monastra, and Azala. (p. 315, B.) South of Nicæa, *Lefke* is easily identified with Leucæ, noticed by Anna Comnena on the road from that city to Dorylæum: (p. 469.) near it was a

^r Second Voyage, tom. I. c. 21.

place called Armeno Castrum. *Lefke* is situated in a valley watered by a river named the *Sakaria*; but Col. Leake justly observes, that this river is not the *Sangarius*, but that branch of it known anciently by the name of *Gallus*. Strabo states that this *Gallus fl.* stream had its source at a place called *Modra*, in Phrygia Epictetus, and joined the *Sangarius* about 300 stadia from Nicomedia. (XII. p. 543.) It was from this river that the priests of Cybele were named *Galli*. (Steph. Byz. v. Γάλλος. Plin. V. 32.) Ammianus Marcellinus describes its course as very winding. (XXVI. 8.) Beyond *Leucæ* was *Agrilium*, noticed by Ptolemy, (p. 118.) and the Table Itinerary, which fixes its situation between Nicaea and Dorylæum, of Phrygia, twenty-four miles from the former, and thirty-five from the latter. Col. Leake is inclined to identify it with *Vissirkhan*, about four hours from *Lefke*. Strabo seems to place in this direction also a small town named *Otrea*, as it was *Otreus* said, from *Otreus*, a Phrygian prince, mentioned in the Iliad, (Γ. 186. Cf. Hymn. Ven. 111. and 147.) it may perhaps answer to *Ortakevi*, a Turkish village which Browne traversed on his road from *Broussa* to *Kutaieh*^s.

Returning to the shores of the Propontis, and advancing eastward of Cape Posidium, we have to speak of a nameless promontory, near which, according to Pliny, stood a small town, founded by some Megarians. (V. 32. Cf. Steph. v. Μεγαρικόν.) *Praenetus*, a town often mentioned by the Byzantine historians and ecclesiastical writers, is known to have been situated on the coast. The Table Itinerary places it under the corrupt name of *Pronetios*,

^s In Walpole's Turkey, tom. II. p. 113.

on the sea, and twenty-eight miles from Nicæa; (Steph. Byz.) who calls it Pronectus, reports, that it was founded by the Phœnicians. (v. Πρόνεκτος.) According to Cedrenus, it was destroyed by an earthquake. (p. 457. Cf. Socr. Eccl. Hist. VI. 16. Hierocl. Syncd. p. 690.) The site seems to answer to

Drepene postea. that of *Debrende*. Drepene, a place also on the coast, is mentioned by more than one writer. (Steph.

Byz. v. Δρεπάνη. Etym. M. v. Δρέπανον.) The name of this town was afterwards changed to that of

Helenopolis, by Constantine, in honour of his mother. (Niceph. Callist. VII. 49.) Frequent reference

to the city under its new denomination is made in the Byzantine history. (Philost. II. p. 483. Socr.

H. Eccl. I. 4, 18. Procop. de AEd. V. 1. Ann. Conn. p. 462.) Col. Leake is of opinion that Helenopolis

was near the modern *Ersek*^t. A small river, now called the *Dil*, which empties itself into the Propontis, is doubtless the Draco of Procopius. That histo-

Draco fl. rian remarks, that it was necessary to cross the Draco more than twenty times in going from Helenopolis to Nicæa; the course of this stream was altered by Justinian, to facilitate communication.

(AEdif. V. 1.) Col. Leake states, that he crossed the *Dil* as many times on the same road^u. The Draco

is also mentioned by Anna Conn. (p. 286.) Pliny names several other small rivers which discharge themselves into this part of the Propontis. They

are the *Aesius*, *Bryazon*, *Plataneus*, *Areus*, *Aesyros*, and *Gendos*; this last was also called *Chrysorrhoas*.

Elsewhere the same geographer speaks of a river of Bithynia, named *Olachas*, which flowed near Bryazon, and whose water could not be endured by those

Bryazon sive Olachas fl.

^t Asia Minor, p. 10.

^u P. 10.

who had sworn falsely. (XXXI. 18.) The Plataneus recalls to mind Platanea, a place in the vicinity mentioned by G. Pachymeres, (p. 286.) And it is not improbable that Brunga and Pontamus, two stations placed in the Jerusalem Itinerary, between Chalcedon and Nicomedia, are corruptions of Bryazon and Plataneus.

The gulf, along whose southern shore we are now advancing, was anciently termed Astacenus, or Olbianus Sinus, from Astacus and Olbia, two Greek cities of note, situated on the coast; if indeed they are not the same city under two different names. It is certain that Scylax, in describing the Mysian coast, speaks of the Sinus Olbianus, and places there Olbia and its port, without naming Astacus. (p. 35.) On the other hand, Strabo speaks only of Astacus, which, he says, was founded by the Megarians and Athenians. This is confirmed by Memnon, cited by Photius. (p. 722.) He says, the Megarians settled here in the 17th Olympiad, and it was not till some years after that the Athenian colony joined them. Astacus was afterwards seized by Dædalsus, a native chief, who became the founder of the Bithynian monarchy. In the war waged by his successor Xipetes, with Lysimachus, Astacus was ruined; but Nicomedes, the son of the former, transferred the inhabitants to the city which he founded, and named Nicomedia, after himself. (Strab. XII. p. 563.) Hence it appears that Pliny is greatly mistaken in stating that Nicæa had previously been called Olbia. (V. 43.) Astacus seems to have been still extant in the time of Arrian, who is cited by Steph. Byz. (v. Ἀστακος. Μεγαρικόν. Cf. P. Mela. I. 19. Steph. Byz. v. Ὁλβία.)

Nicomedia being the chief residence of the Bithynians.

nian kings, soon became a large and flourishing city, and it continued to prosper under the Roman emperors, as may be collected from the letters of Pliny to Trajan, in which he speaks of several public buildings belonging to this city, such as a senate house, an aqueduct, a forum, a temple of Cybele, &c. He mentions also its having suffered much from a great fire. (Ep. X. 42, 46.)

In still later times, Nicomedia was often the residence of the Roman emperors, when engaged in carrying on war with the Parthians or Persians. (Niceph. Callist. VII. ad fin.) It was however nearly destroyed by an invasion of the Scythians (Amm. Marcell. XXII. 9, 12.) and an earthquake. (Philost. IV. p. 506.) The orator Libanius, in his lament over the fortunes of Nicomedia, *μοναδία ἐπὶ Νικομηδίᾳ*, mourns the loss of its Thermæ, Basilicæ, temples, Gymnasia, schools, public gardens, &c. Some of these were restored by Justinian. (Procop. AEd. V. 1.) It was however finally conquered by the Turks, who call it *Ismid*. Nicomedia gave birth to Arrian, the historian of Alexander, (Steph. Byz. v. Νικομηδεία.) and Constantine the Great breathed his last at his villa Ancyron, near the city. (Cassiod. Chron. Const. Philost. II. p. 484.) Scylax (p. 35.) names with Olbia, and in the same bay, the Greek city Callipolis, with a harbour. This is unknown to other geographers, but it may have been the Megaric colony, mentioned by Pliny, on the edge of the bay, hence sometimes called Craspedites Sinus.

Craspedites
Sinus.

Leucatas
sive Acri-
tas pro-
montori-
um.

(V. 43.) On the other side of the gulf, the same Latin geographer notices the promontory of Leucatas, thirty-seven miles from Nicomedia. This is probably the same as the Acritas of Artemidorus (ap. Steph. Byz. v. Χαλκίτης.) and Ptolemy. (p. 118.)

Cibotus appears to have been a name given to the Cibotus. narrow passage across the bay of Nicomedia, by the Byzantine historians. (Ann. Comn. p. 309. A.) Col. Leake, however, seems to place it in the gulf of Cius^x. Ægillus was a spot near Cibotus. (Ann. Comn. p. 438. D.) Eribolum, according to the Table ^{Eribolum} Itinerary, stood on the bay, a little to the south of ^{sive Eri-} ^{bœa.} Nicomedia. Xiphilinus also speaks of it as a landing place on the gulf, near that city. Ptolemy likewise mentions it, under the name of Eribœa, (p. 118.) and the Jerusalem Itinerary calls it Hyribolum. (p. 573^y.) The site answers to that of *Karamusal*. Libum, a station of the Jerusalem Itine- ^{Liba.}rary, on the same road between Eribolum and Nicæa, and twenty-one miles from Nicomedia, is called Liba by Cedrenus. (p. 451.) On the north side of the gulf we have to notice *Ghebse*, or *Dchebse*, which doubtless answers to the Dacibyza ^{Dacibyza.} of the Byzantines. (Sozom. Hist. Eccl. VI. 14. G. Pachym. Andr. Palæol. I. p. 64. Zonar. XIII. 16^z.) Not far from thence stood Libyssa, a spot celebrated ^{Libyssa.} in antiquity as the deposit of Hannibal's remains. Plutarch, in the life of Flamininus, describes it as a small village on the coast of Bithynia, and we know from Ammianus (XXII. 9.) and the Itineraries, that it stood on the road from Chalcedon to Nicomedia. These documents reckon twenty-three miles from the latter city to Libyssa, and thirty-seven from the former. (Cf. Plin. V. 43. Steph. Byz. v. Λιβύσσα.) Appian speaks of a river Libyssus, and Libyssus fl.

^x Asia Minor, notes p. 316.

^y If Sestini is correct in his reading of ΕΠΙΒΟΙΕΩΝ in a medal he assigns to this town, the

true name of the town is that used by Ptolemy.

^z Leake's Asia Minor, p. 9.

the plain Libyssa. (Syr. c. 11.) Some writers have identified Libyssa with *Ghebse*^a, but col. Leake, from a more accurate computation of distances, is inclined to fix this interesting site at *Maldysem*, or *Malsum*, a few miles to the south of *Ghebse*^b.

Pantichi-
um.

Pantichium, situated according to the Itineraries, twenty-two miles from Libyssa, and fifteen from Chalcedon, retains the name of *Pantichi*^c. (Itiner. Hieros. p. 571. Itiner. Anton. p. 140.) This place is likewise noticed by the ecclesiastical writers, Philostorgius (XI. p. 541.) and Sozomenus. (VII. 21.) Artemidorus, in his account of this coast, (ap. Steph. Byz. v. Χαλκίτης.) places, after Cape Acritas, 120 stadia further, another headland, named Hyris, and near it the island Pityodes.

Trarium
sive Tral-
lium.

Trarium, which Ptolemy places in this direction, is probably the same town which Steph. Byz. calls Trallium, near the bay of Astacus. To the south-east of Nicomedia is an extensive lake, and a chain of mountains, which encloses it to the west and south. These are frequently mentioned by the historians of the lower

Sophon la-
cus et
mons.

empire by the name of Sophon. (Cedren. p. 451.) G. Pachymeres calls the former Siphones. (Andr. Pal. p. 228.) This I imagine to be the lake alluded to by Pliny the Younger, in his letter to Trajan, (X. 50.) and from which he was desirous of cutting a canal to the sea, to convey thither more easily the produce of the interior, consisting in marble, timber, provisions. He states that there were vestiges of a cut made under the Bithynian kings. Trajan, in his reply, desires him to have the levels of the lake and sea examined. In Ammianus, the same lake

^a Mannert, tom. VI. p. 586. ^b Asia Minor, p. 9. ^c Leake, p. 8.

seems alluded to by the name of Sunonensis, or Sunmonensis. (XXVI. 8.) Evagrius also mentions a lake called Boane, near Nicomedia. (Hist. Eccl. II. 14.) This piece of water now takes its name from the village of *Shabanja*, which is probably a corruption of Sophon. Telemæa and Petræa were places in the vicinity, according to Cedrenus. (p. 801.) Petræa stood towards Nicæa, and about fifteen stadia from it. Metabole was a fortress on mount Sophon, and near it was another mountain called Maroscus, and a place named Trisca. (Niceph. Bryenn. II. p. 56.)

We must now speak of Chalcedon, a celebrated Grecian city, situated at the southern extremity of the Bosphorus. It was founded by a colony of Megarians, on the site previously called Procerastes and Colpusa. (Plin. V. 43. P. Mela I. 19.) The inhabitants were often taunted with the appellation of blind men, because, having the choice of so magnificent a site as that of Byzantium to build their city on, they had preferred one so avowedly inferior. Herodotus says, this observation was first made by Megabyzus, the Persian general; and he informs us, by the way, that Chalcedon was prior to Byzantium by seventeen years. (IV. 144. Cf. Tacit. Ann. XII. 63.) It was not merely with respect to the beauty of situation that Chalcedon was inferior to its opposite neighbour, but, what was of much greater consequence, it laboured under great disadvantage in a commercial point of view; since the current which set in strongly from the Euxine carried vessels directly into the harbour of Byzantium, but prevented their approach to Chalcedon in a straight course. (Polyb. IV. 43.) Notwithstanding these disadvan-

tages, the Chalcedonians were sufficiently favoured, both in regard to climate, the fertility of the surrounding country, and opportunities for carrying on trade, to become a prosperous and wealthy people. They appear to have preserved their independence till the reign of Darius, to whose arms they were forced to submit. (Herod. V. 26.) They recovered their liberty, however, after the repeated defeats of the Persians, under Xerxes, and became the allies, or rather the tributaries, of the Athenians, to whom the ports of the Bosphorus were an object of the highest commercial and financial importance. (Thuc. IV. 75. Xen. Hell. I. 1, 14.) The disasters of Sieily gave them an opportunity of throwing off their chains, and they consequently joined the Peloponnesian alliance, and received a Spartan harmost. But Alcibiades, after his success off Cyzicus, blockaded Chalcedon by sea and land, and the Spartan general being slain in a sortie, the citizens were forced to comply with the terms offered by the victor; they once more, therefore, were obliged to pay the accustomed tribute, besides all the arrears which were due. (Hell. I. 3, 7.) This state of things lasted however only till the battle of *Aegospotami*; Chalcedon then opened its gates to Lysander, whose first object seems to have been to secure the entrance of the Bosphorus, by the possession of this city and Byzantium. (Hell. II. 2, 1.) Theopompos, who is quoted by Athenæus, observes, that the Chalcedonians at first possessed good institutions, but having been tainted by the democratical principles of their neighbours, the Byzantines, they became luxurious and debauched. (XII. 526. F.) Chalcedon afforded a refuge to the Roman troops under Cotta,

from the pursuit of Mithridates. (Appian. Bell. Mithr. c. 71. Eutrop. VI. 5.)

Chalcedon is further celebrated in ecclesiastical history for the council held there against the Eutychian heresy. (A. D. 451.) Hierocles assigns to it the first rank among the cities of the province, then called Pontica prima. (p. 690.) It is to be observed, that in writing the name of this town, ancient writers have not been uniform, some writing it Καλκηδὼν, others Χαλκηδών. The former mode is however much more frequent, and it is confirmed by the existing coins, the epigraph of which is invariably ΚΑΛΧΑΔΟΝΙΩΝ, according to the Doric form^d. The town was situated on a rising ground, near the mouth of a rivulet of the same name. It had two ports separated by an isthmus, one looking west, the other east. There were many beautiful public buildings and monuments, but the most remarkable was a temple of Apollo. (Dionys. Byzant. p. 23.) The site of this ancient city is now occupied by the Turkish village *Kadikeri*, but the Greeks still preserve the classical name. *Scutari*, a well-known town and harbour, opposite Constantinople, is thought to represent Chrysopolis, a port of Chalcedon, often mentioned in history. The Athenians established there a toll, towards the close of the Peloponnesian war, to be paid by all ships coming from the Euxine. (Xen. Hell. I. 1, 14. Polyb. IV. 44, 3.) The 10,000 Greeks were encamped there for some days prior to crossing over into Thrace. (Xen. Anab. VI. 6, 22.) It is mentioned by Strabo as a small town, (XII. p. 563.) and Pliny says, “ Fuit Chrysopolis.” (V. 32.)

^d Eckhel Doctr. Num. Vet. P. i. vol. I. p. 410. Sestini, p. 67.

Several writers of a later date, however, continue to speak of it. (Zosim. II. 30. Socrat. Hist. Eccl. I. 4. Amm. Marcell. XXII. 12.) Steph. Byz. (v. Χρυσόπολις) gives various etymological derivations of the name. Opposite to the coast of Chalcedon are ranged some islets, the nearest of which to the entrance of the Bosphorus still retains its ancient name of Prote. The next is Chalcitis, (Artemid. ap. Steph. Byz. v. Χαλκίτης.) now *Karkia*. The last, which is also the most considerable, called *Prinkipo*, or Princes' island, is often mentioned under that name in the Byzantine annals. (Ann. Comn. p. 462, 463.) And a monastery was built there by Justinian, the ruins of which may still be seen^e. But the more ancient name of this island was Pityodes, or Pityusa, as we learn from Artemidorus. (ap. Steph. Byz. v. Χαλκίτης. Cf. Plin. V. 32.) The two latter isles were also called Demonesi, and they appear to have been celebrated for the brass which they contained. (Hesych. v. Δημονήσιος χαλκός. Poll. V. 39. Aristot. Mirab. Ausc. p. 877.) Pliny names with these, other obscure islets, such as Elæa, Rhodussæ, Erebinthodes, and Megale. (V. 44.)

Bosphorus
Thracius.

The ancients gave the name of Thracian Bosphorus to the narrow channel which establishes a communication between the waters of the Euxine and those of the Propontis. Tradition asserted that it was derived from the passage of Io, who during her metamorphosis had crossed this arm of the sea, and the names of Βοῦς and Δάμαλις were applied to the spot where the fabled heifer had landed in Asia. (Polyb. IV. 44. Eust. ad Dion. Perieg. 140.) Other writers, however, asserted, that Damalis was the name

^e P. Gyllius Bosph. Thrac. III. 12.

Prote in-
sula.
Chalcitis
insula.

Pityodes
insula.

of a lady, wife of the Athenian general, Chares. (Dionys. Anapl. Bosph. ap. P. Gyll. III. 9.) The breadth of this celebrated channel is variously estimated by different writers. Strabo seems to say, the narrowest part, which he calls $\tauὸν Βυζαντιακὸν στόμα$, (II. p. 86.) is four stadia broad; but Polybius says, the narrowest part is about the Hermæan promontory, somewhere midway between the two extremities, and he does not compute the breadth at less than five stadia; he adds, that it was at this point that Darius built his bridge when he made his Scythian expedition. (IV. 44.) Herodotus agrees with Strabo, and appears to place the bridge of Darius where Polybius does. (IV. 87.) The same historian estimates the length of the channel at 120 stadia. Polybius has described at some length the action and direction of the currents setting in from the Euxine. (IV. 43.) But of all ancient writers, no one has been so minute in his account of the Bosphorus as Dionysius of Byzantium, who composed a work expressly on this subject. Of this, some considerable fragments have been preserved to us, of which P. Gythius has availed himself in his description of the strait, but the originals have disappeared^f. On the side of Chalcedon, the Byzantine topographer notices north of that city the fountain Hermagora, and the heroon of Eurostus. Strabo places above Chalcedon the fountain Azaria, which contained small crocodiles. (XII. p. 563. Cf. Steph. Byz. v. Ζάρητα.) Then follows the promontory Bos, so called from the monument raised to the wife of Chares, as appears from the epigram inscribed on it, and quoted by Dionysius. Beyond,

^f See the preface to the Geogr. Minores, tom. III.

Portus
Amyci.

Nicopolis.

Hieron
sive tem-
plum Jovis
Utrii.

is the wide and beautiful harbour of Chrysopolis; then succeed two points of land called Discus and 'Ποιζοῦσαι ἄκραι, or bluffs, against which the waters beat; the spot named Ciconium; Nausimachium, so called from a sea fight; the bay of Lycadium, or Cycladium; the promontory Perirrhous; the spots called Echæa Nausicleia, where the Chalcedonians gained a naval victory; Potamonion, the point Lembus, and the island Blabe, so termed from the shipwrecks it occasioned. After Lembus, comes Phiela, a natural circular mound, having the appearance of a theatre; then the port of Phrixus; the promontory Oxyrrhoum; the basin called Κατάγγειον, which abounded with fish; the plain named Gronychia, and the bay of Amycus. Pliny calls it the port of Amycus, and places near it the town of Nicopolis. (V. 43.) Steph. Byz. acknowledges also a Nicopolis in Bithynia; beyond, we have the promontory called Aetorynchus, or the Eagle's beak^g; the bay of Mucaporis, with a very good haven, so called from a certain king of Bithynia. Then the spot named Δάφνη μαυνομένη, from a laurel which grew there after the death of Amycus, killed by Pollux, and whose branches were said to cause insanity in those that wore them. Arrian says this place was eighty stadia from Byzantium, and forty from the temple of Jupiter Urius. (Peripl. Eux. p. 25.) Beyond were the Nymphæum, the couch (*Kλίνη*) of Hercules, the Argyronium, (Cf. Procop. AEd. I. 9.) and the low land called Anaplus.

Immediately above this was a high point of land, with a temple built by Phrixus in honour of Jupi-

^e In the Geogr. Min. p. 20. ly a corruption or false print the word is Αετόρχυχον, evident- for 'Αετόρυγχον.

ter Urius, others say of Neptune. This, being a situation commanding the strait and surrounding country, had been fortified, and was often contested by the Byzantines and Chalcedonians. The former finally prevailed, as they were more powerful, and also because they consented to pay a sum of money for it to Callimedes, a general of Seleucus. This Hieron, as it is often simply called, was for some time in the hands of the Gauls, who had crossed over into Asia. (Dionys. Byz. p. 19.) Polybius says that Jason, on his return from Colchis, sacrificed here to the twelve gods; (IV. 39, 6.) and elsewhere he states, that it was wrested from the Byzantines by Prusias, who carried away all the most valuable materials. On making peace, however, he was obliged to replace them. (IV. 50—52.)

The promontory seems to be called Estia by Pliny. (V. 43^b.) Beyond is the spot called Chelæ; and Pantichium, so named from its being surrounded by trenches; the promontory Coracium; a low island, with some reefs and rocks about it, named Cyaneæ; an elevated mound surmounted by a round rock called Medea's tower; Ancyreum, a promontory so called because the Argonauts took from thence a rock to serve in the place of an anchor. This promontory is described by Dionysius as nearly opposite to the Cyanean or Symplegades rocks off the European coast; and here the Bosphorus may be said to terminate, and the Euxine to begin. This sea is said, from its stormy nature, or the wildness of its coasts, to have been formerly called "*Ἄξενος*, or "the inhospitable." (Plin. IV. 24. VI. 1. Mel. I. 19.)

^b We should read, "deinde Naurochum : promontorium Estiæ : " templum Neptuni."

Pontus
Euxinus.

The Grecian navigators, however, had explored its coasts at a very early period, if we are to credit the celebrated expedition of the Argonauts; and long before the time of Herodotus, the colonies which they had established on various points of the Asiatic and European coasts must have familiarized the mariners of the mother country with this once dreaded sea. Herodotus, who probably took his accounts from Hecatæus and Scylax, and other geographers of that period, appears to have had no very accurate notion of the shape of the Euxine, at least of the northern side; but he had taken pains to ascertain the measurement of its greatest length and breadth. The former he reckoned at nine days and eight nights' sail, which, allowing 70,000 orgyæ for a day, and 60,000 for a night, make the sum of 1,110,000 orgyæ, or 11,100 stadia. The breadth he found to be three days and one night's sail, or 3300 stadia. The former direction was measured from the mouth of the Phasis to the straits of the Bosphorus; the latter from Themiscyra in Pontus to Sindice, a country near the Palus Maeotis. (IV. 86.) Strabo allows only 8000 stadia from the Bosphorus to the Phasis, (XII. p. 548.) which agrees with Agrippa's measurement, given by Pliny. (VI. 1.) The latter geographer gives also several estimates of the whole circuit of this sea, which furnish a mean of about 2500 miles. The whole shape of this great basin was considered to be curved in the manner of a bow, made after the Scythian fashion; the middle bend being formed by the Palus Maeotis, the chord by the coast of Asia Minor. (Plin. loc. cit. Strab. II. p. 125. Agathem. II. c. 14.) Of this last, with which we are at present more immediately con-

cerned, we have a very detailed periplus or survey set down from actual observation by Arrian, the historian of Alexander's expedition, and author also of a history of Bithynia, a country which he was qualified for describing, since it was his native land. We have also another periplus, apparently of a more recent date, and compiled in great measure from Arrian, Marcian of Heraclea, and othersⁱ. Menippus of Pergamum, an earlier geographer, had written a work on the same subject, but we have now only a few fragments of it occasionally cited by Stephanus Byz.^k

There exists also a fragment of a third periplus, by an anonymous writer, who is evidently posterior to Arrian, and has compiled from his work and other sources. It is by the help of these documents, and the Itineraries, that we shall endeavour to trace the remainder of the Bithynian coast, as well as that of Paphlagonia and Pontus. After passing the temple of Jupiter Urius, and proceeding ninety stadia, or twelve miles, we reach the mouth of the little river Rhebas, mentioned by several poets, and nearly all the geographers.

αἴψα δὲ τοίγε

'Ρήβαν, ὥχυρόην ποταμὸν, σχόπελόν τε Κολάνης.

APOLL. ARG. II. 652.

'Αγχὶ δὲ Βιθυνοὶ λιπαρὴν χθόνα ναιετάουσι,
'Ρήβας ἐνθ', ἐρατεινὸν ἐπιπροῦησι ρέεθρον,
'Ρήβας, ὃς Πόντοιο παρὰ στομάτεσσιν ὁδεύει,
'Ρήβας, οὐ κάλλιστον ἐπὶ χθονὶ σύρεται ὕδωρ.

DIONYS. PERIEG. v. 793.

ⁱ The two surveys have been published in the Geogr. Min. tom. I. and tom. II.

^k These fragments are also

given in the Geogr. Min. The Scholiast to Apollonius mentions likewise several other peripli.

(Orph. Argon. 711. Fest. Avien. 974.) Pliny observes that some writers have called it Rhesus. (VI. 1. Cf. Scyl. Peripl. p. 34. Arrian. Peripl. Eux. p. 13.) In the Table Itinerary, the name of this stream is disguised under that of Ad Herbas. Tournefort informs us it is now called *Riwa*¹. Cape Melæna was 150 stadia further to the east. It had a small haven formed by an inland. (Marcian. Peripl. p. 69. in Geogr. Min. tom. I.)

Melæna
promonto-
rium.

"Ἄχρην δὲ οὐ μετὰ δηθα παρέξ ἐνέοντο Μέλαιναν.

APOLL. ARG. II. 653.

(Cf. Arrian Peripl. p. 13.) The little river Artanes, with a haven, and a temple of Venus at its mouth, is placed by Arrian (p. 13.) 150 stadia from Melæna. (Cf. Marcian. Peripl. p. 69.) From the Artanes to the Psilis, or Psillis, another little river, with a port for small craft, protected by a rock, we have again 150 stadia. (Arrian. p. 13. Marcian. p. 69. Strab. XII. p. 543.) This river is also called Psillus (Steph. Byz. Ψίλλον.) and Phyllis :

Τῇδε ἄρ' ἐπι προχοὰς Φυλληῖδας, ἐνθα πάροιθε
Διψαχὸς υἱὸς Ἀθάμαντος ἐοῖς ὑπέδεκτο δόμωσιν.

APOLL. ARGON. II. 654.

From this river to the river and port of Calpe the ancients reckoned 210 stadia. (Arrian. Peripl. p. 13.) Xenophon, who halted here for some time with his fellow-soldiers, describes Calpe as an excellent port, about half way between Byzantium and Heraclea. It was formed by a rocky hill advancing into the sea, and enclosing on the land side a considerable tract of excellent land. The port lay beneath the rock, and was supplied with an abundant source of fresh water. The surrounding hills afforded also beautiful timber for building ships, and other pur-

Calpe por-
tus et flu-
vius.

¹ Lettre 16.

poses; and the soil yielded every kind of grain, and wine and fruit, in the greatest plenty. (Anab. VI. 4. Cf. Arrian. Peripl. p. 13.)

Τοῦ μέν θ' ιερὸν αἷψα καὶ εύρειας ποταμοῖο
Ἡιόνας, πεδίον τε, βαθυρρέοντά τε Κάλπην
Δερχόμενοι παράμειβον.

APOLL. ARG. II. 660.

Strabo calls the river Calpas. (XII. p. 543. Cf. Steph. Byz. v. Κάλπη. Plin. VI. 1.) The modern name of the promontory and harbour of Calpe is *Kirpe*. Advancing eastward twenty stadia, we have to notice the little haven of Rhoe; and twenty stadia further, the small island of Apollonia, having a port, and situated close to the land. (Arrian. p. 13.) Its more ancient name was Thynias, which was afterwards changed for that of the deity worshipped there. Rhoe portus.
Thynias quæ et Apollonia insula.

Τῆμος ἐρημαίης νήσου λιμέν' εἰσελάσαντες
Θυνιάδος, καμάτῳ πολυπήμονι βαῖνον ἔραξε.

APOLL. ARG. II. 674.

Εἰ δὲ ἄγε δὴ νῆσον μὲν ἑώου Ἀπόλλωνος
Τήνδ' ιερὴν κλείωμεν.

IDE^M, 688.

(Cf. Plin. VI. 12. Scyl. p. 34. Strab. XII. p. 543. Mela. II. 7. Steph. Byz. v. Θυνίας.) It is situated near the promontory of *Kirpe*. Chelæ was a spot twenty stadia beyond. (Arrian. Peripl. p. 13.) The Table Itinerary reckons twenty-seven miles from the river Psilis to this place, which nearly agrees with the maritime surveys. The Sangarius flows into the sea about 180 stadia further to the east. This is one of the largest and most celebrated of the rivers of Asia Minor, being mentioned by Homer, and several other poets and historians:

*Ηδη καὶ Φρυγίην εἰσήλυθον ἀμπελόεσσαν,
*Ἐνθα ἴδος πλείστους Φρύγας, ἀνέρας αἰολοπάλους,

Λαοὺς Ὀτρῆος καὶ Μύδονος ἀντιθέοιο,
Οἱ δὲ τότ' ἐστρατόωντο παρ' ὅχθας Σαγγαρίοιο.

IL. Γ. 184.

Ἄσιω, δε μήτρας ἦν Ἐκτορος ἵπποδάμοιο,
Αὐτοκαστίγυητος Ἐκάβης, υἱὸς δὲ Δύμαντος,
Ος Φρυγίην ναιεσκε βοῆς ἐπὶ Σαγγαρίοιο. IL. Π. 717.

. Dindyma fundunt
Sangarium, vitrei qui puro gurgite Galli
Auctus, Amazonii defertur ad æquora ponti.

CLAUDIAN. IN EUTROP. II. v. 263.

Marian-
dyni.

Strabo says, “it takes its source in Upper Phrygia, “near a place called Sangia, about 150 stadia from “Pessinus. It then traverses a great part of Galatia “and Phrygia and Bithynia, receiving in its course “the waters of the Thymbres and Gallus, and other “streams; and becoming navigable near its mouth, “falls into the Euxine.” (XII. p. 543. Plin. VI. 1. Scyl. p. 34. Liv. XXXVIII. 18.) The modern name is *Sakaria*. The Sangarius in ancient times separated the Bithynians from the Mariandyni, a people of uncertain origin, but who, differing neither in language nor in customs materially from the Bithynians, might justly be considered as part of the same great Thracian stock. (Strab. XII. p. 542.) That they were barbarians is allowed by all; and Theopompos, whose authority is referred to by Strabo, reported, that when the Megarians founded Heraclea in their territory, they easily subjected the Mariandyni, and reduced them to a state of abject slavery, similar to that of the Mnotæ in Crete, and the Penestæ in Thessaly. (Ap. Strab. XII. p. 542. Cf. Pausan. Eliac. I. 26. Posidon. ap. Athen. VI. 263.) They formed part of the third division or satrapy of the Persian empire, with the Bithynians

and Paphlagonians. (Herod. III. 90. Cf. VII. 72.) Some further particulars respecting this people will be found in Athenæus, (XIV. p. 620.) Steph. Byz., (v. Μαριανδνία.) and Eustathius on Dionys. Perieg. (v. 788.)

"Ενθεν δ' ἀντιπέρην ποταμοῦ στόμα Σαγγαρίοιο,
Καὶ Μαριανδνῶν ἀνδρῶν ἐριθηλέα γαῖαν."

APOLL. ARG. II. 724.

Leaving the Sangarius, we shall reach, after a course of 180 stadia, a river named Hypius, men-^{Hypius}tioned by Apollonius, Scylax, Arrian, and several other writers.^{fluvius.}

'Αλλά με τὸν Βέβρυχες ὑπερβασίη τ' Ἀμύκοιο
Τηλόθι ναιετάοντος ἐνόσφισαν 'Ηρακλῆος,
Δὴν ἀποτεμνόμενοι γαῖης ἄλις, ὅφρ' ἐβάλοντο
Οὐρα βαθυρρέοντος ὑφ' εἰαμενχῖς 'Τπίοιο.

APOLL. ARG. II. 794.

(Scyl. Peripl. p. 34. Arrian. Peripl. p. 13. Marcian. Peripl. p. 70.) In an extract made from the historian Memnon by Photius, (c. 44.) we are told, that this river once afforded shelter to a large portion of Mithridates' fleet during a violent storm. It is now called *Mitan*. The town of Prusias, situated inland, and on its banks, acquired from that circumstance the characteristic denomination of ad Hypium, to distinguish it from another Bithynian city of the same name, situated near the sea, in the bay Cius. Both probably were equally founded by king Prusias; but the maritime Prusias is much oftener mentioned in history, and its situation is much more precisely ascertained, than the one of which we are now speaking. Pliny is singular in mentioning the latter, not with reference to a river, but a mountain called Hypius. That there was a chain of this name cannot indeed be doubted, since the scholiast

to Apollonius affirms, that the river had its source in the Hypian mountains. (Arg. II. 797.) And if Pliny is correct in his topography, we must look for the ruins of the Hypian Prusias not far from the source of the river. The site is generally supposed to exist near the modern *Uskub*. This town is noticed by Ptolemy, and in the Latin Acts of the Nicene Council. (p. 54.) One of the subscribing prelates is Hesychius of Prusias, near the river Hypius^m. A lake of some extent, formed by the waters of the Hypius, above *Uskub*, answers probably to the Daphnusis palus, which Steph. Byz. places near the Bithynian Olympus. (v. Δαφνοῦς.) The modern name is *Efnanly*. The Episcopal Notices record also a see named Daphnusia in Bithynia.

Dia. Dia was a town and small harbour sixty stadia from the mouth of the Hypius. (Marcian. Peripl. p. 70.) It was known to Ptolemy (p. 117.) and Steph. Byz., who calls it Dia of Bithynia on the Pontus. (v. Δία.)ⁿ

Lilium em- porium. Lilium was an emporium forty stadia further to the east, according to Arrian. (Peripl. p. 13.) Pliny mentions the Lilæus among the rivers of Bithynia; (V. 43.) and the Table Itinerary calls it Bylæus.

Elæum emporium. Elæum was another haven, sixty stadia from Lilium. (Arrian. loc. cit.) According to Marcian, there was also a river Elæus, (Peripl. p. 70.) and it is thought to be the same which Ptolemy calls Elatas. From thence to Cales, another emporium, Arrian and Marcian agree in reckoning 120 stadia.

Cales flu- vius et em- porium.

^m It is clear from the coins of this town that its real name was Prusias, since the epigraph is ΠΡΟΤΣΙΕΩΝ ΠΡΟΣΤΠΙΩ; whereas in those of Prusa it is ΠΡΟΤΣΑΕΩΝ. Sestini, p. 70.

Ptolemy and Pliny, therefore, are less accurate when they call it Prusa.

ⁿ Sestini ascribes to this town some very scarce coins, with the inscription ΔΙΑΣ.

But the latter notices, besides the haven, a river of the same name, which is doubtless the Calex of Thucydides. That historian speaks of an Athenian squadron, commanded by Lamachus, having been wrecked, whilst at anchor in this river, from the effect of a violent land-storm and flood. The Athenians, having lost their ships, were forced to march through Bithynia, as far as Chalcedon. (IV. 75.) In Memnon the name is written Calles; (ap. Phot. c. 23.) in Pliny it is distorted to that of Alces. (V. 43.) Forty stadia from the Cales we find the Lycus, a river mentioned by Xenophon and several other writers with reference to the city of Heraclea, whose territory it watered. The maritime surveys reckon twenty stadia from the river to the city, and Xenophon says distinctly that it flowed through the plain of Heraclea. (Anab. VI. 2.) Pliny, less accurately, states that the town was on the river. (VI. 1.)

*Kαὶ Μαριανδυνῶν ἀνδρῶν ἐριθηλέα γαῖαν,
Ἡδὲ Λύκοιο δέεθρα.* APOLL. ARG. II. 725.

Huc Lycus, huc Sagaris, Peniusque, Hypanisque, Calesque,
Influit et crebo vortice tortus Halys.

OVID. ELEG. PONT. X. 47.

Xenophon says its breadth was two plethra. (Anab. loc. cit.) The plain through which it flowed was named Campus Lycaeum. (Memnon. ap. Phot. c. 51.)

Heraclea, surnamed Pontica, from its situation on the Euxine, was founded, according to the general testimony of antiquity by the Megarians^o, who had already formed extensive establishments on the Bos-

Heraclea
Pontica.

^o In Strabo it is called a colony of the Milesians; but this doubtless is an error of the transcribers; and Casaubon has

altered the reading to Megarians, in which he has been followed by subsequent editors, XII. p. 542.

phorus, and who, on this occasion, were joined by some Bœotians from Tanagra. (Pausan. Eliac. I. 26.) This Grecian colony appears to have early attained to a considerable degree of wealth and prosperity, since its citizens are said to have subjected the neighbouring people of Mariandyni, and their success and enterprise in commerce is attested by the foundation of Chersonnesus and Callatis in Thrace. (Theopomp. ap. Strab. loc. cit.) The Heracleotæ adopted wise laws and institutions, and maintained their independence for several years, subject probably, however, to a tribute paid to the Persian monarch. On the arrival of the 10,000 Greeks before their city, the Heracleots, alarmed at the appearance of so great a body of troops, and doubtful of their intentions, collected all their property and provisions within the walls, and closed their gates. But they afterwards supplied the army with vessels, in order to get rid of them sooner. (Anab. VI. 2.) It was about this period that Clearchus, one of the principal citizens of the place, and who had been educated at Athens, in the schools of Plato and Isocrates, usurped the sovereign authority, and overthrew the republican constitution of his native city. He was succeeded by his son Dionysius, who, though addicted to pleasure, was of a mild and gentle disposition, and, unlike his Sicilian namesake, seemed to reign solely for the good of his subjects, and by their desire assumed the title of king. He had married Amastris, a niece of Darius, the last king of Persia; and at his death left her the sole guardian of his sons, and regent of the principality of Heraclea. Amastris afterwards married Lysimachus, one of Alexander's successors;

but being divorced by him, she returned to Heraclea, where she was put to death by her unnatural sons. Lysimachus, however, not long after, seized these monsters, and by a signal punishment made them atone for their crime. These details and incidents relative to the history of Heraclea are preserved to us in the Fragments of Memnon, collected by Photius. (Cod. CCXIV. p. 703—758.) Memnon had composed a history of the tyrants who reigned at Heraclea during a space of eighty-four years; but we have only now the abridgment of Photius^P, which is confirmed by incidental notices contained in Aristotle, (Polit. V. 5.) Strabo, (XII. p. 542—544.) and Athenæus. (III. 85, B. XIII. 549, A.) The Heracleots, after remaining eighty-four years under kingly authority, recovered for a short season their independence; they then successively passed under the dominion of Mithridates, and afterwards under that of Rome. The town was defended for nearly two years by the troops of the former against the Roman general Cotta, who having finally taken the city by assault, tarnished the glory of his success by the cruel and avaricious use he made of victory; since he put to death many of the inhabitants, plundered the city of its most valuable images and statues, among others, one of Hercules, the supposed founder of the town, which was of the most costly description; and finally set fire to the principal buildings. (Memnon. ap. Phot. Justin. XVI. 3.) Before the battle of Actium, Heraclea was occupied for a short time by Adiatorix, tetrarch of Galatia,

^P Memnon probably collected much of his information from Nymphis, whose history of He-

raclea is cited by Athenæus and others.

Aconæ.

Acherusia
chersone-
sus.

who had espoused the cause of Marc Antony. But he was finally conquered by Augustus, after the defeat of Antony, and put to death at Rome. (Strab. XII. p. 543.) Other particulars relative to Heraclea may be collected from Athenæus. (VIII. 531, C. 351, C. D.) It was celebrated for its wine, almonds, and nuts. (I. 32, B. II. 53, D. 54, B.) Heraclea continued to flourish under the Roman emperors, being dignified with the titles of Metropolis and Augusta in the coins of Trajan and Severus ^q. We find it also mentioned as a city of note by Arrian, (Peripl. p. 14.) Pliny, (VI. 1.) Marcian, (Peripl. p. 70.) and the Itineraries. And from the incidental references made to it in the Byzantine annals we find it retained some degree of prosperity as late as the reign of Manuel Comnenus. (Nicet. Ann. p. 158, B.) And even now some traces of the ancient name are still apparent in that of *Erekli*. Near Heraclea was a spot called Aconæ, either from its abounding with whetstones, or the aconite plant. (Steph. Byz. v. Ἀκόναι. Athen. III. 85, B. Strab. XII. p. 543. Eustath. ad Dionys. Perieg. v. 792.) Pliny calls it a port. (VI. 1.) Beyond it the same writer places the Acherusian cave, where Hercules is said to have dragged forth the hell-hound Cerberus to light.

Καὶ Μαριανδυνῶν ιερὸν πέδον· ἐνθ' ἐνέπουσιν
Οὐδαίου Κρονίδαο μέγαν κύνα, χαλκεόφωνον
Χερσὸν ἀνελχόμενον μεγαλόφρονος Ἡρακλῆος
Δευγὸν ἀπὸ στομάτων βαλέειν σιαλώδεα χυλόν.

DIONYS. PERIEG. v. 788.

Xenophon, who terms it the Acherusian peninsula, says, that Hercules descended there to the shades in

^q Sestini, p. 68. There are of Heraclea, and his queen Amastris. also medals of Dionysius, king

quest of Cerberus ; and he affirms, that traces of his descent, for upwards of two stadia in depth, were shewn in his day. (Anab. VI. 2. Cf. Diod. Sic. XIV. 261. Mel. I. 19.)

Arrian names beyond Heraclea, at a distance of eighty stadia, Metroum ; and forty stadia further, Metroum. cape Posidium. Marcian reduces the whole space Posidium to 100 stadia. (p. 70.) Mannert says this promontory is now called *Tchantsche-Aggisi*^r. Next is a spot named Tyndaridæ, forty-five stadia from cape Tynda- Posidium ; (Arrian. p. 14.) and fifteen stadia fur- ridæ. Nymphæum. From thence to the river Oxi- Nymphæ- um, noticed by both geographers, are fifteen stadia. Oxinas fluvius. Mannert supposes this stream to be the Soonantes Soonantes of Apollonius. (Arg. II. 748. et Schol. Cf. Plin. fluvius. VI. 1.^s) But, besides this, we have two others named by Pliny, the Pædopides and Callichorus ; the latter Pædopides of which is also mentioned by Scylax. (Peripl. p. 34.) Callichorus After the Oxinas appears the haven of Sandaraca, Sandaraca at a distance of ninety stadia. Then Crenidæ, sixty Crenidæ. stadia ; Marcian says only twenty. Psyllum was a Psyllum. port thirty stadia from Crenidæ. (Arrian. p. 14. Marcian. Peripl. p. 70. Cf. Steph. Byz. vv. Κραιδες, Ψύλλα. Ptol. p. 117.)

Tium, which next follows, was a Greek town of Tium. some note, founded by the Milesians, in a district belonging to the Paphlagonians, but annexed by Prusias to Bithynia. (Memnon. c. 17—19. Arrian. Peripl. p. 14.) In Strabo's time it was but a small place, remarkable only as the birthplace of Phile-tærus, founder of the Attalic dynasty. (XII. p. 543. Plin. VI. 1. Steph. Byz. v. Τίος.^t) The town ap-

^r Geogr. tom. VI. part i. p. 614.

^s Ibid. p. 615.

^t There are medals of Tium

Billæus
fluvius.

pears to have been advantageously situated on a peninsula, at the mouth of the river Billæus. The site is called *Filius*, or *Filbas*, which is also the modern name of the river. The Billæus is a considerable stream which rises on the confines of ancient Phrygia and Galatia, and was accounted by some geographers the limit of Bithynia and Paphlagonia. (Marcian. Peripl. p. 71.) But it is more usual to extend the confines of the former province to the Parthenius, a few miles further to the east. (Arrian. Peripl. p. 14.)

Παφλαγόνες τ' ἐπὶ τοῖς Πελοπήσιοι εἴκαθον αὗτως,
"Οσσους Βιλλαίοιο μέλαν περιάγνυται ὕδωρ.

APOLL. ARG. II. 792.

The Mariandyni did not occupy the whole space between the Sangarius and Parthenius; for Tium and the adjacent coast were attributed by several writers to the Caucones, a people apparently of great antiquity, and once widely diffused, since they had wandered as far as the western coast of the Peloponnesus^u. Some authors assigned to this people a Scythian origin; others looked upon them as a Pelasgic tribe; while some again maintained that they came originally from Macedonia; which three opinions, it may be observed by the way, might all be perfectly consistent. Callisthenes, a commentator on Homer, even affirmed, that the Caucones of Pontus were mentioned by the poet in conjunction with the Paphlagonians, and produced two lines to that effect in the catalogue of ships, which however were not found usually in the MSS. (Ap. Strab. XII. p. 542.)

as late as the reign of Gallienus. The ethnic is **TIANΩΝ**.

Sestini, p. 71.

^u Anc. Greece, t. III. p. 77.

Καύκωνας αὐτ' ἦγε Πολυχλέος υἱὸς ἀμύμων
Οἳ περὶ Παρθένιον ποταμὸν κλυτὰ δώματ' ἔναιον.

Strabo reports, that in his time there was a remnant of this people near the Parthenius, named Cauconites: and Ptolemy also ranges them next to the Mariandyni.

The interior of Bithynia is much less known to us than the coast; and though the Itineraries give us the details of the principal roads which traversed the province, the names of places which occur there are for the most part obscure and unknown. The country indeed, being very woody and mountainous, could never have been thickly peopled; and it is for this reason that so few towns of note present themselves in the interior. The principal of these was Bithynium Bithynium, which probably was a considerable place ^{postea} Claudio- in ancient times, and perhaps gave its name to the polis. whole province. Mannert is inclined to suppose that it was first founded by Zipetes, king of Bithynia, who called it by his name; but this is only a conjecture, resting on no solid foundation ^x. Respecting the position of Bithynium, we learn from Strabo, that it was situated above Tium, in a district named Salone, celebrated for its excellent pastures, and a cheese much esteemed at Rome. (XII. p. 565. Plin. XI. 42. Steph. Byz. v. Σαλώνεια.) And we collect from the Itinerary of Antoninus, that there was a road leading from it to Ancyra. Pausanias further leads us to suppose it was on the banks of the Sangarius, or near it. (Arcad. 9.) It appears from Ptolemy, and other authorities, that Bithynium afterwards changed its name to Claudiopolis, which it retained till the downfall of the east-

^x Geogr. tom. VI. part i. p. 618.

ern empire. This change probably occurred in the reign of Tiberius, for the name first presents itself in a medal struck under his auspices. Claudiopolis, as the birthplace of Antinous, the favourite of Hadrian, received several privileges from that emperor.^y (Dio Cass. LXIX. 11. Pausan. loc. cit. Xiphil. p. 262.) Under the emperor Theodosius it was made the capital of the province Honorias. Many years after, we learn from Anna Comnena (p. 967.) and Leo Diaconus, (IV. 9.) who describe it as the most wealthy and flourishing city of Galatia, that it was almost totally destroyed by an earthquake, attended with vast loss of lives.

*Hadriano-
polis.*

Hadrianopolis of Bithynia is not to be confounded with Hadriani in the same province, near mount Olympus and the Rhyndacus. The former of these towns is known to us from Hierocles, (Synecd. p. 695.) who places it in the province Honorias, the Notitiæ Imperii, and its coins^z. Most antiquarians agree in fixing the site of this ancient town at *Boli*, a Turkish city of some size, near the *Filbas*, or *Billæus*^a. Ptolemy places in the interior of Bithynia, Flaviopolis, called also Cratia. Besides the fact of its having borne these two names, little is known respecting this town, except that the Itineraries place it between Claudiopolis and Ancyra, twenty-four miles from the former. It was an episcopal see, (Hierocl. Synecd. p. 695.) and coined its own money^b. The Table Itinerary lays down a

*Cratia
que et Fla-
viopolis.*

^y Some coins of that emperor, struck at Claudiopolis, are inscribed with the name of Antinous. Sestini, p. 67.

^z These begin with Hadrian, and end with Philip. Sest. p. 68.

^a Leake's Asia Minor, p. 309.

^b Sestini adduces one autonomous coin, with the epitaph KPH, for Cratia; and several of imperial die, from Antoninus Pius to Gallienus. p. 67.

road leading from Nicomedia, through the interior of Bithynia, into Galatia, Paphlagonia, and Pontus. The three first stations are Lateas, Demetrium, Dusepro Solypnum. Of these, Lateas, which is twenty-four miles from Nicomedia, is most probably the Latania of Ptolemy. In Col. Leake's map *Latania*, this site is made to correspond with *Kondek*, but from the distance it should be on the left bank of the Sangarius. Demetrium, thirteen miles further, ^{Demetri-}_{um.} is unknown. Dusepro Solypnum is evidently a corruption of the Greek *Δύσις πρὸς Ὀλυμπόν*, implying a station at the foot of mount Olympus, i. e. a continuation of the mountain properly so called. Modern travellers have pointed out in this direction a Turkish village, whose name, *Dustchē*^c, bears considerable analogy to the station of the Itinerary, which is placed at a distance of thirty miles from a considerable town, without a name, on the left bank of the Sangarius. The latter circumstance should agree with Claudiopolis, but Col. Leake is inclined to think Hadrianopolis is meant^d.

Another road led from Nicæa to Ancyra, passing to the south of the former, and along the valley of the Sangarius. The Bithynian stations on this road are, Tateabio, a corruption of Tattæum, or Tottæum, ^{Tattæum,}_{sive Tot-} (Itin. Anton. p. 141. Itiner. Hieros. p. 573.) forty ^{tæum.} miles from Nicæa; Dablæ, twenty-eight or twenty-nine miles from Tottæum, which Ptolemy calls Dables; Dadastana, which next follows, at a distance of forty or forty-five miles from the preceding station, is noticed in history as the place where the emperor Jovian died on his return from Syria to

^c Otter, *Voyage en Turquie*, c. 48. Tavernier, tom. I. c. 2.

^d *Asia Minor*, p. 309.

Constantinople. (Socrat. Hist. Eccl. III. in fin. Sozom. VI. 6. Ammian. Marcell. XXV. in fin. Philostorg. VIII. 8.) These writers state it to have been on the borders of Galatia and Bithynia. Ptolemy assigns it to the latter province, as well as Juliopolis, which next follows, at a distance of twenty-six miles from Dadastana. This town could boast of considerable antiquity, having been formerly under the name of Gordium, the residence of the ancient Phrygian kings Gordius and Midas. (Strab. XII. p. 568.) It is also celebrated in history as the scene of Alexander's exploit in cutting the famous Gordian knot. Arrian, who relates the circumstances of this adventure at length, says it took place in the citadel of Gordium, which had been the palace of Gordius. The historian remarks also, that the town was near the Sangarius, and in Hellespontine Phrygia. Alexander appears to have remained some time at Gordium, being joined there by some fresh troops and the deputations sent by different towns. (Arrian. I. 29, 7. II. 3. Quint. Curt. III. 1, 12. Justin. XI. 7.) In the time of Strabo the original town had sunk into the condition of a mere village, but Cleon again raised it to the rank of a city. This person had rendered himself famous by his robberies and marauding warfare in the fastnesses of Olympus; and having conciliated first the favour of Marc Antony, by thwarting the measures of Labienus his enemy, who commanded in Asia Minor, and afterwards that of Augustus, by deserting his former patron, obtained several concessions and grants from the emperor. He was at the same time priest of Jupiter Abrettenus in Mysia, of Comana in Pontus, and possessed besides the Mysian districts of Morene

Juliopolis,
prius Gor-
dium.

and Abrettene: but he did not long enjoy this accumulation of dignities, being seized, soon after his arrival at Comana, with an acute disorder, which in a short time carried him off. (Strab. XII. p. 574.) Gordium is mentioned by Polybius as a small place of Galatia, in his account of the operations of Cn. Manlius against the Gauls of Asia Minor. (XXII. 20, 8.) Livy, who alludes to the same event, and exhibits at length the account of Polybius, of which the above citation is only a fragment, adds, that Gordium was a small town in itself, but a place of much traffick, from its central situation, being nearly equidistant from the Hellespont, the Euxine, and the sea of Cilicia. (XXXVIII. 18.) It continued to flourish, under the name of Juliopolis, from the reign of Augustus for several centuries, being mentioned by Pliny, (V. 43.) Ptolemy, and the Itineraries. Procopius leads us to suppose, however, that in the time of Justinian it had suffered from the inundations of a neighbouring river, and was therefore repaired by that emperor. (Ædip. V. 4.) This stream, as we learn from the coins of the town, was called Scopas^e. It is the Scopius of Pliny. (V. 43.) ^{Scopas}_{fluvius.} The Jerusalem Itinerary mentions another river, called Hieros, which it was necessary to cross in going from Juliopolis to Ancyra, thirteen miles to the east of the former. Pliny also names it, and remarks besides, that it separated Bithynia from Galatia. (loc. cit.) When Procopius says Justinian made a bridge over a river, Siberis in Galatia, about ten miles to the east of Juliopolis, and close to a spot called Sycei, there is very little doubt that he is speaking of the same stream. (Ædip. V. 4.^f) In

^e Sestini, p. 68.

^f Leake's Asia Minor, p. 79.

the Itinerary of Antoninus we have a road leading from Claudiopolis to Ancyra in Galatia, by Cratia, or Flaviopolis, Carum vicum, and Legna. Of Carus nothing is known, unless it should be the Cœue of Xenophon, which is mentioned as a large village of Phrygia, on the road to Paphlagonia. (Hell. IV. 1, 10.) Legna is no doubt the Luginia of Stephanus Byz., which belonged to Bithynia. (v. Λαγίνια.) The same Itinerary furnishes another road from Nicæa to Ancyra in Galatia, by Juliopolis. The first station is called Oriens Medio, sixteen miles from Nicæa. The meaning of the name, as well as the position, are quite unknown. Beyond, the road passes, as in the Table, through Tottiacum and Dables. The next station to that is Cœnon Gallicanon, known also from Ammianus Marcellinus, who reports that the sister of the emperor Constantius was there seized with a sudden fever, and carried off. (XIV. 11.)

Besides the towns hitherto mentioned, and of which something is known, we have now to add a few with which we are acquainted in name only.

Callica.

Patavium.
Protoma-
cra.

Timæa.

Dadau-
cana.
Clitæ.

Orminius
mons.

Agrippen-
ses.
Partheno-
polis.
Coryphan-
ta.

These are, in Ptolemy, Callica, near Nicomedia;

Patavium, to the south of the Ascanian lake^g; Protomacra, between Nicæa and Dadastana, written Pro-

tunica in the Jerusalem Itinerary; (p. 573.) Timæa,

more to the east; Dadaucana, between Prusa, on the Hypius and Bithynium; Clitæ, near the Par-

thenius; and a mountain named Orminius.

In Pliny we find mention made of the Agrippenses, among the towns of Bithynia, and Parthenopolis;

Coryphanta; the two last no longer existed

^g Wesselink thinks this name should be altered to Tattæum.
(Itin. Anton. p. 141.)

in his day. (IV. 43.) He names also the rivers Syrius, Lapsias, Pharmacias, Crynis. Of these, the Syrius fl. Lapsias fl. Pharmacias, or Pharmicas, is perhaps the river cor- Pharma- ruptly named Pharnutis in Suidas, and which, he cias fl. Crynis fl. says, flowed near Nicæa.

Stephanus Byz. names, in Bithynia, Alyatta, per- Alyatta. haps the same which Livy calls Alyattus, (XXXVIII. 18.) though that should seem rather to belong to Galatia. Mazæum, a place mentioned by Arrian, Mazæum. in his Bithyniaca. (v. Ἀμαξόνειον.) Amaxa, cited Amaxa. from Eratosthenes. (v. Ἀμαξα.) Bysnæi, a tribe of Bysnæi the Bebryces, the aboriginal inhabitants of Bithy- gens. nia. (v. Βυσναιοί.) Epiphanea, (v. Ἐπιφάνεια.) Zipœ- Zipœtius. tium, founded by king Zipœtes, near mount Lype- Lyperus rus. (v. Ζιποίτιον.) The latter fact is stated by the mons. historian Memnon. (Ap. Phot.) Corone. (v. Κορώνη.) Corone. Cossus, a mountain mentioned by the poet Demos- Coesus. thenes, in his Bithyniaca. (v. Κοσσός.) Ladepsi and Ladepsi, Tranipsi, Bithynian tribes, cited from the Hellenics Tranipsi, of Theopompus. (v. Λαδεψοί.) Hodiopolis and Mo- gentes. cata, mentioned by Domitius Callistratus, in his Mocata. work on Heraclea. (vv. Ὁδιούπολις, Μόκατα.) Nico- Nicomedium. medium, an emporium, according to Arrian, whose Bithyniaca are referred to. Sete, or Seti. (v. Σητία.) Sete. Simana, a town situated between two rivers. (v. Σί- Simana. μανα.) Tarantus, where Jupiter was worshipped Tarantus. under the name of Tarantæus. It was also called Darandus by some writers; from the Bithyniaca of Demosthenes. (v. Τάρας.) Tarsus and Tarseia, from Tarsus. the same poet. (v. Ταρσός.) Charax, a considerable Charax. emporium in the bay of Nicomedia: this must be said of a very late period in the Byzantine empire. (v. Χάραξ.)

SECTION IV.

PAPHLAGONIA.

Origin and history of the Paphlagonians—Boundaries of their country—Description of the coast between the rivers Parthenius and Halys—Interior of the province.

THE antiquity of the Paphlagonian nation is sufficiently established by the fact of its being enumerated by Homer among the Asiatic defenders of Troy. (Il. B. 851.) The Heneti also, whom the poet mentions as one of their tribes, have given rise to much discussion on the part of his commentators and scholiasts in connexion with the well-known people of the same name, who occupied the head of the Adriatic, and were said to have been transplanted thither by the Trojan Antenor. Whatever may be thought of this tradition, which was certainly ancient, and accredited by many writers, as appears from Strabo's account, (XII. p. 544. XIII. p. 608.) it is plain that no change had taken place in the great body of the nation, from the period alluded to by Homer to that of the above mentioned geographer; since the places mentioned by the poet as belonging to the Paphlagonians still subsisted in the latter's time, and are assigned by him to that people. Strabo himself hazards no remark respecting the origin of the Paphlagones; but he incidentally introduces an

observation, which proves that in his opinion there was a considerable similarity between their language and that of the Cappadocians. Now these last are allowed on all hands to have been Syrians, and therefore if the Paphlagonians spoke the same language, they must have had a common origin. It must be confessed, however, that this argument is not conclusive, for the Cappadocians may have once occupied the country of the Paphlagonians, and this may have produced that uniformity of tongue, which Strabo notices. (XII. p. 553.) And this, in fact, seems to be made out by a circumstance recorded by Herodotus; namely, that the Cappadocians, whom he calls Syrians, once extended on the left bank of the Halys, as far as the Parthenius; (II. 104.) that is, they occupied the whole length of coast usually assigned by ancient geographers to Paphlagonia. The probability therefore is, that the Paphlagonians coming from the west, drove the Leuco-Syri from the country, and finally compelled them to retire beyond the Halys. If I am right in reasoning thus, it will follow, that the Paphlagonians are to be looked upon as being of the same race with the Bithyni, Mysi, and Phryges, that is, they were a Thracian people. Theopompos, indeed, as we learn from Strabo, classed them with the Mariandyni and Bithyni. (XII. p. 541.) Another circumstance which seems further to confirm this opinion is the name of Cotys, which is given by Xenophon to one of their chiefs, (Hell. IV. 1.) and which is so frequently found to occur in the nomenclature of Thracian sovereigns. We may add also from Herodotus, that their arms and accoutrements were very similar to those of the Phrygians. Paphlagonia appears to

have been governed by native princes, from the earliest period till its conquest by the Romans; and even at that epoch we find there were chiefs who boasted of their descent from Pylæmenes, the leader of the Paphlagonian Heneti in the Trojan war, and whose claims were admitted by Pompey. (Strab. XII. p. 541.) When the Lydian monarchy had become so powerful as to bring into subjection the whole Asiatic peninsula within the Halys, Paphlagonia formed the extreme portion of the empire of Crœsus to the east, being separated from the Leuco-Syri or Cappadocians, by the channel of that river. (Herod. I. 72.) On the dissolution of the Lydian empire by the defeat and capture of Crœsus, Paphlagonia submitted, with the rest of Asia Minor, to the Persian arms, and in the reign of Darius formed, with the cities on the Hellespont, the Bithynians, Phrygians, and Cappadocians, the third division or satrapy of the empire. (III. 90.) The Paphlagonians furnished a numerous and well appointed body of troops for the great armament of Xerxes. And about a century later we find the whole force which the country could supply estimated by Xenophon at no less than 120,000 men, horse and foot. The cavalry, indeed, was esteemed by the Persians to be superior to any they possessed; and the whole territory presented great advantages for a defensive warfare. (Anab. V. 6.) Under these circumstances, the Paphlagonian chiefs, knowing their strength, considered themselves almost independent of the Persian satraps, and were ready to join any power at war with those governors which held out sufficient inducement for them to take the field on its side. Thus when Agesilaus had invaded the Persian do-

minions, and was carrying on a destructive war in the plains of Caria and Phrygia, one of his first objects seems to have been to engage the Paphlagonian chief, Cotys, to join the Lacedæmonian army. For this purpose, he himself proceeded into Paphlagonia, and easily secured the alliance of its sovereign, through the intervention of Spithridates, a Persian nobleman, who had attached himself to Agesilaus out of enmity to Pharnabazus. A marriage was afterwards brought about between Cotys and the daughter of Spithridates, at the desire of the Spartan king. Not long after, however, the unjust treatment they met with at the hands of Herippidas, a Lacedæmonian officer, induced the Paphlagonian prince and Spithridates to quit the camp with all their troops; an event which, as Xenophon observes, was more felt by Agesilaus than any other which occurred in the course of the war. (Hell. IV. 1, 1—13.) Paphlagonia submitted to Alexander after the battle of the Granicus, (Arrian. II. 4, 1.) and on the death of that prince it fell to the share of Eumenes, one of his most distinguished generals. (Plut. Eum. Quint. Curt. X. 10.) But the constant wars in which Eumenes was engaged against Antigonus and others, prevented him from securing the possessions allotted to him. During the agitation which pervaded the whole of Asia and Greece, from these contests between Alexander's successors, the kings of Pontus, who possessed a small sovereignty on the shore of the Euxine, and between Paphlagonia and Colchis, gradually emerged from the obscurity in which they had hitherto remained concealed, and began to prove formidable neighbours to the Greek colonies on the Euxine, and the

native chiefs of Paphlagonia. Mithridates, of Persian extraction, one of these sovereigns, extended his dominions to the river Halys, and even proceeded to attack Sinope, a flourishing Greek colony on the coast beyond that river. (Appian. Mithr. c. 9. Polyb. IV. 56.) Sinope resisted his attack with success, through the assistance of the Rhodians; but it was afterwards compelled to yield to his son Pharnaces, (Polyb. XXIV. 10, 1.) who even engaged in war with the kings of Pergamum and Cappadocia, and was only stopped in his career of conquest by the intervention of the Romans. (Polyb. III. 3, 6. XXV. 2. seq.) His grandson, the celebrated Mithridates, surnamed Eupator, not only made war against Nicomedes, king of Bithynia, with such success that he stripped him of his dominions, but even defeated the Romans in several engagements, and for a time was left in possession of nearly the whole peninsula of Asia, except the towns of Chalcedon and Cyzicus. Checked, however, by the exertions of Sylla in Greece, and of Lucullus in Asia Minor, Mithridates saw the fruits of his victories rapidly snatched from him, till he was left solely in the possession of his hereditary dominions. Of these, too, he was finally stripped by Pompey, who annexing the greatest part of Paphlagonia to the province of Bithynia, allotted the remainder to certain native chiefs, who boasted of being descended from Pylæmenes, king of the nation, in the Trojan war. (Strab. XII. p. 541.) The last of these Paphlagonian sovereigns was Dejotarus, son of Castor, and tetrarch of Galatia. (Strab. XII. 562. Cic. pro Dejot.) We find that in the time of the younger Pliny, the whole of Paphlagonia, as far as the Halys, acknowledged his au-

thority as prætor of Bithynia. But the province was commonly known by the name of Pontica^a.

We shall consider Paphlagonia under its more ancient limits; which were, the Parthenius on the side of Bithynia, and the Halys on that of Pontus and Cappadocia. On the north it was bounded by the Euxine, and on the south it was separated from Galatia by a lofty chain of mountains connected on one side with the Bithynian Olympus, on the other with the Cappadocian and Pontic ridges. This range of mountains was covered with forests, which supplied abundance of excellent timber for ship-building, and various kinds of wood for making tables, and other ornamental works. They contained also salt mines, and a rich supply of the mineral called sandarach. Eudoxus reported that fossil fish were likewise to be found in some parts of the country. (Strab. XII. p. 561—563.) The plains afforded rich pastures for horses and cattle, and the mules of the Paphlagonian Heneti were celebrated as early as the days of Homer.

'Eξ Ἐνετῶν, δθεν ἡμιόνων γένος ἀγροτεράων.

IL. B. 852.

The sheep of the county adjoining the Halys furnished wool much esteemed for the fineness of its quality. (Strab. XII. p. 546.) And the Euxine along the whole extent of coast supplied great quantities of excellent fish; especially the kind of tunny called pelamys. (Strab. XII. p. 545. Athen. VII. p. 307.)

The Parthenius, with which we shall commence our description of maritime Paphlagonia, is a considerable river according to Xenophon, and not

^a Inscr. ap. Cellar. Geogr. Ant. t. II. p. 206.

fordable. (Anab. V. 6, 3.) It was supposed to derive its name from the gentleness of its stream, or because Diana loved to bathe in its waters.

Καὶ δὴ Παρθενίοιο ρόδις ἀλιμυρήντος
Πρηγάτου ποταμοῦ παρεμέτγεον· ὃ ἐνι κούρῃ
Λητωῖς ἄγρηθεν ὅτ' οὐρανὸν εἰσαναβαίνει,
Οὐ δέμας ἴμερτοῖσιν ἀναψυχει ὑδάτεσσιν.

APOLL. ARG. II. 938.

(Cf. Schol. ad loc. Steph. Byz. v. Παρθένιος.) It is mentioned for the first time by Homer, in his Catalogue of ships. (Il. B. 854.)

Ἄμφι τε Παρθένιον ποταμὸν κλυτὰ δώματ' ἔναιον.

Herodotus also mentions the Parthenius. (II. 104.) And Strabo affirms that it was so called from the beauty of the country which it traversed. (XII. p. 543.) Its source was in Mount Pœmen, a Paphlagonian mountain, situated in the interior of the province, (Steph. Byz. v. Ποιμῆν.) and after a winding course it fell into the Euxine, not far from the town of Amastris. (Id. v. Παρθένιος.) The modern name is *Bartan*.

Sesamus
postea
Amastris.

The first town to be noticed on the right bank of this river is Sesamus, a Greek colony from Miletus probably, and of great antiquity, since it is alluded to in the Iliad. (B. 853.)

Οἳ δα Κύτωρον ἔχον, καὶ Σήσαμον ἀμφενέμοντο.

Scylax has also mentioned it in his Periplus. (p. 34.) From Strabo we learn that it was afterwards colonized by Amastris, niece of Darius Codomanus, and wife of Dionysius, tyrant of Heraclea, who transmitted her name to the new settlement. Cromna and Cytorum, two neighbouring towns, contributed also to the foundation of Amastris, but Sesamus was the acropolis and seat of royalty. (XII. p. 544. Cf.

Plin. VI. 2. Steph. Byz. v. Σήσαμον. Schol. Apoll. Arg. II. 945.) According to Arrian, Amastris was ninety stadia from the Parthenius, (Peripl. p. 15.) which measurement is confirmed by Marcian. (Peripl. p. 70.) We learn from Pliny the Younger that in his time Amastris was a handsome town, adorned with squares and public buildings; in one of his letters to Trajan, he recommends that a common sewer which was open, and was a great public nuisance and disfigurement to the town, should be covered. This was allowed by the emperor. (X. 99.) Ecclesiastical writers speak of Amastris as a flourishing town and episcopal see, in the seventh century. (Hierocl. p. 696. Nicet. Paphlag. Orat. in S. Hyacinth. XVII.) The Table Itinerary calls it Mastrum. Abulfeda, the Arabian geographer, *Samsari*. The modern name is *Amasera*^b.

Sixty stadia further east we find Erythini, (Arrian. Peripl. p. 15.) which, according to the Scholiast of Apollonius, were cliffs or hills.

Νυχτί τ' ἔπειτ' ἄλληκτον ἐπιπροτέρωσε θέοντες,
Σήσαμον, αἰπεινούς τε παρεξενέοντ' Ἐρυθίους.

ARG. II. 942.

Κρῶμνάν τ', Αιγίαλόν τε, καὶ ύψηλοὺς Ἐρυθίους.

IL. B. 855.

Strabo reports that there were two rocks called Erythini, in his time, from their colour. (XII. p. 545.) Stephanus says there was a town so named. (v. Ἐρυθίοις.) Cromna, another place mentioned by *Cromna*. Homer, was sixty stadia from thence. (Arrian. loc. cit. Apoll. loc. cit. Plin. VI. 2. Strab. XII. p. 544.)

^b There are coins extant, both of queen Amastris and the city she founded, the latter have the epigraph ΑΜΑΣΤΡΙΑΝΩΝ. Sestini, p. 64.

Cytorum. It belonged to Amastris. (Steph. Byz. v. Κρῶμνα.) The site retains the name of *Cromena*^c. Cytorum was ninety stadia further. It was a Greek town of great antiquity, since Homer alludes to it:

Oἱ δα Κύτωρον ἔχον, καὶ Σίσαμον ἀμφένεμοντο.

**Cytorus
mons.**

It is also mentioned in the Periplus of Scylax. (p. 34.) According to Ephorus, cited by Strabo, it took its name from Cytorus, son of Phrixus, and belonged to the Sinopians. This place derived further celebrity from mount Cytorus, which rose above it, and was covered with boxwood.

Et juvat undantem buxo spectare Cytorum.

VIRG. GEORG. II. 437.

Κρωβίαλον, Κρώμναντε, καὶ ύλήεντα Κύτωρον.

APOLL. ARG. II. 944.

Mox etiam Cromnam atque jugo pallente Cytoron.

VAL. FLACC. V. 106.

(Cf. Plin. VI. 2.) The modern name is *Sagra*. In the Table Itinerary, as Col. Leake has well observed, the road which followed the coast to Sinope has by an error of the transcriber been moved out of its proper direction along the sea, into the interior. This is evident from the names of Cromea, Cytherum, and Carambus, for Cromna, Cytorum, and Carambis^d. The vestiges of Cytorum have been observed by travellers near the present *Kidros*, which is evidently a corruption of the ancient name^e.

Ægialus.

The ancient geographers applied the name of *Ægia-*

^c Sestini notices some autonomous coins belonging to Cromna.

^d Col. Leake has in my opinion most satisfactorily accounted for this mistake, by shewing that the similarity of name between Amastris and Amasia

induced the transcriber to substitute the coast road from Amastris to Sinope, for that leading from Amasia to Sinope. Asia Minor, p. 307.

^e Tavernier, Voyage, tom. III. c. 6.

lus to a portion of the Paphlagonian coast in the immediate vicinity of Cytorus, and which extended for a hundred stadia towards cape Carambis. There seems also to have been a small town of this name sixty stadia from Cytorus. (Arrian. Peripl. p. 15.) Strabo observes, that some commentators of Homer read Cobialus in that poet for Ægialus. (XII. p. 545.) And it is worth while to remark, that in Apollonius we find the place called Crobialus, (Arg. II. 944.) *Crobialus.* which is imitated by Valerius Flaccus. (Arg. V. 102.)

Altius in ventos recipit ratis; ac fugit omne
Crobiali latus, et fatis tibi, Tiphy negatum
Parthenium.

The Homeric appellation prevailed however in the time of Arrian; and still later we find in the Table Itinerary the corrupt word Egilan for Ægialus. From thence to a spot called Climax, Marcian in *Climax.* his Periplus reckons fifty stadia. (p. 71.) It is acknowledged also by Ptolemy. Timolæum, according to Marcian, (Peripl. p. 71.) was sixty stadia from Climax. Thymena, called also Teuthrания by the *Thymena.* last geographer, was forty stadia further, or ninety from Ægialus, as Arrian reports. (p. 15.) Cape Ca- ^{Carambis.} rambis, which next follows, forms an important ^{promonto-}_{rūm.} feature on this coast, since it advanced so far as to divide as it were the Euxine into two distinct seas, with the opposite cape of Criumetopon. (Strab. XII. p. 545. Plin. VI. 2.)

Ἐθάδε αύτε Κάραμβιν ἀμ' ἡελίοιο βολῆσι
Γνάμψαντες, παρὰ πουλὺν ἔπειτ' ἥλαινον ἐρετμοῖς
Αἰγιαλόν.

APOLL. ARG. II. 945.

Καραμβίδος ἔγγυθεν ἄχρης.

DIONYS. PERIEG. 785.

This headland is not however the most northern point of Asia Minor, since its latitude falls somewhat short of that attained by the promontory of *Inje* to the north-west of Sinope. The ancient name is easily recognised in that of *Kerempe*, which it bears at present. Scylax speaks of a Greek town which bore the same appellation as the Cape; (Peripl. p. 34.) a fact which is confirmed by Pliny. (VI. 2.)

Carambis
urbs.

Marcian places next to Carambis the little town of Callistratia, twenty stadia distant. (Peripl. p. 73.) This place, according to the anonymous author of the Periplus, was also called Marsilla; (p. 6.) then follows the Zephyrium of Arrian, (Peripl. p. 15.)

Callistra-
tia.

sixty stadia from Carambis, consequently forty from

Zephy-
rium.

Callistratia. Garium was eighty stadia further, ac-

Garium.

cording to Marcian's computation. Aboni-tichos, a small town and harbour noticed by Strabo (XII.

Aboni-
tichos.

p. 545.) and Arrian, (Peripl. p. 15.) was the birth-

place of an impostor named Alexander, who assumed the character of Æsculapius. Lucian, who exposes the fraud in his Pseudopropheta, affirms that this man had the boldness to petition the emperor—it is not stated who he was—to allow his native town to

take the name of Ionopolis for that of Aboni-tichos^f, a request which seems to have been granted, since

Marcian affirms that the later name prevailed in his time. And it is evident that the modern *Ineboli* is only a corruption of Ionopolis. (Lucian. Pseudo-

prop. II. p. 262. Marcian. Peripl. p. 72. Hierocl. p. 695. Steph. Byz. v. Ἀβώνον Τεῖχος.)

Æginetes.

Arrian places Æginetes, a small town and har-

^f There are coins of Anto-
ninus and L. Verus, with the

legend ΑΒΩΝΟΤΕΙΧΙΤΩΝ and
ΙΩΝΟΠΟΛΙΤΩΝ. Sestini, p. 64.

bour, 160 stadia to the east of Abonitichos. (Peripl. p. 15.) Marcian (p. 72.) reckons 160. Stephanus mentions also a river of the same name. (v. Αἰγινήτης.) Cinolis, or Cimolis, next follows, at a distance ^{Æginetes} of sixty stadia; this is a naval station, and is mentioned by Scylax, (p. 34.) Strabo, (XII. p. 544.) Arrian, (p. 15.) Marcian, (p. 72.) Mela, (I. 19.) and Pliny. (VI. 2.) Abulfeda, the Arabian geographer, calls it Kinuli, and the site yet retains the name of *Kinla*. Anticinolis was another small haven, probably on the opposite side of the bay, and sixty stadia distant. (Strab. loc. cit. Marc. loc. cit.) Stephane lay ^{Anticinolis.} 150 stadia more to the east. (Arrian. p. 15. Marc. p. 72. Scyl. p. 34. Steph. Byz. v. Στεφανίς. Plin. VI. 2.) The site, according to Tournefort, preserves the name of *Stephanio*, or *Estifan*. Scylax seems to place between Stephane and Cinolis a Greek town named Colussa, which no other writer has noticed. (p. 34.) ^{Colussa.} Potami, a station probably situated at the mouth of some small river, follows, after an interval of 150 stadia from Stephane. (Arrian. p. 15. Marc. p. 72.) *Cape Inje*, the most northern point on this coast, appears under two different names in the ancient maritime surveys, which constitute our principal authorities. Arrian calls it Lepte, (p. 15.) but Mar-^{Syrias sive} cian and the anonymous Periplus, Syrias. (Marcian. ^{Lepte pro-} p. 72. Anonym. Peripl. p. 7.) In both cases the ^{montori-}^{um.} distance of 120 stadia from Potami is specified. From this cape the shore bends gradually to the south-east in the form of a crescent, at the extremity of which stands *Sinub*, the representative of the ancient Sinope. But before we speak of that celebrated city, we have to point out the situation of Armene, a small town and port belonging to the ^{Armene.}

Sinopians. It was a place of so little traffick or note, that it gave rise to the proverb,

Ος ἔργον οὐκ εἶχε 'Αρμένην ἐτείχισεν.

(Strab. XII. p. 545.) Scylax says it was a Grecian colony, (p. 33,) and places after it, towards the west, another town named Tetracis, which is unknown to all other geographers. Xenophon states that the ten thousand, after obtaining vessels to convey them home, were stationary for some days in the port of Armene. (Anab. VI. 1, 9. Cf. Arrian. p. 15. Marcius. p. 72. Steph. Byz. v. *'Αρμένη*. P. Mel. I. 19. Plin. VI. 2.) A small river which flowed into the sea close to this place is called Ochosbanes by Marcius; (p. 72.) Ochthomanes, by the anonymous writer of the Periplus; (p. 7.) and Ocherænus, by Scylax. (p. 33.) The modern name is not known to me, but Armene corresponds with the site of *Aklimen*.

Sinope.

Sinope was a town of great antiquity, since its origin was referred by some writers to the Argonauts, by others to the Amazons. Mythologists derive the name from the nymph Sinope, daughter of the Asopus.

*Αὐτίκα δ' Ασσυρίης ἐπέβαν χθονός· ἐνθα Σινώπην
Θυγατέρ' 'Ασωποῦ καθίσσατο, καὶ οἱ ὄπαστε
Παρθενίην Ζεὺς αὐτὸς ὑποσχεσίησι δολωθείσ.*

APOLL. ARG. II. 947.

. alta Carambis
Raditur, et magnæ pelago tremit umbra Sinopes.
Assyrios complexa sinus stat opima Sinope;
Nympha prius, blandosque Jovis quæ luserat ignes,
Cœlicolis immota procis.

VAL. FLACC. V. 108.

The Sinopians themselves assigned the foundation

of their city to Autolycus, a companion of Hercules, and one of the Argonauts. They erected statues to him, and even paid him divine honours. (Strab. XII. p. 546.) But the original town was of small extent and power, till the accession it received from a colony of Milesians. This people, as we learn from Scymnus of Chios, were in their turn dispossessed by the Cimmerians, to whom Herodotus seems to assign the foundation of the city. But when they had been driven away by the Scythians, and overran Asia, the Milesians returned, and regained possession of their colony. (Scymn. Ch. Frag. v. 204—215. Anonym. Peripl. Eux. p. 8.) Towards the commencement of the Peloponnesian war, the Sinopians, who had fallen under the government of a tyrant named Timesileon, received assistance from the Athenian people; and after the tyrant had been expelled, Pericles, who was then at the head of affairs, proposed that 600 colonists should be sent to Sinope, which was agreed to, and carried into execution. (Plut. Pericl. c. 20.) At the time of the retreat of the ten thousand, we collect from Xenophon that Sinope was a rich and flourishing city, holding many of the neighbouring towns in its dependence, and possessing considerable influence over the barbarian tribes of Paphlagonia and Cappadocia. Among its colonies were Cerasus, Cotyora, and Trapezus, all situated on the Euxine, and flourishing settlements. It was principally through the assistance of the Sinopians, that the Greeks were enabled to procure ships to convey them to Heraclea. (Anab. V. 5. Diod. Sic. XIV. c. 32.) Strabo also reports, that the navy of Sinope held a distinguished rank amongst the maritime powers of Greece. It was

mistress of the Euxine as far as the Cyanean rocks, and divided with Byzantium the lucrative fishery of the pelamys, a kind of tunny. It appears, from a curious passage in Tacitus, that in the time of Ptolemy Soter, who sent an embassy to Sinope, that city was governed by a prince named Scydrothemis, who was doubtless a Paphlagonian. (Hist. IV. 82—84. Cf. Plut. II. 361.) Its great wealth, and the peculiar advantages of its situation, rendered it however in later times a most desirable acquisition to the neighbouring sovereigns of Pontus, a state almost unknown in history before the time of Alexander. It was assailed for the first time by Mithridates IV. great grandfather of the celebrated king of that name, in the year 220, B.C.^h Polybius, who is our chief authority for this event, thus describes the situation of Sinope: (IV. 56.) “ Sinope is situated in that part of the Pontus which lies to the right in sailing along towards the Phasis. It is built on a certain peninsula, which advances out into the sea. The isthmus, which connects this peninsula with the continent of Asia, is not more than two stadia in breadth, and is entirely barred by the city which comes up close to it; but the remainder of the Chersonnese stretches out towards the sea. It is quite flat, and of easy access from the town, but on the side of the sea it is precipitous all round, and dangerous for vessels, and offers very few spots for effecting a landing. The Sinopians, therefore, fearing lest Mithridates should erect works on the side of Asia, and at the same time by making a descent from the sea, and advancing to the level part of the peninsula, and

^h Clinton, Fast. Hell. Append. P. II. p. 425.

“ those points which overhang the town, should blockade them, set about fortifying the peninsula with trenches and pallisades on every point which was accessible from the sea: they also placed engines of war and soldiers in the most favourable stations, which they were easily enabled to defend, as the ground was naturally strong, and of no great extent.” Strabo, describing the Sinopian peninsula, says, “ It is girt all round with rocks hollowed out in the form of basons, thence called Chœnicides. At high water these troughs are filled, and render the shore inaccessible, especially as the rocks are every where so pointed, that it is impossible to walk on them with bare feet.” The Sinopians, though severely pressed by the king of Pontus, defended themselves with great vigour and courage, and finally, through the timely support and assistance they derived from the Rhodians, compelled Mithridates to raise the siege. They were not so successful in resisting the attack of Pharnaces, his son and successor. This prince having assaulted the town unexpectedly, found the citizens unprepared to resist, and easily overpowered them. (183. B. C.ⁱ) Sinope from that time became the chief town and residence of the kings of Pontus. (Strab. XII. p. 545—546. Polyb. XXIV. 10, 2.) Pharnaces was succeeded by Mithridates, surnamed Euergetes, who was an ally of the Romans, and obtained Phrygia in return for his services. (Justin. XXXVIII. 5.) This prince having been assassinated at Sinope, (120 B. C. Strab. X. p. 477.) left the crown to his son, the famous Mithridates Eupator, who was born and brought up in the city which we are now no-

ⁱ Clinton, Fast. Hell. Append. P. II. p. 425.

ticing. When at the height of his power, Mithridates, owing to this circumstance, employed himself in embellishing the place of his birth, and adding the contrivances of art to its local advantages. He formed a harbour on each side of the isthmus, erected naval arsenals, and constructed admirable reservoirs for the tunny fishery.

When the king of Pontus, after the disasters of Cyzicus, found himself forced to retreat before the victorious Lucullus, he left a strong force in Sinope, under the command of Bacchides, with orders to defend the town to the last extremity. This officer, suspecting the fidelity of the citizens, treated them with great cruelty and oppression, which precluded him from deriving any aid from their exertions; so that the Roman general easily overpowered the garrison, which consisted chiefly of Cilician troops, and put them to the sword^k. (Plut. Lucull. c. 18. Appian. Bell. Mifhr. c. 83.) Lucullus treated the Sinopians with kindness, and left them in possession of all the works of art which embellished their city, with the exception of the sphere of Billarus and the statue of Autolycus. (Strab. XII. p. 546. Cic. pro Leg. Manil. 8. Plut. loc. cit. Appian. loc. cit.) Pharnaces, the son of Mithridates, for a short time regained possession of Sinope; but after the rout of that prince at Zela, it opened its gates to Cæsar, who took the city under his protection, and sent a Roman colony there^l. Strabo informs us, that in his time Sinope

^k Sestini is inclined to ascribe to these Cilicians a coin of Sinope, with Phœnician characters, which he reads SINUP-KERT. Lettere Numismat. t. VII. p. 37. Class. Gen. p. 63.

I should be inclined to refer it rather to a much earlier period, when the Leuco-Syri occupied Paphlagonia as far as the Parthenius.

^l This appears from a coin of

was in a flourishing state. He describes it as surrounded by strong walls, and adorned within with fine porticoes, squares, gymnasia, and other edifices. It possessed also extensive suburbs, and numerous villas in the immediate vicinity. (XII. p. 546. Cf. Plin. VI. 2. Steph. Byz. v. Σινόπη.) It appears from Pliny's Letters, that the Sinopians suffered some inconvenience from the want of a good supply of water. This Pliny appears to have endeavoured to obviate by obtaining a grant from Trajan to erect an aqueduct, for the purpose of conveying water from a distance of sixteen miles. (X. 91.) Sinope was yet a flourishing town in the time of Arrian and that of Marcian. In the middle ages it formed part of the small empire of Trebizond, and fell into the hands of the Turks in the reign of Mahomet II, about 1470. Sinope is further remarkable for having given birth to the Cynic Diogenes; Baton, an historian, whose works are cited by Athenæus and Plutarch; and Diphilus, a much esteemed writer of the middle comedy. (Strab. XII. p. 546.) Near Sinope was a small island, named Scopelus, which larger vessels were obliged to circumnavigate before they could enter the harbour; but small craft could pass between it and the land, by which means a circuit of forty stadia was avoided. (Marcian. Peripl. p. 72, 73.) Sinope, according to Strabo, was 3500 stadia from the Hieron of Jupiter Urius; 2000 from Heraclea; and 700 from cape Carambis. (XII. p. 546.) As these distances agree with those of Marcian, it is probable that they are both derived

Sinope, with the letters C. I. C. F. S. for Colonia Julia Cæsarea Felix Sinope. The imperial

series extends from Augustus to Gallienus. Sestini, p. 63.

Evarchus
fl.

Carusa.

Gazorum.

Zagora.

Zaleucus
fluvius.

from Artemidorus, whom Marcian professes to follow. Eighty stadia beyond Sinope, the geographers notice the river Evarchus, (Marcian. Peripl. p. 73. Anonym. Peripl. p. 9.) which was once the boundary of Paphlagonia and Cappadocia. The anonymous geographer says it was commonly called Evechus in his time. (Cf. Menipp. ap. Steph. Byz. v. Καρναδοκία. Plin. VI. 2.) Near this river was the station called Cyptasia by Ptolemy, Cloptasa by the Table, which reckons seven miles from Sinope. Carusa was seventy stadia further, or 150 from Sinope, according to Arrian, who observes its port was very insecure. (p. 15. Marcian. p. 73.) Scylax also notices Carusa, and dignifies it with the title of Greek town. It answers to the station now called *Kerze*, unless this should be thought to represent the Gurzubanthon of the anonymous geographer, sixty stadia from Carusa. Gazorum of the same geographer is probably the Zagora of Arrian and Marcian, though they do not agree precisely in the distance; Arrian assigning 150 stadia from Carusa, Marcian 120, and the Anonymous Periplus 150 from Gurzubanthon. The latter writer states, that Gazorum was afterwards called Calippi. (p. 9.) In Ptolemy it is evident we should read Gazorum, instead of Galorum. I conceive the Orgibate of the Table to be the Gurzubanthon of the anonymous geographer. From Zagora to the little river Zaleucus, Marcian reckons 120 stadia; the anonymous geographer only ninety from Gazorum; which makes it still more doubtful whether we ought to identify those two places. Ptolemy writes the name of the river here spoken of, Zaliscus. It is, I imagine, the Hegela of the Table. From thence to the great river

Halys, which forms the boundary of Paphlagonia, Marcian reckons 150 stadia, the Anonymous Periplus only 110. The course of the Halys will be described when we have to speak of Pontus and Cappadocia; we shall therefore now leave the coast, and proceed to describe the remaining part of Paphlagonia.

The interior of Paphlagonia was divided, as appears from Strabo, into a number of small districts, some of which he names, but without defining accurately their positions or their extent. On the side of Bithynia he places the region called Timonitis,^{Timonitis regio.} and in succession the territory of Gezatorix and the districts called Marmolitis, Sanisene, and Potamia. But the principal feature in the internal geography of the province is an elevated chain, now called *Ulgax*, and anciently Olgasys, which extends from ^{Olgasys mons.} the Parthenius to the Halys. Strabo describes it as a lofty chain, and of difficult access, and adds, that the surrounding country was filled with temples erected by the Paphlagonians. Modern travellers speak of this mountain as being in some parts covered with snow nearly all the year. At the foot of Olgasys, and on the side of Sinope, was an ancient fortress, named Cimiata, which had been the ^{Cimiata.} strong hold of Mithridates Ctistes, the first sovereign of his line who effected the conquest of Pontus, as his surname indicates. Cimiata, according to Strabo, was the capital of a small district called from thence Cimiatene. (XII. p. 562.) More to ^{Cimiatene regio.} the north, and nearer the sea, the country was less mountainous, and consequently more productive, and better peopled. It was principally watered by the river Amnias, celebrated for a great battle ^{Amnias fluvius.}

fought on its banks between Nicomedes, king of Bithynia, and Mithridates Eupator, in which the former was defeated with great loss. This decisive victory was followed by the conquest of Bithynia, and nearly the whole of Asia Minor. (Strab. XII. p. 562. Appian. Mithr. c. 18.) The Amnias is the river of *Castamouni*, which rises in the northern chain of hills, running parallel with the coast, and at no great distance from it. After a course of nearly 120 miles, from N. W. to S. E., it falls into the Halys, about thirty miles south of Sinope. The country which this river traverses was anciently known by the names of Blæne and Domanitis.

Blæne
regio.Domanitis
regio.Pompeio-
polis.

Strabo (XII. p. 562.) places in this part of Paphlagonia, but apparently nearer the Halys, a town which, from its name of Pompeiopolis, would appear to have been founded by Pompey the Great.

The Table Itinerary reckons twenty-seven miles from Sinope to Pompeiopolis, which would fix the site of the latter in the valley of the Amnias, not far from the modern *Tash-Kupri*¹. Pompeiopolis is often referred to, as an episcopal see of Paphlagonia, by the ecclesiastical writers. (Socrat. II. 39—41. Sozom. 22. Hierocl. Synecd. p. 695. Justinian. Novell. XXIX. 1. Steph. Byz. v. Πομπηϊούπολις^m.) In the vicinity of this town Strabo places the great mine of sandarach, already noticed when speaking of the productions of this province. The mineral was extracted from a mountain, which was pierced in several directions to a considerable depth. The works were carried on at the public expense; and such

Sandara-
curgium.

¹ Capt. Kinneir observed some ruins at *Tash-Kupri*. p. 286.

^m There are some imperial

medals belonging to this town, but not earlier than the reign of M. Aurelius. Sestini, p. 64.

was the unwholesome nature of the service, that it was found necessary to employ slaves, and even malefactors. Owing to the little profit derived from the mine, the works were frequently suspended. When Strabo wrote, about 200 slaves were in employment. (XII. p. 562.) The particular district in which this mine was situated is called Pimolisene ^{Pimoli-}
^{sene.} by Strabo; a name derived from Pimolisa, a royal ^{Pimolisa.} fortress near the Halys, but in ruins at the time of which the geographer was speaking.

To the south of mount Olgasys, and at a distance of thirty-five miles from Pompeiopolis, according to the Table, stood Gangra, a city of some note, and ^{Gangra.} the royal residence of Morezus, or Morzus, a Paphlagonian prince mentioned by Livy. (XXXVIII. 26.) It was afterwards held by Dejotarus, the last sovereign of the country. (Strab. XII. p. 563. Cf. Plin. VI. 2. Ptol. p. 117.) Alexander Polyhistor, in his account of Paphlagonia, ascribed the foundation of this town to a goatherd, who had found one of his goats straying there: the word Gangra in the Paphlagonian language being significative of that animal. (Ap. Steph. Byz. v. Γάγγρα.) Frequent mention of this town occurs in the ecclesiastical writers, as the metropolitan see of Paphlagonia. A provincial synod assembled there in the fifth century. (Socrat. II. 43. Sozom. III. 14. Hierocl. Synecl.) This town was much exposed to the attacks of the Persians under the Byzantine emperors, and the historians of that period mention its having been often taken and retaken. (Nicet. Chon. Ann. p. 14, 15. Cinnam. p. 8. Cedren. p. 347, 361.) Some traces of the ancient name are yet perceptible in that of *Kiengareh*, or *Kangreh*, a Turkish town of

some size, which occupies the same siteⁿ. Before we quit Gangra, it may be worth while to mention, from Athenæus, that its orchards produced apples, which were much esteemed by the Romans. (III. 82.)

Germani-
copolis.

Near Gangra was the town of Germanicopolis, as we collect from the Novellæ of Justinian. (XXIX. 1.^o) The period of its foundation is uncertain, but it was probably built in honour of Germanicus. Its coins, however, are not of a higher date than the reign of M. Aurelius^p. The mention of the Halys on these monuments proves that it was situated near that river. Germanicopolis is named by Ptolemy in his list of Paphlagonian towns. The same geographer mentions also Neoclaudiopolis, which, before it received that name, was called Andrapa. The latter appellation appears, however, to have been still used as the title of the see attached to the town. (Hierocl. p. 705. Justinian. Novell. XXIII.) The coins of Neoclaudiopolis bear the dates and effigies of M. Aurelius, Sept. Severus, and Caracalla^q. Ptolemy seems to place this town to the south-east of mount Olgasys. In the same direction we have Conica, which is perhaps the Ciniata of Strabo. More to the west, Sacorsa and Moson. Further north Ptolemy has Zagira, Plegra, and Secora: in the central region, Elvia, Tobata, and Xoana: all obscure places, which occur nowhere else. Sora, or Zora, is mentioned by Hierocles (Synecd. p. 695.) and Constantine Porphyrogenetes (Them. I. 7.) as an episcopal town of Paphlagonia; also Dadybra,

Audrapa,
sive Neo-
claudiopo-
lis.

Conica.

Sacorsa.
Moson.
Zagira.
Plegra.
Secora.
Elvia.
Tobata.
Xoana.
Sora.

Dadybra.

ⁿ Tavernier, Voyages, I. 2. ^o See Wesselink's note on Pococke, Travels, tom. III. p. 136. Hierocles, p. 695. ^p Sestini, p. 64. ^q Ibid.

or Dadibra, which is besides known to the Byzantine historians. It was taken by the Turks in 1196. (Nicet. Ann. p. 305, C.) Mastya, which Pliny styles *Mastya*, a Milesian colony, is thought to correspond with the Mastrum of the Table Itinerary, if that name is not there intended to designate Amastris^r.

Mantinium, mentioned by Socrates, the ecclesiastical historian, as a town of Paphlagonia, is unknown. (II. 38.)

We have also some obscure stations in the Table Itinerary, which stand much in need of illustration by a comparison with the accounts of modern travellers. In the road which stands in the Table along the coast from Tium to Sinope, but which, as Col. Leake observes, is certainly misplaced, we have the following stations. From Tium to Mastrum, XII. M. P.; to Tycae, XX; to Cereae, XV; to Milletum, XV; to Sinope, XVIII. The only stations on this road which are well known are those of Tium and Sinope; the rest are all open to conjecture. It is certain that the distances are much too short; for the real distance from Tium to Sinope, in a straight line, cannot be less than 180 miles, whereas the Itinerary only furnishes for the sum total of its stages eighty miles. I may observe here, that *Tosia*, a town situated on the *Derek*, a river which falls into the Halys, represents the *Docea* of the Byzantine historians. (Nic. Ann. p. 336. Curopal. p. 843.)

Castamouni, another Turkish town of some population and extent, is evidently the Castamon so often mentioned by the same writers. (Nicet. Ann.

^r Sestini adduces a coin with the epigraph ΜΑΣΤΙΕΩΝ, which he ascribes doubtfully to this town. p. 64.

p. 14, 15. Niceph. Bryenn. p. 63, 64.) Near it was an extensive plain, called Gunaria. Capt. Kinneir says, "Castamouni stands in a hollow, in the centre of which rises a lofty and perpendicular rock, " crowned with a ruined fortress, formerly possessed " by the noble house of Comneni." The same traveller estimates its population at more than 12,000 souls^s.

Another road is indicated in the Table, as leading from a large town without a name, but which there is good reason to suppose is Hadrianopolis, to Gangra: the intermediate stations are, Manoris, XX; Potomia Cepora, XXXII; Antoniopolis, XV; Anady-nata, XXVIII; Gangaris, XXXVI. Manoris is quite unknown. Potomia Cepora is a corruption probably for Potamos Seporas, a river which is not mentioned by any other writer, but which seems to be the *Beinder sou*, a branch of the Parthenius^t. Antoniopolis, which Col. Leake imagines to be Antinoopolis^u, may be placed at *Tchirkis*. Perhaps we should read Antoninopolis; in which case it would indicate a town founded by the emperor Antoninus. On the Bithynian frontier we must place, with Appian, a mountain named Scorobas, which is perhaps the *Beinder dagh* of modern travellers^x. Near it was a fortress called Protopachium, where the generals of Mithridates defeated the Romans commanded by Manius (Appian. Mithr. c. 19.)

Seporas
fluvius.

Antonio-
polis.

Scorobas
mons.

Protopa-
chium.

Daridna.

^s Travels in the East, p. 281.

^t Kinnier's Travels, p. 278.

At present there seems to be no road leading from *Boli* to

Giengareh directly, but through *Angorah*.

^u Map of Asia Minor.

^x Kinneir's Travels, p. 278.

der Polyhistor. (v. Δάριδνα.) Candara, which was Candara about three schoeni, or twelve miles, from Gangra, and possessed a temple sacred to Juno Candarena. (v. Κάνδαρα.) Thariba was another small place in Thariba. the same vicinity, (Steph. Byz. ead. v.) perhaps the same as Dadibra. Coryleum, a place so called from Coryleum. Corylas, a king of Paphlagonia, mentioned by Xenophon. (Anab. VI. 1, 1. Steph. Byz. v. Κορύλειον.) Cressa, founded by Meriones, after the siege of Cressa. Troy; but afterwards occupied by Zeilas, son of Nicomedes. (Steph. Byz. v. Κρῆσσα.) It was probably on the sea coast, and perhaps should be identified with Carussa. Papitium. (v. Παπίτιον.) Timonitium, a fortress which gave its name apparently to the district called Timonitis by Strabo. (v. Τιμώνιον.) Tiriza, the inhabitants of which are named Tirizi-Tirizabani by Ctesias. (v. Τίριζα.)

SECTION V.

P O N T U S.

Dynasty of Pontus from its foundation as a kingdom till its conquest by the Roman arms—Boundaries and geographical features—Course of the river Halys—Description of the coast—Interior.

THE name of Pontus implies a political rather than a geographical division of territory: having been applied in the first instance to the coast of the Euxine situated between the Colchian country and the Halys, it was in process of time extended to the mountainous districts which lie towards Cappadocia and Armenia; and it even, at one time, included Paphlagonia and part of Bithynia. The denomination itself was unknown to Herodotus, who always designates this part of Asia by referring to the particular tribes who inhabited it, and who then enjoyed a separate political existence, though tributary to the Persian empire. Xenophon also appears to have been ignorant of it, since he adheres always to the same local distinctions of nations and tribes used by Herodotus; such as the Chalybes, Tibareni, Mosynœci, &c. It was not indeed till after the death of Alexander, that the Pontic dynasty makes any figure in history; and I think it probable, that the first sovereign of his line who assumed the title of king of Pontus was Mithridates, surnamed Ctistes,

or the founder. This prince, by the common consent of ancient authorities, was descended from one of the seven Persian nobles who conspired against the false Smerdis and his brother; and his ancestors, during three generations, had held a small principality in Cappadocia and Paphlagonia^a. Having assisted Eumenes, the general of Alexander, in his wars against Antigonus, Mithridates became naturally exposed to the vengeance of the latter, and after the death of Eumenes was forced to abandon his principality, and seek refuge in the fastnesses of Paphlagonia. It was here, as we learn from Strabo, that he maintained himself in the fortress of Cimata, amongst the passes of mount Olgassys; and not only resisted the attacks of his enemy, but when his attention had been withdrawn to more formidable adversaries, was enabled gradually to extend the frontiers of his little territory, till it had acquired a form and power worthy of the title of kingdom. (Appian. Mithr. c. 9. Plut. Demetr. c. 4. Strab. XII. p. 562.) According to Diodorus, he reigned thirty-six years, and was slain by order of Antigonus at Cius, who suspected him of forming designs against his power, in conjunction with Cassander. (Diod. Sic. XX. 111.) Lucian reports, that he lived to the advanced age of eighty-four years, on the authority of Hieronymus of Cardia, and other historians. (Macrob. III. c. xiii. p. 217.) His death happened in 302. B.C.^b He was succeeded

^a These, according to Mr. Clinton, were, Ariobarzanes I, Mithridates I, Ariobarzanes II, Mithridates II, or Ctistes: for the proofs of this lineal arrangement, the reader will con-

sult with advantage his very learned and valuable work, Fast. Hellen. part II. Append. Kings of Pontus, p. 421.

^b Clinton, Fasti Hellen. part II. Append. p. 422.

by Mithridates his son, of whom it is only known that he reigned thirty-six years, leaving the crown to his successor Ariobarzanes. (Diod. Sic. XX. 111.) This prince, as we learn from Memnon, conquered Amastris, (ap. Phot. p. 720.) and drove from the country, in conjunction with the Gallo-Græci, or Galatæ, lately arrived in Asia Minor, an Egyptian force sent by Ptolemy. (Apollod. ap. Steph. Byz. v. Ἀγκυρα.) He was succeeded by his son Mithridates IV. who was a minor when his father died. This sovereign makes a more conspicuous figure in history. He made war upon the Sinopians; (Polyb. IV. 56.) married two of his daughters to Antiochus Theus, king of Syria, and Achæus, who was then master of a considerable part of Asia Minor; (Polyb. V. 43. VIII. 22.) and made several munificent donations to the Rhodians, whose city had been overwhelmed by the shock of an earthquake. (Polyb. V. 89, 90.) Mithridates IV. reigned nearly fifty years, and left the kingdom to his son Pharnaces, who conquered Sinope and Tium, (Strab. XII. p. 545. Diod. Sic. Frag.) and was engaged in a war with Eumenes, king of Pergamum, which lasted for some years, and was put an end to chiefly through the interference of Rome. (Polyb. Exc. XXIV. 4. et seq.) Polybius records of Pharnaces, that he was the most wicked of all the kings who had preceded him. (XXVII. 15, 1. XXV. 2, 7.) Mithridates his son, the fifth of that name, ascended the throne about the year 150 B.C., and took the surname of Evergetes, probably from the services he rendered to the Romans. He assisted that people in the conquest of Pergamum, and furnished them with a few ships against Carthage in the third Punic

war; (Appian. Mithr. c. 10.) and received from them in return the province of Phrygia Major. (Justin. XXXVII. 1.) On his death, which took place at Sinope, by the hand of an assassin, he was succeeded, after a reign of nearly thirty years, by his son, the celebrated Mithridates Eupator. This great sovereign, who, by the splendour of his reign, and the brilliancy of his talents, throws all the other princes of his dynasty in the shade, ascended the throne in the year 120 B. C. The first war in which he distinguished himself was against Nicomedes, king of Bithynia, whom he engaged in Paphlagonia, on the banks of the Amnias, and totally routed. He was equally successful against the Roman generals Cassius, Manius, and Oppius, who had moved forward to support their Bithynian allies. These rapid and brilliant victories rendered him master of Bithynia, Mysia, and Phrygia; and he soon after added Ionia, Lydia, and Pamphylia to his conquests; so that the whole of Asia Minor might be said to have fallen under his arms. (Appian. Mithr. c. 17 —22.) Not content, however, with this success, and feeling that his conquests could never be secure as long as so many Roman citizens remained in the country, he formed the bold, but atrocious design of cutting off in one day many thousand families, living in peace and security throughout the different provinces. This horrid design was but too well executed. Secret letters having been despatched to all the governors and commanders in the several towns and districts under his authority, on an appointed day a general massacre of the Romans and Italians took place, in which neither age nor sex was spared, but all were slain indiscriminately, and

even their bodies were denied the rites of burial, and their goods were declared forfeited to the king. The readiness with which the people of Asia executed this sanguinary decree proves, as Appian observes, that the Romans had already made themselves odious throughout the different countries in which they resided rather as masters than allies. No less than 80,000 souls are said to have perished in this barbarous manner. (Appian. Mithr. c. 22—24. Cic. pro Leg. Manil. 3—5. Vell. Paterc. 11, 18. Liv. Epit. LXXVIII. Val. Max. IX. 2.) Mithridates, feeling now secure in Asia Minor, despatched his general Archelaus with a large army into Greece, in the hope of wresting that country also from the Roman dominion; while he himself was engaged in reducing such places as yet withstood his power. The determined resistance of the Rhodians baffled however all his efforts to obtain possession of their city in a long and vigorous siege, so that, despairing of success, he gave up the attempt, and employed himself in the prosecution of his enterprise in Greece and other countries. (Appian. Mithr. c. 24—28.) His empire was indeed now the most formidable which the Romans had had to contend with; since, in addition to the great resources which the possession of Asia Minor placed in his hands, he was master also of Colchis and the different warlike tribes inhabiting round the Euxine and Palus Maeotis, as far as Thrace and the country of the Bastarnæ. He was besides allied to Tigranes, king of Armenia, and Arsaces, king of the Parthians. His infantry, at the commencement of the war, amounted to 250,000, his cavalry to 40,000 soldiers. His fleet consisted of 300 galleys, the

whole admirably appointed, and commanded by able and experienced officers. (Appian. Mithr. c. 15—17.) Had Mithridates himself led his forces into Greece, and carried on the war there with vigour, before the Romans had assembled their forces, his success in that quarter would probably have been no less decisive. But his love for Monimia, a young lady of Stratonicea in Caria, is said to have detained him in Asia, and prevented him from prosecuting his designs against the Romans with his usual energy. Archelaus, though an able general, was no match for the great commander whom the Romans opposed to him in Greece. Sylla commenced his operations by the siege of Athens; and though it was vigorously and obstinately defended by Archelaus in person, he succeeded at length in overpowering all resistance, and taking the place by assault. (Appian. Mithr. c. 30—40. Plut. Syll.) Archelaus withdrew into Bœotia, where he was joined by large reinforcements sent by Mithridates; and he soon found himself at the head of 120,000 troops. Sylla, though unable to bring into the field a force amounting to one third of so great an army, marched also without hesitation into Bœotia, and, after a series of able manœuvres, compelled the enemy to fight near Chæronea, under great disadvantages, and succeeded in gaining a complete victory. (Appian. Mithr. c. 41—45. Plut. Syll.) Such was the activity, however, with which Mithridates collected and sent reinforcements to his general, that Archelaus was soon enabled to encounter his adversary once more in the plains of Orchomenus. He was nevertheless again defeated, and his camp forced; himself escaping with difficulty to Chalcis

in Eubœa. (Appian. Mithr. c. 49, 50. Plut. Syll.) Whilst Sylla was thus successfully carrying on the war in Greece, Cinna, and his other enemies at Rome, had caused him to be superseded in his command, and had sent out Flaccus with troops to carry on operations in Asia Minor against the king of Pontus. Flaccus, a man of no experience in military affairs, and hated by the soldiers for his avarice and cruelty, was soon deprived of the command through the intrigues of Fimbria, a Roman, who had been sent by the senate to assist him with his counsels, and not long after was put to death at Nicomedia. Fimbria then assumed the command, and proceeded to carry on the war with vigour against Mithridates. He defeated his son, and compelled the king of Pontus himself to seek refuge within the walls of Pergamum. From thence, however, he escaped to Pitane, and finally sailed to Mitylene. Meanwhile, negotiations were carried on between Sylla and Archelaus in Greece; and these being happily concluded, Sylla was enabled to march his army through Macedonia and Thrace, and to cross into Asia Minor, with the view of taking vengeance on Fimbria and his party, and compelling Mithridates to ratify the conditions agreed upon with his general Archelaus. Sylla had an interview with that monarch near Abydos, and it was finally settled that Mithridates should give up all his ships of war; restore all the prisoners he had taken; withdraw his garrisons from the places he had occupied since the beginning of hostilities; pay all the expenses of the war; restore Bithynia to Nicomedes, Cappadocia to Ariobarzanes; and retire within his hereditary dominions. (Appian. Mithr. c. 54—58.

Plut. Syll.) Thus ended the first Mithridatic war. The peace which ensued was not, however, of long duration, being broken, in the first instance, by Murena, whom Sylla had left as commander in Asia, while he himself returned to oppose Cinna and his faction in Italy. Murena, without any apparent motive but that of a vain desire to distinguish himself, crossed the Halys, and ravaged the territory of Mithridates, who, finding expostulation vain, and perhaps secretly desirous of renewing the war under advantageous circumstances, since Sylla was no longer opposed to him, collected a large force, and suddenly attacked the Roman general near the Halys, drove him from his position with great slaughter, and compelled him to retreat hastily, and with considerable difficulty, into Phrygia. Sylla and the Roman senate, conscious that hostilities had been unjustly commenced on the part of their officer, sent Aulus Gabinius to forbid Murena from prosecuting the war, and to renew the treaty made with Mithridates. This, according to Appian, was the conclusion of the second Mithridatic war. (c. 64—66.)

Mithridates now employed himself in conquering the Cimmerian Bosphorus, which he assigned to one of his sons: he made also war upon some Sarmatian nations, and formed a still closer alliance with Tigranes, king of Armenia. At this period he received overtures from the Roman general Sertorius, who was at the head of a formidable party in Spain, which were too inviting to be easily rejected, and which induced him to take up arms once more against the Romans; since Sertorius promised to cede to him the whole province of Asia, with Bi-

thynia, Paphlagonia, Cappadocia, and Galatia. Mithridates, once resolved on undertaking a war which he saw would be implacable and final, applied his whole energies to this one object, and collected all the resources of his empire, and those of the numerous barbarous and warlike nations contiguous to his dominions, both in Asia and in Europe. Having thus assembled a well-appointed force of 140,000 infantry, and 16,000 horse, besides a vast number of irregular troops, in the year 680 of Rome, or 74 B.C., he invaded Bithynia, which had just been bequeathed to the Romans by the last will of Nicomedes. Cotta, the Roman governor, fled on his approach to Chalcedon; and thus the whole province, with the exception of that city, fell without a blow into the hands of the king of Pontus. Mithridates, after reducing Chalcedon, proceeded to invest the important city of Cyzicus, which had refused to surrender: but though he employed every resource which art could suggest, and the powerful means he possessed rendered available, he was unable to overcome the gallant resistance of the Cyzicenes. Meantime Lucullus, who had been appointed to the command in Asia, arrived in that province; and though unable, with an army greatly inferior in numbers, to give battle to the enemy, he took up an advantageous position in the vicinity of Cyzicus, and by continually harassing the besiegers, cutting off their supplies, and intercepting communications, and routing some detached corps, he finally compelled Mithridates to raise the siege, and to withdraw his forces hastily to Parium, which he did not effect without considerable loss. And finally, after encountering fresh disasters both by sea and land,

he retreated to Sinope, abandoning the whole of Bithynia, and his other conquests, to the victor. From Sinope he proceeded to Amisus, and finally into Armenia, where he was received by Tigranes, his son-in-law, and with his assistance prepared to renew the war with fresh vigour. He sent likewise to his son Machares, who commanded in Bosphorus, to collect all the reinforcements that he was able. Lucullus, after settling the affairs of Bithynia, crossed the Halys, and commenced the sieges of Amisus, Eupatoria, and Themiscyra, important cities of Pontus. To relieve these, Mithridates moved forward from Armenia, and fixed his quarters at Cabira, a strong fortress on the borders of Armenia and Pontus, and at no great distance from the besieged places. He was now at the head of 40,000 foot, and 4000 horse; and as he received daily reinforcements, it became necessary to dislodge him from his position, or bring him to an action. In the campaign which now ensued among the mountains of Pontus and Cappadocia, it appears that Mithridates made such skilful movements, that in several actions he had a decided advantage over the Romans, and finally reduced Lucullus to such distress, by cutting off his supplies, that he was on the point of commencing his retreat. An unsuccessful attack on the part of Mithridates' cavalry had the effect, however, of deranging all the plans of that monarch, and finally deciding the fate of the war; since the defeat of this corps threw such a sudden panic into the whole camp, that the soldiers abandoned their entrenchments and baggage, and fled in the greatest confusion, pursued by the Roman legions. Mithridates and a few followers escaped with difficulty to

Comana, and thence once more joined Tigranes. Despairing now of success, he despatched the eunuch Bacchus to his palace at Sinope, with orders to put to death his sisters, wives, and concubines. The execution of this barbarous decree was the signal for a general defection on the part of the governors and other officers who held situations of trust throughout Pontus. They now joined, with few exceptions, the Roman general, who soon reduced Heraclea and Amastris, and proceeded to besiege Sinope by sea and land, which, after a vigorous defence on the part of the governor Bacchus, or Bacchides, and his garrison, was taken by assault. Amisus likewise surrendered; and Lucullus, having received the submission of Machares, son of Mithridates, who commanded in Bosphorus, and sent an embassy to Tigranes, to demand that Mithridates should be delivered up to him, returned into the province of Asia, which required his presence.

In the spring of the ensuing year, finding that the king of Armenia not only refused to give up his ally, but seemed disposed to support him with his forces, Lucullus moved forward with a small but chosen army, and having crossed the Euphrates, invaded Armenia. Such was the celerity and secrecy of his movements, that Tigranes had only time to throw some troops into Tigranocerta, his capital, and to withdraw hastily into the interior of his dominions. Lucullus now commenced the siege of Tigranocerta, which was a place of great strength; he had already made some progress, when the approach of Tigranes, at the head of a large army, amounting, according to Appian's statement, to 250,000 foot, and 5,000 cavalry, compelled him to

desist, in order to meet the enemy. Mithridates in vain urged his ally to avoid an engagement, but to harass the Romans by protracted operations and petty assaults ; Tigranes, relying on the vast numerical superiority of his forces, marched to the attack. His positions, however, were so ill chosen, and the movements of his troops so confused and disorderly, that Lucullus, seizing a favourable opportunity, made a combined attack of infantry and cavalry on his columns, and routed them with immense slaughter. Tigranocerta now fell into the power of the Romans, and the war seemed at an end ; but such was the vigour and perseverance of Mithridates, who was now intrusted by Tigranes with the whole of the military operations, that he was again ready to take the field in the ensuing year with an army of 70,000 foot and 35,000 horse, chiefly disciplined after the Italian manner. The campaign was chiefly employed in marches and countermarches, and skirmishes, without any decisive action being fought ; and on the approach of winter, both parties retired into their quarters. Mithridates now proceeded into Pontus, whither he was followed by Lucullus : here different partial engagements took place, in several of which Mithridates was victorious ; especially in one, which was fought when Triarius the lieutenant of Lucullus commanded in that general's absence. The king of Pontus defeated him with considerable loss, and would have gained a complete victory, if a severe wound he received had not spread alarm among his soldiers, and caused them to desist from the pursuit. When the king was sufficiently recovered from his wound, he moved his quarters into the lesser Armenia ; thither he was followed by

Lucullus, but the campaign ended without any decisive advantage being gained on either side; and the Romans being now pressed at home by the Italic war, and the injuries done to their commerce and revenue by the pirates of Cilicia, were forced to desist from carrying on operations in Pontus, till they could remedy the evils which were more sensibly felt by them. (Appian. Mithr. c. 66—91. Plut. Lucull.) When Italy had been reduced, and the pirates had been destroyed by Pompey, the Mithridatic war was intrusted to that general. (A.U. 687.) After an unsuccessful attempt to form negotiations for peace on the part of Mithridates, the Roman commander opened the campaign with 30,000 foot and 3,000 horse, of the choicest troops. He commenced his operations by endeavouring to blockade Mithridates within his lines, and cutting off his supplies, in which project, through the unaccountable supineness of his enemy, he succeeded so well, that after enduring every privation for several days, Mithridates was forced to abandon his camp, and escape at night by bad and difficult roads. Though closely pursued by the Romans, he succeeded in making good his retreat to a very strong position among the mountains, which was only accessible on one point. The next day both sides prepared for battle; but before the army of Mithridates was ready, the action commenced on the part of the Roman horse with such vigour, that the enemy were thrown into confusion, and the disorder increasing throughout the camp, a complete rout ensued; Mithridates lost ten thousand men, and his camp, with all his stores and baggage. Escorted by a few troops, he proceeded first to Sinorega, a strong

fortress, where he kept his treasures. Having drawn from thence 6000 talents, he advanced to the sources of the Euphrates, and traversing Chotene, a district of Armenia, he entered Colchis, and the territory of the Iberians ; and wintered at Dioscurias, a port on the Euxine, near the mouth of the Phasis. (Appian. Mithr. c. 97—101. Plut. Pomp.) Though vanquished, the mind of this extraordinary man remained unbroken and unsubdued, and shewed itself yet greater in adversity than before. He now formed the daring project of collecting another army on the Cimmerian Bosphorus, and opposing a new front to his antagonists. Thither therefore he proceeded ; and as he received every where on his passage through the Sarmatian and Scythian hordes, demonstrations of respect and admiration, and promises of support, he felt his hopes raised to the highest pitch; and he now conceived the gigantic design of penetrating through Thrace and Pæonia into Macedonia and Illyria ; and from thence crossing the Alps, and carrying the war into Italy itself. (Appian. Mithr. 101—103.) Whilst he was forming these plans, and raising troops throughout the Bosphorus, treachery began to shew itself in his own family, and among his own subjects : the Phanagoreans revolted, and their example was followed by several other towns : still Mithridates persisted in his design of advancing towards Italy, and crossing the Alps, as Hannibal had done before him ; and he had already concerted measures with the Gauls for that enterprise, when the treachery of Pharnaces, his favourite son, who incited the army to open rebellion, disconcerted all his plans, and brought him to the grave. Abandoned by his followers, and

dreading lest he should be betrayed into the hands of the Romans, to grace the triumph of Pompey, he swallowed poison, which he always carried about his person; but the effect of the deadly potion being counteracted by the frequent use of antidotes, to which he had had recourse to guard against the designs of others, he hastened death by the sword of a Gaul, who remained faithful to the last. Thus died Mithridates, in the 68th year of his age, after a reign of fifty-seven years, the last and perhaps the most formidable antagonist which the colossal power of Rome had to contend with; and whose life, if it had not been tarnished by vices and deeds of cruelty, which are to be charged in great measure perhaps to eastern habits of despotism, would call forth the highest degree of admiration and praise. It should be remembered, too, that these dark crimes have been handed down to us by historians who are not altogether free from the suspicion of partiality; and it is much to be regretted, that we have no good ancient life of this extraordinary man. The body of Mithridates was sent by the traitor Pharnaces to Pompey, who caused it to be deposited with kingly honours in the royal tombs at Sinope. Pharnaces, as a reward for his perfidy, was proclaimed king of Bosphorus, and styled the ally and friend of the Roman nation. (Appian. Mithr. c. 103—114.) Pompey annexed the greatest part of Pontus to Bithynia, and the rest he assigned to Dejotarus, tetrarch of Galatia, and a zealous ally of Rome; a small portion of Paphlagonia, as we have before said, being reserved for some native chiefs of that country. (Strab. XII. p. 541—547. Appian. Mithr. c. 114.) During the civil wars waged by Caesar

and Pompey, Pharnaces made an attempt to recover his hereditary dominions, and succeeded in taking Sinope, Amisus, and some other towns of Pontus. But Julius Cæsar, after the defeat and death of Pompey, marched into Pontus, and encountering his army near the city of Zela, gained a complete victory; the facility with which it was gained being expressed by the victor in those celebrated words, “Veni, Vidi, Vici.” (Hirt. Bell. Alex. c. 72. Plut. Cæs. p. 731. E. Suet. Cæs. c. 37. Dio Cass. XLII. 47.) After his defeat, Pharnaces retired to the Bosporus, where he was slain by some of his own followers. (Appian. Mithr. c. 120. Dio Cass. XLII. 47.) He left a son named Darius, who was made king of Pontus for a short time, by Antony; (Appian. Bell. Civ. V. 75.) but he was soon deposed, and Polemo, son of Zeno of Apamea, was appointed in his stead. This person, who had the art to ingratiate himself alike with Antony, Augustus, and Agrippa, was made king of that eastern portion of Pontus, named Polemoniacus from him, and which will be more particularly described in the course of this section. Polemo was killed in an expedition against some barbarians of Sindice, near the Palus Maeotis; but his widow, Pythodoris, was reigning in his stead at the time that Strabo wrote his Geography. (XII. p. 556. 578. Dio Cass. LIII. 25. LIV. 24.) Ptolemy divides Pontus into three districts, which he terms Galaticus, Cappadocius, and Polemoniacus; and under the Byzantine emperors the two former were included under the name of Helenopontus, derived from the mother of Constantine, as they had been usually comprehended before by the Romans themselves under that of Pontica Prima.

(Dio Cass. LI. 2. Sueton. Ner. 18. Ptol. p. 125. Justin. Novell. XXVIII. 1. Not. Imp. c. 1. Hierocl. Syncd. p. 701, 702.)

We shall consider Pontus as extending along the coast of the Euxine from the Halys to the river Acampsis, which separated it from Colchis, though some geographers have been disposed to remove this eastern boundary as far as the Phasis^c; (Ptol. p. 125.) but Strabo does not carry it beyond Trapezus, (XII. p. 548.) and Pliny only as far as the Apsarus. (VI. 4.) On the south, Pontus is separated from Cappadocia by a lofty range of mountains, which connects itself towards the west with the Paphlagonian chain, and in a southerly direction with the central ridge of Taurus. On the side of Armenia and Colchis, the same chain, under the various names of Paryadres, Scydisces, and generally the Moschic mountains, extends as far as the Phasis, and unites with the different ramifications of Caucasus and Ararat. It will be seen from this outline that Pontus is chiefly mountainous; especially towards the north-east frontier. Here we have some of the highest table land in Asia, from whence flow the great streams of the Euphrates and Tigris, the Araxes, and the Phasis. The climate was consequently extremely bleak and severe, the soil rugged and barren, and the different tribes scattered over its surface wild and savage to the last degree. (Xen. Anab. V. 4. Strab. XII. p. 548, 549.) But the western portion of the country around the Halys, and the valleys of the Thermodon and Iris,

^c This arrangement has been adopted by Mannert, tom. VI. p. 358. Cellarius does not extend the limit of Pontus on this

side beyond Trapezus. Geogr. Ant. tom. II. p. 197. I have adhered to that of D'Anville. Geogr. Anc. p. 98. ed. fol.

were rich and fertile, and abounded in produce of every kind, and furnished the finest flocks and herds. There were also mines of salt, iron, and rock crystal; and the coast exhibited some large and flourishing Greek cities, possessed of good harbours, and having an extensive traffick with the other parts of the Euxine, the Hellespont, and the Ægean.

The Halys, which divides Pontus from Paphlagonia, is by much the largest river of Asia Minor, since, as Herodotus observed, it nearly divides the peninsula in two. According to that historian, it had its rise in the mountains of Armenia, and after flowing through part of Cilicia, separated first the Matieni from the Phrygians, and next the Syrians of Cappadocia from the Paphlagonians. (I. 72.) Strabo reports that it took its source in Great Cappadocia, but towards Pontica, and the particular district called Camisene. He adds, that it flowed for a considerable space from east to west, but afterwards taking a turn towards the north, traversed the country of the Galatæ, and divided the Paphlagonians from the Leucosyri. (XII. p. 546.)

This description agrees very little with that of Herodotus, who says nothing about the long course from east to west, but rather makes it flow from south to north. Arrian, however, in his Periplus, (p. 16.) criticises the geography of Herodotus on this point, and observes, that it does not flow as he states from the south, but from the east, and falls into the Euxine between Sinope and Amisus. Pliny, on the other hand, seems to adhere rather to the description of the father of history, since he makes it rise in mount Taurus, and flow through Cataonia and Cappadocia, (VI. 2.) Cataonia being that south-

eastern portion of Cappadocia which was contiguous to Cilicia, and the valley of the Euphrates.

These apparent discrepancies are however cleared up, when we find that the Halys, now called *Kizil-Ermak*, has two main branches, which rise at a considerable distance from each other. The one, according to the best modern maps, has its source towards the south, in that part of Taurus which supplies the Sarus and Pyramus, Cilician rivers which flow into the Mediterranean. This seems to answer to the account of Herodotus and Pliny. The other is laid down in the same maps as flowing from the mountains of lesser Armenia, considerably to the north-east of the former branch. This runs in a westerly direction for a considerable space, as Strabo and Arrian report, and joining the other near *Manjour*, they flow in one stream towards the north, and discharge their waters into the Euxine near *Bafra*, and between *Samsoun* and *Sinoub*^d.

Strabo reports that the Halys took its name from some salt mines near which it flowed. (XII. p. 546, 561.) This great river formed the boundary of the Median and Lydian empires, when they were swayed by Cyrus and Croesus; (Herod. I. 72.) and it is fur-

^d In the best maps hitherto published of Turkey in Asia, the eastern branch of the *Kizil-Ermak* is made to come from the mountains a little to the east of *Siwas*, the ancient *Sebaste*; but a recent traveller is disposed, from personal observation, confirmed by the reports of the natives, to remove its source as far back as *Sunnur*, in the vicinity of *Baibout*, a town of Armenia. I do not

think, however, that the evidence adduced by Mon. Fontanier, the writer in question, is conclusive on the subject; and though I am disposed to think with him that this branch of the *Kizil-Ermak* ought to be removed more to the east of *Siwas*, I do not imagine it will be found to rise so far back as *Sunnur*. Fontanier, Voyages en Orient. Paris, 1829, 8vo. p. 41 and p. 140—146.

ther connected with the history of the latter monarch, by the ambiguous oracle which might have been construed into a warning, but which ambition led him to interpret in a manner most congenial to his wishes. (Herod. I. 53. Aristot. Rhet. III. 5. Cic. de Divin. II. 56.) Xenophon reports that the Halys was not less than two stadia, or nearly a quarter of a mile in breadth, towards its mouth; (Anab. V. 6, 3.) and Mr. Kinneir, who crossed it in a ferry near *Bafra*, describes it as a wide and powerful river.

On the right bank of the Halys were once established the Syrians of Cappadocia, whom the Greeks termed Leuco-Syri, or white Syrians, to distinguish them from their more swarthy countrymen who occupied Syria Proper on the shores of the Mediterranean. (Strab. XII. p. 544.) The poets not unfrequently call the district which they occupied, Assyria.

Τοῖς δ' ὅμοῦ μετέπειτα θοῆ πεφορημένοι αὔρη
Λεῖπον Ἀλυν ποταμὸν, λεῖπον δ' ἀγχίρροον Ἰριν,
Ἡδὲ καὶ Ἀσσυρίης πρόχυσιν χθονός.

APOLL. ARG. II. 964.

And a little before he had said, v. 948,

Αὐτίκα δ' Ἀσσυρίης ἐπέβαν χθονός· εἴθα Σινώπην
Θιγατέρ' Ἀσαποῖο καθίσσατο.

Assyrios complexa sinus stat opima Sinope.

VAL. FLACC. V. 110.

Τοῖς δὲ μετ' Ἀσσυρίης πρόχυσις χθονὸς ἐκτετάνυσται.

DIONYS. PERIEG. 784.

Scylax also calls the district of which we are speaking, Assyria. (p. 33.) Herodotus never uses the appellation of Leuco-Syri, but calls them Syrians, and says that the Medes, whose subjects they had been before the time of Cyrus, gave them the name

of Cappadocians. (I. 72. V. 49. VII. 72.) Pindar also, in a passage quoted by Strabo, applied the denomination of Syrians to this people. (XII. p. 544.) Herodotus mentions likewise another curious particular respecting these Syrians, which strongly connects them with the Phœnicians and Syrians of Palestine. It is, that they practised the rite of circumcision; and though he pretends that they derived it from the Colchians, who themselves borrowed it from the Egyptians, it appears in fact much more rational to suppose it had been transmitted to them by the mother country. It is true, that the facts stated by Herodotus have been much controverted, and in particular it has been denied that the Syrians of Palestine used the rite of circumcision, unless he meant indeed to call the Jews by that name, which was the opinion of Josephus. (Ant. Jud. VIII. 10.) But though it certainly appears from the incontrovertible testimony of scripture, that the Philistines did not use circumcision in the time of Saul and David, it does not follow that in the time of Herodotus the practice had not prevailed among them also, especially when the Jews had become settled in these towns, and so many of the neighbouring nations had learned to use it. (Herod. II. 104. where see the observations of Wesselink, and the list of authors whom he quotes.) We have already seen from the same historian that the Leuco-Syri once extended on the left bank of the Halys as far as the Parthenius, a fact which is confirmed by other writers of authority; (Eustath. ad Dion. Perieg. 772.) and though we have no positive account of their migration from the east or south, it is not improbable that they

owed their position on this coast to some remote event under the great Assyrian empire, of which no certain record has reached us. Ctesias, indeed, who is quoted by Diodorus, reported that the Assyrians had penetrated into these parts as early as the reign of Ninus, (II. 2.) and if the Syrians of Cappadocia had formed a part of the Assyrian empire, it would be easy to account, from that circumstance, for their having afterwards become subject to the Medes.

After the mouth of the Halys, Arrian (p. 16.) notices a marsh and station called Naustathmus,^{Naustath-}
^{mus.} distant ninety stadia; Marcian says 120: (p. 74.) then another marsh named Conopeium, fifty stadia ^{Conopei-}
^{um.} further; Marcian writes 120, but his numbers are certainly not correct. It seems to answer to the site of *Coumjougax*. From thence to Eusene, Arrian Eusene reckons 120 stadia. Ptolemy places this station inland, but the Table on the coast twenty miles from Naustathmus, and eight from Amisus.

It appears from Herodotus that the country on this side the Halys was in his time known by the name of Pteria; since he states, that Croesus having crossed the Halys, marched into that part of Cappadocia which is opposite to the Sinopian territory, and is called Pteria. After wasting the country, and taking the principal town and others in the neighbourhood, he was encountered by Cyrus, and a great battle was fought in Pteria, but without any decisive result. (I. 76.) Stephanus Byz. is the only other author who speaks of Pteria, and it is probable he merely copied Herodotus. (v. Πτερία.) This district, which Herodotus describes as the best and most important part of the Leuco-Syrian territory, Gadilonitis
vel Gaze-
lonitis re-
gio.

and Saramene. The former he places immediately after the mouth of the Halys, and he reports that it was a rich champaign country, producing every sort of fruit and grain, and a breed of sheep whose wool was so fine, that it was found necessary to protect their fleeces with skins. (XII. p. 546.) There was also to be found in this country a particular sort of goats (*ξόρκες*) which are rare elsewhere. Some commentators have supposed that these were the famous goats of *Angora*, which are now so much esteemed for the fine quality of their hair^f. Gadilonitis, or Gazelonitis, appears to have taken its name from Gadilon, or Gazelon, a town situated in this vicinity. (Plin. VI. 2.) After Gazelonitis follows the canton Saramene, and the city of Amisus, situated on the coast at a distance of 900 stadia from Sinope. It was founded, as we learn from Theopompus, quoted by Strabo, (XII. p. 547.) by the Milesians, but was subject for a time to the authority of a Cappadocian chief; afterwards it received an Athenian colony, led by Athenocles, and took the name of Piræus^g. Amisus subsequently fell under the dominion of the kings of Pontus. Mithridates enlarged the town, and adorned it with several temples and palaces. (Cic. pro Leg. Manil. §. 8. Strab. loc. cit.) In the wars waged by that sovereign against the Romans, it was besieged and taken by Lucullus. Some years after, it was again occupied by Pharnaces, on which occasion

^f Note to the French edition of Strabo, t. III. and XIII. p. 35.

^g The date of this event is not ascertained. Amisus does not appear to have existed in the time of Scylax; nor is it mentioned by Herodotus or Xenophon. The Athenian colony was

therefore certainly posterior to the time of the Anabasis. There are some coins with the legend ΠΕΙΠΑ, which are assigned to Amisus, and which appear to be more ancient than those with the epigraph ΑΜΙΣΟΤ. Sestin. p. 58.

the inhabitants were treated with the greatest cruelty. (Appian. Bell. Civ. II. c. 91. Strab. loc. cit.) Cæsar, after defeating Pharnaces, restored them to liberty. Antony annexed their town to the kingdom erected by him in favour of Polemo; but they were oppressed for a time by a tyrant named Strato: finally, however, Augustus took Amisus under his protection, and made it a free city. It possessed, as we learn from Strabo, an ample and fertile territory, (XII. p. 547.) and enjoyed laws and privileges of its own. (Plin. Epist. X. 93.) The chief magistrate was named Ecdicus, and there were, besides, a senate and a popular assembly. (Epist. X. 111. Cf. Plin. Hist. Nat. VI. 2. Plut. Lucull. p. 514. Polyæn. Strat. VII. 21. Arrian. Peripl. p. 16. Marcian. Heracl. p. 74. Steph. Byz. v. Ἀμισός. Ptol. p. 116.) Amisus still continued to flourish under the Greek emperors of Byzantium and Trebizond, but the name was corrupted to that of *Samsoun*, which it retains at the present day. (Georg. Acrop. p. 6. D. Abulfed. Tab. XIX. p. 318.) In Constantine Porphyrog. the name is written Aminsus; (Them. I. 2.) in the Table Itinerary, Missos. After Amisus, we find the town and river of Lycastus mentioned by Seylax (Peripl. p. 33.) and Marcian from Artemidorus and Menippus. (P. 74. Cf. Menip. ap. Steph. Byz. v. Χαδίσια. Anonym. Peripl. p. 10.) Arrian omits them. The former geographers reckon twenty stadia from Amisus to Lycastus, and forty stadia to another river called Chadisius, which Arrian again passes over in silence. From thence to the port Ancon, so called from a bend made here by the land, Marcian reckons 100 stadia; Arrian gives 160 from Amisus to the same place. Ancon is men-

Lycastus
urbs et
fluvius.
Chadisius
fl.
Ancon
portus.

tioned also by Apollonius Rhodius, (II. 369.) but rather as a headland.

Κεῖθεν θὲ προτέρωσε μέγας καὶ ὑπείροχος ἄγκων
Ἐξανέχει γαῖης.

Iris fl. It was close to the mouth of the Iris, a considerable river of Pontus, which flowed from the mountains on the frontier of Cappadocia, and after receiving the Lycus, and other smaller streams, fell into the bay of Amisus. We shall have occasion to speak more particularly of its course in the interior when we come to Amasia, the native city of Strabo, near which it flows. The Iris, according to Xenophon, was three plethra, or half a stadium, in breadth. (Anab. V. 6, 3.)

Ἄχτῃ ἐπὶ προβλῆτι ροᾶι Ἀλυος ποταμοῖο
Δεινὸν ἔρεύγονται. μετὰ τόνδ' ἀγχίρροος Ἰρις
Μειότερος λευκῆσιν ἐλίσσεται εἰς ἄλα δίναις.

APOLL. ARG. II. 366.

Ἴρις δ' ἔξείης καθαρὸν ρόον εἰς ἄλα βάλλει
Τῷ δὲ ἐπιμορφύρουσι ροᾶι Ἀλυος ποταμοῖο.

DIONYS. PERIEG. 783.

(Cf. Eustath. ad loc.) This river is now called *Tokatlu*.

After the mouth of the Iris, we come to the cape Heracleum and port Heracleum, distant, according to Arrian, promont. et portus. 360 stadia; (p. 16.) but the anonymous Periplus reckons only 106, which is much nearer the truth. Apollonius alludes to this cape when he says,

..... ἥματι δὲ αὐτῷ
Γνάμψαν Ἀμαζονίδων ἔκαθεν λιμενηόχον ἀκρην·
Ἐνθα ποτὲ προμολοῦσαν Ἀρητιάδα Μελανίππην
Ἡρως Ἡρακλέης ἐλοχήσατο· καὶ οἱ ἄποινα
Ιππολύτη ζωστῆρα παναιόλον ἐγγυάλιξεν.

APOLL. ARG. II. 966.

The Scholiast informs us from Artemidorus that there was a temple sacred to Hercules on this headland, which in modern charts is named *Thermeh*. From Heracleum to the mouth of the Thermodon the ancients reckon 100 stadia. This river is celebrated by the poets of antiquity as the fabled seat of the Amazons. It would exceed the limits I have proposed to myself in the execution of the present work, to enter into a discussion of the origin and groundwork of a tale which seems to have obtained so much credit in former ages. I shall confine myself at present to those authorities which prove their existence in Asia Minor. Homer certainly recognises them in this part of the peninsula, when he speaks of their wars with the kings of Phrygia.

"Ηδη καὶ Φρυγίην εἰσήλυθον ἀμπελόεσσαν,
 "Εὐθαῦ δον πλείστους Φρύγας, ἀνέρας αἰολοπάλους,
 Λαοὺς Ὀτρῆος καὶ Μύγδονος ἀντιθέοιο,
 Οἳ ρα τότ' ἐστρατόωντο παρ' ὅχθας Σαγγαρίοιο.
 Καὶ γὰρ ἐγὼν ἐπίκουρος ἐών μετὰ τοῖσιν ἐλέχθην
 "Ηματι τῷ, ὅτε ἥλθον Ἀμαζόνες ἀντιανειραί"

IL. Γ. 184.

In another passage the poet alludes to their defeat by Bellerophon. (Il. Z. 186.)

Τὸ τρίτον αὖ, κατέπεφνεν Ἀμαζόνας ἀντιανειρας.

Several grammarians and commentators pretended also that the Halizones, whom he elsewhere mentions as the allies of the Trojans, were the same as the Amazons; and some critics contended that the word Amazones ought to be substituted for Halizones; but Strabo, who seems to have examined every thing connected with the Homeric geography with great care and attention, rejects this opinion

as destitute of foundation. He seems to allow, however, that the traditions which established the Amazons on the Ionian coast in the vicinity of Smyrna, Ephesus, and Cyma, were better supported, especially since they were advocated by Ephorus, who was a native of the latter city. (Strab. XII. p. 550—552.) Herodotus places also the Amazons on the Thermodon, and affirms that it was from thence they advanced into Greece, and invaded Attica. (IX. 27.) He likewise speaks of an expedition undertaken by the Greeks against these warlike females, in which the latter were defeated near the Thermodon, and led away captive. A part of them however escaped to Scythia, and became the mothers of the Saromatae. (IV. 110.) The same historian adds, that the Scythian term which answered to the Greek word Ἀμάζων was Oirpata, i. e. the manslayer; corresponding, it should seem, with the Homeric expression ἀντιάνειραι. Other traditions relative to the wars of the Amazons with Hercules and Theseus, and still more anciently with Bacchus, are noticed by Pausanias. (Attic. 15. Ach. 2. Plut. Thes. et Quæst. Gr. p. 541. Diod. Sic. IV. 16. II. 44. Justin. II. 4.) Apollodorus states that the Amazons cut off their right breast, in order that they might use the bow with greater effect, but preserved the left, to be able to suckle their offspring. (II. 5, 9^h.) The poets with one consent recognise the shores of the Euxine and the banks of the Thermodon as the principal seat of this singular people.

^h See the observations of Heyne on this passage, who justly remarks, that this cir-

cumstance is not generally adhered to by the sculptors of antiquity. Obs. p. 153, 154.

. . . ἐνθ' Ἀμαζόνων στρατὸν
 "Ιξει στυγάνορ', αἱ Θεμισκυράν ποτε
 Κατοικιοῦσιν ἀμφὶ Θερμώδονθ'"—

ÆSCHYL. PROM. VINCT. 748.

Quales Threiciæ cum flumina Thermodontis
 Pulsant et pictis bellantur Amazones armis.

VIRG. ÆN. XI. 659.

Qualis Amazonidum nudatis bellica mammis
 Thermodontæis turba lavatur aquis.

PROPERT. III. 14.

The district which they occupied is sometimes called by Apollonius Rhodius the Dœantian plain, from a Dœantius chief named Dœas, as we are told by the Scholiast. The same poet adds, that the community of the Amazons was divided into three separate cantons, though acknowledging the authority of the same queen.

. . . ἐπὶ δὲ στόμα Θερμώδοντος
 Κόλπῳ εύδιόωντι Θεμισκύρειον ὑπ' ἄκρην
 Μύρεται, εὔρείης διαειμένος ἡπείροιο,
 "Ενθα δὲ Δοιάντος πεδίον· σχεδόθεν δὲ πόλης
 Τρισσαὶ Ἀμαζονίδαι" — ÆC. II. 370.

Οὐ γὰρ Ἀμαζονίδες μάλ' ἐπητέες, οὐδὲ θέμισσας
 Τίουσαι πεδίον Δοιάντιον ἀμφενέμοντο·
 'Αλλ' ὕβρις στονόεσσα καὶ "Αρεος ἔργα μέμηλε.

• • • • • • • • •
 "Ενθα Θεμισκύραι Ἀμαζόνες ὠπλίζοντο.
 Οὐ γὰρ ὁμηγερέες μίαν ἀμπόλιν, ἀλλ' ἀνὰ γαῖαν
 Κεχριμέναι κατὰ φῦλα διάτριχα ναιετάεσκον.
 Νόσφι μὲν αἵδ' αὐταὶ, τῷσιν τότε κοιρανέεσκεν
 'Ιππολύτη, νόσφιν δὲ Λυκάστιαι ἀμφενέμοντο,
 Νόσφι δὲ ἀκοντόβολοι Χαδήσιαι" —

I.B. v. 989—1002.

The Thermodon, according to Strabo, is a large river, formed by the junction of several minor

streams which watered the fertile plain of Themiscyra. (XII. p. 548.) Apollonius affirmed that these rivulets were not less than ninety-six in number.

Τῆς οὖγ' ἐν κόλπῳ προχοαῖς ἐπὶ Θερμώδοντος
Κέλσαν· ἐπεὶ καὶ πόντος δρίνετο νισσομένοισιν.
Τῷ δὲ οὗτις ποταμῶν ἐναλίγκιος· οὐδὲ ρέεθρα
Τόσος' ἐπὶ γαιῶν ἵησι παρὲξ ἔθεν ἄνδιχα βάλλων.
Τέτρακις εἰς ἑκατὸν δεύοιτό τε, εἴτις ἑκαστα
Πιμπάζοι· μία δὲ οἵη ἐτήτυμος ἐπλετο πηγή.
Ἡ μέν τ' ἐξ ὀρέων κατανίσσεται ἡ πειρόνδε
Ὑψηλῶν, ἀτε φασὶν· Αμαζόνια κλείεσθαι.
Ἐνθεν δὲ αἰπυτέρην ἐπικίδναται ἔνδοθι γαιῶν
Αντικρύ· τῷ καὶ οἱ ἐπίστροφοι εἰσὶ κέλευθοι.
Αἰεὶ δὲ ἄλλυδις ἄλλη, ὅπη κύρσεις μάλιστα
Ἡπείρου χθαμαλῆς εἰλίσσεται· ἡ μὲν, ἀπωθεν,
Ἡ δὲ, πέλας· πόλεες δὲ πόροι νώνυμοι ἔασιν,
Οτπη ὑπεξαφύονται· δὲ δὲ ἀμφαδον ἄμμιγα παύροις
Πόντον ἐστι· Αξεινον κυρτὴν ὑπερεύγεται ἄκρην.

ARG. II. 972.

Xenophon also describes the Thermodon as a considerable river, not less than three plethra, or half a furlong, in width, and not easy for an army to cross. (Anab. V. 6, 3.) Dionysius Periegetes affirms, that crystal and jasper were found on its banks. (v. 773—182.)

Ἐνθ' Αμαζονίδεσσιν ἀπ' οὔρεος Αρμενίοιο
Λευκὸν ὕδωρ προΐησιν Ενυάλιος Θερμώδων.
· · · · ·
Κείνου δὲ ἀν ποταμοῖο περὶ κρυμώδεας ὥχθας
Τέμνοις κρυστάλλου καθαρὸν λίθον, οἵα τε πάχνην
Χειμερίην δήεις δὲ καὶ ὕδατόεσσαν ἴασπιν.

(Cf. Eustath. ad loc. et Plut. de Fluv. Val. Flacc. Arg. IV. 600. IV. 122. Plin. VI. 2.) This river, which retains the name of *Thermeh*, rises in the

mountains to the north-east of *Niksar*, which separate its course from that of the *Carahissar* river, the ancient Lycus. The plain of Themiscyra, watered by the Iris and Thermodon, is described by Strabo as a most rich and beautiful district, ever verdant, and able to supply food for innumerable herds of oxen and horses. The principal kinds of grain cultivated there were panic and millet; and these, from the constant supply of water, were always produced in great abundance; so that scarcity was never known in the country. Towards the mountains, the soil furnished a great variety of fruits, such as grapes, apples, pears, and nuts in such quantities, that they were suffered to waste on the trees, or drop off without being gathered. This great supply of vegetable food naturally caused a great quantity of game of every sort to resort thither. (XII. p. 548.) Scylax mentions a town of the name of Themiscyra which he terms a Greek city; (p. 33.) Herodotus also speaks of it; (IV. 86.) and Appian reports that it was besieged by Lucullus after the retreat of Mithridates from Cyzicus. The Themiscyrians defended themselves with vigour, and when their walls were undermined, they sent bears, and other wild beasts, and even swarms of bees, against the workmen of the enemy. (Mithr. c. 78. Steph. Byz. v. Θεμισκυρα. Hecat. ap. eund. v. Χαδισία.) The plain of Themiscyra belonged to Amisus in Strabo's time, as well as that of Sidene, ^{Sidene re-} situated next to it towards the east. It derived ^{gio.} its name from Side, a town seated on the coast; and was likewise fertile and well watered. This district consists also of a valley, through which flows the river *Sidin*, which recalls the ancient name.

Pliny, indeed, calls it Sidenus. (VI. 4.) Arrian does not speak of Side, or Sidene, but he names after the Thermodon the river Beris, distant ninety stadia. (p. 16.) The anonymous geographer, who calls it Bires, says sixty stadia. (p. 10.) From thence to the river Thoaris, Arrian measures sixty stadia, the anonymous Periplus ninety. Thirty stadia further we find Cœnoe. (Arrian. p. 16.) This was a town, and not a river, as the anonymous writer calls it, and it still retains the name of *Unieh*. It was a place of some consequence in the middle ages, being often mentioned by the Byzantine writers, who call it Cœnaeum. (Nicet. Ann. p. 410. D. Cinnam. p. 102.) In the Table Itinerary it is probable that we ought to read Cœnoe for Cœna, which is placed at a distance of thirty miles from Heracleum. From Cœnoe to the river Phigamus, Arrian reckons forty stadia, in which he agrees with the anonymous geographer. After the Phigamus the anonymous Periplus names Ameletum, twenty stadia, and Phadisana. Periplus names Ameletum, twenty stadia, and Phadisana, or Phadissa, which Arrian also recognises, 150 stadia ^k. This place probably answers to the Phauda of Strabo, (loc. cit.) and is now called *Fatsah*. Ten stadia further bring us to Polemonium, which evidently derives its name from Polemo, the favourite of Antony and Augustus, and king of that portion of Pontus named Polemoniacus from him. Polemonium is not named by Strabo, and therefore was probably founded after his time; but it is noticed by Ptolemy; and in the Table Itinerary it is marked as a place of consequence. The same document names between it and Cœna, which

Beris sive
Bires flu-
vius.

Thoaris
fluvius.

Cœnoe.

Phigamus
fluvius.

Ameletum.
Phadisana.

Polemo-
nium.

^k Geogr. tom. VI. p. 439.

I take to be ΟEnoe, Camisa, which is probably Phigamus, eight miles from Cœna, and beyond it Pytane, twenty from Polemonium ; this last place is doubtless the Phadisana of Arrian, but the distances are incorrect. Pliny reckons 120 miles from Amisus to Polemonium¹. (VI. 4.) Mannert is inclined to think that the latter place usurped the name and situation of Side, which is mentioned by no writer posterior to Strabo^m. From Polemonium to the promontorium Jasonium, Arrian and the other Peri-Jasonium plus reckon 130 stadia. This cape was so called from the ship Argo having anchored in its vicinity. (Xen. Anab. VI. 2, 1.) It is also mentioned by Strabo, (XII. p. 548.) and it preserves evident vestiges of the ancient appellation in that of *Iasoun*. From thence to the isle of the Cilicians the mari- Cilicum in- time surveys reckon fifteen stadia. This islet is sula. not laid down in modern charts. The whole of this coast from the Jasonian cape to the vicinity of the Thermodon was once inhabited by the Chalybes, Chalybes a barbarous people, celebrated in antiquity for the ^{sive Chal-} ^{dæi gens.} great iron mines and forges which existed in their country.

. . . . "Ηματι δ' ἄλλῳ
Νυκτὶ τ' ἐπιπλομένῃ Χαλύβων παρὰ γαῖαν ἰχοῦτο·
Τοῖσι μὲν οὔτε βοῶν ἄροτος μέλει, οὔτε τις ἄλλη
Φυταλιὴ χαρποῖο μελίφρονος· οὐδὲ μὲν οἶγε
Ποίμνιας ἀρσήντι νομῷ ἔνι ποιμαίνουσιν·
Ἄλλα σιδηροφόρον στυφελὴν χθόνα γατομέοντες,
Ωνον ἀμείβονται βιοτήσιον· οὐδέ ποτέ σφιν
Ἡὰς ἀντέλλει χαμάτων ἄτερ, ἀλλὰ κελαινῆ
Λιγνῦι καὶ χαπνῷ χάματον βαρὺν ὀτλεύοντι.

APOLL. ARG. II. 1002—10.

¹ This distance is much too great. ^m Geogr. tom. VI. p. 439.

. . . μετὰ δὲ σμυγρώτατοι ἀνδρῶν
Τρηχείην Χάλυβες καὶ ἀτειρέα γαιῶν ἔχουσιν
Ἐργατίναι· τοὶ δὲ ἀμφὶ σιδήρεα ἔργα μέλονται.

APOLL. ARG. v. 374.

. sævissima quamquam
Gens Chalybum; duris patiens cui cultus in arvis,
Et tonat afflictæ semper domus ignea massa.

VAL. FLACC. ARG. IV. 610.

At Chalybes nudi ferrum, virosaque Pontus
Castorea— VIRG. GEORG. I. 58.

Τοῖς δὲ ἐπὶ καὶ Χάλυβες στυφελὴν καὶ ἀπηνέα γαιῶν
Ναιούσιν, μογεροῦ δεδαηκότες ἔργα σιδήρου
Οἱ δὲ βαρυγδούποισιν ἐπ' ἄχμοσιν ἐστηῶτες
Οὕποτε παύονται καμάτου καὶ οἰξύος αἰνῆς.

DIONYS. PERIEG. v. 768.

(Cf. Eustath. ad loc.) We are ignorant of the grounds on which the ancients attributed this active employment in the manufacture of iron to the Chalybes, for it does not appear at present that this part of Asia is at all productive of that most useful metal; perhaps, however, if the mountainous district was examined accurately, there would be found traces of the ancient works. It is clear, however, that they had not ceased to furnish a good supply of metallic ore in Strabo's time, for he observes, that the two great articles of produce in the land of the Chalybes, who were then commonly called Chaldæi, or Chaldi, where the fisheries of the pelamys, and the iron works; the latter kept in constant employment a great number of men. (XII. p. 549.) Strabo observes also, that these mines formerly produced a quantity of silver; and this circumstance, together with some affinity in the names, led some commen-

tators of Homer to identify the Alybe of that poet with the Chalybes of Pontus.

Αὐτὰρ Ἀλιξώνων Ὅδιος καὶ Ἐπίστροφος ἥρχον,
Τηλόθεν ἐξ Ἀλύβης, ὅθεν ἀργύρος ἐστὶ γενέθλη.

I.L. B. 856.

Strabo himself strongly contends for this interpretation, though he has against him Hecataeus of Miletus, Menecrates of Elaea, and Palæphatus, who placed the Halizones, or Alazones, in Mysia; (XII. p. 550.) but the geographer justly observes that the word *τηλόθεν* cannot be applicable to a people situated so near Troy, and besides, it does not appear that the northern part of Mysia, in which those writers placed the Halizones, was ever rich in silver. Upon the whole, then, I am inclined to adhere to the geography of Strabo; and the Halizones, as Mannert ingeniously observes, may have derived their name from the river Halys, on whose banks their country was situated^m. It is remarkable that Herodotus names the Chalybes among the nations of Asia Minor which were conquered by Croesus, (I. 28.) and yet they certainly are found afterwards considerably beyond the Halys, which separated his dominions from those of Cyrus: either therefore they must have shifted their position, or Croesus subsequently lost what he had gained on the right bank of the Halys. In the enumeration of the armament of Xerxes the Chalybes are not mentioned, though Wesseling has supposed that there is an omission of a people immediately after the Asiatic Thracians, (VII. 76.) and proposes to insert there the name of the Chalybes, chiefly on account of the oracle of Mars, which is said to have existed

^m Geogr. tom. VI. p. i. p. 455.

among this nameless people. But if Herodotus had named the Chalybes, he would surely have classed them with the Macrones, Tibareni, Mosynœci, and other Pontic nations contiguous to them. (VII. 78.) The nameless people, considering that they are classed with the Cabelees, Lasonii, and Milyæ, who were certainly in the north-west and north-east of Lycia, should be rather sought for in Pisidia and Isauria. It is not improbable that the Chalybes, whose business it was to furnish a great supply of iron for the use of the army, would be exempted from military service. Xenophon, who traversed the country of the Chalybes with his fellow-soldiers, speaks of them as being few in number, and subject to the Mosynœci; he adds, that their chief employment was forging iron. But it is worthy of remark, that he places these Chalybes more to the east than other writers. (Anab. V. 5, 2.) Zeunius therefore is of opinion that this people must have lived a wandering sort of life, and have often changed their territory ⁿ. Xenophon, however, speaks elsewhere of some other Chalybes who were situated apparently on the borders of Armenia, and were much more numerous and warlike. (Anab. IV. 7, 10.) Strabo reports, that the Chalybes in his time had changed their name to that of Chaldæi; (XII. p. 549.) and it is remarked, that Xenophon speaks of an Armenian tribe of Chaldees, who encountered the Greeks near the river Centrites. (Anab. IV. 3, 4. Cf. Eustath. ad Dion. Perieg. v. 768.) but Menippus in his Periplus calls

ⁿ Dissert. Geogr. ad Anabas. rus, quoted by Strabo. (XIV. p. xxvii. ed. Oxon. 1809. This p. 678, 679.
would also appear from Epho-

the Pontic tribe Chaldi, and their canton Chaldia. (ap. Steph. Byz. v. Χαλδία.) Contiguous to the Chalybes, towards the east, were the Tibareni, or Ti-Tibareni. bari, who are named by Scylax, Herodotus, Hecatæus, Strabo, and other geographers. The form Tibareni is the more usual, but the other occurs also in Menippus (ap. Steph. Byz. Χαλδία Hecatæus ap. eund. v. Χοιράδες) and Euseb. Præp. Ev. (I. p. 11. C.) They occupied a small extent of coast from cape Genetes to the extremity of the bay of Cerasus. Xenophon describes their country as consisting of fertile plains, and possessing some fortified places along the coast. (Anab. V. 5, 3.) Other accounts speak of the Tibareni as possessed of numerous flocks, and they are said also to have been a most laughter-loving people. (Ephor. ap. Steph. Byz. v. Τιβαρηνία P. Mel. I. 19.) Eusebius, on the other hand, affirmed, that they destroyed their old men by casting them down precipices. (Præp. Ev. I. p. 11.^o) A more harmless and ridiculous custom was that of causing the married women to attend upon their husbands after parturition, as if they had undergone the labour of childbirth.

Τοὺς δὲ μέτ' αὐτίκ' ἔπειτα Γενηταίου Διὸς ἄκρην
Γνάμψαντες, σώοντο πάρεξ Τιβαρηνίδα γαιῶν.
Ἐνθ' ἐπεὶ ἂρ κε τέχωνται ὑπ' ἀνδράσι τέκνα γυναικες,
Αὐτοὶ μὲν στενάχουσιν ἐν λεχέεσσι πεσόντες,
Κράστα δησάμενοι· ταὶ δ' εὔχομέουσιν ἐδαῦῃ
Ἄνερας, ἥδε λοετρὰ λεχώϊα τοῖσι πένονται.

APOLL. ARG. II. 1011.

(Cf. Nymphodor. ap. Schol. ad loc.) The same poet elsewhere says,

◦ Possibly some other name should be substituted for that of the Tibari, or Tibareni; perhaps that of the Tapyri.

*Αγχὶ δὲ ναυετάουσι πολύβρηνες Τιβαρηνοὶ,
Ζηνὸς ἐῦξείνος Γενταίην ὑπὲρ ἄκρην.

APOLL. ARG. II. 377.

(Cf. Dionys. Perieg. v. 767. and Eustath. ad loc.)

Genetes
prom. et
fluvius.

Boona.

Cotyora.

The Genetæan promontory, which formed the commencement of the Tibarenian district, took its name from a small river and port named Genetes, which is noticed by Scylax, (Peripl. p. 33.) and the Scholiast to Apollonius, who observes that there was a temple of Jupiter on the promontory. (Cf. Steph. Byz. v. Γενήτης.) Strabo also calls the cape Genetes, but in Arrian's time this appellation appears to have been lost, since he mentions directly after the cape Jasonium and the island of the Cilicians a place called Boona, which is easily recognised in that of *Vona*, which it now bears ; and cape *Vona* can be no other than the Genetes of Strabo, and others. (XII. p. 548.) The ancient surveys reckon fifty-five stadia from the isle of the Cilicians to the river Genetes, and twenty from thence to Boona.

Cotyora, which next follows at a distance of ninety stadia, was a place of note, as appears from Xenophon, who reports that it was a colony of Sinope, and able to furnish supplies for the ten thousand Greeks who were quartered in its vicinity forty-eight days. (Anab. V. 5, 4. Diod. Sic. XIV. p. 261.) In Arrian's time it was scarcely more than a village ; a circumstance accounted for by Strabo, who states that the population had been removed to the more modern town of Pharnacia. (XII. p. 548. Arrian. Peripl. p. 17. Steph. Byz. v. Κοτύωρα Mel. I. 19. Plin. VI. 4. Ptol. p. 125.) The situation of Cotyora would seem to answer to the modern *Buzuk-*

kalé, about ten miles to the south-east of cape *Vona*^p. It must have possessed a port, since the 10,000 embarked there for Heraclea. After crossing the river Melanthius, we enter upon the territory of the Mo-
synœci, who were divided apparently by that stream from the Tibareni. Cotyora, according to Xenophon, belonging to the latter. (Anab. V. 5, 4.) The Maritime Itineraries give sixty stadia from that town to the Melanthius. (Arrian. Peripl. p. 17. Anonym. p. 12.) That little river, according to modern maps, still serves to separate the district of *Djanik* on its left bank from that of *Heldir* on the right. The Mosynœci were so called by the Greeks from their dwelling in small wooden turrets, termed *μόσυνοι*. They are described as a savage race, subsisting chiefly on the flesh of wild animals and roots; and addicted to robbery, and other lawless habits. (Strab. (XII. p. 549.) They were said to keep their chief a close prisoner in one of their wooden huts; and if he ordered any thing contrary to law, they deprived him of food. (Anonym. Peripl. p. 12, 13. Scymn. Ch. v. 162. Nic. Damasc. Excerpt. Mel. I. 19.)

Τῇ δὲ ἐπὶ Μοσσύνοικοι ὁμούριοι ὑλήσσαν
 Ἐξείης ἥπειρον ὑπωρείας τε νέμονται,
 Δουρατέοις πύργοισιν ἐν οἰκίᾳ τεκτήναντες
 Κάλλινα, καὶ πύργους εὐπηγέας, οὓς καλέουσι
 Μόσσυνας· καὶ δὲ αὐτοὶ ἐπώνυμοι ἔνθεν ἔσασιν.

APOLL. ARG. II. 379.

'Ιερὸν δὲ αὐτὸν ἐπὶ τοῖσιν ὄρος καὶ γαῖαν ἀμειβον.
 'Ηι ἔνι Μοσσύνοικοι ἀν' οὔρεα ναιετάουσι
 Μόσσυνας· καὶ δὲ αὐτοὶ ἐπώνυμοι ἔνθεν ἔσασιν.
 'Αλλοίη δὲ δίκη καὶ θέσμια τοῖσι τέτυχται.
 "Οσσα μὲν ἀμφαδίην ρέζειν θέμις, ἡ δὲ δῆμῳ,

^p Mr. Kinneir places it at the east, and may perhaps agree *Ordou*, which is a little more to better in point of distance.

"Η ἀγορῇ, τάδε πάντα δόμοις ἔνι μηχανώσται.
"Οσσα δὲνὶ μεγάροις πεπονήμεθα, κεῖνα θύραζε
'Αψεγέως μέσσησιν ἐνὶ ρέζουσιν ἀγυιαῖς.

• • • • •
Αὐτὰρ ἐν ὑψίστῳ βασιλεὺς μόσσυνι θαάσσων
'Ιθείας πολέεσσι δίκας λαοῖσι δικάζει,
Σχέτλιος· ἦν γάρ που τὴ θεμιστεύων ἀλίτηται,
Λιμῷ μιν κεῖν' ἡμαρ ἐνικλείσαντες ἔχουσιν.

APOLL. ARG. II. 1017.

Xenophon, who passed through their country, enters into great detail respecting their habits and manner of life. He found them, on his arrival with the Greek army, in a state of dissension, and by siding with one party obtained the victory over the other faction, who were determined to oppose his progress, and thus secured a safe passage for the army. It appears from his narrative, that the Mosynœci had several villages, all built of wood, and a chief town, or metropolis, which was taken, and set on fire. On which occasion the king of the Mosynœci, refusing to quit his tower, was burnt, together with his attendants. In this town were found great stores of bread and corn; also pickled fish, chestnuts, and wine. Their villages were generally not more than eighty stadia apart, and being situated on the heights, it was easy to shout from one to the other, by which means they assembled their forces. They had also a great number of canoes, made of one single tree, and able to contain three men. (Anab. V. 4.) The tract of country which this people inhabited is now called *Heldir*. Following the coast, we have to notice with the Itineraries the river *Pharmatenus*, (Arrian. p. 17.) or *Pharmantus*, (Anonym. p. 12.) 150 stadia from the *Melanthius*. *Pharnacia*. After which we find, 120 stadia further, *Pharnacia*,

as Arrian reports, more anciently called Cerasus, Cerasus. a town of some celebrity, colonized by the Sino-pians. Xenophon and the Greeks rested there for ten days, having been three days on their march from Trapezus. (Anab. V. 3, 5. Diod. Sic. XIV. c. 31.) Cerasus is named by Scylax, but not in its proper place, for it occurs in the text as it stands at present after Sinope. This is probably an interpolation, and it remains uncertain whether the town existed at the time he wrote his Periplus. (p. 33.) Ammianus Marcell. affirms, that the cherry derives its name from Cerasus, having been brought from thence by Lucullus. (XXII. 13.) Arrian is the only writer who affirms that Pharnacia had usurped the place of Cerasus, for though he is copied in this instance by the anonymous geographer, yet that writer afterwards places Cerasus 530 stadia further to the east. (p. 13.) It should be observed also that Strabo says that Cotyorum, and not Cerasus, had contributed to the foundation of Pharnacia; (XII. p. 548.) and he afterwards names Cerasus as a small place distinct from that town and nearer Trapezus. Pliny moreover distinguishes Pharnacia and Cerasus, and he besides informs us that the former was 100 miles from Trapezus, (VI. 4.) a distance much too great to be accomplished by an army in three days, especially over a difficult country. It is apparent, therefore, that the Cerasus of Xenophon is not to be identified with Pharnacia^p, though it might be thought so in Arrian's time; and it is remarkable that this opinion should have prevailed so strongly, as to leave the name of *Keresoun* to the site occupied by the ancient Pharnacia. With respect to

^p This is also the opinion of Mannert, Geogr. t. VI. p. ii. p. 386.

**“Η ἀγορῇ, τάδε πάντα δόμοις ἔνι μηχανόωνται·
Οσσα δὲ ἐνὶ μεγάροις πεπονήμεθα, κεῖναι θύραζε
Αψεγέως μέσσησιν ἐνὶ ρέζουσιν ἀγυιαῖς.**

Αύτὰρ ἐν ύψιστῳ βασιλεὺς μόσσυνι θαάσσων
Ίθειας πολέοσσι δίκαιοις λαοῖς δικάζει,
Σχέτλιος· ἦν γάρ που τὴν θεμιστεύων ἀλίτηται,
Λιμῷ μιν κεῖν' ἡμαρ ἐνικλείσαντες ἔχουσιν.

APOLL. ARG. II. 1017.

Xenophon, who passed through their country, enters into great detail respecting their habits and manner of life. He found them, on his arrival with the Greek army, in a state of dissension, and by siding with one party obtained the victory over the other faction, who were determined to oppose his progress, and thus secured a safe passage for the army. It appears from his narrative, that the Mosynœci had several villages, all built of wood, and a chief town, or metropolis, which was taken, and set on fire. On which occasion the king of the Mosynœci, refusing to quit his tower, was burnt, together with his attendants. In this town were found great stores of bread and corn; also pickled fish, chestnuts, and wine. Their villages were generally not more than eighty stadia apart, and being situated on heights, it was easy to shout from one to the other, by which means they assembled their forces. They had also a great number of canoes, made of a single tree, and able to contain three men.

V. 4.) The tract of country which this people inhabited is now called *Heldir*. Following we have to notice with the Itineraries of Pharmatenus, (Arrian. p. 17.) or Pharnatene, (Anonym. p. 12.) 150 stadia from the Mediterranean. After which we find, 120 stadia further, Plataea.

as Arrian reports, more anciently called Cerasus, *Cerasus*. a town of some celebrity, colonized by the Sino-pians. Xenophon and the Greeks rested there for ten days, having been three days on their march from Trapezus. (Anab. V. 3, 5. Diod. Sic. XIV. c. 31.) Cerasus is named by Scylax, but not in its proper place, for it occurs in the text as it stands at present after Sinope. This is probably an interpolation, and it remains uncertain whether the town existed at the time he wrote his *Periplus*. (p. 33.) Ammianus Marcell. affirms, that the cherry derives its name from Cerasus, having been brought from thence by Lucullus. (XXII. 13.) Arrian is the only

"Η ἀγορῆ, τάδε πάντα δόμοις ἔνι μηχανόωνται.
"Οσσα δὲ ἐνὶ μογάροις πεπονύμεθα, κεῖνα θύραζε
·Αψεγέως μέσσησιν ἐνὶ ρέζουσιν ἀγυιᾶς.

Αὐτὰρ ἐν ὑψίστῳ βασιλεὺς μόσσυνι θαάσσων
·Ιθείας πολέεσσι δίκαιοις δίκαιζει,
Σχέτλιος· ἦν γάρ που τὸ θεμιστεύων ἀλίτηται,
Λιμῷ μιν κεῖν' ἡμαρ ἐνικλείσαντες ἔχουσιν.

APOLL. ARG. II. 1017.

Xenophon, who passed through their country, enters into great detail respecting their habits and manner of life. He found them, on his arrival with the Greek army, in a state of dissension, and by siding with one party obtained the victory over the other faction, who were determined to oppose his progress, and thus secured a safe passage for the army. It appears from his narrative, that the Mosynœci had several villages, all built of wood, and a chief town, or metropolis, which was taken, and set on fire. On which occasion the king of the Mosynœci, refusing to quit his tower, was burnt, together with his attendants. In this town were found great stores of bread and corn; also pickled fish, chestnuts, and wine. Their villages were generally not more than eighty stadia apart, and being situated on heights, it was easy to shout from one to the other, by which means they assembled their forces. They had also a great number of canoes, made of a single tree, and able to contain three men. (V. 4.) The tract of country which this people inhabited is now called *Heldir*. Following this we have to notice with the Itineraries.

Pharmatenus, (Arrian. p. 17.) or
Pharmatenus, (Anonym. p. 12.) 150 stadia from the
Pharnacia. After which we find, 120 stadia fur-

as Arrian reports, more anciently called ~~Cerasus~~,
a town of some celebrity, colonized by the Sino-
pians. Xenophon and the Greeks rested there for
ten days, having been three days on their march
from Trapezus. (Anab. V. 3, 5. Diod. Sic. XIV. c.
31.) Cerasus is named by Scylax, but not in its
proper place, for it occurs in the text as it stands at
present after Sinope. This is probably an interpola-
tion, and it remains uncertain whether the town
existed at the time he wrote his Periplus. (p. 33.)
Ammianus Marcell. affirms, that the cherry derives
its name from Cerasus, having been brought from
thence by Lucullus. (XXII. 13.) Arrian is the only
writer who affirms that Pharnacia had usurped the
place of Cerasus, for though he is copied in this in-
stance by the anonymous geographer, yet that writer
afterwards places Cerasus 530 stadia further to the

"Η ἀγορῇ, τάδε πάντα δόμοις ἔνι μηχανώσαται.
"Οσσα δὲ ἐνὶ μεγάροις πεπονήμεθα, καὶνα θύραζε
'Αψεγέως μέσσησιν ἐνὶ ρέζουσιν ἀγυιαῖς.

· · · · ·
Αὐτὰρ ἐν ὑψίστῳ βασιλεὺς μόσσυνι θαάσσων
'Ιθελας πολέεσσι δίκας λαοῖς δικάζει,
Σχέτλιος· ἦν γάρ που τὴν θεριστεύων ἀλίτηται,
Λιμῷ μιν κεῖν' ἡμαρ ἐνικλείσαντες ἔχουσιν.

APOLL. ARG. II. 1017.

Xenophon, who passed through their country, enters into great detail respecting their habits and manner of life. He found them, on his arrival with the Greek army, in a state of dissension, and by siding with one party obtained the victory over the other faction, who were determined to oppose his progress, and thus secured a safe passage for the army. It appears from his narrative, that the Mosynœci had several villages, all built of wood, and a chief town, or metropolis, which was taken, and set on fire. On which occasion the king of the Mosynœci, refusing to quit his tower, was burnt, together with his attendants. In this town were found great stores of bread and corn; also pickled fish, chestnuts, and wine. Their villages were generally not more than eighty stadia apart, and being situated on the heights, it was easy to shout from one to the other, by which means they assembled their forces. They had also a great number of canoes, made of one single tree, and able to contain three men. (Anab. V. 4.) The tract of country which this people inhabited is now called *Heldir*. Following the coast, we have to notice with the Itineraries the river *Pharmatenus*, (Arrian. p. 17.) or *Pharmantus*, (Anonym. p. 12.) 150 stadia from the *Melanthius*. *Pharnacia*. After which we find, 120 stadia further, *Pharnacia*,

Pharmate-
nus fluvius.

as Arrian reports, more anciently called Cerasus, Cerasus. a town of some celebrity, colonized by the Sino-pians. Xenophon and the Greeks rested there for ten days, having been three days on their march from Trapezus. (Anab. V. 3, 5. Diod. Sic. XIV. c. 31.) Cerasus is named by Scylax, but not in its proper place, for it occurs in the text as it stands at present after Sinope. This is probably an interpolation, and it remains uncertain whether the town existed at the time he wrote his Periplus. (p. 33.) Ammianus Marcell. affirms, that the cherry derives its name from Cerasus, having been brought from thence by Lucullus. (XXII. 13.) Arrian is the only writer who affirms that Pharnacia had usurped the place of Cerasus, for though he is copied in this instance by the anonymous geographer, yet that writer afterwards places Cerasus 530 stadia further to the east. (p. 13.) It should be observed also that Strabo says that Cotyorum, and not Cerasus, had contributed to the foundation of Pharnacia; (XII. p. 548.) and he afterwards names Cerasus as a small place distinct from that town and nearer Trapezus. Pliny moreover distinguishes Pharnacia and Cerasus, and he besides informs us that the former was 100 miles from Trapezus, (VI. 4.) a distance much too great to be accomplished by an army in three days, especially over a difficult country. It is apparent, therefore, that the Cerasus of Xenophon is not to be identified with Pharnacia^p, though it might be thought so in Arrian's time; and it is remarkable that this opinion should have prevailed so strongly, as to leave the name of *Keresoun* to the site occupied by the ancient Pharnacia. With respect to

^p This is also the opinion of Mannert, Geogr. t. VI. p. ii. p. 386.

this town, it appears to have been founded by Pharnaces, grandfather of Mithridates Eupator, though we have no positive authority for the fact^q. We know only that it existed in the time of Mithridates Eupator, being mentioned by Plutarch in the life of Lucullus. (p. 502.) Mannert is inclined to think that Pharnacia was founded on the site of a Greek settlement named Chærades, which Scylax places in this vicinity: (p. 33.) it is also noticed by Steph. Byz. as a town of the Mosynœci on the authority of Hecataeus. (v. Χοραδες.) From Pharnacia, Arrian reckons thirty stadia to the islet called Aretias, or Mars' island, and this distance agrees nearly with that of the little islet to the east of *Keresoon*. This rock is celebrated in the Argonautic mythology as the spot occupied by the two Amazon queens, Otrere and Antiope, who erected there a temple sacred to Mars.

Τοὺς παραμειβόμενοι, λισσῇ ἐπικέλσετε νῆσῳ,
Μήτι παντοὶ μέγ' ἀναιδέας ἔξελάσαντες
Οἰωνοὺς, οἱ δῆθεν ἀπειρέσιοι ἐφέπουσι
Νῆσον ἐρημαίην· τῇ μέν τ' ἐνὶ τηὸν Ἀρηὸς
Δαΐνεον ποίησαν Ἀμαζονίδων βασίλειας
Ὀτρηρή τε καὶ Ἀντιόπη, ὅπότε στρατόωντο.

APOLL. ARG. II. 384.

Zephy-
rium.

Tripolis.

(Cf. Arg.-II. 1032—1234.) Pliny calls it Chalceritis. (VI. 12.) From the island of Mars to Zephyrium the surveys measure 120 stadia. Here was a small port (Cf. Scyl. p. 33.) which doubtless answers to the *Zefré* of modern charts. From thence to Tripolis ninety stadia. Pliny also mentions this place as a fortress seated on a river; (VI. 4.) and

^q There are some autonomous coins of Pharnacia with the epigraph ΦΑΡΝΑΚΕΙΑΣ, and ΦΑΡΝΑΚΕΩΝ. Sestini, p. 60.

there is no doubt of its answering to the present *Tireboli* at the mouth of the river of *Gumeh-kaneh*. Strabo places in this neighbourhood a town named *Ischopolis*, which seems to have been in ruins when Ischopolis he wrote; this possibly may have been replaced by Tripolis. Beyond Tripolis we find Argyria, or Ar-Argyria. gyra, twenty stadia distant. (Arrian. Peripl. p. 17. Anonym. p. 13.) Thence to Philocalea, ninety sta- Philocalea. dia. This place is noticed by Pliny, who leads us to suppose it was situated on a river. (VI. 4.) From this circumstance, I should be disposed to fix the site of Philocalea at *Helehou*, about half way between *Keresoun* and *Trebizond*. In Ptolemy, the name of Philocalia is corruptly written Cocalia. (p. 125.) Apollonius Rhodius places on this coast, after the Mosynœci, the Philyres, who were supposed to Philyres gens. be the offspring of Philyra and Saturn.

Νήσου δὲ προτέρως καὶ ἡπείροιο περαιῶν
Φέρβονται Φίλυρες· Φιλύρων δὲ ἐφύπερθεν ἔασι
Μάκρωνες.

ARG. II. 394.

Elsewhere the same poet mentions the island of the Philyres, which the Argonauts passed soon after leaving that of Mars.

Νυχτὶ δὲ ἐπιπλομένη Φιλυρῆδα νῆσον ἄμειθον,
Ἐνθα μὲν Οὐρανίδης Φιλύρη Κρόνος, εὗτ' ἐν Ὁλύμπῳ
Τιτῆνων ἥνασσεν, δὲ δὲ Κρηταῖον ὑπ' ἄντρον
Ζεὺς ἔτι Κουρήτεσσι μετετρέφετ' Ἰδαιοῖσιν.

Philyreis insula.

ARG. II. 1235.

In captain Gauttier's chart, I find two small islands. laid down close to *Tireboli*, one of which answers doubtless to the isle of Philyra. From Philocalia the Itineraries reckon 100 stadia to Coralla, the Coralla. name of which is preserved in that of cape *Kourélih*. The anonymous geographer then proceeds to Cera- Cerasus.

sus, which he places on a river of the same name sixty stadia from Coralla, (p. 13.) while Arrian, passing over this intermediate station, goes on to Hieron Oros, or the sacred mountain, which, according to his reckoning, is 150 stadia from Coralla. The anonymous writer also places Hieron Oros immediately after Cerasus, at the distance of ninety stadia from that town, or 150 from Coralla, so that they both agree exactly in the whole distance. The difference between the two geographers, with regard to the mention of Cerasus, is however important, and, from what has been said above, there can be little doubt that the authority of the anonymous geographer is here superior to that of Arrian; for though he was certainly much posterior to that historian, he appears to have followed older authors, especially Scymnus of Chios, in whose time Cerasus still existed as a place of note^r. It seems therefore probable, that the original Cerasus, where Xenophon and the Greeks remained for ten days, was situated near the site called *Skefié* in modern charts, between capes *Kourelih* and *Iorox*, the latter being the Hieron Oros of the ancients. From the coins of Cerasus, we know that it existed in the reigns of Antoninus Pius and M. Aurelius, and as late as Alex. Severus. The Byzantine writers also, (Nic. Ann. p. 340. D.) and the ecclesiastical councils, attest its existence under the Greek emperors^s; but I ima-

^r In the fragments of Scymnus, I observe that Cerasus is certainly placed in the vicinity of the isle of Mars, but the passage is very mutilated, and affords no decisive evidence on the point in question. Geogr. Min. tom. II. p. 53. v. 173.

I understand the expression Κερασοῦς κτισθεῖσ' ἵπ' αὐτῷ, to refer to the proximity of the town to the Hieron Oros, which must have been mentioned previously.

^s Geogr. Sacr. a Car. S. Paul, p. 257.

gine all these notices refer to the Pharnacian Cerasus of Arrian, or *Keresoun*. The Hieron Oros is alluded to by Apollonius Rhodius, and he places it on the coast of the Mosynœci ;

'Ιερὸν δ' αὐτόν ἐπὶ τοῖσιν ὅρος καὶ γαῖαν ἄμειθον,
Ἡι, ἐν Μοσσύνοικοι ἀν' οὔρεα γαιετάουτι.

ARG. II. 1017.

but Suidas the historian, as the Scholiast reports, placed it in the country of the Macrones ; and Agathon, in his Periplus of the Pontus, fixed its position still more precisely at the distance of 100 stadia from Trapezus. From this point commences the bay of *Trebizond*, and as all writers agree in assigning this part of the coast to the Macrones, it is probable they were separated from the Mosynœci by the headland above mentioned. The Macrones are called Macrocephali by Scylax, (p. 33.) but Pliny seems to distinguish them as two different people. (VI. 4.) The more usual appellation is however Macrones.

Φιλύρων δ' ἐφύπερθεν ἔασι
Μάκρωνες.

APOLL. ARG. II. 395.

Μάκρωνες, Φίλυρές τε καὶ οἱ μόσσουνας ἔχουσι
Δουρατέους.

DIONYS. PERIEG. 766.

(Cf. Schol. Apoll. et Eust. ad loc.) Herodotus mentions the Macrones on more than one occasion ; they formed, with the Tibareni and Mosynœci, the nineteenth section of the Persian empire under Darius, and contributed 300 talents to the royal treasury. All these people likewise served in the army of Xerxes, and were equipped alike. (Herod. III. 94. VII. 78.) Elsewhere the same historian affirms that the Macrones used circumcision, having, as they themselves

reported, lately derived the practice from the Colchians. (II. 104.) The natural inference to be drawn from this passage is, that the Macrones were of Colchian origin. According to Xenophon, who with the ten thousand journeyed through their country, the Macrones occupied the mountains contiguous to the Colchians, and above Trapezus. They were separated by a river from another people called Scythini, and whose name bears some affinity to the mount Scydisces of Strabo, (XII. p. 548.) and the Scotius of Appian. (Mithr. c. 100.) It is to be observed, however, that Xenophon extends the Colchians as far as Trapezus, (Anab. IV. 8, 17.) whereas other writers assign that town to the Macrones. Strabo affirms that this people were in his time no longer called by their ancient appellation, but were *Sannigens.* named Sanni, (XII. p. 548.) and Eustathius, who confirms this statement, writes the word Tzani, according to the more modern Greek orthography. (ad Dionys. Perieg. v. 766.) I am of opinion that the modern name of *Djanik* is a corruption of San-nice. (Cf. Menipp. ap. Steph. Byz. v. Χαλδία.) Arrian, *Drilæ gens.* however, identifies the Sanni with the Drilæ, whom Xenophon places in the mountains above Trapezus, and describes as the most warlike people of that district. (Anab. loc. cit.) Arrian says that they were once tributary to the Romans, but that confiding in their fastnesses they disclaimed all subjection. He promises, however, the emperor Hadrian, that he would compel them to pay tribute for the future. (Peripl. p. II. Steph. Byz. v. Δρυλαι leg. Δριλαι.) After the Sacred Mountain, where, according to the anonymous Periplus, was a town and port, we have Cordyle, another maritime sta-

tion, forty stadia; then Hermonassa, forty-five stadia further. (Arrian. p. 17.) In the anonymous geographer the name is corruptly written Ermiese. Hermonassa is mentioned as a small town on this coast between Cerasus and Trapezus; (XII. p. 548.) and Menippus, who is cited by Steph. Byz. (v. Ἐρμίσσα) affirmed that it belonged to the latter city. It was also known to Hecatæus and Theopompus. Pliny does not mention Hermonassa; but he places next to Trapezus an unknown town named Livo- polis. (VI. 4.) The situation of Hermonassa answers nearly to that marked in captain Gauttier's chart under the name of *Platana*. Trapezus was sixty stadia further. This city, which under the modern name of *Trebizond* is still a considerable and flourishing sea-port, is acknowledged by all ancient authorities to have been colonized by the Sinopians, who, as we have seen, formed extensive establishments on this coast. (Xen. Anab. V. 8. Arrian, p. 1. Scyl. p. 33.) It was pretended indeed by the Arcadian Trapezuntii, that they were the ancestors of the Pontic colony; but this was probably an opinion grounded only on the similarity of name; and it was perhaps only a piece of policy in the Sinopians, who wished to strengthen the infant colony, to receive these Arcadian refugees as friends and kinsmen. (Pausan. Arcad. c. 27.) Trapezus was already a flourishing town, when Xenophon and his fellow-soldiers reached it in the course of their memorable retreat. They remained in its vicinity for thirty days, during which they were treated in the most friendly and hospitable manner by the citizens, and received every assistance for the prosecution of their journey home. The abundant supplies which were

furnished, to them for subsistence, and votive offerings, prove that the town was opulent, and the country fertile and populous. (Anab. V. 8, 17.) Trapezus at that time was situated in the Colchic territory, but later writers remove the Colchians considerably further to the east, and include it within the district occupied by the Macrones. Ancient geographers reckoned about 6600 stadia from the temple of Jupiter Urius, at the entrance of the Bosphorus, to Trapezus, and 1400 stadia from that city to the mouth of the Phasis. (Strab. XII. p. 548.) We learn from Arrian, that Trapezus was the most considerable place on their coast when he visited it, as governor of Pontus, under Hadrian. He commences his letter, which contains the Periplus, and is addressed to the emperor, from thence. He reminds Hadrian of the spot he had once visited, from whence it was supposed that Xenophon and the ten thousand first beheld the sea, and where altars had been erected, with inscriptions commemorative of that event. Arrian signifies his intention of erecting altars of white marble, instead of the rude monuments then existing, and he requests the emperor to send his statue, to add further to the decoration of the spot; the effigy which stood there being a coarse and inelegant representation of him. (Peripl. p. 1—3.) The spot alluded to by Arrian seems to have been above Trapezus, and at no great distance from the town; but it appears from Xenophon, that the mountain from which he and the army beheld the sea, and which he calls Thekes, or the Sacred Mount, was in the country of the Scythini, above the Macrones, and at least five days' journey from Trapezus. (Anab. IV. 7.) But

we will reserve the discussion of this interesting question on ancient topography for a future opportunity, in order to conclude what we have to say respecting Trapezus, and the remaining coast of Pontus. That town is noticed by Tacitus as an ancient and important seaport on the Euxine. (Annal. XIII. 39. Hist. III. 47.) Pliny styles it a free town. (VI. 4. Cf. Mel. I. 19. Steph. Byz. v. Τραπεζοῦς.) In the reign of Gallienus it was sacked and burnt by the Goths, who were spreading devastation along the shores of the Euxine. (Zosim. I. p. 30.) Some centuries later we find it becoming the seat of a small empire, under the government of a branch of the princely house of the Comneni. Its sovereigns assumed the pompous title of emperors of Trebizond, and declared themselves independent of the Greek empire.

This principality even stood for some time after the taking of Constantinople; but, too feeble to resist the overwhelming power of the Turks, it finally yielded by capitulation in 1460 to Mahomet II; and Trebizond from that time became a Turkish city. (Chalcond. IX. p. 263—266. Duc. c. 45^t.) Modern travellers describe it as situated on an elevated terrace above the sea, whence the name of Trapezus was doubtless derived, and surrounded by hills which are succeeded at a greater distance by loftier mountains. (Cf. Plin. VI. 4.) The citadel is built on a rock, which advances out into the sea, and forms the port anciently called Daphni. (Anon. *Daphni portus*.

^t For a further account of the empire of Trebizond, see the Fam. Byzant. of Du Cange,

quoted by Gibbon in the Decline and Fall of the Roman Empire, tom. XI. p. 249.

Peripl. p. 13.) This port is by no means protected against the north winds, which blow with violence during the winter season. There are no ruins of any size or interest, as they chiefly belong to the lower Greek empire. The modern town has a population of about 60,000 or 70,000 souls, and keeps up an active trade with different ports on the Black Sea. It is the chief town of a Turkish pashalik, to which it gives its name^u.

Hyssus
portus.

Psoron
portus.

Ophius fl.

From Trapezus the Itineraries lead us to Hyssus, a port afterwards called Susarmia, and distant 180 stadia; (Arrian. p. 3. Anonym. p. 14.) perhaps this is the same haven which Scylax calls Psoron; (p. 33.) at all events the name of Susarmia agrees with that of the little river called *Sourmenah*. The port Hyssus was probably therefore situated at the mouth of it. From thence to the river Ophius, where was a naval station, the anonymous geographer reckons ninety stadia: he states also that this river separated the Colchi from the district of Thianitice; (Peripl. p. 14.) perhaps we should read Sannice. Various barbarous tribes are noticed on this coast by ancient writers.

Μάχρωνες· μετὰ δὲ αὐτὸν περιώσια φῦλα Βεγχείρων.
Ἐξείης δὲ Σάπειρες ἐπὶ σφίσι ναιετάουσι·
Βύζηρες δὲ ἐπὶ τοῖσιν ὁμώλακες, ὃν ὑπερ τὴν
Αὐτοὶ Κόλχοι ἔχονται ἀρήιοι.

APOLL. ARG. II. 396.

Κεῖθεν δὲ αὐτὸν Μάχρωνας, ἀπειρεσίην τε Βεγχείρων
Γαιῶν, ὑπερφιάλους τε πάρεξ ἐνέοντο Σάπειρας,
Βυζηράς τ' ἐπὶ τοῖσιν.

IBID. 1246.

^u Tournefort, Voyage au Levant. Kinneir's Travels, p. 340. Fontanier, Voyages dans l'Orient, p. 17—23. There are

only imperial coins of Trapezus from Trajan to Philip: the epigraph is ΤΡΑΠΕΖΟΤΝΤΙΩΝ. Sestini, p. 60.

Φράξεο δὲ ἐκ Κόλχων καὶ Φάσιδος ἐς δύσιν ὥδη
Εὐξένου παρὰ χεῖλος, ἐπιλαδὸν ἔθνεα Πόντου
Ἄχρι Θρηϊκίου στόματος, τόθι Χαλκὶς ἄρουρα
Βúζηρές τοι πρῶτα καὶ ἄγχοθι φῦλα Βεχείρων.
Μάχρωνες Φίλυρές τε.

DIONYS. PERIEG. 762.

Scylax, after the Phasis and the Colchi, proceeding from east to west, names the Byzeres, Ecechiries, Bechires, and Macrocephali, who are the same as the Macrones. (p. 32, 33.) The Bechires then appear to follow the Macrones, and after them the Ecechiries, whom the anonymous Periplus places between the Ophius and Archabis. (p. 16.) The Byzeres, according to Strabo, were afterwards called Hepta-Cometæ. They were a wild and savage race who inhabited mount Scydisces, and cut to pieces three cohorts of Pompey's army by placing on their way a quantity of honey, which had the effect of intoxicating them, and depriving them of the power of resistance. (XII. p. 549.) This singular circumstance recalls to mind the description given in Xenophon of a similar effect produced by honey on the Greeks in the country of the Colchians, near Trapezus. (IV. 8.) Pliny affirmed that this honey was chiefly extracted from the flower of the rhododendron, and he states that it was found in the country of the Sanni. (XXI. 13.) Aristotle also noticed it as peculiar to the neighbourhood of Trapezus. (ap. Steph. Byz. v. Τραπεζοῦς.) The Ophius, or Orphis, as Arrian (p. 6.) writes the name, is probably the river *Caouchi*. After an interval of thirty stadia we find another small stream called Psychrus, or the *Cold* river; and at an equal distance the Calos, or *Beautiful* stream, where was a station named Cale Parembole. (Anon. p. 14. Ar-

Byz. v. Τραπεζοῦς.
Hepta-Co-
metæ gens.
Ecechiries
gens.
Archabis.
Cale Pa-
rembole.

Peripl. p. 13.) This port is by no means protected against the north winds, which blow with violence during the winter season. There are no ruins of any size or interest, as they chiefly belong to the lower Greek empire. The modern town has a population of about 60,000 or 70,000 souls, and keeps up an active trade with different ports on the Black Sea. It is the chief town of a Turkish pashalik, to which it gives its name^u.

Hyssus
portus.

Psoron
portus.

Ophius fl.

From Trapezus the Itineraries lead us to Hyssus, a port afterwards called Susarmia, and distant 180 stadia; (Arrian. p. 3. Anonym. p. 14.) perhaps this is the same haven which Scylax calls Psoron; (p. 33.) at all events the name of Susarmia agrees with that of the little river called *Sourmenah*. The port Hyssus was probably therefore situated at the mouth of it. From thence to the river Ophius, where was a naval station, the anonymous geographer reckons ninety stadia: he states also that this river separated the Colchi from the district of Thianitice; (Peripl. p. 14.) perhaps we should read Sannice. Various barbarous tribes are noticed on this coast by ancient writers.

Μάκρωνες· μετὰ δὲ αὐτὸν περιώσια φῦλα Βεγχείρων.
Ἐξείης δὲ Σάπειρες ἐπὶ σφίσι ναιιτάουσι·
Βύζηρες δὲ ἐπὶ τοῖσιν ὁμάλακες, ὡν ὑπερ ἥδη
Αὐτοὶ Κόλχοι ἔχονται ἀρήιοι.

APOLL. ARG. II. 396.

Κεῖθεν δὲ αὐτὸν Μάκρωνας, ἀπειρεσίην τε Βεγχείρων
Γαιαν, ὑπερφιάλους τε πάρεξ ἐνέοντο Σάπειρας,
Βυζηράς τ' ἐπὶ τοῖσιν.

Ibid. 1246.

^u Tournefort, Voyage au Levant. Kinneir's Travels, p. 340. Fontanier, Voyages dans l'Orient, p. 17—23. There are

only imperial coins of Trapezus from Trajan to Philip: the epigraph is ΤΡΑΠΕΖΟΥΝΤΙΩΝ. Sestini, p. 60.

Φράξεο δὲ ἐκ Κόλχων καὶ Φάσιδος ἐς δύσιν ἥδη
Εὐξένου παρὰ χεῖλος, ἐπιλαδὸν ἔθνεα Πόντου
Ἄχρι Θρηϊκίου στόματος, τόθι Χαλκὶς ἄρουρα
Βύζηρές τοι πρῶτα καὶ ἄγχοθι φῦλα Βεχείρων.
Μάχρωνες Φίλυρές τε.

DIONYS. PERIEG. 762.

Scylax, after the Phasis and the Colchi, proceeding from east to west, names the Byzeres, Ecechiries, Bechires, and Macrocephali, who are the same as the Macrones. (p. 32, 33.) The Bechires then appear to follow the Macrones, and after them the Ecechiries, whom the anonymous Periplus places between the Ophius and Archabis. (p. 16.) The Byzeres, according to Strabo, were afterwards called Hepta-Cometæ. They were a wild and savage race who inhabited mount Scydisces, and cut to pieces three cohorts of Pompey's army by placing on their way a quantity of honey, which had the effect of intoxicating them, and depriving them of the power of resistance. (XII. p. 549.) This singular circumstance recalls to mind the description given in Xenophon of a similar effect produced by honey on the Greeks in the country of the Colchians, near Trapezus. (IV. 8.) Pliny affirmed that this honey was chiefly extracted from the flower of the rhododendron, and he states that it was found in the country of the Sanni. (XXI. 13.) Aristotle also noticed it as peculiar to the neighbourhood of Trapezus. (ap. Steph. Byz. v. Τραπεζοῦς.) The Ophius, or Orphis, as Arrian (p. 6.) writes the name, is probably the river *Caouchi*. After an interval of thirty stadia we find another small stream called Psychrus, or the *Cold* river; and at an equal distance the Calos, or *Beautiful* stream, where was a station named Cale Parembole. (Anon. p. 14. Ar-

Byzeres
qui et
Hepta-Co-
metæ gens.
Ecechiries
gens.
Archabis
gens.

Psychrus
fluvius.
Calos flu-
vius.
Cale Pa-
rembole.

Rhizius fluvius et portus.

Ascurus fluvius.

Adienus fluvius.

Cordyle.

Athenæ portus.

Zagatis fluvius.
Prytanis fluvius.
Anchialij regia.

Armene Limne.
Pyxites fluvius.
Archabis fluvius.

rian, p. 7.) It must have been situated a little to the west of *Cape Foudgi*. Rhizius, a port and river 120 stadia from thence, is easily recognised in the present *Rixieh*, a commercial town of some size near the eastern extremity of the Black Sea^x. It is probably the Bechireus portus of Scylax. (p. 33.) Rhizæum is also mentioned by Ptolemy, (p. 125.) and Procopius. (Bell. Got. IV. 2.) The port was improved by Justinian. (Procop. AEd. III. 7.) From thence to the mouth of the Ascurus, Arrian reckons thirty stadia. (Per. p. 7.) The anonymous Periplus calls this river Asurnas. (p. 14.) From thence to the Adienus we have sixty stadia. (Arrian. p. 7. Anonym. p. 14.) It is probably the river *Mapourah*. Then follows, after an interval of 100 stadia, a place called Cordyle, (Anonym. p. 14. Ptol. p. 125.) and eighty stadia further a small port, which derived the name of Athenæ from a temple of Minerva erected there. (Arrian, p. 6, 7. Anonym. p. 14. Steph. Byz. v. 'Αθηναί.) It is probably the same place which Scylax calls Ordinius, and styles a Greek town. (Per. p. 32.) Procopius also mentions Athenæ in the history of the Gothic wars. (IV. 2.) The site is now called *Ordouna*. Beyond Athenæ was the river Zagatis, seven stadia; and thirty-three stadia further the Prytanis, with a spot called the palace of Anchialus. (Arrian. p. 7. Anon. Per. p. 15.) Scylax names the river Pordanis, and places it near a town called Limne. (Per. p. 32.) After the Prytanis we have the Pyxites, ninety stadia distant; (Cf. Plin. VI. 4.) then the Archabis at an equal distance. (Arrian. p. 7. Anonym. p. 15.) Scylax calls the latter Arabis. (p. 32.) The modern

^x Peyssonel, Commerce de la Mère Noire.

name is *Arkava*. The anonymous *Periplus* places between the *Prytanis* and the *Pyxites* a spot called *Armene*, twenty-four stadia from the former and sixty-six from the latter. From the *Archabis* to *Apsarus* sixty stadia were reckoned. The name of *Apsarus*^{portus.} this last place, it was said, had been originally called *Apsyrtus*, from the brother of *Medea*, but the barbarians had corrupted it to its present form. Arrian reports that it was a town, and military station for five cohorts. (*Peripl.* p. 7. *Anon.* p. 15.) Pliny writes, “*flumen Absarum cum castello cognomine* “*in faucibus a Trapezunte CXL. mill. passuum.*” (VI. 4.) Procopius speaks of it as a more consequential place, since it possessed a theatre, an *hippodromus*, and other public buildings. The tomb of *Absyrtus* was shewn in the vicinity. (*Bell. Got.* IV. 2. Cf. Arrian. p. 6.) *Absarum* was probably not far from the modern town of *Gonieh*. Arrian after this place names the river *Acampsis*, which he describes as a navigable river, from the mouth of which a fresh breeze set in toward the sea about sun-rise. It was fifteen stadia from *Absarum*^{y.} Now there is no river of any size in this part of the coast but the *Tchorok*, or river of *Batoun*, which flows from the south, having its source in the mountains of *Baibont* and *Sunnur*, not far to the west of *Erzeroum*. This is evidently therefore the *Acampsis* of Arrian; but other geographers have named the same river *Apsarus*, probably from the town situated near its mouth. Thus Scylax seems to identify the *Apsarus* and *Acampsis*, as he only

Absaros,
qui et
Acampsis
fluvius.

^y Arrian nowhere speaks of *Apsarus* as a river, but as a military station; this has not been

sufficiently attended to by Manner, and other geographers.

Glaucus
fluvius.

Lycus flu-
vius.

Boas flu-
vius.

names the former. He mentions besides the Daraanon and Arion, which no other geographer recognises. (Perp. p. 32.) Pliny says the Absarus flowed from mount Paryadres, and separated the greater from the lesser Armenia. (VI.9.) Ptolemy, who writes the name Apsorru, says also that it rose in the Armenian mountains, and was formed by the junction of two principal streams which he names Glaucus and Lycus. (p. 125.) Of these the Glaucus appears to come from the south-west, and is the real *Tchoroksov*. Fontanier says it has two distinct sources, one rising in mount *Agh-Dagh*, the other more to the west: they meet about two leagues below *Baibout*, and fall into the Euxine near *Batouni*. But there is another main branch of the *Tchoroksov*, which rises in the mountains to the north of *Erzeroum*, and joins the former near *Artavani*; it is called *Gorgoro* in modern maps, and answers to the Lycus of Ptolemy. Procopius, speaking of the same river, says it was called Acampsis near its mouth, but Boas in the upper part of its course. (Bell. Got. IV. 2. Cf. Pers. II. 17.) It appears therefore from all that has been said, that the Acampsis of Arrian, and the Absarus of other writers, are the same river, namely, the *Tchoroksov* of modern geography ^z. It should be observed also that the latter name of the two is more generally used, and better attested. Before we quit this extremity of Pontus, it may be proper to say a few words respecting Ptolemy's account of it. This

^z D'Anville, in his map of Asia Minor, has confounded the Acampsis and Bathys, a stream which flowed to the north of

Batouni, and has made the Absarus a distinct river from the Acampsis.

geographer places in succession on this coast after Trapezus, the river Ophius, the port Rhizus, the promontory Athenæ, Chordyle, a place called Mar-^{Marthyla.} thyla, the river Arcadis, (the Arcabis of Arrian,) a town named Xyline, and the rivers Cissus and Ap- sorus. Now with respect to the former of these rivers it may be observed, that its name corresponds with that of the Cissii, a people to whom Ptolemy ^{Cissii.} assigns this part of the coast. The Table Itinerary names also Cissa as a station on this line of coast, ^{Cissa.} and I am inclined to think that this people are the same as the Zygi of Strabo, (XI. p. 492.) and Dionysius Perieg. (v. 687.) and Pliny. (VI. 7.) Ar- rian, it should be remarked, calls them Zichi, and certainly places them north of the Phasis; (Per. p. 19.) but continual changes seem to have taken place in the situation of these small tribes, for we find the Heniochi, who were also near the Mœotis at one ^{Heniochi} time, and the Machelones, taking the places of the ^{gens.} ^{Mache-} Bechires and Ecechiries; (Anonym. Peripl. p. 15.) ^{lones gens.} and most probably a portion of the Zygi, or Zichi, ^{Zygi gens.} were shifted at the same time. It is certain that Strabo places a town called Zygopolis on this coast, ^{Zygopolis.} (XII. p. 548.) and the Zagatis, or Zygatis, of the Anonymous Periplus may be referred to the same people. (Cf. Steph. Byz. v. Ζυγοί.) Another people who are noticed in this part of Pontus, but rather more inland and among the mountains, are the Cer-^{Cercetæ} cetæ, (*Κερκεταὶ*,) who are placed by Strabo in this ^{gens postea} ^{Apaitæ.} direction, and also with the Zygi and Heniochi near Sindice and the Palus Mœotis; the Armenian Cer- cetæ had in his time exchanged their name for that of Apaitæ, but there seems to be some trace of the ancient appellation in Xenophon, who calls them

Cœti, (*Κοῖτοι.*) He does not mention them in the course of his narrative, but at the end of the work, where he sums up the different nations they had met with in the whole of the retreat; he there names the Cœti as an independent people, together with the Macrones, Mosyncæci, and Tibareni; but as the Scythini, who are named in the narrative more than once, do not appear in this summary, perhaps the Cœti are no others than this people, who are also, I think, the Cercetæ of Strabo. The Scythini of Xenophon I certainly think are connected with the mountain called Scydisces by Strabo, and Scotius by Appian, (Mithr. c. 100.) as we know besides that they were contiguous to the Macrones. The position of this people is of considerable importance with respect to the geography of the Anabasis, as it will enable us to fix the point where the ten thousand entered Pontus from Armenia, and, generally speaking, the line of march which brought them from the river called Harpasus by Xenophon to Trapezus and the sea. According to the historian, it seems that the Harpasus was a river of Armenia, apparently separating the country of the Armenian Chalybes from that of the Scythini, and four plethra in width, which shews that it was a considerable stream. Now there is no river in Armenia of this size but the Araxes, and one of its branches called *Harpasou*, which in all probability is the Harpasus of Xenophona^a. At the same time, in order to bring the Greeks to the *Harpasou*, which flows through the district of *Kars*, we must suppose with Rennell that they wandered for several

^a See Rennell's Illustration of the Retreat of the Ten Thousand, p. 225.

days without a guide, and were obliged to retrace their steps when they came to that river, of which circumstance, it must be confessed, there is no apparent indication in the *Anabasis*^b. From the Harpasus they proceeded through the country of the Scythini, which appears to have consisted of plains, for four days, and having rested three days in some villages, they marched on again for four days, till they came to a large, opulent, and populous town called Gymnias. The governor of this place on their approach sent a person to the Greeks offering them a guide who should conduct them, on pain of forfeiting his life, in five days to a place whence they should see the sea. The position of this town is very uncertain: Rennell places it at *Coumbase*, or *Kumakie*, on the northern bank of the Araxes^c, about ninety-one geographical miles from the *Harpasou*, and 110 from Trebisond^d. A more recent writer is inclined to suppose Gymnias may be *Ippsera* on the *Tchorok*^e, but it is not easy to see how the Greeks could get there; and besides, that town is so much nearer the sea, that it would not require five days to bring them in sight of it.

However, the situation of this place is not of so much importance, perhaps, as that of the Scythini, who certainly were contiguous to the Macrones, whose position is well ascertained. They were divided from the Macrones by a river, which from the map could hardly be any other than the western branch of the Apsarus, or *Tchorok*, which flows near the

^b Illustrations of the Retreat of the Ten Thousand, p. 224.

Araxes.

^c In Lapie's map of the Turkish empire *Coumbase* stands on the southern shore of the

^d P. 236.

^e An Essay on the Geography of the *Anabasis*, p. 309.

town of *Baibout*. Appian, in the history of the Mithridatic war, (c. 101.) speaks of a part of Armenia situated on the borders of Pontus, and near the sources of the Euphrates: he calls it Chotene, a name which bears some analogy to that of the Scythini, or Cœti, of Xenophon. Chotene, besides, was contiguous to Iberia and the river Apsarus; all which circumstances concur in fixing the march of the ten thousand in the line of *Erzeroum* and *Baibout*. It was before, however, they arrived on the borders of the Macrones that they beheld the sea. (Anab. IV. 7.) The Sacred Mountain, or Thekes, could not therefore be *Tekeh* near *Gumiskend*, as major Rennell supposes^f; but it must have been situated between *Erzeroum* and *Baibout*, where the road crosses some of the highest table land in Asia. On crossing the river of *Baibout* the Greeks would enter the territory of the Macrones, which they traversed in three days, till they came to another high range occupied by the Colchi. These were no doubt the Sanni of Strabo and Pliny, who came afterwards to be identified with the Macrones, and to absorb that name within their own. Having driven the Colchians from the heights, and passed through the mountainous defiles, the Greeks descended, and after resting some time in the villages of the enemy, where they found the honey which had so singular an effect upon them, they marched for two days more, and reached Trapezus. The only obstacle to the

^f "Tekes, or the Sacred
"Mountain, is the great chain
"lying between *Erzeroum* and
"*Trebisond*. Here is a sum-
"mit, with a castle called *Teke*,
"one day's journey from *Gu-*

"*miskend*, the noted silver
"mine." Major Rennell esti-
mates the distance from Teke
to the sea to be about thirty
English miles.

line of march here marked out for the Greek army, is the distance at which they must have been from the sea at the point where I have supposed them to come in sight of it, being not less than fifty miles in a straight line. But there is no impossibility in their seeing the sea from that, or a still greater distance, if they had attained to a sufficient elevation, and their view was not intercepted by other mountains. This question, in fact, can only be decided by actual observation^g; but it should be borne in mind that, according to Xenophon's account, the Greeks were certainly not less than six days' march from the sea when they beheld it. I am not aware of any other route by which they could have come down upon Trapezus, except the one I have traced. It is that which nature seems to have pointed out from the earliest time for establishing a communication between Pontus and Armenia; and it is clearly laid down in the Table Itinerary as leading from Trapezus into the latter country. The first station on leaving Trapezus was Magnana, distant twenty miles from that city. It is probably the site called *Machka* by modern travellers^h. The next stage, according to the Itinerary, was Gihenenica, ten miles from Magnana. The analogy of names points out the site of *Ghemiskhana* as likely to answer to this second station. It would appear, however, from Kin-

^g The view from the summit of mount *Cop Dagh*, the ancient Sydisces, according to Kinneir, is most magnificent; and though he does not state that he beheld the sea from thence, I see no reason why it might not be visible on a

clear day. The guides said they could discern mount Ararat from thence. Mr. Kinneir observes, that he had been ascending all the way from Trebisond to this mountain, p. 357.

^h Fontanier, *Voyages en Orient*, p. 37.

neir's account, to be more than thirty miles from Trebisondⁱ. Fontanier, however, reckons only ten leagues^k. Bylæ, which next follows in the Table at a distance of eighteen miles, has been thought by some travellers to be *Bayboot*, but the distance of that town from Trebisond seems to allow this. I should imagine Bylæ, which ought perhaps to be written Pylæ, is the *Boos Kela* of Kinneir^l. Frigidarium, six miles further, would be the station on the summit of the mountains beyond, and Patara, which is eight miles beyond it, is probably *Balkare*^m. Medocia, twelve miles further, must be looked for near *Bayboot*. It is not necessary to follow this Itinerary further; enough has been traced to shew its agreement with the present route from Trebisond to *Erzeroum*, which I conceive also to have been that of the Ten Thousand.

Having now sufficiently surveyed the coast of Pontus, and likewise discussed the ancient geography of the eastern extremity of that province in connexion with the Anabasis, we must once more return to the river Halys, for the purpose of exploring those districts in the interior of Pontus situated along that river and the upper valleys of the Iris, Lycus, and Thermodon. We have already said that Strabo gave the name of Gazelonitis, or Gadilonitis, to the district on the right bank of the Halys, at no great distance from the sea. It derived its name apparently from Gazelon, or Gadi-lon, the principal town, but noticed only by Strabo

Gazelon
sive Gadi-
lon.

ⁱ Fontanier, *Voyages en Orient*, p. 348.

^k Ibid. p. 39.

^l The village of *Booskela*

stands at the foot of a stupendous rock, crowned by an ancient castle, p. 350, 351.

^m P. 351.

(XII. p. 547.) and Pliny. (VI. 2.) It was probably situated in the vicinity of *Vixir-Kupri*, not far from the Halys, and between *Bafra* and *Osmanjik*. Contiguous to *Gazelonitis*, on the south-east, was Phazemonitis, a district so called from Phazemon, a small town, in the vicinity of which Pompey founded a colony named Neapolis. Hence the same district Neapolis. appears to have been sometimes termed Neapolitis ⁿ. (Strab. XII. p. 560.) Steph. Byz., who copies Strabo, writes the name Phamizon. (v. Φαμιζών.) Phazemon is generally supposed to correspond in situation with the modern town of *Maxifun*. On the north-eastern side of Phazemonitis apparently, and towards the Iris, was an extensive lake named Stiphane: it abounded in fish, and its shores were surrounded by excellent pastures ^o. Above this lake was a hill, with a deserted and ruinous fortress, named Cizari. This had once been a royal residence. (Strab. XII. p. 560.) Towards the south-west, and in the direction of Amasia, were some warm medicinal springs, accounted very efficacious in the cure of various disorders. Mr. Kinneir ob-

ⁿ The text of Strabo is here supposed to be corrupt. The reader may consult an elaborate note on the passage in the French translation of that author, vol. IV. p. ii. p. 71. See also Mannert, tom. VI. p. ii. p. 465.

^o No mention is made of this great lake by modern travellers, nor is there any appearance of it in the maps. Could this be the same which is spoken of in the Life of Gregory Thaumaturgus, and which is said to

have been dried up at his prayer, p. 277 : ἡπειρον ἐποίησε, τῷ ὄρθρῳ τὴν λίμνην ἔηράν τε καὶ ἀγικμον. ὡς μηδὲ ἐν τοῖς κοῦλοις ἔχειν τί τοῦ ὄδατος λείψαντο, τὴν πρὸ τῆς εὐχῆς πελαγίζουσαν. It is remarkable, that the last word in the quotation agrees so nearly with the expression in Strabo, λίμνη πελαγία τὸ μέγεθος. The biographer of Gregory says again, p. 279, καὶ πῶς ἡ ἀντὶ θαλάσσης ὥσα τῷ τόπῳ τὸ πρότερον, νῦν πρὸς καρπῶν ἄγεισι φοράν.

Sagylum
castellum.

serves, that on the road from *Vixir Kupri* to *Marsian* there is a place called *Gouxus*, famous for its mineral baths. The springs are very abundant, and there are also to be seen some ancient ruins of considerable magnificence^{p.} Here was also a fort named Sagylum, placed on a lofty conical hill. This castle, being a place of great strength and well provided with water, had been of great service to the kings of Pontus; but Pompey rendered it useless by filling up the wells with great stones. Strabo reports, that in consequence of this, Arsaces, a rebel chief, who was guardian of the sons of Pharnaces, and had retired to this fortress, was forced to surrender to Polemon, king of Pontus, and Lycomedes, priest of Comana, who besieged him^{p.} (Strab. XII. p. 560.) Contiguous to Phazemonitis to the east, was the city and territory of Amasia, the birthplace of Strabo; a circumstance which accounts for his dwelling on its topography with so much feeling and evident graphic accuracy of detail.

Amasia.

"My native town," says the geographer, (XII. p. 560.) "is situated in a deep and large valley, "through which flows the river Iris. It has been "provided in a surprising manner, by art and

^p Travels, p. 298.

^p The passage in Strabo, as it stands at present, is evidently corrupt. 'Εγταῦθα δὲ ἔάλω, καὶ διεφθάρη ὑπὸ τῶν Φαρνάκου τοῦ βασιλέως παιδῶν Ἀρσάκης (var. lect. Ἀρσάνης) βασιλεύων (MSS. δυναστεύων) καὶ γεωτερίζων, ἐπιτρέψαντος οὐδενὸς τῶν ἥγεμόνων. ἔάλω δὲ οὐ βίᾳ τοῦ ἐρύματος ληφθέντος ὑπὸ Πολέμωνος, καὶ Λυκομήδους βασιλέων ἀμφοῖν ἀλλὰ λιμῷ. Here it is said that this Arsaces, or Arsanes,

was taken and destroyed by the sons of king Pharnaces; and from the sequel it follows that Polemo and Lycomedes were those princes, which is absurdly false. It is evident that we ought to read, 'Εγταῦθα δὲ ἔάλω καὶ διεφθάρη, ἐπὶ τῶν Φαρνάκου τοῦ βασιλέως παιδῶν Ἀρσάκης δυναστεύων. "Arsaces, who was at "the head of affairs in behalf, "or as guardian of the sons of "Pharnaces."

" nature, for answering the purpose both of a city
" and fortress. For there is a lofty and perpendicu-
" lar rock which overhangs the river, having on
" one side a wall built close to the bank of the
" river where the town has been built; while on
" the other, it runs up on either hand to the summits
" of the hill. These are two, connected with each
" other, and excellently provided with towers. With-
" in this peribolus are the royal residence, and the
" tombs of the kings. But the heights have on each
" side a very narrow neck of land, about five or six
" stadia in height, as you ascend from the river and
" the suburbs. From this ridge to the summits,
" there remains another sharp ascent, about a sta-
" dium in length, which it would be impossible to
" force. In this direction, too, water is carried up,
" by means of two channels cut in the rock, one
" towards the river, the other towards the ridge.
" Two bridges are thrown over the river; the one
" from the town to the suburb, the other from the
" suburb to the outer country: for the mountain
" which overhangs the rock, terminates at the point
" where this bridge is placed." (XII. p. 561.) Mo-
dern travellers have borne witness to the accuracy
of this description, though time has produced some
change in the position of the town. Busbequius,
who visited Amasia in the sixteenth century, found
it situated on both banks of the river, and rising in
the form of an amphitheatre on either side. Taver-
nier says, it is placed on the hollow slope of a moun-
tain, and that on the south the view extends over a
fine plain. Towards the west he observed the ruins
of the citadel, which stood on an elevated summit.
The same traveller noticed also some remains of the

conduits mentioned by Strabo^r. That geographer tells us nothing of the origin and history of his native city: we collect only from his account, that it was a place of considerable importance and antiquity, from the mention of the king's palace and the royal tombs. The sovereigns here alluded to, were most probably some of the early kings of Pontus. When Strabo wrote, Amasia formed part of the Roman province; (XII. p. 561.) and we learn from its coins that it bore the title of Metropolis of Pontus^s. (Cf. Plin. VI. 3. Ptol. p. 125. Steph. Byz. v. Ἀμάσεια. Herocl. p. 701. Procop. Hist. Arc. c. 18.) Some of its public buildings were restored by Justinian. (Procop. AEd. III. 7. Cf. Nicet. Ann. p. 331. Leo Diacon. VI. 3. p. 59.) *Amasieh*, as it is now called by the Turks, preserves still its ancient site, and many vestiges of its former state. A recent traveller reports, that there are considerable portions of the walls leading up to the citadel remaining. In the upper town are to be seen the ruins of a temple, a fountain, and the aqueducts mentioned by Strabo; these remains are in a good state of preservation, and it is supposed that excavations would be attended with success. Outside the town are some curious caverns, which the traveller in question supposes may have been the royal tombs; but Strabo positively states that they were within the walls. The country about *Amasieh* is beautiful, and the valley of the *Tokatlou* highly picturesque, and richly cultivated^t.

^r Voyages, I. c. i. p. 9.

^s These coins are of the reigns of Trajan, Hadrian, and Antoninus; the epigraph is AMA-

CIAC ΜΗΤΡΟΠΟΛΕΩΣ or ΠΡΩ-
ΤΗΣ ΠΟΝΤΟΥ. Sestini, p. 58.

^t Fontanier, Voyages en Orient, ch. 17. p. 233.

The territory of Amasia, as Strabo informs us, was extensive and very productive; though it had suffered greatly from the wars waged by Mithridates against the Romans, many towns being destroyed, and several tracts of land depopulated. Towards the north, the valley of the Iris widened to an extensive plain named Chiliocomon, and contiguous to this were the two fertile districts, Diacopene and Pimolisene, which reached to the Halys. (XII. p. 561.) The valley of the Iris is called Gazacena by Pliny, (VI. 3.) and Strabo himself incidentally recognises the appellation. (XII. p. 553.) Towards the south-east, and still keeping on the right bank of the Halys, Amasia included within its jurisdiction the cantons of Babanomus^t and Ximene. The latter contained some salt mines, from which the Halys was supposed to derive its name. (Strab. XII. p. 561.)

The Iris, according to the same geographer, rose in the mountains of Pontus, passed the town of Comana, and watered the fertile plains of Daximonitis from east to west. On reaching Gazioura, it turned towards the north, and then again to the east; after which, having received the Scylax, and several other rivers, it flowed under the walls of Amasia; and being then joined by the Lycus in the plains of Phanarœa, it traversed the rich lands of Themiscyra, and finally reached the Euxine. The Scylax seems to be the river of *Gulkiras*, which joins the *Tokatlou*, or Iris, about ten miles above Amasia, coming from the south-west. Gazioura was once a place of note, and a royal residence, but it was de-

^t This is probably the same district which Strabo elsewhere calls Bamonitis. XII. p. 553.

serted when Strabo wrote his description of the country. (loc. cit.) It is also noticed by Dio Cassius, as a place where Mithridates took up a position to oppose the Roman general Triarius. (XXXV. p. 5. Cf. Plin. VI.3.) Gaziura is said to retain the name of *Azurnis*^u.

Daximoni-tis regio. Daximonitis must be sought for in the upper valley of the Iris, near the modern town of *Tokat*. The

Zela. town of Zela and its territory, was situated on the left bank of the Iris, towards the frontier of Galatia: (Strab. XII. p. 561.) it appears to have been a place of great antiquity, since Strabo reports that it was erected on the mound of Semiramis. It was at first apparently a spot consecrated to the worship of the goddess Anaïtis, a deity highly revered by the Persians, Armenians, and Cappadocians. (XII. p. 559.) The same writer elsewhere relates, that the temple of Zela had been raised by the Persians in commemoration of a signal victory obtained by their arms over the Sacæ, who had penetrated into Pontus and Cappadocia. They raised a mound on a rocky foundation, and having surrounded it with walls, erected two temples, one to the goddess Anaïtis, the other to the Persian deities Omanus and Anandates: a festival, named Sacæa, was likewise instituted to commemorate the same event. The priest of the temple was considered as sovereign of the district of Zela; he was possessed of great wealth, and was surrounded with much pomp and state. (XI. p. 511, 512. XII. p. 559.) Zela remained however a small town, till Pompey, after the defeat of Mithridates, increased its population and extent, and raised it to the rank of a city. (XII. p. 560.)

^u Sestini, p. 69, who ascribes to it some scarce coins with the epigraph ΓΑΖΙΩΤΡΩΝ.

Zela is further rendered remarkable in history, by a victory obtained over the Roman forces under Triarius, by Mithridates, and still more by the defeat and discomfiture of Pharnaces, son of the latter, which Cæsar expressed in the laconic sentence—"Veni, "Vidi, Vici." (Plin. VI. 3. Appian. Mithr. c. 89. Plut. Cæs. p. 731. Hist. Bell. Alex. c. 72. Dio Cass. XLII. p. 207.) This town is noticed also by Ptolemy, (p. 125.) Hierocles, (p. 701.) and Steph. Byz. (v. Ζῆλα.) We learn from the Itineraries, that Zela stood on the road leading from Tavium, in Galatia, to Neocaesarea. The name of *Zeleh* sufficiently marks the site about thirty miles to the south-west of *Tokat*.

The town of Comana, (surnamed Pontica, to distinguish it from a Cappadocian city of the same name,) was apparently situated to the north-east of Zela, and not far from the source of the Iris. (Strab. XII. p. 547.) It was celebrated for the worship of the goddess Ma, supposed to answer to the Bellona of the Greeks, and likewise revered with equal honours in the Cappadocian town. The priesthood attached to the temple was an office of the highest emolument and dignity, and was sought after by kings and princes. Strabo mentions that it had been conferred on Dorylaus, one of his maternal ancestors, by Mithridates Eupator; afterwards Pompey bestowed it on Archelaus, and added to the sacred territory a district of sixty stadia. Archelaus was succeeded by Lycomedes, but he having been deposed, the priesthood was bestowed on Cleon, the Olympian robber, who founded Juliopolis, (XII. p. 575.) but he died soon after his appointment, and Augustus then conferred it on Dyteutus, son of

Adiatorix, a Galatian chief, whom he had put to death for having zealously espoused the cause of Antony. Dyteutus, his eldest son, was to have been executed with him, but he was saved by the generous devotion of his younger brother, who perished in his stead. Augustus, on learning too late this heroic trait, restored Dyteutus to his favour, and gave him the priesthood of Comana. This city was large and populous, and kept up a considerable traffick with Armenia. The festivals of Bellona, which were held twice a year, drew thither an immense concourse from the surrounding countries and towns, as well as more distant parts. There were no less than 6000 slaves attached to the service of the temple, and most of these were courtesans. Hence it was remarked that the citizens were generally addicted to pleasure, and the town itself was styled by some, the little Corinth. The chief produce of the country was wine. (Strab. XII. p. 559. Cf. Appian. Mithr. c. 82. Hist. Bell. Alex. c. 34, 35.) When the Romans, under Lucullus, invaded Pontus, a report was spread, probably by Mithridates, that they were come for the express purpose of plundering the shrine of Comana. (Cic. Leg. Manil. §. 9.) In Pliny's time the town appears to have fallen into decay, the oracle alone subsisted; since he says, "Comana nunc Manteium." (VI. 3. Ptol. p. 125.) The Table Itinerary places Comana of Pontus on a road leading from Tavium in Galatia, and which appears to be partly the same as that from Tavium to Zela, but the names of some stations are omitted, and others are very corrupt, so that it is difficult to decide any thing on this point. We know, however, from Strabo, that Comana was seated in the upper

valley of the Iris, and some remains which exist not far from *Tokat*, under the name of *Komanak*, sufficiently point out the ancient site^x.

The Lycus, which has been already mentioned as *Lycus flu-*
joining the Iris below Amasia, is a considerable river, now called Carahissar. It rises on the eastern border of Pontus, in the high mountains to the south of *Ghemizkhan*, which belong to the chain of Parryadres and Scydisces. Pliny informs us that the Lycus separated Pontus from Armenia Minor, near the town of Neocæsarea, now *Niksar*. Below that town it traversed the rich and fertile district of Phanarœa, accounted the most productive of Pontus, and joined the Iris in the plains between Amasia and Themiscyra. Precisely at the confluence of these two rivers, Mithridates had founded a town named Eupatoria, which was not yet completed, when he was forced to fly from Pontus by the Roman armies. Pompey, after the conquest of the country, completed the town, added to its territory, and called it after himself, Magnopolis. (Strab. XII. p. 556.) Appian says, Eupatoria was near Amisus, and that it was besieged by Lucullus; (Mithr. c. 78.) he also speaks of its second foundation by Pompey, under the name of Magnopolis. (c. 115.) Strabo has elsewhere bestowed on this town the appellation of Megalopolis, (XII. p. 560.) and Mannert has been led by that circumstance, to suppose these were two distinct places^y; but this is very improbable, when we consider that the geographer places them together

Eupatoria
postea
Magnopo-
lis.

^x There are some few autonomous and imperial coins belonging to Comana. The legend is KOMANΩN and KOMA-

NEΩN. Sestini, p. 59.

^y Geogr. tom. VI. p. ii. p. 480.

in the vicinity of Zela and Comana, and assigns both to Pythodoris, widow of Polemon, and queen of Pontus. (XII. p. 559, 560. Cf. Plin. VI. 3.) The vestiges of Magnopolis are to be seen near *Tchenikeh*, a little below the junction of the Iris and Lycus^z.

Phanarœa regio.

Pythodoris, besides the above-mentioned towns and territories, possessed the whole of Phanarœa, which Strabo describes as a broad and extensive valley, watered by the Iris and Lycus, and confined between the chain of Paryadres to the east, and mounts Lithrus and Ophlimus to the west. The soil was the best in Pontus, and yielded excellent wine and oil, and other produce in abundance. (XII. p. 556.) This tract of country now takes its name from the modern town of *Niksar*. The mountains Lithrus and Ophlimus are unknown to other geographers. I should imagine, from Strabo's account, that they must be sought for on the right bank of the Iris, in the neighbourhood of *Tokat*. The same writer places, apparently in the Phanarœa, 150 stadia to the south of Magnopolis, and at the foot of Paryadres, the town of Cabira, which had once been the favourite residence of Mithridates. His palace, and park, and preserves were still in existence when Strabo wrote, as well as a water-mill, (*ὑδραλέτης*), erected by him, probably for the use of the mines which were in this vicinity. (XII. p. 556.) It was here that Mithridates posted himself with his army in the campaign which followed the disastrous retreat from Cyzicus, in order that he might afford succours to the neighbouring towns of Amisus and

Lithrus et
Ophlimus
montes.

Cabira.

^z Note of Monsieur Gosselin. French Strabo, tom. IV. p. ii. p. 69.

Eupatoria, besieged by Lucullus. (Appian. Mithr. c. 78.) On his second defeat, however, it fell into the hands of that general, with several other places. (Plut. Lucull. p. 502. Eutrop. VI. 7.) Pompey afterwards enlarged the place, and changed its name to Diopolis. Pythodoris subsequently made further improvements in this town, and having finally fixed her residence there, bestowed on it the appellation of Sebaste. (Strab. loc. cit.) Sebaste, or Sebastia, is mentioned also by Pliny and the Itineraries, but there is also a Sebastopolis in this part of Asia Minor, which causes some difficulty in regard to the site of Cabira. The Antonine Itinerary places both on a route leading from Tavium, through Pontus, into Armenia; the stations are from Tavium to

	M. P.
Mogaron	XXX.
Doranon	XXIII.
Sebastopolis	XL.
Virisa	XXIII.
Phiarasi	XII.
Sebastia	XXXVI.

from which it appears that Sebastia was seventy-two Roman miles from Sebastopolis. Pliny, however, in his usual hurried manner, collocates them in the district of Colopene: “In Colopena vero Sebastiam “ et Sebastopolim; hæc parva, sed paria supra dictis.” (VII. 3.) The Table Itinerary places Sebastia on a route leading from Cæsarea in Cappadocia, into Armenia; and there can be little doubt that the direction of this road, leading up the Halys to *Siwas*, points out, together with the strong analogy of the name, that site as the representative of Sebastia. But was this Sebastia the Cabira of Mithridates, and the Se-

baste of Pythodoris? I conceive not. For in the first place, *Siwas* is at least 120 miles from the site of Magnopolis, whereas, according to Strabo, Cabira was only 150 stadia from that town. Nor, in the second place, would so distant a place have answered Mithridates' purpose of relieving the towns near the coast, besieged by Lucullus. Again, Sebastia is spoken of in the Martyrologium as a town of Armenia, which agrees rather with the position of *Siwas*, than that which, from the Itineraries, ought to belong to Sebastopolis; that town, according to these documents, being seventy miles nearer Tavium. Ptolemy also places Sebastopolis to the southwest of Neocæsarea, which is known to be *Niksar*, and near the Iris. Sebastopolis, and not Sebastia, or *Siwas*, was therefore the successor of Cabira, and the capital of Pythodoris, who would of course fix her residence in the Phanarœa, the best part of her principality, and also the most central. Gregory of Nyssa, in his Life of Saint Macrina, quoted by Wesselink, (Itin. Anton. p. 205.) speaks of Sebastopolis as a small town of Pontus; and this was already the case in Pliny's time, Neocæsarea having doubtless attracted many of the neighbouring inhabitants to resort thither under the auspices of the Roman emperor, who had taken the new city under his protection. But it is impossible to admit, with Mannert^z, that Cabira, or Sebaste, and Neocæsarea, are one and the same town, since Pliny and the Itineraries, together with other authorities, forbid our entertaining such a supposition. It appears then, that we should look for the ruins of Cabira, or Sebastopolis, on the right bank of the Lycus, and between

^z Geogr. tom. VI. p. ii. p. 473.

Niksar and *Tchenikeh*, or Magnopolis. Some antiquaries place it at *Turkal*, to the north of *Tokat*, but^a this site is on the Iris, a circumstance which would not have been omitted by Strabo, if it had belonged to the topography of Cabira, or the river^b.

At a distance of somewhat less than 200 stadia from Cabira, stood once the fortress of Cænonchorion, one of the strongest holds of Mithridates. It had been erected, as Strabo reports, on a precipitous rock, which rose to a very great elevation; a situation which rendered it impregnable. A plentiful source gushed out from the rock near the summit, and a river flowed in a deep valley at the foot of the fortress. The surrounding country was thickly covered with wood, and so hilly and barren, that, from want of subsistence, no army could encamp nearer than 120 stadia. When Pompey took possession of this castle, after the defeat and flight of Mithridates, he found there all the most precious jewels and other articles belonging to that monarch, together with his secret correspondence and papers. Pompey caused all these valuable curiosities to be removed to Rome, and deposited them after his triumph in the Capitol. (Strab. XII. p. 556. Plut. Pomp. §. 36, 37.) Appian does not speak of Cænonchorion, but says Mithridates kept his most precious effects in the town of Talauri, where Pompey found them^c. The historian enumerates in particular

^a Marginal note of the edit. of the French Strabo, tom. IV. p. ii. p. 61.

^b There are some few autonomous coins of Cabira, with the epigraph ΚΑΒΗΡΩΝ. Sestini, p. 59; and some also of Sebastopolis struck under Antoni-

nus Pius, ΣΕΒΑСΤΟΠΟΛΙΤΩΝ. Sestini, p. 60.

^c As no historian or geographer speaks of this place, I should imagine the name is corrupt, and for ἡ Ταλαύροις, I would propose reading ἡ Γαζιούροις or ἡ Καβείροις.

“ 2000 goblets of onyx stone, set in gold; many
 “ cups also, and wine-coolers, chalices, couches, and
 “ richly ornamented seats; likewise bridles and
 “ trappings; all equally adorned with jewels and
 “ goldwork. Some of these costly articles had be-
 “ longed to Darius Hystaspes, others had come from
 “ the court of the Ptolemies, having been presented
 “ to the people of Cos by Cleopatra, and by them to
 “ Mithridates. But the greater number had been
 “ collected by that monarch, who was fond of what
 “ was ornamental and splendid.” (Mithr. c. 115.)

Cænonchorion must be sought for in the mountainous district, to the north of *Niksar*, and on the right bank of the Lycus. The whole of this country, as we have already learned from Strabo, belonged in his time to Pythodoris. She held besides the temple of Men Pharnaces, who was supposed to be the deity of the moon, and was worshipped by the Phrygians, Pisidians, and Albanians^d. This edifice was held in the greatest veneration by the kings of Pontus, and the most solemn oath which they pronounced was, “ By the Fortune of the King and Men Pharnaces!” It was situated in or near Ameria. a place named Ameria; Strabo styles it *κωμόπολιν*, or a village which might almost be called a town; and from the number of dependents attached to the temple, and the ample revenues annexed to the pontifical office, it must have had a considerable population; so that it is somewhat surprising that no mention is made of this place in any other writer.

^d The worship of the god Men appears to have its principal seat in Asia Minor; but it was doubtless introduced by the Phœnicians, or Assyrians.

Isaiah seems to allude to it under the name of Meni. LXV. 11. Cf. Biel. Nov. Thes. Phil. tom. III. p. 479.

(XII. p. 557.) If however, as I am inclined to think, Ameria is to be identified with Neocæsarea, ^{Neocæsa-}
 rea. which must have been in the immediate vicinity, this silence of all subsequent writers to Strabo respecting the former, is readily accounted for. Now we have nowhere any positive information of the foundation of Neocæsarea; but we are pretty certain on the one hand, that it did not exist in Strabo's time, or he would have noticed it; and on the other, we know that it existed less than a century after, since it is named by Pliny. But the coins of Neocæsarea enable us to fix the æra of its foundation with still greater precision. The earliest we have, bear the effigy of Tiberius, and were doubtless struck in his reign. It is therefore highly probable, that Neocæsarea was founded, or received a new name and existence in the time of that emperor, and after Strabo had composed his work^e. Its rise and progress must have been very rapid, since in the time of Gregory Thaumaturgus, who was a native of the place, it is stated to have been the most considerable town of Pontus^f, and he flourished in the middle of the third century. (Greg. Neoc. Vit. p. 577. Cf. Ammian. Marc. XXVII.) It appears also from the Life of the same saint, that Neocæsarea was the principal seat of pagan idolatry and superstitions, which affords another presumption that it had risen on the foundation of Ameria and the worship of Men Pharnaces. We know from Pliny that

^e Sestini mentions one earlier coin, which he calls "au-
 "tonomus unicus." Epigraphe
NEOKAIΣAPEΙΑΣ. But there is
 a great reason for doubting its
 authenticity; for how could a

town be autonomous in the time
 of the Cæsars?

^f On the coins of Valerian
 we find it styled the metropolis
 of the province. Sest. p. 60.

Neocæsarea was situated near the Lycus, and frequent mention of that river is made in the Life of Gregory. The Itineraries and ecclesiastical writers also often name the town. From Steph. Byz., who quotes Phlegon Trallianus, it would seem that it was once called by the name of Hadrianopolis. (v. Νεοκαισάρεια.) *Niksar*, the modern representative of Neocæsarea, is a town of some size, and the capital of a district of the same name in the pashalick of *Siwas*, or *Roum*.

Beyond Neocæsarea, the upper valley of the Lycus constituted a separate district from Phanarœa, Colopene. known to the ancients by the name of Colopene, or Couloupene. Strabo places this small canton in Pontus, but on the borders of Armenia Minor. (XII. p. 560.) Pliny likewise speaks of it as a portion of Pontus Cappadocius; and since he states that the Lycus, to the east of Neocæsarea, separated that province from Armenia Minor, it is plain that Colopene must have been situated on the right or northern bank of the river. On the other hand, by including in this district the towns of Sebastopolis and Sebastia, the latter of which is certainly *Siwas*, it would seem that he gives to it a much greater extent than Strabo contemplated. (Plin. VI. 3.) The name was probably derived from a place called Colope, or Coulope, but not recorded by any geographer. Some vestige of this appellation, however, exists in that of *Koulei hissar*, which is at once the name of a small town on the right bank of the Lycus, and of the adjacent country.

Sebastia. The origin of Sebastia, which Pliny places in Colopene, is uncertain. **Camisene regio.** Camisene, another district near it, we know took its name from Camisa, an

ancient fortress, according to Strabo, near which were some salt mines; and the Itinerary of Antoninus informs us, that it was twenty-four miles beyond Sebastia, on the road to Nicopolis. Strabo besides has elsewhere reported, that the Halys had its source in the district of Camisene, on the borders of Pontus and Cappadocia; (XII. p. 546.) and as we know, from the report of modern travellers, that the *Kizil-Ermak* rises some miles to the east of *Siwas*, we can have no doubt as to the situation of Camisa and its territory. With respect to Caranitis, another small district of Pontus, Strabo says it had belonged to Ateporix, a Galatian prince; but on his death it devolved to the Roman empire, and was kept under the jurisdiction of a separate governor from the other petty principalities of Pontus. (XII. p. 560.) Carana, the capital of this small government, is mentioned by no writer subsequent to Strabo; I think it therefore extremely probable, that it afterwards changed its name to Sebastia, the latter being unknown to that geographer, but known to Pliny. The latter however, it must be allowed, speaks of Caranitis as a *præfectura* of Armenia Major, in which the Euphrates had its source; (V. 24.) and this would carry us as far to the east as *Erzroum*; but Strabo's statement allows us at the most to include it within the boundaries of the Lesser Armenia; and it is observable, that Sebastia is often attributed to the latter province by the ecclesiastical writers. The identity of Sebastia with the modern *Siwas* is fully established by the resemblance of names, and still more by the agreement of the latter site with the description of Gregory of Nyssa. That father states Sebastia to have been situated in the

valley of the Halys. A small river flowed through the town, and fell into a neighbouring lake, which communicated with the Halys. (Orat. I. in 40 Martyr. p. 501. Orat. II. p. 510. Cf. Basil. M. Epist. VIII. Hierocl. Synecd. p. 703.) Under the Byzantine emperors, Sebastia is spoken of as a large and flourishing town of Cappadocia. (Nicet. Ann. p. 76, C. Cf. Duc. p. 31.) Steph. Byz. assigned it to Armenia. (v. Σεβαστή. Cf. Sozom. Hist. Eccl. IV. 24. Theodor. Hist. Eccl. II. 24.) Other documents style it the metropolitan see of Armenia Prima^g. In the Table Itinerary the name appears already corrupted to that of Sevastia, and in Abulfeda it is actually *Siwas*. (Tab. XVII. p. 303.) This town is still large and populous, and the capital of an extensive pashalick, to which it gives its name. A modern traveller noticed there the remains of a citadel, but which appeared to him to belong to the Byzantine empire; some fragments of columns, and several coins, but no inscriptions. He adds, that it is entirely built in the plain; from which circumstance he justly doubts whether it can be the representative of Cabira. Some extensive ruins were reported to exist about six leagues to the south of *Siwas*, which he conceives might be referred to Sebaste; but the Itineraries will not allow us to admit this hypothesis^h.

Between Sebastopolis and Sebastia the Antonine Itinerary places two stations, Virisa and Phiarasi. The former is supposed, with great probability, by Wesseling to be Berissa, an episcopal see of Arme-

Berissa,
forsan quæ

^g Geogr. Sacr. Car. S. Paul. p. 255.

^h Fontanier, Voyages en Ori-

ent, p. 179. This gentleman constantly misquotes Xenophon for Strabo. p. 149.

nia Prima, according to the Ecclesiastical Notices^{i.} et Boryza
(Itin. Ant. p. 205. not.) We ought perhaps also to et Borissus.
identify it with the Boryza of Steph. Byz., (v. Βό-
ρυζα,) and Borissus, a small town of Cappadocia 2da,
mentioned by Philostorgius. (Hist. Eccl. IX. p. 529.)
This place, according to the above-mentioned Itine-
rary, was twenty-four miles from Sebastopolis. Phi-
rasi was thirty-six miles nearer Sebastia, or *Siwas*.
Wesseling, with equal judgment, traces this station
to the Phiara of Ptolemy. (p. 126.) The latter geo- Phiara.
grapher names several other obscure sites, of which
a few only can be made to agree with other authori-
ties. In Pontus Galaticus he places Bænasa, Te-
benda, Choloe, Piala, Pida, Sermuta. Tebenda, or Tebenda,
Tebenna, as Anna Comnena writes the name, is ^{sive Te-}
stated to have been a town of Pontus, in the vici-
inity of Trapezus. (p. 364, B.) I imagine also, that
the name of this place is disguised in the Table Iti-
nerary under that of Tomba, a station on the road
from Tavium to Comana, and sixteen miles from
the former. The same Itinerary exhibits the three
next towns named by Ptolemy, on the road from
Amasia to Neocæsarea, in the following order : Pa-
lalce, (Piala^k,) fifteen miles from Amasia ; Coloe, Piala.
twelve from Palalce ; Pida, (Pidis in the Table,) ^{Coloe.} Pida.
ten from Coloe. Sermuta, or, as it should probably
be written, Seramus, appears in the same Itinerary Seramus.
on a road leading from Tavium to Neocæsarea by
Zela, fifty-four miles from the last-mentioned town,
and sixteen from Neocæsarea. There is, however,

ⁱ Geogr. Sacr. Car. S. Paul. p. 256.

^k Palalce is a corruption of Pialasus, as Phiarasi of Phiara-

sus. The Cappadocian and Ar-
menian names of places very
generally end in sus.

*Ægonea,
vel Eugonea.*

another Sermusa in the Table, between Tavium and Cæsarea in Cappadocia. Itonia, which Ptolemy places between Chloœ and Piala, is probably the same town with the *Ægonne*, or *Eugone*, of the Table; in which case we should correct the former by the Itinerary. But, *vice versa*, the station which the latter places on the same road from Tavium to Neocæsarea, by Zela, immediately after *Ægonea*, under the corrupt name of *Pterami*, must be restored by the help of the Alexandrine geographer, who writes it *Pleumaris*. In the interior of Pontus Polemoniacus, Ptolemy has a great many obscure names, of which the following seem confirmed by other authorities. (p. 126.) *Gazalina* is probably the *Gazacena*, or *Gazelonitis*, of Strabo. (XII. p. 553.) *Carvanis* should be referred to the *Carana* of the same geographer. (XII. p. 560.) *Sarbanissa* is known from its coins to have been once dependent on Sinope¹. *Danaë*, or *Danati*, seems to have some affinity with the *Daranon* of Antonine. (Itin. p. 205.) *Metorome*, or *Mesorome*, answers probably to the *Rogmon* of the Table, on the road from Tavium to Neocæsarea, by Zela. *Metadula*, or *Megaluda*, I am inclined to refer to the *Mesyla* of the same Itinerary, on the road from Tavium to Comana Pontica. *Sabalia* seems to correspond with the station *ad Stabulum*, on the same route. *Metalassus*, or *Megalossus*, should perhaps be connected with *Mogaron*, a station in the Antonine Itinerary, on the road from Tavium to *Sebastopolis*, (p. 205.) and which Wesseling, with great probability, identifies with

¹ On one side is the head of king Polemo; on the reverse a figure of Fortune, with the legend ΣΑΡΒΑΝΙΣΣΕΩΝ ΤΩΝ ΣΙΝΩ. Sestini, p. 60.

Mogarissus, a village of Cappadocia, mentioned in the Life of St. Theodosius Abbas. (c. 1.) Eudiphus, Ablata, and Saurania, are not recognised by other authorities, unless the former name should be read Euliphus; in which case it may be identified with Eulepa, a station placed by the Antonine Itinerary on the road from Cæsarea to Satala. (p. 206.) In the interior of Pontus Cappadocius, Ptolemy places, in addition to certain sites which have been already noticed in the description of the sea-coast, Aza, Asiba, Mardara, and Camuresarbum. Asiba is also known from its coins^m. Mardara is evidently the Marandara of the Antonine Itinerary, between Cæsarea and Sebastia. (p. 206.) Camuresarbum I should imagine to be corrupt, and we ought perhaps to read Camisa, Zara, as in the Itinerary just referred to. (p. 207.) I should here present the reader with a list of the several roads which traversed Pontus in various directions, but I have thought it better to defer this part of our inquiry till we could connect it with the topography of Galatia, on which it materially depends. I shall conclude this section with a list of names of places and tribes classed under the head of Pontus by Stephanus Byz. Abrinatæ, a people. (v. Ἀβρινάται.) Aratzus, a town. (v. Ἀραζός.) Arbanium, a town apparently on the coast. (v. Ἀρβάνιον.) Diobulum, a small place near Pontus. (v. Διοβούλιον.) Thiba, a spot so called from an Amazon slain by Hercules. The inhabitants, called Thibii, were said to be enchanters, whose breath was poisonous, and eye malignantly fascinating. (v. Θίβαι.) Other authors,

^m Sestini, p. 59. Imperatorius unicus Gordiani. Epigraphe ACIBAIΩΝ.

who have mentioned the Thibii, asserted that they could not perish by water, but would float on the surface. (Plut. Symp. V. 7. Phylarch. ap. Plin. VII. 2.) Creme, a town mentioned by Phlegon. (v. Κρέμη.) Crossa, noticed by Hecatæus. (v. Κρόσσα.) Mares, a people near the Mossynœci. (v. Μάρες.) They are also named by Herodotus in conjunction with that people; (III. 94.) and elsewhere he states that they furnished a body of troops for the expedition of Xerxes. (VII. 79.) Patrasys, a town noticed by Hecatæus. (v. Πατρασύς.) Sonia. (v. Σιωνία.) Charimatæ, a people placed next to the Moschi and Cercetæi by Palæphatus and Hellanicus. (v. Χαριμάται.)

SECTION VI.

IONIA AND LYDIA.

General history of the Ionian colonies and their confederacy—
Description of the twelve states of Ionia and the adjacent islands—Origin of the Meonians and Lydians—Dynasties of Lydia—Boundaries and topography of that country.

THE beautiful country which received the name of Ionia from the Greek colonists who settled on its shores, had, previous to that event, been peopled by a race of barbarians, so often alluded to by the ancients under the indefinite appellations of Leleges and Carians. These, unable to resist their more powerful invaders, withdrew from the coast, and retired across the Maeander, to that portion of Asia Minor which, from the latter people, obtained the name of Caria. (Pherecyd. ap. Strab. XIV. p. 632. Herod. I. 146. Paus. Ach. 2.) The causes which led to the Ionian migration are well known. The chief of these, according to Thucydides, was the crowded state of Attica; a poor and barren country, unable to support the great influx of population which the disturbed state of Greece had drawn thither. The greatest number of these refugees were Ionians, who had been expelled from the Aegialus of Peloponnese by the Achaeans, and had retired to Attica, the mother country of the Ionian race. At this time a dissension arose between Medon and

Neleus, the descendants of Codrus, respecting the succession to the throne of Athens; and when the oracle of Delphi had decided in favour of the former, Neleus determined, in conjunction with the other sons of Codrus, to abandon Attica, and form settlements in Asia Minor, already colonized for many years by the Æolians. The Ionians gladly listened to the proposals made to them, of joining the expedition, and their numbers were soon swelled by a mixed multitude collected from almost every part of Greece. Herodotus names in particular the Abantes of Eubœa, who migrated in great numbers; the Minyæ of Orchomenus; the Cadmei, headed, as Pausanias reports, by Philotas, grandson of Peleus; (Ach. 2.) the Dryopes; a body of Phocians; some Molossians, Arcadians, and Dorians of Epidaurus; besides several other tribes. (Herod. I. 146. Cf. Pausan. loc. cit.) On the arrival of the emigrants on the coast of Asia, they proceeded to found several towns, under the conduct of different leaders. The followers of Androclus, the legitimate son of Codrus, colonized Ephesus, which, from that circumstance, was always denominated the royal city of Ionia. (Pherecyd. ap. Strab. XIV. p. 633.) Another party, under the command of Neleus, settled at Miletus, the foundation of which, however, was much more ancient. Cydrelus, a third son of Codrus^a, occupied Myus: Andropompus, Lebedos. Andraemon, likewise a descendant of Codrus, built Colophon. Priene was founded by Ægyptus, son of Neleus^b, in conjunction with Philotas, a Bœotian leader. Teos owed its first origin to Athamas; but,

^a Pausanias calls him Cyare-tus. Ach. 2.

^b He is named Ægyptus by Pausanias.

on the arrival of the Ionians, it was recolonized by Nauclus, a natural son of Codrus, together with Apœcus and Damasus of Athens, and Geres the Bœotian. Cnopus, another son of Codrus, was the founder of Erythræ. Philogenes, at the head of a body of Athenians, colonized Phocæa: Paralus^c, Clazomenæ. The island of Chios received different settlers, collected from various nations, under the command of Egertius, or Egertilus. Samos, finally, was occupied by two successive colonies, under Timbrion and Procles of Epidaurus. (Strab. loc. cit. Pausan. loc. cit.) These were the twelve states, which, not long after their foundation, united themselves into one political body, called the Ionian confederacy. Herodotus accounts for this particular number, from the circumstance of its having been previously adopted by the Ionians, when they occupied the northern coast of Peloponnese, under the name of Pelasgi Ægialees. He reports, that even at that early period they had formed a confederacy of twelve cities, and probably carried with them the same political system into Asia^d. (I. 146.) The Ionians then formed a federal body, whose solemn meetings and festivals were held in a temple called Panionium, dedicated to the Heliconian Neptune, and erected on the promontory of Mycale, opposite to Samos. But the government in each state or city appears to have been decidedly monarchical, and in many instances this subsequently degene-

^c Pausanias writes the name Parphorus, which sounds corrupt, and ought probably to be corrected from Strabo.

^d The Tyrrhenian Pelasgi appear to have introduced the same confederate form in Etruria.

rated into absolute power. Some of these Ionian princes, as Herodotus informs us, were descended from the Lycian Glaucus ; others claimed a Pylian origin through Codrus, the son of Melanthus, and some again could trace their pedigree to both sources. (I. 147.) The country occupied by these Grecian colonists surpassed, in the opinion of the same historian, all other lands in beauty and mildness of temperature. To this were added several other important local and physical advantages : great richness and fertility of soil ; large and abundant rivers intersecting wide and beautiful valleys ; spacious and commodious harbours, admirably calculated for commercial enterprise and connexion with every part of the Mediterranean sea. All these combined tended to render the Ionians a most opulent and flourishing people, and had their spirit and energy been equal to the means which nature had placed within their reach, they might have become the founders of a powerful empire ; but the softness of the climate, and the great facility afforded by so rich a country for procuring the necessaries of life, rendered them an indolent and voluptuous nation, so that they not only ceased to aspire to extend their power and influence by conquest, but were content to live in subjection, first to the effeminate Lydians, and afterwards under the more powerful, but equally mild sway of the Persians. Some resistance, indeed, was offered by individual cities to the arms of both Crœsus and Cyrus, and rare instances of patriotic devotion and love of liberty, more especially in the case of the latter, were manifested by the citizens of Phocæa and Teos. But the general

conduct of the Ionians on that occasion, and their appeal to Sparta, proves them as a nation to have been weak and contemptible. (Herod. I. 152.)

A more determined and noble effort to recover their liberty and independence was made by the Ionians in the revolt against the Persians, to which they were instigated by Histiaeus and Aristagoras. But though quickly roused, their zeal and ardour in the cause of freedom was not equal to endure an arduous and protracted conflict against so formidable a power as that of Persia. The capture and burning of Sardis was but a short-lived triumph, followed by some signal defeats which broke the courage of the revolters, and speedily exhausted their means of resistance by land. (Herod. V. 99—124.) The contest was still, however, carried on by sea, and with some hopes of success, since the Persians were not equally formidable on that element. But here again the national indolence, together with disunion, and the treachery of some of their princes, paralysed the efforts of the brave and well-intentioned, and speedily terminated the struggle in favour of the Persian monarch. (Herod. VI. 7—22.) After the glorious victory achieved by the Greeks, Ionia for a time regained her freedom; but the respite was of short duration, and the battle of Mycale seemed only to have caused a change from one state of subjection to another, and to have merely transferred the wealth of the country from the royal treasury at Susa, to that of the Acropolis at Athens. (Thuc. I. 95.) During the greater part of the Peloponnesian war, the latter power drew considerable resources from the tribute imposed on the Ionians, and the fear of losing so rich a portion of

their dominions induced the Athenians to make the greatest efforts, after their overthrow in Sicily, to preserve it from the united attacks of Sparta and the Persian Tissaphernes. Destined to be the prize of one or the other of the belligerent parties, the Ionians remained, except in the affair of Miletus, (Thuc. VIII. 25.) passive spectators of the contest. They were sure to pay contributions, and they cared but little whether it was enforced by the Athenian galleys, the Spartan harmosts, or the Persian satrap. Agesilaus, indeed, during the war he carried on in Asia against Pharnabazus, succeeded in exciting among the Ionians a warlike spirit, and a degree of enthusiasm, of which the nation hitherto had exhibited so little indication. (Xen. Hell. III. 4.) But on the departure of that great prince, the excitement died away, and the disgraceful treaty of Antalcidas resigned the Ionians once more to their wonted condition of slaves to the Persian monarch. (V. 1, 28.) Unworthy of liberty, they beheld with indifference the exploits of Alexander, and the subsequent contentions of his captains. The victory of Magnesia wrested them from the feeble sway of Antiochus, and gave them to the Romans ; but if we may judge from the readiness with which they obeyed the mandate of Mithridates to massacre his enemies, they had less reason to be satisfied with the prætorial or proconsular administration than that of the lieutenant of Persia or Syria. But if the political and moral history of the Ionian colonies offers but little on which the admirer of national virtue and the lover of liberty may wish to dwell, this defect is in part redeemed and supplied by interest of another kind. If Ionia is inferior to its mother coun-

try in the patriotism, moral feeling, and energy of its inhabitants, yet in the arts and sciences, in the polish and refinement of life, it equals all that we are accustomed to admire in Grecian genius, elegance and purity of taste. Æolis and Ionia were the nurses of Grecian poetry and literature of almost every kind, if we except the drama. Ionia exclusively led the way to those contemplations and studies which were subsequently improved by the philosophers of Greece. She had schools also of painting and sculpture, and in grandeur of design and beauty of proportions her temples were accounted, by no incompetent judge in this branch of architecture, to have surpassed those of the mother, or any other country. (Pausan. Ach. 5.) In navigation also and commercial enterprise we find the names of Samos, Phocæa, and Miletus, already famous, when scarcely any city of the parent state, with the exception perhaps of Corinth, possessed vessels of burden calculated for a distant voyage. Whatever Ionia therefore had originally received from Greece, just emerging from barbarism, she improved in a tenfold degree; through her channel the arts and language of the mother state attained to a state of cultivation and polish hitherto unknown, and were disseminated and established in distant countries, cut off apparently from civilized society and the means of intercourse^e.

The length of coast occupied by the Ionian settlements is estimated by Strabo at 3430 stadia, including all the sinuosities of the different bays by

^e This is remarkably the case with respect to Marseilles, founded by the Phocæans, and the Milesian colonies on the Borysthenes.

which it is indented. The distance by land in a straight line is much smaller. The two extreme points between which it lies, are, to the north, the cape, near which stood the city of Phocæa, close to the mouth of the river Hermus, and between it and the bay of Cyme; to the south, the promontory of Posidium in the Milesian territory, and on the left bank of the Mæander. (Strab. XIV. p. 632.) The extent of territory possessed by the Ionian states on the land side was narrowly circumscribed by a chain of mountains extending from the Herinus to the Caystrus. This ridge, known to the ancients under the celebrated names of Sipylus and Tmolus, formed the natural separation between them and the plains of Lydia. Beyond the Caystrus another mountain, named Messogis, ranged along the remainder of the Ionian coast till it terminated in the promontory of Mycale: then follows the mouth of the Mæander and the territory of Miletus, circumscribed by that river, and the bay and mountain of Latmos. Phocæa, the most northern of the Ionian cities, was founded, as Pausanias reports, by some emigrants of Phocis under the guidance of two Athenian chiefs named Philogenes and Damon. The town was built, with the consent of the Cumæans, on part of their territory; nor was it included in the Ionian confederacy till its citizens had consented to place at the head of the government princes of the line of Codrus. Phocæa, from the excellence of its harbours, and the enterprising spirit of its inhabitants, soon obtained a distinguished name among the early maritime states of the world. Herodotus has given us some very interesting particulars on this head. He states that the Phocæans were the first Greeks

who undertook distant voyages, and made their countrymen acquainted with the Adriatic, and the coasts of Tyrrhenia and Spain. Tartessus, in the latter country, was the spot which they most frequented; and they so conciliated the favour of Arganthonius, sovereign of the country, that he sought to induce them to leave Ionia, and settle in his dominions. On their declining this offer he munificently presented them with a large sum of money, for the purpose of raising a strong line of fortifications round their city, a precaution which the growing power of the Median empire seemed to render necessary. The historian observes, that the liberality of this Iberian sovereign was attested by the circuit of the walls, which were several stadia in length, and by the size and solid construction of the stones employed. Phocæa was one of the first Ionian towns besieged by the army of Cyrus under the command of Harpagus. Having invested the place, he summoned the inhabitants to surrender, declaring that it would be a sufficient token of submission, if they would pull down one battlement of their wall, and consecrate one dwelling in the city. The Phocæans, aware that to comply with this demand was to forfeit their independence, but conscious also of their inability to resist the overwhelming power of Cyrus, determined to abandon their native soil, and seek their fortune in another clime. Having formed this resolution, and obtained from the Persian general a truce of one day, under the pretence of a wish to deliberate on his proposal, they launched their ships, and embarking with their wives and children, and their most valuable effects, sailed to Chios. On their arrival in that island

they sought to purchase the Ænussæ, a neighbouring group of islands belonging to the Chians; but as they refused to comply with their wishes, they resolved to sail for Corsica, where, twenty years prior to these events, they had founded a town named Alalia. On their way thither they touched at Phocæa, and having surprised the Persian garrison left there by Harpagus, put it to the sword. They then bound themselves by a solemn oath to continue the voyage on which they had determined: nevertheless one half of their number, overcome by the feelings which the sight of their native city recalled to their minds, could not be prevailed upon to forsake it a second time. The rest continued their voyage to Corsica, and were well received by their countrymen already settled in the island. During the five years in which they remained there, they rendered themselves formidable to the surrounding nations by their piracies and depredations, so that at length the Tuscans and Carthaginians united their forces to check these aggressions and destroy their power. The hostile fleets met in the Sardinian sea, and, after a most obstinate engagement, the Phocæans succeeded in beating off the enemy. They sustained however so great a loss in the conflict, and their ships were so crippled, that, despairing of being able to continue the contest against their powerful foes, they resolved to abandon Corsica and proceed to Rhegium in Italy. Soon after their arrival at that port, they were persuaded to settle at Velia, or Elæa, in Lucania, by a citizen of Posidonia. This new colony became in process of time a considerable and flourishing town. (Herod. I. 163—168.) It is remarkable that Herodotus, in this de-

tailed account of the settlements made at different times by the Phocæans, should have made no mention of the most important and celebrated of their foundations ; I mean Marseilles, which he only notices once, and that incidentally, and not as a Phocæan colony. (V. 9.) Thucydides, however, distinctly ascribes the origin of that city to the Phocæans, (I. 13.) as also Strabo, who enters very fully into the history of that event. (IV. p. 179—180. XIV. p. 647. Cf. Liv. V. 34. Athen. XIII. p. 576. A. Harpocr. et Steph. Byz. v. Μασσαλία.) I think it probable that Marseilles had been already founded by the Phocæans before they were forced to abandon Ionia by the Persians ; and that the Corsican settlement was but an off-set of the principal colony. Phocæa still continued to exist under the Persian dominion, but greatly reduced in its population and commerce. This is apparent from the fact of its having been able to contribute only three ships to the combined fleet of the revolted Ionians assembled at Lade. Dionysius, the commander of this small force, was evidently however a man of genius and courage, and if the confederates had followed implicitly his directions, affairs might have taken a very different turn. (VI. 11.) Herodotus relates that in the sea-fight, fought soon after, Dionysius took three ships of the enemy ; but finding that success was hopeless, he first of all sailed to Phœnicia, where he destroyed many merchant-vessels, and collected much valuable booty ; after which he retired to Sicily, and committed various acts of piracy on the ships of the Carthaginians and Tuscans. (VI. 17.) Little mention is made of Phocæa subsequent to these events ; (Thuc. VIII. 31.)

but some centuries later it is described by Livy as a town of some size and consequence, on occasion of its being besieged by a Roman naval force in the war against Antiochus. (XXXVII. 31.) “The town,” says the historian, “is placed in the inmost recess of a bay. Its shape is oblong, and the walls enclose a space of 2500 paces: they unite afterwards so as to form a narrower wedge. This they call ‘Lampter’^f, and it is about 1200 paces in breadth. A tongue of land, advancing out towards the sea for the space of 1000 paces, nearly divides the bay into two equal portions, and forms on either side of the narrow isthmus a very secure port. The one towards the south was called Naustathmus, from the circumstance of its being able to contain a great number of vessels. The other was situated close to the Lampter.” The town was taken by the Romans after an obstinate resistance, and given up to plunder, though the inhabitants had submitted, and voluntarily opened their gates: but the prætor was unable to restrain the fury and rapacity of his soldiers. The town, with its territory, was however restored to the inhabitants by that officer. (XXXVII. 32. Polyb. XXII. 27, 7. Cf. V. 77, 4. XXI. 4. Liv. XXXVIII. 39.) Subsequently the Phocæans incurred the anger of the Roman senate, from having espoused the cause of Aristonicus, who pretended to the throne of Pergamum: and they would have been severely punished, if the inhabitants of Marseilles had not strongly interceded in their behalf. (Justin. XXXVII. 1. XLIII. 3. Strab. XIV. p. 646.) We can trace the existence of Phocæa through the Cæsars by means of its

^f In Greek Λαμπτήρ, i. e. the light-house.

coins^g, and Pliny, (V. 31.) and even down to the latest period of the Byzantine empire, with the help of its annalists and the ecclesiastical writers. (Hierocl. Synecd. p. 661. Act. Concil. Eph. et Concil. Chalced.) We learn from Mich. Ducas, that a new town was built not far from the ancient site, which still retains the name of *Palæo-Phoggia*, by some Genoese, in the reign of Amurath, A. D. 1421. (Ann. p. 89.) This, as Chandler informs us, is situated on the isthmus, mentioned above in Livy's description^h.

A little to the south of Phocæa was a small town Leucæ. named Leucæ, (Scyl. Peripl. p. 37.) which Aristonicus, a descendant of the kings of Pergamum, occupied, in his attempt to recover the throne of his ancestors. He was however defeated, and put to death by the Romans; but Marcus Peperna, his conqueror, and Publius Crassus before him, both died at Leucæ. (Strab. XIV. p. 646. Tit. Liv. Epist. LIX. Justin. XXXVI. 4. Vell. Patrc. II. 4.) Leucæ, as we are informed by Diodorus,^j had in former times been a subject of contention between the Clazomenians and Cymæans, but it had been awarded to the former by the oracle of Delphi. It was at that time an island, and deserted, but Tachos, a Persian, who had revolted from Artaxerxes, built a town on it. (IV. 18. Cf. Plin. V. 31.) According to Chandler, it would seem to be now joined to the main land, "having a small mountain or hill "with a smooth top; and a long spit now runs from

^g Sestini mentions some gold staters, coined at Phocæa, without any epigraph. The imperial series reaches from Claudius to the Philips. The legends are

ΦΩ. ΦΩΚΑΙ. ΦΩΚΑΕΩΝ and ΦΩ-
ΚΑΙΕΩΝ, p. 83.

^h Travels in Asia Minor, p. 96. Le Brun, p. 166.

Hermus
fluvius.

“it out into the seaⁱ.” Near this are several rocks, which were anciently called Myrmeces. In Pliny’s time they stood at the mouth of the Hermus, but that river appears to have undergone great changes since then, and at present it discharges its waters into the sea much nearer Smyrna^k. The Hermus, according to Strabo, had its source in mount Dindymene, on the borders of Mysia; or, as Pliny reports, near Dorylæum in Phrygia. (V. 31.) It received the waters of the Pactolus, Hyllus, called also Phrygius, and other less celebrated streams, and discharged itself into the sea between Phocæa and Smyrna. (Strab. XIII. p. 626. Herod. I. 80. V. 101. Arrian. Exp. Alex. V. 5, 6.) The Hermus was reported to contain gold among its sand; a circumstance for which it was probably indebted to the Pactolus.

Sed neque Medorum silvæ, ditissima terra,
Nec pulcher Ganges, atque auro turbidus Hermus,
Laudibus Italiæ certent. GEORG. II. 136.

Servius thinks it was a figurative allusion to the fertility of its plains.

Vel quum sole novo densæ torrentur aristæ,
Aut Hermi campo, aut Lyciæ flaventibus arvis.
ÆN. VII. 720.

Homer applies to this river the epithet δινήεις; (Il. Υ. 392.)

“Τλλω ἐπ' ιχθυόεντι καὶ Ἐρμῷ δινήεντι.

and again, in the poet’s Life, ascribed to Herodotus. (c. 9.)

ⁱ Travels in Asia Minor, p. 95.

^k Chandler expatiates on the probable alterations which will in time be effected on this coast

by the Hermus; but his imagination seems to outstrip the course of time and the powers of the river, p. 96.

'Αμβρόσιον πίνοντες ὑδωρ θείου ποταμοῖο,
 'Ερμοῦ διηγέντος, ὃν ἀθάνατος τέκετο Ζεύς.

This fine river is known to the Turks by the name of *Sarabat*.

Smyrna, situated in a gulf which lies nearly east of the mouth of the Hermus, was said to derive its name from an Amazon so called, who, having conquered Ephesus, had in the first instance transmitted her appellation to that city. The Ephesians afterwards founded the town, to which it has ever since been appropriated; and Strabo, who dwells at length on this point, cites several poets, to prove that the name of Smyrna was once applied specifically to a spot near Ephesus, and afterwards generally to the whole of its precincts. The same writer affirms, that the Ephesian colonists were afterwards expelled from Smyrna by the Æolians; but being aided by the Colophonians, who had received them into their city, they once more returned to Smyrna, and retook it. He cites the following fragment of Mimnermus, in confirmation of this fact:

'Ημεῖς δ' αἰκὺν Πύλον Νηλήιον ἄστυ λιπόντες
 'Ιμερτὴν 'Ασίην νηυσὶν ἀφικόμεθα.
 'Ες δ' ἐρατὴν Κολοφῶνα βιὴν ὑπέροπλον ἔχοντες
 'Εξόμεθ' ἀργαλέης ὕβριος ἡγεμόνες.
 Κεῖθεν δ' 'Αστήεντος ἀπορνύμενοι ποταμοῖο
 Θεῶν βουλῇ, Σμυρνην εἴλομεν Αἰολιδα!¹

Herodotus differs from Strabo in some particulars: (ap. Strab. XIV. p. 634.) he states that Smyrna originally belonged to the Æolians, who received into

¹ I have given this passage according to Brunck, who has been followed by Prof. Gaisford. Poet. Min. vol. I. p. 424. The French translators of Strabo

have taken unwarrantable liberties with some of the lines in their version, tom. IV. p. ii. p. 271.

the city some Colophonian exiles. These afterwards, taking advantage of a festival held without the town, to which the Smyrnæans resorted in great numbers, shut the gates, and became masters of the place. From that time Smyrna ceased to be an Æolian city, but was received into the Ionian confederacy. (I. 150. Pausan. Ach. 5.) Of all the different cities which laid claim to the birth of Homer, Smyrna seems to assert her pretensions to that honour with the greatest zeal and plausibility; and if we are to credit the author of his Life, commonly supposed to be Herodotus, we can have no hesitation in adhering to the accounts which he has collected on this very interesting point of history, supported as they are by other traditions and testimonies of antiquity. The Smyrnæans, as we learn from Strabo, were so convinced that the great poet was their countryman, that they had erected and dedicated to him a temple containing his statue. This edifice was called Homerium, a name also given to a brass coin struck at Smyrna, in commemoration of the same event. (Strab. XIV. p. 646. Cic. pro Arch. c. 8.)

They also shewed a cave, where it was said that Homer composed his verses^m. (Pausan. Ach. 5.) It was objected, by those who sought to weaken the claims of Smyrna, that the poet had never once mentioned the name of that town, nor the river Meles which ran through it; but Strabo does not consider the objection to have any weight, (XII.

^m Chandler informs us that he had searched for this cavern, and succeeded in discovering it above the aqueduct of the Meles. It is about four feet wide, the roof of a huge rock, cracked

and slanting, the sides and bottom sandy. Beyond it is a passage cut, leading into a kind of well, &c. Travels in Asia Minor, p. 91.

p. 554.) and besides, as Smyrna was not in existence during the Trojan war, it could only have been alluded to by anticipation. The author of the Poet's Life introduces the following verses, said to be written by him, and which speak of Smyrna as his native city. (c. 14.)

ΟἽη μ' αἴσῃ δῶκε πατὴρ Ζεὺς κύρμα γενέσθαι
Νήπιον αἰδοίης ἐπὶ γούνασι μητρὸς ἀτάλλων,
“Ην ποτ' ἐπύργωσαν βουλῆ Διὸς αἰγιόχοιο
Λαοὶ Φρίκωνος, μάργων ἐπιβήτορες ἵππων,
‘Οπλότεροι μαλεροῖο πυρὸς χρίνοντες” Αρηα,
Αιολίδαι Σμύρνην ἀλιγείτονα ποτνιάνακτον
“Ην τε δι' ἀγλαὸν εἶσιν ὅδωρ ιεροῖο Μέλητος.

Smyrna was attacked by Gyges, king of Lydia, but resisted with success. (Herod. I. 14. Mimner. ap. Pausan. Bœot. 29.) It was compelled to yield however to his descendant Alyattes, and in consequence of this event it sunk into decay, and became deserted for the space of 400 years. (Herod. I. 16. Strab. XIV. p. 646.) Alexander is said to have formed the project of rebuilding the town, in consequence of a vision he had on mount Pagus, a hill above the river Meles. Whilst he slept near the temple of Nemesis, the goddess appeared to him, and ordered him to found a city for the Smyrnæans on the site where he then lay. (Pausan. Ach. 5.) The Macedonian king did not live to execute the design, but it was commenced by Antigonus, and finally completed by Lysimachus, in compliance with the oracle delivered by the Clarian Apollo.

Τρισμάχαρτες κεῖνοι καὶ τετράκις ἄνδρες ἔσονται,
Οἱ Πάγον οἰκήσουσι πέρην ιεροῖο Μέλητος.

(Paus. loc. cit. Strab. XIV. p. 646.) The new town was built at a distance of twenty stadia from the

ancient site, partly on the side of the hill, but chiefly in the plain, and extending to the sea-coast, on which stood the harbour, the temple of Cybele, and the gymnasium. The streets were remarkably handsome, well paved, and drawn at right angles. There were several fine square porticos, a public library, the temple of Homer, and other buildings, which rendered it one of the most beautiful cities of Ionia. (Strab. loc. cit.) In an inscription preserved amongst the Marmor. Oxon. it is styled πρώτη τῆς Ἀσίας κάλλει καὶ μεγέθει, καὶ λαμπροτάτη, καὶ μητρόπολις τῆς Ἀσίαςⁿ. Cicero also speaks of it as one of the most flourishing towns of Asia. (pro L. Flacc. c. 30.) It had received various grants and privileges from the Roman senate, for the part it took in the wars with Antiochus and Mithridates. (Liv. XXXV. 42. XXXVII. 16, 54. XXXVIII. 39.) But it afterwards suffered much from the siege sustained by Trebonius, one of Cæsar's murderers, against Dolabella, who finally overcame him, and put him to death. (Strab. XIV. p. 646. Cic. Phil. XI. 2. Liv. Epit. CXIX. Dio Cass. XLVII. 29.) In the reign of Tiberius, eleven cities of Asia pleaded before the senate for the honour of being allowed to erect a temple to the emperor: the chief contest lay between Sardes and Smyrna; but the merits of the latter city prevailed with the judges, and she obtained the disputed favour. (Tacit. Ann. III. 63. IV. 56.) It continued to flourish throughout the following reigns, (Plin. V. 31.) and its schools of eloquence and philosophy were in considerable repute. (Aristid. in Smyrn.)

ⁿ The epigraph on the coins of Caracalla and other emperors, is ΚΑΜΠΝΑΙΩΝ ΠΡΩΤΩΝ

ΑΙΑΚ ΚΑΛΛΕΙ ΚΑΙ ΜΕΓΕΘΕΙ.
Sestini, p. 84.

The Christian church flourished also, through the zeal and care of Polycarp, its first bishop, who is said to have suffered martyrdom in the stadium of the city, about 166 years after the birth of our Saviour. (Iren. III. 3, 4. p. 176.) There is also an epistle from Ignatius to the Smyrnaeans, and another addressed to Polycarp. Under the Greek emperors Smyrna experienced great vicissitudes. Having been occupied by Tzachas, a Turkish chief, towards the close of the eleventh century, it was nearly destroyed by a Greek fleet, commanded by John Ducas. It was, however, restored by the emperor Comnenus, but suffered again severely from a siege which it sustained against the forces of Tamerlane. Not long after, it fell into the hands of the Turks, and has remained ever since in their possession. It is now the great mart of the Levant trade. Chandler gives a detailed description of the ruins of this city. They consist “ of the old wall, of which many remnants may be discovered, of a solid, massive construction ; the stadium, stripped of its marble seats and decorations, between the western gate and the sea; a theatre on the side of a hill fronting the bay. The port which shut up reached to the foot of the castle-hill, is now dry. Beyond the deep valley in which the river Meles winds, behind the castle, are several portions of the wall of the pomærium, which encompassed the city at a distance, but broken. The ancient sepulchres were chiefly in the pomærium without the city. These ruins have supplied materials for the public edifices erected by the Turks. Many pedestals, statues, inscriptions, and medals have been, and are still discovered in digging. Perhaps no place

" has contributed more than Smyrna to enrich the collections and cabinets of the curious in Europe^o. " The Meles," according to the same traveller, " is a clear stream, shallow in summer, not covering the rocky bed, but winding in the deep valley behind the castle, and murmuring among the evergreens, approaches the gardens without the town, where it is branched out by small canals. In winter, after heavy rains on the mountains, or the melting of snow, it swells into a torrent rapid and deep, often not fordable, or with danger. Old Smyrna was about twenty stadia, or two miles and a half from the present city, and on the other side of the river. It is described as near the sea, with the clear stream of the Meles running by, and existed in the second century. Perhaps some vestiges might be discovered even now in tracing the river toward the bay. This is less wide than it was anciently, and has been removed from the site by a large accession of low land, formed of soil washed from the mountains near, or of mud and slime brought down by the torrents^p."

Smyrnæus, qui et Hermius sinus. We may remark that the bay in which Smyrna was situated, generally took its name from that city, but sometimes it was denominated Hermius, from the principal river which there united itself with the sea. (Hom. Vit. c. 2.)

Clazome-næ.

Clazomenæ, which follows next on the coast, did not exist prior to the Ionian migration; it was founded, as we learn from Pausanias, by a colony of Cleonæans and Phliasians, who abandoned the Peloponnese at the time of the Dorian invasion, and joined the Ionians. They at first settled on a site

^o Travels in Asia Minor, p. 76—79.

^p P. 87.

called Scyppium or Scyphia, (Steph. Byz. v. Σκυφία,) in the Colophonian territory, but afterwards removed further north to a spot named Chytrium, or Chytrum^q, (Arist. Polit. V. 2. Strab. XIV. p. 645.) under the conduct of Parphorus, or Paralus, a native of Colophon. (Paus. Ach. 3. Strab. loc. cit.) Herodotus reports, that Alyattes, king of Lydia, having attacked Clazomenæ, met with a determined resistance, and sustained finally a signal defeat. (I. 16.) On the conquest of Lydia by the Persians, the Clazomenians abandoned the original site of their town, and retired to a small island close to the land, where they built a new city. This measure was adopted from fear of the Persians. (Paus. loc. cit.) It was not till many years after, that the latter obtained possession of the island, and the town erected on it, under the conduct of the two satraps, Artaphernes and Otanes. This occurred at the commencement of the Ionian revolt. (Herod. V. 123.)

Xenophon, in the Hellenics, speaks of Clazomenæ as an island; (V. 1, 28.) but in Strabo's time it appears to have been connected with the mainland; (XIV. loc. cit.) and Pausanias leads us to infer that this was undertaken by Alexander the Great. (Ach. 3.) Thucydides relates that the Clazomenians, having revolted from Athens after the Sicilian disasters, were employed in founding a place called Polichna, on the continent, but the Athenians opposed the work, and finally reduced them under their power. (VIII. 14. 23.) After the defeat of Antiochus, Clazomenæ was declared independent by the Romans, and received the little island of Drymusa, situated

^q In Steph. Byz., who quotes Ephorus, it is probable we ought to read Χύτρον instead of Χυτόν.

in its vicinity. (Liv. XXXVIII. 39. Polyb. XXII. 27. 5.) It was taken by the Cilician pirates in the time of Scylla. (App. Mithr. c. 63.) Clazomenæ derives further celebrity from having given birth to Anaxagoras the philosopher, whose disciple Archelaus taught Socrates and Euripides. (Strab. loc. cit. Diog. Laert. II. 16.) It had a treasury at Delphi, in which the magnificent offerings of Crœsus were deposited. (Herod. I. 51.) The Clazomenians joined the Phocæans, and some other states, in forming the emporium of Naucratis, in Egypt, (II. 178.) and first attempted to colonize Abdera, in Thrace. (I. 168.) Their town retained its name and existence throughout the Roman and Greek empires, (Plin. V. 31. Ptol. p. 119. Hierocl. Synecd. p. 660.) but towards the middle of the eleventh century it was much infested by pirates, and finally sunk under the power of the Turks, and has never risen from its ruins. These are to be seen somewhat to the north-east of *Vourla*, on a site corresponding with the descriptions of ancient authors. Chandler, who visited these remains, saw considerable vestiges of the work ascribed to Alexander. "The mole," says that traveller, "was two stadia, or a quarter of a mile in length, but we were ten minutes in crossing it. The width, as we conjectured, was about thirty feet. On the west side, it is fronted with a thick, strong wall, some pieces appearing above the water. On the opposite is a mound of loose pebbles, shelving as a buttress, to withstand the furious assaults of storm and tempest. The upper works have been demolished. We computed the island to be about a mile long, and a quarter broad. The city was small, its port on the

“ N. N. W. side. Traces of the walls are found by “ the sea; and in a hill are vestiges of a theatre^r.” Close to Clazomenæ is a cluster of small islands, which Pliny names Pele, Drymusa, Anhydros, Scopelos, Sycussa, Marathussa, Psile, Perirrheusa. (V. 38.) Thucydides also notices Pele, Drymussa, and Marathusa, (VIII. 31.) and we have already quoted a passage from Livy, in which mention is made of Drymusa. (Cf. Steph. Byz. vv. Πήλη, Δρυμοῦσσα, Μαράθουσσα.) Chandler observes; “ By Clazomene is “ a cluster of islets, all once cultivated, now neg- “ lected and barren. Their number was eight, but “ I could only count six^s.” Lampsus, according to Ephorus, cited by Steph. Byz. was a portion of the Clazomenian territory. (v. Λάμψος.) Thucydides speaks of a spot called Daphnus, which seems to Daphnus. have been in the vicinity of Clazomenæ, and dependent on that city. (VIII. 23 and 31.) I should imagine that the temple of Apollo, mentioned by Strabo, must have stood here. (XIV. p. 646.) Pliny states that Daphnus no longer existed in his time. (V. 31.) The same site was celebrated on account of some warm springs, called the Agamemnonian baths, from the circumstance of their having proved beneficial to the Greeks who had been wounded in an engagement with the troops of Telephus. (Philostr. p. 664. Strab. loc. cit.) Chandler discovered several remains of the buildings near *Vourla*; he says, “ you descend by steps to the bath, which is “ under a modern vaulted roof, with vents in it for “ the steam; and adjoining to this is a like room, “ now disused. The current, which is soft and

^r Travels in Asia Minor, p. 107, 108

^s P. 109.

" limpid, is conveyed into a small round basin of
 " marble, and runs over into a large cistern or re-
 " servoir beneath. Our thermometer rose in the
 " vein to one hundred and fifty^{s.}"

Resuming our periplus of the Ionian coast from Clazomenæ, we have to point out a rugged promontory, which forms the north-west extremity of the little bay of *Tcharpan*, which represents Chytrium. This headland, now called *Esomeno*, is probably the Apocremnus, or Hypocremnus, of Strabo. (XIV. p. 645.) Beyond this, the coast advances still to the north, as far as cape Melæna, now *Kara-bouroun*, near which, according to Strabo, was a quarry, from which millstones were dug up. (XIV. p. 645.) After doubling this point, we proceed along the coast to the south, as far as the bay in which stood the ancient city of Erythræ. It will be seen, from the map, that the sea forms a considerable peninsula in this part of Ionia, the neck of which stands between Clazomenæ and the last mentioned town. A lofty ridge, known to the ancients by the name of Mimas, occupies the centre of the peninsula, and terminates in cape Melæna, its northern extremity. It is now called *Kara-vouno*. Mount Mimas is described by Strabo as elevated and woody, and well stocked with game. (XIV. p. 645.) Pliny asserts, that its chain occupied an extent of 250 miles through the interior of Asia Minor; he adds, that Alexander had conceived the project of cutting a passage through the isthmus of Erythræ, and also the mountain we are at present concerned with. (V. 31.) The poets make frequent allusions to mount Mimas.

Apocrem-
nus sive
Hypocrem-
nus pro-
montori-
um.

Mimas
mons.

**Η ύπεντρος Χίοιο, παρ' ἡντμόντα Μίμαντα.*

ODYSS. Γ. 172.

**Ιρις ἐπεὶ πάσησιν ἀφ' ὑψηλοῖο Μίμαντος
Σπερχομένη μάλα πολλὸν ἀπέτραπεν.*

CALLIM. H. IN DEL. 157.

. Cynthus et Othrys,
Et tandem Rhodope nivibus caritura, Mimasque.

. Ossaque cum Pindo. OVID. METAM. II. 221.

Mixtus Athos Tauro, Rhodopeque adjuncta Mimanti.
SIL. ITAL. II. 494.

(Cf. Thuc. V. 34. Ptol. p. 119.) Chandler, who crossed this mountain, represents “its shores as “covered with pines and shrubs, and garnished with “flowers. He passed many small pleasant spots, “well watered, and green with corn or with myrtles “and shrubs^t.” The view from the summit extends over the bays of Smyrna, Clazomenæ, and Erythræ, the islands of Samos and Chios, and several others.

Near cape Melæna was a small town, named Cy- Cybellia. bellia, or Cybelia. (Strab. XIV. p. 645. Steph. Byz. v. Κυβέλεια.) Thucydides points out a port called Phœnicus, on this coast, and under mount Mimas. Phœnicus (VIII. 34.) Livy also notices it in his account of the naval operations of the Romans and their allies against Antiochus. He states that it belonged to the Erythræans (XXXVI. 45. Steph. Byz. v. Φοιν- κοῦς.) It is now called *Egri-limen*. Erythræ, one of the twelve states of Ionia, (Herod. I. 142.) is said, by Pausanias, to have derived its name and origin from Erythrus, son of Rhadamanthus, at the head of a Cretan and Lycian colony; but it was subse-

^t Chandler's Travels, p. 113.

quently strengthened by a body of Ionian emigrants, led by Cnopus^u, son of Codrus. From the latter chief it was sometimes called Cnopopolis; (Steph. Byz. v. Ἐρυθρά. Polyæn. Strat. VIII.) but the original appellation always remained in use, and the other presently died away. (Strab. XIV. p. 633. Pausan. Ach. 3.) Athenæus quotes an interesting extract from Hippias of Erythræ, relating to the history of Cnopus. (VI. p. 259, 260.) Herodotus reports, that the Erythræans and Chians spoke the same dialect; (I. 142.) but, notwithstanding this apparent tie, they are stated to have been early engaged in hostilities against each other. (I. 18. Anticl. ap. Athen. IX. p. 384. D. E.) The latter were however greatly superior in naval power, since they had 100 ships engaged at Lade, whilst the Erythræans furnished only eight to the combined fleet. (VI. 8.) Erythræ revolted from Athens at the close of the Peloponnesian war. (Thuc. VIII. 14.) The Romans, on the conclusion of the war with king Antiochus, rewarded the citizens with grants of lands, and other marks of their approbation, for the zeal they had displayed in their service. (Liv. XXXVIII. 39. XXXVII. 11. 27. Polyb. XXII. 27, 6, XVI. 6, 5—8.) This city obtained further celebrity from the sibyl, who was said to have delivered prophecies there. Strabo distinguishes between the more ancient prophetess and another named Athenais, who flourished in the time of Alexander. (XIV. p. 645. Tacit. Ann. VI. 12. Lactant. Inst. I. 16.) We may trace the existence of this town, by means of coins and inscriptions, to a late

^u Pausanias calls him Cleopus; but this is doubtless a false reading.

period of the Roman empire^x. Acts of councils, and other ecclesiastical documents, prove it to have been the see of a bishop in the province of Asia^y: In the Synecdemus of Hierocles, (p. 660.) Wesselink wishes to substitute Erythræ for Σατράτη. The territory of this city was rugged and mountainous; (Hom. Vit. c. 18.) but it produced good wine, (Athen. I. 32. B.) and fine wheaten flour.

Ἐν δὲ φερεσταφύλαις Ἐρυθραῖς ἐκ κλιβάνου ἐλθαῖν
Λευκὸς ἀβραῖς θάλλων ὕδαις τέρψει παρὰ δεῖπνον.

ARCHESTR. AP. ATHEN. III. 112. B.^z

A rivulet, called Aleos by Pliny, flowed into the bay of Erythræ. (V. 31.^a) The same writer states, that its waters had the property of making the hair grow. (XXXI. 10.) Pausanias reports, that there was a very ancient temple of Hercules in this place. (Ach. 5.) The site of the town retains the name of *Ritré*. A modern traveller states, that “the “walls were erected on two semicircular rocky “brows, and had square towers at regular distances. “They were very thick, the stones massive and “rugged, the masonry that called *pseudisodō-“mum*. In the middle is a shallow lively stream, “clear as crystal, which turns a solitary mill, in its “way through thickets of myrtle and bushes to the “sea. This rivulet was anciently named Aleos. “By a conical hill on the north are vestiges of an

^x Nummi Imperatorii EPT-ΘΡΑΙΩΝ ab Augusto et Claudio, indeque a Trajano usque ad Otacilium, deinceps Valeriani tantum. Sestini, p. 82. The coins of Erythræ, anterior to the Roman dominion, are very scarce.

^y Geogr. Sacr. Car. S. Paul.

p. 238.

^z In the description of Greece I have inadvertently applied this quotation to Erythræ of Bœotia.

^a On the coins of Erythræ the name of this stream appears to be ΑΞΟΣ. Sestini, p. 82.

“ ample theatre in the mountain side ; and further
 “ on, by the sea, three pedestals of white marble.
 “ Beyond these is an old square fortress, standing on
 “ a low spot, a little island ; and by it was a short
 “ sepulchral inscription. Erythræ has been long
 “ deserted, and, like Clazomene, stripped even of its
 “ ruins, except some masses of hard cement, a few
 “ vaults of sepulchres, a fragment of inscribed archi-
 “ trave, a broken column or two, and a large stone,
 “ on which is carved a round shield. The bare rock
 “ afforded a natural foundation for the houses and
 “ public edifices ; and the materials, when they were
 “ ruined, lay ready to be transported to *Scio*, and
 “ other places which continued to flourish ^b.” Ery-
 thræ possessed two ports ; one situated close to the
 town, the other somewhat to the south, and named
 Cyssus, according to Livy. (XXXVI. 43.) Casystes
 in Strabo, if the text of the latter is sound. (XIV.
 p. 644.) The latter corresponds with the well-known
 modern harbour of *Tchesmeh*, or *Chismeh*. Part of
 the coast bore the name of Leopodon. (Hipp. ap.
 Athen. VI. 259. A.) In front of Erythræ were four
 small islands, named Hippi, now *Ogni* and *St. George*. (Strab. loc. cit. Plin. V. 31.) The bay in
 which the city was placed was closed by two pro-
 montories, the northernmost of which bore the name
 of Coryne ; the other, to the south-west, advancing
 towards Chios, that of Mesate. (Pausan. Ach. 5.
 Pomp. Mel. I. 19.) Thucydides assigns to Erythræ
 two small towns, or fortresses, named Pteleum and
 Sidussa. (VIII. 24. Cf. Steph. Byz. v. Πτελέουν.) The
 latter speaks of Embatum as a spot in this vicinity,
 (v. **Εμβατον*,) also known from Thucydides. (III.

Coryne et
Mesate
promonto-
ria.

^b Travels in Asia Minor, p. 113, 114.

29.) To the south of Erythræ, a lofty mountain, anciently named Corycus, and connected with the range of mount Mimas, advances out to the west in the direction of Chios, and terminates in cape Ar-Argennum promonto-^{rium}, which lies nearly opposite to cape Posidium, the easternmost point of that island : the strait which divides the two headlands is estimated by Strabo to be about sixty stadia in breadth. (XIV. p. 645.) Thucydides writes the name Arginus. (VIII. 34.) In Greek, Ἀργεννός and Ἀργινόεις denote the same idea, which is equally expressed by the modern Frank name *Capo Bianco*, or the *White Cape*. The high and rugged coast formed by mount Coryc-^{Corycus}_{mons.}us harboured formerly a wild and daring population, greatly addicted to piracy ; and who, by disguising themselves, and frequenting the harbours in their vicinity, obtained private information of the course and freight of any merchant vessel, and concerted measures for the purpose of intercepting it. The secrecy with which their intelligence was procured gave rise to the proverb,

Toῦ δὲ ἀρ' ὁ Κωρυκῖος; ἡχροάζετο.

The modern name of this elevated ridge is the *Table Mountain*, but the ancient appellation is still preserved in that of *Kourko*, which belongs to a bold headland forming the extreme point of the Erythræan peninsula towards Samos. When Thucydides speaks of Corycus in the eighth book, I conceive he alludes to this cape. (VIII. 14. 33, 34. Cf. Liv. XXXVII. 12.) Pliny calls it *Coryceon promontorium*. (V. 31.) Between this headland and that of Argennum is a small island, close to the mainland, which Strabo names *Halonne-sus insula*. (XIV. p. 645.) Beyond the Corycian promontory the

*Chalcis
regio.*

shore recedes, and forms a considerable bay, advancing inland towards the north-east, and with that of Clazomenæ forming the neck of the Erythræan peninsula. Strabo places here some Chalcidians, who were contiguous to the isthmus, and who, as Pausanias reports, constituted a third part of the Erythræan state. He does not however quite agree with Strabo as to the name of this tribe, since he calls it Chalcitis. (Ach. 5.) He adds, that there was also a promontory so called, near which were some warm springs and baths, highly esteemed throughout Ionia for their medicinal efficacy. Above this district was a grove, consecrated to Alexander the Great, in which solemn games, named after that prince, were celebrated by the general states of Ionia. From this wood to the coast of Clazomenæ the distance by land was only fifty stadia, whereas by sea it exceeded a thousand. (Strab. XIV. p. 644.) Beyond the Chalcidian coast, and without the peninsula, was a port belonging to the city of Teos. Strabo writes the name *Cherrœidæ*, or *Gerrhœidæ*, (loc. cit.) but Livy *Geræsticus*. (XXXVII. 27.) There was also in the same vicinity a town called *Eræ*, or *Geræ*, and apparently a place of some strength. (Thuc. VIII. 19, 20. Strab. loc. cit.) Its site, if we may judge from the analogy of name, agrees with that now called *Erekevi*. In Scylax, I imagine we ought to substitute *Γεραὶ* for "Αγρα. (p. 37.)

*Gerrhœi-
dae sive
Geræsticus
portus.*

*Eræ sive
Geræ.*

Teos.

Teos had been originally colonized by a party of Minyæ from Orchomenus, led by Athamas; but it subsequently received great accession of strength from Athens at the time of the Ionian migration. The Athenian chiefs were Nauclus, son of Codrus, Apœcus, and Damasus; another reinforcement was

afterwards brought by Geres from Bœotia. (Strab. XIV. p. 633. Pausan. Ach. 3. Herod. I. 142. Scyl. p. 37. Steph. Byz. v. Τέως.) When Ionia was invaded by the armies of Cyrus after the overthrow of Crœsus, the Teians, despairing of being able to resist the Persian power, abandoned their native city, and retired to Abdera in Thrace. This colony became so flourishing in consequence, that it quite eclipsed the parent state. (Herod. I. 168. Strab. loc. cit.) Teos is celebrated in the literary history of Greece for having given birth to Anacreon, (Herod. III. 121.) and Hecataeus the historian, though the latter is more frequently known by the surname of Abderite. (Strab. loc. cit.) This town produced also Protagoras the sophist, Scythinus an Iambic poet, Andron a geographical writer, and Apellicon the great book collector, to whom literature is indebted for the preservation of the works of Aristotle. (Strab. loc. cit. Steph. Byz. v. Τέως.)

Vitabis æstus, et fide Teia
Dices laborantes in uno
Penelopen, vitreamquæ Circen.

HOR. OD. I. 17, 18.

Though deserted by the greater part of its inhabitants, Teos still continued to subsist as an Ionian city, as may be seen from Thucydides. (III. 32.) It revolted from Athens after the Sicilian overthrow, (VIII. 16, 19.) but was again reduced. (VIII. 20.) From Livy it appears, that, besides the harbour called Geræsticus, there was another port belonging to the city nearer to it, and more commodious. (XXXVII. 27. Cf. Polyb. V. 77. 5.) The chief produce of the Teian territory was wine; (Liv. loc. cit.) and Bacchus was the deity principally revered

by the inhabitants. It is singular that Pliny should rank Teos among the islands of Ionia ; (V. 38.) at most it could only be reckoned as a peninsula. The site once occupied by this ancient city is now called *Boudroun*. Chandler says, “ We found it almost “ as desolate as Erythræ and Clazomenæ. The “ walls, of which traces are extant, were, as we “ guessed, about five miles in circuit ; the masonry “ handsome. It was with difficulty we discovered “ the temple of Bacchus ; but a theatre in the side “ of the hill is more conspicuous. The vault only, “ on which the seats ranged, remains, with two “ broken pedestals, in the area. The city port is “ partly dry, and sand-banks rise above the surface “ of the water. On the edge are vestiges of a wall, “ and before it are two small islets. On the left “ hand, or toward the continent, is a channel, which “ seemed artificial, the water not deep. The heap “ of the temple of Bacchus, which was visible from “ the theatre beneath on the right hand, lay in the “ middle of a corn-field, and is overrun with bushes “ and olive-trees. It was one of the most celebrated “ structures in Ionia. The remains of it have been “ engraved at the expense of the society of Dilet- “ tanti, and published, with its history, in the Ionian “ Antiquities c.”

Myonne-
sus.

To the south of Teos is another peninsula, in which was situated the town of Myonnesus, dependent on the former city. Livy describes it as “ a promontory placed between Samos and Teos. “ It is a hill rising from a base sufficiently broad to

c Travels in Asia Minor, p. 119, 120. We have gold and silver money of Teos ; the legend is TION and THIΩN. The

imperial series is traced from Augustus to Saloninus. Sestini, p. 85.

" a very pointed summit. The approach to it from " the land is by a narrow path. On the sea-side it " is girt by rocks, so worn by the waves, that in " some parts the overhanging cliffs extend further " out to sea than the ships which are stationed " there." (XXXVII. 27.) Strabo also states that the town was situated on an elevated peninsula. (XIV. p. 643. Cf. Thuc. III. 32.) Strabo mentions that certain mimes and players of Teos, having been expelled from that city during a sedition, had been afterwards settled at Myonnesus by king Attalus ; but the Teians disliking their proximity, obtained from the Romans that they should be removed to Lebedos. (XIV. loc. cit. Steph. Byz. v. Μυόνησος.) The hill of Myonnesus is now called *Hypsili-bounos*: it is described by modern travellers as commanding a most extensive view of a picturesque country, of the sea-coast and islands^d. Close to the shore was a small island named Macris, near which the com- Macris in- bined fleet of the Romans and Rhodians gained an sula. important victory over that of Antiochus. (Liv. XXXVII. 28, 29.) Pausanias seems to give the name of Macria to the promontory of Myonnesus. He states that there were some hot springs which oozed out among the rocks on the sea-shore. Others were used as baths, and decorated with elegant buildings. (Ach. 5.) Strabo notices another island between Teos and Lebedos : it was named by some Aspis, by others Arconnesus. (XIV. p. 643.) " It Aspis, sive Arconne- " is now called *Carabash*, and stands about the sus insula. " middle of the bay, stretching to the south-west ^e."

Lebedos, which follows next, appears, accord- Lebedos. ing to Pausanias, to have been originally held by

^d Chandler's Travels, p. 124.

^e Ibid. p. 126.

^f Chandler's Asia Minor, p. 125, 126.

Steph. Byz. reports, that between Lebedos and Colophon, which follows soon after, there was a place named Dioshieron, (v. Διός ἱερόν,) and this position seems to agree with the reference made to it by Thucydides. (VIII. 19.) But it must not be confounded with a Lydian town of the same name, situated near the Cayster.

Colophon, another Ionian city, and of greater celebrity, was founded, as we learn from Strabo, by Andraemon, son of Codrus, who has been already mentioned more than once. (Cf. Pausan. loc. cit.) It was situated about two miles from the coast, and its port, called Notium, was connected with the city by means of long walls. (Liv. XXXVII. 26. Thuc. III. 34. Scyl. p. 37.) We learn from Herodotus that it was through the Colophonians that Smyrna was brought over to the Ionian confederacy. (I. 150.) The same historian relates that the Colophonians were however excluded, together with the Ephesians, from the Ionian festival called Apaturia, on account of some bloodshed in which they were implicated. (I. 147.) Colophon is also stated by him to have fallen into the hands of Gyges, king of Lydia. (I. 14.) During the Peloponnesian war Colophon was occupied by a Persian force, but some of the inhabitants retired to Notium, and being supported by Paches, an Athenian commander, were enabled to maintain themselves successfully. (Thuc. III. 34.) Strabo observes that Colophon at one period possessed a flourishing navy, and its cavalry was in such repute, that victory followed wherever it was employed: hence the proverb τὸν Κολοφῶνα ἐπέθηκεν, that is, "he has brought his work to a good conclusion;" but the Scholiast of Plato gives

another version of the saying, which appears somewhat more probable, though his authority is not so good. He states, that the Colophonians had the right of a double vote in the Panionian assembly, on account of the service they rendered the confederacy in the matter of Smyrna. Hence they were frequently enabled to decide points left undetermined from a parity of suffrages. (Schol. Plat. in Theæt. p. 319.) Colophon is further celebrated from the number of distinguished poets it has produced. It was one of the rival claimants to the birth of Homer, and was unquestionably the native city of Mimnermus, an elegiac poet, who flourished in the time of Solon^g; of Polymnestus, a musician, noticed by Pindar; Phœnix, an iambic poet, quoted by Athenæus and Pausanias; Hermesianax, a distinguished writer of elegiacs, of which a celebrated fragment has been preserved to us by Athenæus; (XIII. p. 597. A.^h) Antimachus, a well known epic poet; Xenophanes, a writer of (*σίλλοι*) sillî on physical subjects; and Nicander, who wrote Georgics, and poems on venomous creatures, and their antidotes. He is also said to have written a treatise on the poets of Colophon. (Schol. Nicandr. Ther. 3.)

Colophon was destroyed by Lysimachus, together with Lebedos, in order to swell the population of the new town he founded at Ephesus; a circumstance which we learn from Pausanias. (Attic. c. 9. Ach. c. 3. Cf. Diod. Sic. XX. p. 483.) The Colophonians are stigmatised by several writers as very effeminate and luxurious. (Athen. XII. p. 526.) In the war with Antiochus, Colophon, or rather No-

^g See Fabr. Bibl. Gr. tom. I. p. 733. ed. Harles.

^h See Ruhuk. Epist. Crit. II. p. 374.

tium, was besieged by that king ; but the siege was raised by the Romans. (Liv. XXXVII. 26, 27.) The conduct of the inhabitants of Notium on this occasion obtained for them the approbation of the Roman senate, and several privileges. (XXXVIII. 39. Cic. Orat. Man. c. 12. Hor. Epist. I. 11, 3. Plin. V. 29.)

The little river Hales, which flowed near Colophon, was noted for the coldness of its waters. (Pausan. Arcad. c. 28.) It is thought by some learned critics that in the following fragment of Mimnermus, preserved by Strabo, (XIV. p. 634.) we should read 'Αλήεντος for 'Αστήεντος.

'Ες δ' ἐρατὴν Κολοφῶνα βίην ὑπέροπλον ἔχοντες
 'Εξόμεθ' ἀργαλέης ὕβριος ἡγεμόνες.
 Κεῖθεν δ' 'Αστήεντος ἀπορνύμεοι ποταμοῖο
 Θεῶν βουλῇ Σμύρνην εἴλομεν Αἰολίδα.

This stream appears to flow from mount *Aleman*, anciently called Gallesus, or Gallesium. (Strab. XIV. Gallesus p. 642.) It was connected with the chain of mount Corax, or Coracium, (Strab. loc. cit.) which stretched to the north in the direction of Smyrna and Clazomenæ. Chandler describes Gallesus as a vast mountain clad with pines, and abounding in rapid streams and waterfallsⁱ. Colophon derived further celebrity from its vicinity to the oracle of the Clarian Apollo. Claroë. This famous seat of divination is supposed to have been discovered soon after the siege of Troy, and the poets relate many tales with regard to a contention of prophetic skill which took place here between Calchas and Mopsus, which ended in the defeat and death of the former. (Strab. XIV. p. 642.)

ⁱ Travels in Asia Minor, p. 130.

Παιπαλόεις τε Μίμας, καὶ Κωρύκου ἄκρᾳ κάρηναι
Καὶ Κλάρος αἰγλήσσα, καὶ Αἰσαγένης ὄρος αἴπù,
Καὶ Σάμος ύδρηλή, Μυχάλης τ' αἰπεινὰ κάρηναι.

HOM. HYMN. APOLL. 40.

"Η δὲ ἵππους ἄρσασα βαθυσχοίνοιο Μέλητος,
·Ρίμφα διὰ Σμύρνης παγχρύσεον ἄρμα διώκει
·Ἐς Κλάρον ἀμπελόεσσαν, ὅθ' ἀργυρότοξος Ἀπόλλων
·Ησται, μιμνάζων ἐκατηβόλον ιοχέαιραν.

HYMN. IN DIAN. 5.

Ολος δὲ ἐκ νηῶν θυάδεος εἰσιν Ἀπόλλων
Δῆλον ἀν' ἡγαθέην, ἡὲ Κλάρον, ἡ δὲ Πυθὼ,
·Η Λυκίην εύρεῖαν, ἐπὶ Ξάνθοιο ροῆσι.

APOLL. RH. I. 307.

. mihi Delphica tellus
Et Claros, et Tenedos, Pataræaque regia servit.
OVID. METAM. I. 515.

Trojugena, interpres Divum, qui numina Phœbi,
Qui tripodas, Clarii lauros, qui sidera sentis.

AEN. III. 359.

(Cf. Pausan. Ach. c. 3, 5.) Tacitus gives us an account of the visit paid by Germanicus to this oracle. The priesthood was confined to certain families, principally of Miletus. The number and names of those who came to consult the oracle were announced to the seer, who, having descended into the cave, and drank of the spring, revealed in verse to each the subject of his secret thoughts. On this occasion, it is said that a speedy death was announced to Germanicus. (Ann. II. 54.) The oracle continued to flourish in the time of Pliny, (V. 29.) and as late as the reign of Constantine. Considerable vestiges are still to be seen at *Zille*, which occupies the site of the ancient Claros: these consist of several sepul-

chres ; the prophetic fountain and cave, with marble steps leading down to it ; also remains of a large temple, a theatre, and several churches^k. A few wretched huts mark the position of the once flourishing city of Colophon. Notium has also entirely disappeared^l. Beyond Colophon and Claros we come to the river Caystrus, and the marshes it forms Caystrus fl. at its mouth. The latter are doubtless the ^{"Αστιος Ασιæ pa- λειμών} of Homer, the favourite haunt of swans and other water-fowl.

**Χηνῶν, ἡ γεράνων, ἡ κύκνων δουλιχοδείρων,
Ἄστρῳ ἐν λειμῶνι, Καῦστρίου ἀμφὶ ρέεθρα.**

I.L. B. 470.

Jam varias pelagi volucres, et quæ Asia circum
Dulcibus in stagnis rimantur prata Caystri.

GEORG. I. 383.

Ceu quondam nivei liquida inter nubila cycni,
Quum sese e pastu referunt, et longa canoros
Dant per colla modos ; sonat amnis, et Asia longe
Pulsa palus. ÆN. VII. 699.

. . . . non illo plura Caystros
Carmina cygnorum labentibus audit in undis.

OVID. METAM. V. 386.

Sic niger in ripis errat quum forte Caystri,
Inter Ledæos videtur corvus olores.

MART. EP. I. 546.

Strabo speaks of two marshes, or lakes, near the mouth of the Caystrus, one of which was called Selinusia. They both belonged to the temple of ^{Selinusia}_{palus.} Ephesus, and were a source of considerable revenue.

¹ Chandler's Travels in Asia Minor, p. 130, 131.

¹ Ibid. p. 132, 133.

The sovereigns of Asia had at one time sequestered these funds, but they had been restored by the Romans. The revenue officers of the province, however, again endeavoured to appropriate these lands to the purposes of the state. This led to a deputation on the part of the Ephesians to Rome, when Artemidorus, the celebrated geographer, as we learn from Strabo, pleaded the cause of his countrymen before the senate, and obtained a fresh grant in their favour. The Ephesians, in recompense for this service, erected a golden statue to the orator in their temple. At the end of the lake, which lies most in a hollow, was a temple of Jupiter, or Pluto^m, said to have been built by Agamemnon. (Strab. XIV. p. 642.)

Pliny, describing the course of the Caystrus, says, it rises in the Cilbian mountains, and after receiving many streams, and among others the Pegasean marsh which the river Phyrites brings down, waters the plain of Ephesus. (V. 29.) The Phyrites seems to be that stream which rises in the south-western chain of Tmolus, and after passing by the village of *Tourbali*, close to the ruins of Metropolis and the foot of mount Gallesus, forms with the Caystrus the marshes above alluded to. The Caystrus is now called *Kutchuck Mendere*, or Lesser Meander, by the Turks. We shall have to speak of the upper valley of this river when we enter upon the description of Lydia. Near its mouth, and on the southern

Pegaseum
stagnum.

Phyrites
fluvius.

^m Τῆς δὲ λίμνης ἐν τῷ κοιλοτάτῳ βασιλέως ἐστιν ἱερόν φασὶ δ' Ἀγαμέμνονος ἕδρυμα. The French translators render it "un temple "royal;" the Latin version "fa-

" πυν regis." I conceive Βασιλεὺς to mean here either Jupiter, (vid. Hesych. v. Βασίλειος στοὰ, et not.) or Pluto, who is styled by Homer ἄναξ ἐνέρων.

bank, was situated the renowned city of Ephesus. Ephesus. Its foundation was so ancient as to be ascribed by some to the Amazons, at which time it was called Smyrna. (Callin. ap. Strab. XIV. p. 663. Steph. Byz. v. Ἔφεσος.) It also bore successively the names of Samorna, Trachea, Ortygia, and Ptelea. Bennamia and Sisyrba were parts of the town. (Steph. Byz. vv. Βεναμία, Σίσυρβα.) The first inhabitants of the country, according to Strabo, were the Leleges and Carians, who made way for the Ionian colonists brought by Androclus, son of Codrus. (XIV. p. 640.) The latter occupied also the island of Samos. (Pausan. Ach. c. 2.) The colonists appear not to have dwelt together in one place at first, but to have been scattered throughout the Ephesian district till the time of Crœsus, when the city began to assume an appearance of wealth and prosperity. (Strab. loc. cit.) Herodotus relates, that the Ephesians, being invaded by that prince, dedicated their city to Diana, by fastening a rope from their walls to the temple of the goddess, a distance of seven stadia. The historian remarks, that this applies to the old town. (I. 26.) Not long after the Ephesians quitted their former abodes, and drawing nearer to the temple, built around it the new city, which subsisted till the time of Alexander the Great. (Strab. loc. cit.) The shrine of Diana, as Pausanias affirms, was already in great repute before the arrival of the Ionians in Asia :

Σοὶ καὶ Ἀμαζονίδες, πολέμου ἐπιθυμήτειραι,
Ἐν κοτε παρραλίῃ Ἐφέσου βρέτας ιδρύσαντο
Φηγῷ ὑπὸ πρέμνῳ, τέλεστεν δέ τοι ἱερὸν Ἰππώ.

CALLIM. HYMN. IN DIAN. 238.

Τάων ἀμφοτέρων γε βορειότερην ἐσίδοιο
 Παρραλίην *Ἐφεσον, μεγάλην πόλιν Ἰοχεαίρης.
 *Ἐνθα θεῇ ποτε νηὸν Ἀμαζονίδες τετύκοντο.
 Πρέμυῳ ἔνι πτελέης, περιώσιον ἀνδράσι θαῦμα.

DIONYS. PERIEG. 826.

and it was even affirmed that the Amazons, at a remote period, had sacrificed to the goddess there. The image of Diana, said to have descended from Jupiter, (Act. Apost. XIX. 35.) was especially the object of superstitious veneration. It had been preserved throughout all the vicissitudes and revolutions experienced by the city and temple, though the material was only of wood ; it was affirmed by Pliny, on the authority of Mutianus, who had inspected the idol himself, that nard, or some other unctuous substance, was used to guard against decay, to which it would otherwise have been exposed. (XVI. 79.) It was richly adorned with embroidered robes, and concealed from view, except during sacrifices, and other solemn occasions. The service of the temple was performed by priests, who were eunuchs, named Megabyzæ, and accounted peculiarly sacred ; with these were associated a number of virgins as priestesses, (Strab. XIV. p. 641. Xen. Anab. V. 3, 7.) besides several other inferior officers and retainersⁿ. The annual festival of the goddess was attended by all the Ionian states, and the month Artemisius was moreover set apart as altogether to be dedicated to her service^o. The first temple was planned and constructed by Chersiphron, a Cretan architect, assisted by his son Metagenes, who con-

ⁿ Inscript. Ant. ap. Chand. p. 11.

^o Chand. Inscr. Ant. p. 13.

trived a machine for conveying the huge marble blocks of which it was constructed from the quarries of mount Prion. (Vitruv. X. 6.) This edifice, which for its size and decorations was accounted superior to all other buildings of the kind, alone escaped the conflagration to which the other temples of Asia were doomed by Xerxes on his return from Greece. (Strab. VII. p. 273.) But several years after it was set on fire by a madman named Herostratus, and entirely destroyed, with the exception of the outer columns. This event is said to have happened the same night that Alexander the Great was born. (Plut. Alex. c. 3. Cic. de Nat. Deor. II. 27. Valer. Max. VIII. 14. Strab. XIV. p. 640.) The building remained in ruins till Alexander himself, on his arrival in Asia, offered the Ephesians to restore it, on condition that he should be declared the founder. The Ephesians however declined the proposal, alleging, in a style of flattery suited to the vanity of the monarch, that it was unbecoming in one god to erect temples to other deities. (Artemid. ap. Strab. loc. cit.) They therefore determined to rely on their own resources, and those of voluntary contributors, to complete this great work, the execution of which was entrusted to Dinocrates^p, the architect who is reported to have entertained the gigantic and extravagant project of forming a statue of Alexander out of mount Athos. The ladies of Ephesus are said to have contributed on this occasion all their jewels and ornaments, and the wealthier ci-

^p The name of this artist is variously given. Some MSS. of Strabo read Chirocrates; Plutarch calls him Stasicrates; (Alex. c. 52.) Eustathius, Dio-

cles: (Il. O. p. 980.) but Vitruvius, (II. Praef.) Val. Maximus, (I. 4.) Pliny, (VII. 37.) and Strabo, according to some MSS., write Dinocrates.

tizens were not slow in devoting their property to the service of the goddess; a certain sum was also raised from the sale of the materials of the former building. These details were set forth in a decree delivered by the Ephesians on this subject. (Artemid. ap. Strab. loc. cit.) The new temple greatly surpassed the original building in dimensions and magnificence; being not only reckoned the most beautiful sacred edifice of Ionia, but even of the world, and accounted for that reason one of its seven wonders. (Pausan. Ach. 5. Plin. XXXVI. 14.) It was 425 feet in length, and 220 in breadth. The pillars were 127 in number, and sixty feet in height, and each of them had been the offering of a sovereign. Of these, thirty-six were carved; one by the celebrated sculptor Scopas. (Plin. loc. cit.) The order is said to have been Ionic. The gates were of cypress, highly polished, and the roof of cedar; the steps leading up to it of vine. The internal decorations corresponded with the size and external appearance of the structure. The altar was almost entirely adorned by the master hand of Praxiteles. There were also some celebrated works of Thraso, and Scopas, and a picture of Apelles, in which Alexander appeared armed with thunder. For this the artist received the enormous sum of twenty talents of gold. (Strab. loc. cit. Plin.) The asylum attached to the temple was regarded with peculiar sanctity. Alexander had extended it to a stadium, and Mithridates somewhat further; Mark Antony nearly doubled that distance: but the abuses to which this privilege subsequently gave rise, caused it to be abolished by Augustus. (Strab. loc. cit.) The city itself had been gradually increasing with the cele-

brity and splendour of its fane ; to this Lysimachus also contributed, by causing the inhabitants to remove from the old site, which was subject to disastrous inundations, to a better position, which he had marked out and surrounded with walls. (Strab. loc. cit. Dur. Epigr. ap. Steph. Byz. v. Ἔφεσος.) This prince was desirous that the new town should be called after his wife Arsinoe, but the attempt did not succeed. (Strab. loc. cit.) Ephesus was considered in some sort the metropolis of Ionia, from its having been originally founded by Androclus, son of Codrus ; and the descendants of that prince were, even in the time of Strabo, honoured with the title of kings, and were decorated, on certain festive occasions, with the purple robe and sceptre, and presided at the sacrifices of the Eleusinian Ceres. (Strab. XIV. p. 633.) After the defeat of Antiochus this city was made over to the kings of Pergamum by the Roman senate, (Liv. XXXVII. 4, 5. XXXVIII. 39.) and it seems to have enjoyed a considerable degree of prosperity under the mild sway of these sovereigns. Attalus Philadelphus caused some extensive works to be made at the mouth of the Cays-trus in order to prevent the alluvial deposit of that stream from blocking up the harbour ; but the enterprise was injudiciously formed, and rather aggravated the evil it was intended to correct. Such was however the advantageous situation of the city, that, in Strabo's time, it was the great emporium of all Asia. (XIV. p. 641. XII. p. 540.) We know, too, that at this period the temple of Ephesus had lost nothing of its splendour and celebrity, though they were destined, by the arrival of St. Paul, and the power of the Gospel, to sustain a blow from which

they never recovered. The circumstances which St. Luke has described in the nineteenth chapter of the Acts illustrate so forcibly the history of this period, and are so closely connected with the annals of Ephesus, that it seems desirable to insert his account here in his own words. The sacred historian, having in the eighteenth chapter mentioned the first short visit paid by the apostle of the Gentiles, and his departure for Cæsarea and Antioch, after promising to return again, goes on to state the arrival of Apollos at Ephesus, and the effect of his preaching there. He then, at the beginning of the nineteenth chapter, returns to St. Paul : “ And it “ came to pass, that, while Apollos was at Corinth, “ Paul having passed through the upper coasts came “ to Ephesus : and finding certain disciples, he said “ unto them, Have ye received the Holy Ghost since “ ye believed ? And they said unto him, We have “ not so much as heard whether there be any Holy “ Ghost. And he said unto them, Unto what then “ were ye baptized ? And they said, Unto John’s “ baptism. Then said Paul, John verily baptized “ with the baptism of repentance, saying unto the “ people, that they should believe on him which “ should come after him, that is, on Christ Jesus. “ When they heard this, they were baptized in the “ name of the Lord Jesus. And when Paul had “ laid his hands upon them, the Holy Ghost came “ on them ; and they spake with tongues, and pro- “ phesied. And all the men were about twelve. “ And he went into the synagogue, and spake boldly “ for the space of three months, disputing and per- “ suading the things concerning the kingdom of “ God. But when divers were hardened, and be-

“ lieved not, but spake evil of that way before the
“ multitude, he departed from them, and separated
“ the disciples, disputing daily in the school of one
“ Tyrannus. And this continued by the space of
“ two years ; so that all they which dwelt in Asia
“ heard the word of the Lord Jesus, both Jews and
“ Greeks. And God wrought special miracles by
“ the hands of Paul : so that from his body were
“ brought unto the sick handkerchiefs or aprons,
“ and the diseases departed from them, and the evil
“ spirits went out of them. Then certain of the
“ vagabond Jews, exorcists, took upon them to call
“ over them which had evil spirits the name of the
“ Lord Jesus, saying, We adjure you by Jesus whom
“ Paul preacheth. And there were seven sons of
“ one Sceva, a Jew, and chief of the priests, which
“ did so. And the evil spirit answered and said,
“ Jesus I know, and Paul I know ; but who are ye ?
“ And the man in whom the evil spirit was leaped
“ on them, and overcame them, and prevailed against
“ them, so that they fled out of that house naked
“ and wounded. And this was known to all the
“ Jews and Greeks also dwelling at Ephesus ; and
“ fear fell on them all, and the name of the Lord
“ Jesus was magnified. And many that believed
“ came, and confessed, and shewed their deeds.
“ Many of them also which used curious arts, brought
“ their books together, and burned them before all
“ men : and they counted the price of them, and
“ found it fifty thousand pieces of silver. So mightily
“ grew the word of God and prevailed. After these
“ things were ended, Paul purposed in the spirit,
“ when he had passed through Macedonia and
“ Achaia, to go to Jerusalem, saying, After I have

“ been there, I must also see Rome. So he sent
“ into Macedonia two of them that ministered unto
“ him, Timotheus and Erastus; but he himself
“ stayed in Asia for a season. And the same time
“ there arose no small stir about that way. For
“ a certain man named Demetrius, a silversmith,
“ which made silver shrines for Diana, brought no
“ small gain unto the craftsmen; whom he called
“ together with the workmen of like occupation, and
“ said, Sirs, ye know that by this craft we have our
“ wealth. Moreover ye see and hear, that not alone
“ at Ephesus, but almost throughout all Asia, this
“ Paul hath persuaded and turned away much
“ people, saying that they be no gods, which are
“ made with hands: so that not only this our craft
“ is in danger to be set at nought; but also that the
“ temple of the great goddess Diana should be de-
“ spised, and her magnificence should be destroyed,
“ whom all Asia and the world worshippeth. And
“ when they heard these sayings, they were full of
“ wrath, and cried out, saying, Great is Diana of
“ the Ephesians. And the whole city was filled
“ with confusion: and having caught Gaius and
“ Aristarchus, men of Macedonia, Paul’s companions
“ in travel, they rushed with one accord into the
“ theatre. And when Paul would have entered in
“ unto the people, the disciples suffered him not.
“ And certain of the chief of Asia, which were
“ his friends, sent unto him, desiring him that he
“ would not adventure himself into the theatre.
“ Some therefore cried one thing, and some another:
“ for the assembly was confused; and the more part
“ knew not wherefore they were come together.
“ And they drew Alexander out of the multitude,

" the Jews putting him forward. And Alexander
" beckoned with the hand, and would have made
" his defence unto the people. But when they knew
" that he was a Jew, all with one voice about the
" space of two hours cried out, Great is Diana of the
" Ephesians. And when the townclerk had appeased
" the people, he said, Ye men of Ephesus, what man
" is there that knoweth not how that the city of the
" Ephesians is a worshipper of the great goddess
" Diana, and of the image which fell down from
" Jupiter? Seeing then that these things cannot be
" spoken against, ye ought to be quiet, and to do
" nothing rashly. For ye have brought hither
" these men, which are neither robbers of churches,
" nor yet blasphemers of your goddess. Wherefore
" if Demetrius, and the craftsmen which are with
" him, have a matter against any man, the law is
" open, and there are deputies: let them implead
" one another. But if ye enquire any thing con-
cerning other matters, it shall be determined in a
" lawful assembly. For we are in danger to be
" called in question for this day's uproar, there being
" no cause whereby we may give an account of this
" concourse. And when he had thus spoken, he
" dismissed the assembly. And after the uproar
" was ceased, Paul called unto him the disciples,
" and embraced them, and departed for to go into
" Macedonia." It was probably to this tumult, and
to the danger which he then encountered, that the
apostle alludes in his Epistle to the Corinthians, (I.
xv. 32.) where he says, " If after the manner of men
" I have fought with beasts at Ephesus, what ad-
" vantageth it me, if the dead rise not." Many
respectable commentators are, I know, disposed to

take the words, *εἰ κατὰ ἄνθρωπον ἐθηριομάχησα ἐν Ἐφέσῳ;* in a literal sense, as if the apostle had indeed been compelled to engage with wild beasts in the arena; but I cannot help thinking, with Grotius and others, that the metaphorical meaning is to be preferred; that is, “if I have fought against man at Ephesus, “like unto a ferocious animal;” for so remarkable a fact would not have been omitted by St. Luke in his circumstantial narrative of the occurrences at Ephesus; and it cannot be said that the figurative sense is forced and unnatural. This narrative fully agrees with the notions conveyed by profane authorities of the idolatry and gross superstitions then prevalent at Ephesus. But the great apostle, during a three years’ residence there, (Acts xx. 31.) was enabled, with the divine assistance, to establish there the faith of Christ, and to found a church, which became, as it were, the metropolis of Asia. Of his great care of the Ephesian community we have a strong proof in the affecting charge he delivered to their elders at Miletus, where he had convened them on his return from Macedonia; (Acts xx. 16—38.) and still more in the Epistle he afterwards addressed to them from Rome, and which forms part of the sacred volume. Tradition represents Timothy to have been the first bishop of Ephesus; but there is greater evidence that St. John resided towards the close of his life in that city. He is also supposed, on good authority, to have composed his Gospel, and finally to have ended his life there. In the Revelations the apostle places the church of Ephesus first among the seven; and from the gentle rebuke which it received from the Lord, we may conclude that it was yet flourishing under

his care. (Rev. ii. 4, 5.) As the Christian religion prospered, the worship of Diana diminished and sunk into insignificance. Nero is said to have plundered the temple of many votive images, and great sums of gold and silver. This edifice appears, however, to have remained entire in the second century; since we are told, by Philostratus, that a sophist, named Damianus, at that time expended great sums of money in erecting a portico, and other structures connected with its service. (Vit. Soph. p. 601.) At a later period it was again spoiled by the Goths, and other barbarians, and time has so completed the havoc made by the hand of man, that, according to the reports of competent eye-witnesses, the mighty fabric has entirely disappeared^q. Ephesus was governed, as we learn from Strabo, by a senate, with a select body of magistrates called Epicleti. (XIV. p. 640.) The Asiarchs, mentioned in the Acts of the Apostles, were deputies chosen by the several towns of Asia to preside over the sacred games, and other affairs connected with religion. Among other distinguished persons who were natives of this city may be mentioned Heraclitus the philosopher, surnamed the Obscure; Hermodorus, from whom the Romans borrowed a part of their code; Hippoanax the poet, Artemidorus the geographer, Alexander Lychnus, an orator, historian, and poet, and the two great painters Apelles and Parrha-

^q Chandler's Travels in Asia Minor, p. 173. For further information respecting this celebrated temple and the worship of Diana, the reader may consult the great Thesaurus Gr. of Gronovius, tom. VIII. p. 2646.

also Deyling. Obss. Sacr. p. iv. p. 283. and Polckius Diss. de Magn. Ephes. Diana, Lips. 1718, 4to. Democritus, an Ephesian, had written a work in several books on the temple. Athen. XII. p. 525.

Lepre
Acte.

Opistho-
lepre.
Prion
mons.
Trachea.
Coressus
mons.

sius. (Strab. loc. cit.) Several spots are mentioned by ancient writers in connexion with the history of Ephesus. Of these may be noticed Lepre Acte, a part of the old town, situate near the base of mount Prion; some lands lying at the back of that acclivity were named Opistho-lepre. (Strab. XIV. p. 633.) Mount Prion was perhaps so called from its resemblance to a saw. Trachea was another portion of the old city on the slope of mount Coressus, in which stood the temple of Minerva, and the fountain Hypelæus. (Strab. loc. cit. Athen. VIII. p. 361.) We hear also of a temple sacred to Venus Hetæra, (Athen. XIII. p. 573.) an Olympeum and gate leading towards Magnesia. (Pausan. Ach. 2.) Pausanias speaks of mount Prion as a natural curiosity, and commends likewise the whole Ephesian district for its clime and fertility. (Ach. 5.) These advantages rendered the Ephesians as prone to luxury and voluptuousness as the rest of the Ionians. (Athen. XII. p. 525. XV. p. 688.) The ruins of Ephesus are to be seen near the Turkish town of *Ayasluck*, which seems to have risen about the middle of the fourteenth century. Chandler has entered into much detail in regard to these interesting remains, and the following extracts from his account may not be unacceptable to the reader. “Ephesus,” says that traveller, was situated by the “mountains, which are the southern boundary of “the plain, and comprehended within its walls a “portion of mount Prion and of Corissus. Mount “Prion is a circular hill; Corissus a single lofty “ridge, extending northward from near mount Pac- “tyas, and approaching Prion; then making an “elbow, and running westerly towards the sea.

“ We entered Ephesus from *Aiasluck*, with mount
“ Prion and the exterior lateral wall of a stadium
“ which fronted the sea, on our left hand. We
“ measured the area, and found it 687 feet long.
“ The vestiges of the theatre, (alluded to in the Acts
“ of the Apostles,) which was very capacious, are
“ further on in the side of the same mountain.
“ Going on from the theatre you come to a narrow
“ valley, which divides mount Prion from Corissus ;
“ within the valley you find broken columns and
“ pieces of marble, with vestiges of an odeum in the
“ slope of Prion. Beyond the odeum the valley
“ opens gradually into the plain of *Aiasluck*. Keep-
“ ing round by Prion, you meet with vestiges of
“ buildings, and come to the remains of a large edi-
“ fice. This was the gymnasium. The street at
“ the entrance of the city from *Aiasluck* was nearly
“ of the length of the stadium. The opposite side
“ was composed of edifices equally ample and noble.
“ The way was between a double colonnade, as we
“ conjectured, from the many pedestals and bases of
“ columns scattered there. This street was crossed
“ by one, leading from the plain to the valley. It
“ had on the left the front of the stadium, and the
“ theatre, with the portico adjoining. On the right
“ are ample substructions, with pieces of massive
“ wall. These remains reach as far as the portico,
“ and have behind them a morass, once the city port.
“ Opposite to the portico is a vacant quadrangular
“ space, with many bases of columns, and marble
“ fragments. Here, it is probable, was the agora,
“ or market-place, which in maritime towns was
“ generally near the port. At the end of the street,
“ and near the entrance of the valley between Prion

“ and Corissus, turning towards the sea, you have
 “ the market-place on the right hand, on the left
 “ the sloping side of Corissus, and presently the
 “ prostrate heap of a temple. The extent of the
 “ city toward the plain, on which side it was washed
 “ by the Cayster, cannot now be ascertained ; but
 “ the mountainous region has preserved its boun-
 “ dary, the wall erected by Lysimachus, which is of
 “ excellent masonry. It may be traced from behind
 “ the stadium over mount Prion, standing often
 “ above twenty feet high. It crossed the valley,
 “ and from thence it ascended mount Corissus, and
 “ is seen ranging along the lofty brow, almost entire,
 “ except near the precipice, where it ceases. On
 “ mount Prion are likewise remnants of an exterior
 “ wall. Near the entrance of Ephesus from *Aias-*
 “ *luck* are the vaults of several sepulchres, and others
 “ along the slope of Corissus shew that the Ephe-
 “ sians buried likewise within the city.”

Panormus. The port of Ephesus bore the name of Panor-
 mus ; near it, at a little distance from the sea, was
 Ortygia. a spot named Ortygia, thickly planted with cypresses
 Cenchrius and other trees, and watered by the little river Cen-
 chrius, where Latona was said to have been deli-
 vered of her twins. The grove was filled with
 shrines, adorned with statues by the hand of Scopas
 and other eminent sculptors. Above the wood rose
 Solmissus mount Solmissus, where the Curetes, by the loud
 mons. din of their arms, prevented Juno from hearing the
 cries of Latona. Splendid festivals and entertain-
 ments took place annually in these sacred haunts.
 (Strab. XIV. p. 639.) According to Chandler, this
 part of the coast has undergone considerable altera-

^r Travels in Asia Minor, ch. 35.

tions: Ortygia has disappeared, the land having encroached on the sea^s. This process had already been carried on for some time when Pliny lived, since he affirms that the little island of Syria, at the mouth of the Cayster, was then in the plain. (V. 31.)

Continuing along the coast, the following places present themselves to our notice: Pygela, or Phy-gela, said to have been founded by some deserters of Agamemnon's fleet. Here was a temple sacred to Diana Munychia. (Strab. XIV. p. 639. Plin. V. 29. Pomp. Mel. I. 17. Steph. Byz. v. Πύγελα.) Xenophon writes the name Πύγελα. (Hell. I. 2, 2.) It is also alluded to by Livy. (XXXVII. 11.) Dioscorides (V. 12.) commends the wine of this town, a local circumstance which it has yet preserved, according to Chandler, who observed its remains on a hill between Ephesus and *Scala Nova*^t. Further inland was Marathesium, ceded by the Samians to the Ephesians in exchange for Neapolis, a maritime town, situate nearer their island. (Strab. XIV. p. 639. Scyl. p. 35. Plin. V. 29. Steph. Byz. v. Μαραθησιον.) Neapolis is represented by *Scala Nova*, distant about three hours from Ephesus. It is situate in a bay, and has some vestiges of antiquity^u. Proceeding south we come to the celebrated chain of Mycale, which extends for some distance along the right bank of the Mæander towards the east, and to the west runs out into the sea, opposite the island of Samos. It was already known to Homer:

^s Travels in Asia Minor, p. 176. The coins with the epigraph ΦΥ. and ΦΥΓ. are ascribed

to this town. Sestini, p. 83.

^t Chandler's Travels, p. 176.

^u Ibid. p. 178.

Μαιάνδρου τε ροὰς, Μυχάλης τ' αἰπεινὰ κάρηνα :

IL. B. 869.

and became still more celebrated from the Panionium, or solemn assembly, of the Ionian states, held in a temple situated at its foot; (Herod. I. 148.) and also from the great victory obtained by the Greek naval army, under the command of Leotychides, king of Sparta, against the Persian forces encamped near the shore; (Herod. IX. 97.) and which wrested the whole of Ionia for a time from the Persian dominion. Herodotus describes the action as taking place near the temples of the Eumenides and that of the Eleusinian Ceres, founded by Philistus, a follower of Neleus, son of Codrus. He also particularizes two spots, called Gæson and Sclopoeis. (*loc. cit.*) The Persians had drawn up their ships on shore, and fortified themselves with entrenchments and pallisades; but they were forced by the Greeks, after an obstinate resistance, and defeated with great slaughter. Mount Mycale, according to Strabo, was well wooded, and abounded with game; a character which, as Chandler reports, it still retains. This traveller describes it as a high ridge, with a beautiful cultivated plain at its foot, and several villages on its side^u. Towards the north-east it was connected with mount Pactyas, belonging to the Ephesian territory; and its termination in the sea formed the bold promontory of Trogilium, nearly opposite to cape Posidium, in the isle of Samos, and separated from it by a strait, not more than seven stadia wide. (Strab. XIV. p. 636.) C. Trogilium is mentioned by St. Luke

Trogilium
promonto-
rium.

^u Travels, p. 179, 180.

in the Acts, in his account of St. Paul's voyage from Troas to Miletus, by Mitylene, Chios, and Samos. From the latter island they crossed over to Trogylion, and after remaining there, it appears, one night, they reached Miletus the following day. (Acts xx. 15.) Strabo says there was a small island of the same name off the point, and he reckons the distance from thence to cape Sunium at 1600 stadia. (loc. cit.) Pliny names three Trogilian islets, Psilon, Argennon, Sandalion. (V. 31.) The modern appellation of Trogilium is *C. S^{ta}. Maria*; that of mount Mycale, *Samsoun*. The Panionium, according to Panioni-Strabo, was about three stadia from the shore, and um. appears to have been resorted to by the Ionian cities from the earliest period after their colonization. Both the assembly and the temple itself, which was dedicated to the Heliconian Neptune, were called Panionium. The worship of Neptune had been imported by the Ionians from Achaia in Peloponnesus, and the surname of Heliconian was derived from Helice, one of their cities in that country. (Strab. XIV. p. 639. VIII. p. 384. Pausan. Ach. 24.) But the assembly was not merely convened for religious purposes: it was also a political body, and met for deliberative and legislative ends; and it appears that some remnant of this ancient institution was preserved till very late in the Roman empire, if it be true, as Chandler imagines, that there is a medal of the emperor Gallus, which gives a representation of a Panonian assembly and sacrifice ^x. (Cf. Herod. I. 148. VI. 7.) The site of this celebrated convention is supposed, with great probability, to answer to that of *Tchangeli*, a Turkish village close to the

^x Travels, p. 192.

sea, and on the northern slope of Mycale. Chandler, who explored this ancient spot but imperfectly, could discover only a few uninteresting remains^y. Sir W. Gell subsequently observed an inscription, in which mention is made of the Panionium: this appears conclusive as to the identity of that site with *Tchangelis*^z.

According to Thucydides, there was a place or port named Glauce, near Mycale. It was in the narrow part of the strait which divides Samos from the continent. (VIII. 79.) Steph. Byz. calls it Glaucia. (v. Γλαυκία.)

Priene, another considerable city of the Ionians, was founded at first by Ægyptus, son of Neleus, but received afterwards a second colony, brought by Philotas of Thebes; hence it was sometimes called Cadme. (Strab. XIV. p. 633, 636. Pausan. Ach. 2.) It had originally belonged to the Carians. (Herod. I. 142.) The chief circumstances relative to its history are these. It was conquered by Ardys, king of Lydia; (Herod. I. 15.) but, after the defeat of Croesus, it was forced to submit to the arms of Cyrus. (I. 142.) It could boast of having given birth to Bias, one of the seven sages, and an able statesman, as well as philosopher. (Herod. I. 27, 170. Diog. Laert. Cicer. Paradox. 1. Hippo. ap. Strab. XIV. p. 636.) After this, we find Priene a subject of contention between the Milesians and Samians; when the former, being worsted, applied for assistance to the Athenians. (Thuc. I. 115.) Strabo informs us, that the Prienians had the right of electing the president of the Panonian sacrifices. (XIV. p. 639.) Pausanias reports, that this town was at

^y Travels, p. 196.

^z Leake's Asia Minor, p. 260, 1.

one time greatly oppressed by Tabates, a Persian; and subsequently by Hiero, one of its own citizens. (Ach. 2.) The same writer speaks of a temple of Minerva in this city, which contained a very ancient statue of the goddess. (Ach. 5. Cf. Polyb. XXXIII. 12. Plin. V. 29.) Scylax states, that Priene had two ports, one of which might be closed; (Peripl. p. 37.) but Strabo reports, that when he wrote, the town was forty stadia from the sea. (XII. p. 579.) This was caused by the great alluvial deposits made by the river Meander at its mouth. The remains of this ancient city are to be seen on the southern slope of Mycale, near the Turkish village of *Samsoun*. - Chandler says, "it "was seated on the side of the mountain, flat be- "neath flat, in gradation to the edge of the plain. "The areas are levelled, and the communication is "preserved by steps cut in the slopes. The whole "circuit of the wall of the city is standing, besides "several portions within it worthy of admiration "for their solidity and beauty ^a." There are also the ruins of several public edifices, including those of the temple of Minerva Polias, which have been engraved in the Ionian Antiquities. Near Priene was a river named Gessus by Pliny, (V. 20.) but Gæson fl. Gæsonis by Mela. (I. 17.) We have seen that Hero- palus. dorus mentioned a site called Gæson, near Mycale; (IX. 97.) and Athenæus, in explaining these lines of Archestratus,

Λάμβανε δ' ἐκ Γαισωνος, ὅταν Μίλητον ἴκηαι
κεστρέα τὸν κέφαλον, κ. τ. λ.

observes, that Gæson, or Gæsonis, was, according to Neanthes of Cyzicus, a lake between Priene and

^a Travels, p. 200-2.

Miletus, which had a communication with the sea : he adds, that Ephorus spoke of the Gæson as a river which flowed into this lake. (VII. p. 311.)

Meander
fluvius.

We are now arrived at the Meander, one of the largest and most celebrated rivers of Asia Minor, as well from the fertility and richness of its valleys, the number of flourishing cities situated along its banks, as from the unusual sinuosity of its course ; whence even its name has been employed to denote the tortuous channel of a stream.

*Non secus ac liquidus Phrygiis Meandros in arvis
Ludit; et ambiguo lapsu refluitque fluitque:
Occurrensque sibi venturas aspicit undas:
Et nunc ad fontes, nunc in mare versus apertum,
Incertas exercet aquas.* OVID. METAM. VIII. 162.

. qualis incerta vagus
Mæander unda ludit, et cedit sibi
Instatque ; dubius litus an fontem petat.

SENEC. HERC. FUR. 683.

According to Pliny, Livy, and other writers, this considerable river had its rise in a lake situated on mount Aulocrene in Phrygia, close to the citadel of Celænæ : being then joined by the Marsyas and several other streams, it flowed through Phrygia, Caria, and Ionia, and discharged itself finally into the sea between the cities of Priene and Miletus. (Plin, V. 29. Liv. XXXVIII. 13. Pausan. Corinth. 4. Arcad. 41.)

Another remarkable feature in the Meander was the great tendency it had to throw up soil at its mouth. This had already proceeded to such an extent, that, in Strabo's time, Priene, which once was considered as a maritime town, was then forty stadia from the sea ; and when Pausanias wrote, he states that the whole of the space between

the last-named city and Miletus had been by this process reclaimed from the sea, and united to the land. (Arcad. 24.) The same operation has been still going on, and has produced perhaps the greatest metamorphosis of which we have any evidence in comparative geography. These alterations will be best explained when we come to examine the topography of the country which surrounds Mile-
Miletus. That once great and flourishing city, being situated at the mouth of the Meander, and on the left bank, must certainly be considered as belonging to Caria; but it seemed more convenient to comprise it in the section which included the Ionian cities, and not to detach from them one which held so conspicuous a place in the confederacy. The account which Ephorus, who is cited by Strabo, (XIV. p. 635.) and corroborated by Pausanias, (Ach. 2.) gives of the origin of the city is principally as follows. The whole of this part of Asia was called Anactoria, from Anax, a native prince, and was occupied by the Carians. On the arrival of Sarpedon, brother of Minos, from Crete, with some natives of that island, he was kindly received by the Carians, and allowed to found a city, which was called Miletus, either from a Cretan town, or an individual of that name. (Cf. Steph. Byz. Μίλητος. Plin. V. 29.) Herodotus does not appear to have been acquainted with this tradition, since he speaks merely of Sarpedon's establishment in Lycia. (I. 173.) Homer also, though he mentions Miletus, has recorded only the fact of its belonging to the Carians:

Νάστης αὐτὸν ήγήσατο βαρβαροφάνων,
Οἱ Μίλητον ἔχον, Φθειρῶν τ' ὄρος ἀχριτόφυλλον,

Μαιάνδρου τε ροᾶς, Μυχάλης τ' αἰπεινὰ κάρηνα·
Τῶν μὲν ἄρ' Ἀμφίμαχος καὶ Νάστης ἡγησάσθην·

IL. B. 867.

When the Ionians subsequently arrived there, under the conduct of Neleus, they put to death or expelled the Carian inhabitants, and occupied the town. (Pausan. Ach. 2. Strab. loc. cit. Herod. IX. 97.) The admirable situation of Miletus, and the convenience of having four harbours, one of which was capable of containing a large fleet, gave it at an early period a great preponderance in maritime affairs. Its commerce was most flourishing, and the number of its colonies probably exceeded that of any other city of antiquity. Pliny reckoned no less than eighty, and some modern critics have taken the trouble to identify them^b; but it will be sufficient to name in this place Abydos, Lampsacus, and Parium, on the Hellespont; Proconnesus and Cyzicus on the Propontis; Sinope and Amisus on the Euxine: others also in the Chersonnese, the coast of Thrace, Tauris, and on the Borysthenes. (Strab. XIV. p. 635, et pass.) Among the ancients, Anaximenes of Lampsacus had given a list of the Milesian colonies, but Strabo observes that it was incomplete. (XIV. p. 635. Athen. XII. p. 523.) The kings of Lydia made several attempts to possess themselves of so considerable a city: first Ardys, then Sadyattes, who defeated the Milesians in two engagements. In this war the Chians alone of the Ionians befriended them. After the death of Sadyattes, the war was still prosecuted by his son Alyattes, who falling sick, as it was affirmed, through the anger

^b Rambach de Mileto ejusque Colonias, Hal. Sax. 1790. Larcher, Hist. d'Hérod. tom. VIII. p. 344, 359.

of Minerva, whose temple had been burnt by his troops at Assessus, in the Milesian territory, was glad to make an atonement for the injury, and be reconciled with the Milesians. (Herod. I. 17—20.) The affairs of the latter were at this time administered by Thrasybulus with sovereign authority, as Herodotus states; and if we may judge from the advice which he gave to Periander of Corinth, with whom he was very intimate, he was a deep, but unprincipled politician. (V. 92.) The historian asserts, that it was chiefly through an artifice of his that Alyattes consented to desist from his attempts on Miletus. (I. 20.) The Milesians appear subsequently to have made a treaty with Croesus, in which they probably acknowledged that sovereign as their liege lord, and consented to pay him tribute. The same treaty was also agreed upon between them and Cyrus, when the latter had conquered Lydia; and this saved Miletus from the disasters which befell at that time the other Ionian states. (I. 141, 143.) But it was not always equally fortunate. In the reign of Darius the whole of Ionia was excited to revolt by the intrigues and ambitious schemes of Histiaeus, who had been raised to the sovereignty of Miletus, his native city, by the Persian monarch, in recompense for the services he had rendered during the Scythian expedition. Aristagoras, his deputy and kinsman, also greatly contributed to inflame the minds of his countrymen. At his instigation the Athenians sent a force to Asia Minor, which surprised and burnt Sardis; but this insult was speedily avenged by the Persian satraps, and, after repeated defeats, Miletus was besieged by land and by sea, and finally taken by storm. This beau-

tiful and opulent city, the pride and ornament of Asia, was thus plunged into the greatest calamity ; the surviving inhabitants were carried to Susa, and settled, by order of Darius, at Ampe, near the mouth of the Tigris, on the Erythrean sea. The town itself was given up by the Persian commanders to the Carians. The Athenians are said to have been so much affected by this event, that when Phrynicus, the tragic writer, introduced on the stage his play of “the Capture of Miletus,” the whole house burst into tears, and the people fined the poet 1000 drachms, and forbade the performance. (Herod. VI. 6—21. Callisth. ap. Strab. XIV. p. 635.) The battle of Mycale restored the Milesians to liberty : this however they only enjoyed in name, as they became, together with the rest of Ionia and Caria, dependent on Athens. (Thuc. I. 15. 115, 16.) Towards the close of the Peloponnesian war, they revolted from that power ; and, in a battle fought under the walls of their town, they defeated the Argive force which was opposed to them, whilst the Athenians overcame the Spartan troops, and prepared to besiege the town ; but on the approach of the Peloponnesian fleet, Phrynicus, the Athenian admiral, thought it advisable to abandon the enterprise. (Thuc. VIII. 25—27.) We learn from the same historian, that the Milesians, not long after, demolished a fort which Tissaphernes, the Persian satrap, was erecting in their territory, with the view of bringing them into subjection. (VIII. 85.) When Alexander, after the battle of the Granicus, appeared before Miletus, the inhabitants, encouraged by the presence of a Persian army and fleet stationed at Mycale, refused to submit to that prince, and

open their gates to his forces; upon which he immediately commenced a most vigorous attack on their walls, and finally took the city by assault: he however forgave the surviving inhabitants, and granted them their liberty. (Arrian. Exp. Alex. I. 18—20. Strab. loc. cit.) The Milesians sided with the Romans during the war with Antiochus. (Liv. XXXVII. 16. XLIII. 6.) This city was yet flourishing when Strabo wrote; (loc. cit. Tacit. Ann. IV. 63. IV. 55.) and still later, in the time of Pliny (V. 29.) and Pausanias. (Ach. 2.) It appears, from the Acts of the Apostles, that St. Paul sojourned here a few days, on his return from Macedonia and Troas, and summoned thither the elders of the Ephesian church, to whom he delivered an affectionate farewell address. (xx. 17, et seq.) The Milesian church was under the direction of bishops, who sat in several councils, and ranked as metropolitans of Caria. (Hierocl. Syn. p. 687.) This continued as late as the decline of the Byzantine empire; (Mich. Duc. p. 41.) at which time, however, the town itself was nearly in ruins, from the ravages of the Turks and other barbarians, and the alluvial deposits caused by the Meander. Miletus deserves further mention as the birthplace of Thales, the celebrated mathematician and philosopher; and his successors, Anaximander and Anaximenes; also of Cadmus and Hecatæus, two of the earliest historians of Greece. (Strab. XIV. p. 635. Plin. V. 39. Suid. v. Κάδμος.) The Milesians were equally voluptuous and effeminate with the rest of the Ionians, though they had once been brave and warlike; whence the proverb cited by Athenæus from Aristotle:

Πάλαι ποτ' ἥταν ἄλκιμοι Μιλήσιοι.

Heraclides Ponticus, in a fragment quoted also by Athenæus, affirmed that the serfs of the Milesians were called *Gergithæ*^c. (XII. p. 523, 4.) The Milesians were in repute for their manufactures of couches and other furniture; and their woollen cloths and carpets were especially esteemed. (Athen. I. p. 28. XI. p. 428. XII. p. 540, 553. XV. p. 691.)

Nec minor usus erit : quamvis Milesia magno
Vellera mutentur Tyrios incocta rubores.

GEORG. III. 306.

. . Eam circum Milesia vellera Nymphæ
Carpebant, hyali saturo fucata colore.

GEORG. IV. 335.

Chandler reports, “that Miletus is a very mean place, but still called *Palat*, or *Palatia*, the *Palaces*. The principal relic of its former magnificence is a ruined theatre, which is visible afar off, and was a most capacious edifice, measuring in front 457 feet. The external face of this vast fabric is marble. The seats ranged, as usual, on the slope of a hill, and a few of them remain. The vaults, which supported the extremities of the semicircle, are constructed with such solidity as not easily to be demolished. On the side of the theatre next to the river is an inscription in mean characters, rudely cut, in which the city Miletus is mentioned several times. The whole site of the town, to a great extent, is spread with rubbish, and overrun with thickets. The vestiges of the heathen city are pieces of wall, broken arches, and a few scattered pedestals and inscrip-

^c These were probably Carians; and the term seems to have been common to the Teu-

cians and Mysians, and should therefore be referred to the old Thracian tongue.

"tions. One of the pedestals has belonged to a
 "statue of the emperor Hadrian, who was a friend
 "to the Milesians, as appears from the titles of
 "saviour and benefactor bestowed on him. An-
 "other has supported the emperor Severus, and has
 "a long inscription, with this curious preamble:
 " 'The senate and people of the city of the Mile-
 "sians, the first settled in Ionia, and the mother of
 "many and great cities both in Pontus and Egypt,
 "and in various other parts of the world ^{d.}' "

There were several small islands off Miletus, of which the most considerable was Lade, famous for ^{Lade in-}_{sula.} the battle fought there between the Ionian fleet and that of Darius, in the revolt of Histiaeus and Aristagoras. The former had 360 galleys, the latter 600. The victory which the Persians obtained decided the fate of the war. (Herod. VI. 14—16.) Mention of this island is also made during the siege of Miletus by Alexander, whose fleet was stationed to blockade the port. (Arrian. Exp. Alex. I. 19.) This island, like many others, has been joined to the continent by the mud of the Meander; and its place is only marked now by a hill, and village named *Bautenau*. Strabo speaks of Lade as a station for pirates. (XIV. p. 635.) The mouth of the river, according to Chandler, is distant about eight miles; the plain smooth and level as a bowling-green, except certain knolls extant in it, near midway before Miletus ^e. But the most remarkable change in this vicinity, caused by the waters of the Meander, is that which has taken place with regard to the bay once called Latmicus Sinus, from mount Latmus, the fabled seat of the adventures of Endy-

^d Travels in Asia Minor, p. 181.

^e Ibid. p. 219.

mion, and a small town of the same name situate at its south-eastern extremity. This bay, which Strabo describes minutely, with the different towns and hills which lined its shores, was not less than 100 stadia in length from Miletus to Heraclea, a port under mount Latmus; but it now exists only as an inland lake, its mouth having been closed by the slime which the Meander has thrown up. (Strab. XIV. p. 636.)

One of the most interesting sites in the district of Didymi. Miletus is that called Didymi, where stood the celebrated temple and oracle of Apollo Didymæus. It was served by priests named Branchidæ, from Branchus, a favourite of Apollo, and it was already in great repute in the time of Croesus, who presented many rich offerings to its shrine. (Herod. I. 46. 92.) The historian adds, that it was very ancient, and much resorted to by the Æolians and Ionians. (I. 157.) Necho, king of Egypt, had sent presents to the temple, when he took Cadytis in Palestine. (II. 159.) This edifice was burnt by order of Darius, together with the other temples of Asia Minor, after the revolt of Miletus. (Herod. VI. 20.) But this appears to have been only partially executed, for it was burnt more completely again by Xerxes after the battle of Mycale, and the Branchidæ, having accompanied him in his flight into Persia with the sacred treasury, were settled by him in Sogdiana. Here they were found by Alexander in the course of his conquests, and barbarously put to the sword, as a punishment for their reputed treachery. (Strab. XIV. p. 634. XI. p. 517. Quint. Curt. VII. 5.) The Milesians subsequently built

^c Travels in Asia Minor, p. 219.

another temple on the same site, which surpassed all other edifices of the kind in magnitude. So great was its size, that they were unable to roof it in. The whole circuit, including the groves and chapels annexed to it, was equal to that of a town. It was in the latter that the oracles were delivered. The interior of the temple was decorated with splendid sculptures and paintings by the first artists. (Strab. XIV. p. 634. Cf. Pausan. Ach. 2. 5. Plin. V. 29.) The temple stood at the distance of twenty stadia from the sea. (Strab. loc. cit. Plin. loc. cit.) The tomb of Neleus, the founder of Miletus, was on the road leading from Miletus to Didymi. (Pausan. loc. cit.) There are yet some extensive ruins of this celebrated edifice remaining, views of which have been engraved in the volume of Ionian Antiquities published by the Dilettanti Society. Chandler gives a very animated and picturesque description of this ruin. He states, that "it is approached by a gentle ascent, and seen afar off; the land toward the sea lying flat and level. The memory of the pleasure which this spot afforded me will not be soon or easily erased. The columns yet entire are so exquisitely fine, the marble mass so vast and noble, that it is impossible perhaps to conceive greater beauty and majesty of ruin. The whole mass was illuminated by the declining sun with a variety of rich tints, and cast a very strong shade. The sea, at a distance, was smooth and shining, bordered by a mountainous coast, with rocky islands^f."

The promontory Posideum was in the vicinity of Posideum Didymi, and terminated the Milesian territory and ^{promonto-}_{rium.} Ionia to the south. (Strab. loc. cit. Plin. loc. cit.

^f Travels in Asia Minor, p. 188.

P. Mel. I. 19.) The modern name is cape *Arbora*. Somewhat more to the north is a little port called *Kobella*, which probably answers to the Panormus of antiquity^g. (Herod. I. 157.) The ruins of the temple of Apollo are situated between the villages of *Oura* and *Jeronta*. It appears that the name of Didymi was given to this spot from two hills, situated near it. A fortress, named Melanodium, was erected there in the middle ages. (Pachym. Andr. Pal. p. 144.) Limeneium was a place in the territory of Miletus, where, according to Herodotus, (I. 18.) the inhabitants of that city were defeated by the Lydians.

Myus. Myus, another Ionian city, was situate apparently on the left bank of the Maeander, and about thirty stadia from the mouth of that river. It was founded by Cydrelus, a natural son of Codrus, (Strab. XIV. p. 633.) and became one of the twelve states which sent deputies to the Panionian assembly. (Herod. I. 142. Cf. V. 37. VI. 8.) Thucydides informs us, that this was one of the three towns granted to Themistocles by the Persian king, for his subsistence during his residence in Asia. (I. 138. Cf. Strab. loc. cit. Diod. Sic. XI. c. 57. Plut. Themist. c. 29. Athen. I. p. 29.) The same historian mentions a check received by the Athenians near this place during the Peloponnesian war, from the Carians. (III. 19.) Athenæus states, on the authority of Polybius, that Philip, son of Demetrius, king of Macedon, having obtained possession of Myus, ceded it to the Magnesians. (III. p. 78.) Strabo reports, that in his time Myus was so much reduced

^g Chandler noticed some vestiges of antiquity there. Ibid. p. 187.

that it had been annexed to Miletus. Pausanias accounts for this by the action of the Meander, which had choked up the bay in which it stood, and brought such a host of gnats around the place that the inhabitants were forced to abandon it, and retire to Miletus. The only edifice which this writer observed in Myus was a temple of Bacchus, of white marble. (Ach. 2. Cf. Plin. V. 29. Steph. Byz. v. Μύοῦς.) The little town of Pyrrha was between Pyrrha. Myus and Miletus, on the same side of the river, and near the entrance of what was the gulf of Latmus, but is now called the lake of *Oufa Bafi*. The distance from thence to Miletus, in a straight course, was thirty stadia. This site, which Strabo only notices, is supposed to agree with that of *Sarikomer*. Heraclea, which derived the surname of ^{Heraclea}_{Latmi.} Latmus from its vicinity to the mountain so called, was 100 stadia from Pyrrha, and rather more from Miletus. It had a port on the Latmicus Sinus. ^{Latmicus}_{Sinus.} (Strab. loc. cit.) The site of Heraclea corresponds nearly with the village of *Oufa Bafi*, at the south-east extremity of the lake so called. Chandler mistook its ruins for those of Myus, and the lake also he erroneously connected with that town. He says, that “ it is visible both from Priene and Miletus, and is called by the neighbouring Greeks the “ Sea. The water is not drinkable h.” The site of Heraclea, which he miscalls Myus, he represents as highly romantic. “ The wall encloses a jumble of “ naked rocks, rudely piled, of a dark dismal hue, “ with precipices and vast hollows, from which per-“haps stone has been cut.” He observed “ the “ remains of a theatre hewn in the mountain, a quad-

^h Travels in Asia Minor, p. 209.

“angular area, edged with marble fragments, and
“a small temple. The city wall was constructed
“like that at Ephesus, with square towers, and is
“still standing, except toward the water^h. ” Heraclæa Latmi is mentioned as a town of Caria by Polyænus, (Strat. VII. 2. Steph. Byz. v. Ἡράκλεια) the scholiast of Apollonius, (IV. 57.) Hierocles Syncd. (p. 687.) and the Acts of several councils. Mount Latmus, celebrated for the fable of Endymion, rises above the site of this town and its lake, and is described by Chandler as remarkably wild and craggyⁱ. It is now called *Betchek parmak* by the Turks. The cave and tomb of Endymion was shewn to the curious in Strabo's time. (XIV. p. 635. Cf. Cic. Tusc. Disp. I. 38. Apoll. Rh. IV. 57.)

Latmus
mons.

Οὐκ ἄρ' ἐγὼ μούνη κατὰ Λάτμιον ἀντρον ἀλύσκω
Οὐδ' οἴη καλῶ περιβαίομαι Ἐνδυμίωνι.

(Plin. V. 29. Pomp. Mel. I. 19.)

Grius
mons.

The name of Grius was applied to the chain which ran parallel to mount Latmus, on the western side of the Latmic bay. Strabo says it extended from near Miletus to Euromus in Caria. It was disputed which of the two chains should be identified with the Φθειρῶν ὅρος, mentioned by Homer. (Il. B. 868.)

Phthira
mons.

Οἱ Μίλητον ἔχον, Φθειρῶν τ' ὅρος ἀκριτόφυλλον.

(Cf. Steph. Byz. v. Φθίρα.)

Assessus.

Assessus was a small place in the Milesian territory, with an ancient and much venerated temple sacred to Minerva. (Herod. I. 19. Steph. Byz. v. Ἀσσησός.) The fountain of Biblis, mentioned by

Biblis
fons.

^h Travels in Asia Minor, p. 205. for mount Titanus throughout. (p. 202.)

ⁱ He mistakes it, however,

Pausanias, (Ach. 5.) was also in this district. We must add to the list of Ionian towns the following, which are of uncertain position. Buthia, noticed Buthia. by Steph. Byz. on the authority of Theopompus. (v. Βουθία.) Gambrium and Palægambrium, ceded ^{Gambrium et Palæ-} by the Persians to Gongylus the Eretrian, on account of some services he had rendered them towards the end of the Peloponnesian war. (Xen. Hell. III. 1, 4. Steph. Byz. v. Γαμβρεῖον.) It was probably situated in the north of Ionia, if it did not belong to Lydia. Thebe, a place near Miletus. (Steph. Thebe. Byz. v. Θήβη.) Carnia, a town mentioned by Nicolaus of Damascus. (Steph. Byz. v. Καρνία.) Myes ^{Myes} and Sidele, which are given to Ionia by the same Sidele. lexicographer, on the authority of Hecataeus. (vv. Μύης. Σιδήλη.) Sillyus (Id. v. Σίλλυος) was near Smyrna.) Trampe. (Id. v. Τράμπη.) We must now speak of the islands of Chios and Samos, which belonged to the Ionian league, and occupy a distinguished place generally in Grecian history.

Chios, as Pliny reports, bore anciently the names ^{Chios insula.} of Æthalia, Macris, and Pityusa, and was first inhabited by the Leleges and Carians, and a Pelasgian colony from Thessaly. (Strab. XIII. p. 621. XIV. p. 633.) Pausanias, who enters at some length into its antiquities, expresses his surprise that Ion, the tragic poet, a native of this island, and from whom he derives his information, should not have explained how the Chians came to be connected with the Ionians. (Ach. 4.) This connexion must be sought for, I imagine, in the colonies, which the island derived at an early period from the Abantes of Eubœa, who finally prevailed over the Carians under their king Hector. This prince is probably

the same as Egertius, mentioned by Strabo. (XIV. p. 633.) The Abantes are named by Herodotus among the mixed tribes which formed the Ionian states. (I. 146.) The Chians applied themselves early to maritime affairs, and were thus enabled to preserve their independence against the Lydian monarchs. (Herod. I. 18. 27.) They particularly distinguished themselves in the Ionian revolt under Aristagoras, and sent 100 ships to the combined fleet assembled at Lade. In the naval action which ensued they fought with great gallantry, but being ill seconded, and even deserted by the other confederates, they were forced to retreat, with the loss of a great part of their squadron. Having then taken shelter on the Ephesian coast, and advanced towards that city, they were mistaken by the Ephesians for pirates, and almost entirely destroyed. (Herod. I. 15, 16.) They were further barbarously treated by Histæus. (I. 26.) After these disasters the island was compelled to submit to the Persian yoke. (I. 31.) These appear to have set over it a tyrant named Strattis. (VIII. 132.) After the battle of Mycale, the Chians recovered their liberty, and readily joined the confederacy of Greek states for the prosecution of the Persian war. They remained faithfully attached to the Athenian interests during nearly the whole of the Peloponnesian contest, as it appears to have been the policy of Athens to pay them greater deference than their less powerful tributaries: (Thuc. III. 10.) but after the Sicilian failure, they were among the first to throw off the heavy burdens which oppressed them, and to declare for the Spartans. The feeble succours which the latter sent them, and the double policy of the Per-

sian satraps, gave the Athenians time to collect an imposing force. Pedaritus, the Spartan commander, was defeated and slain, and the Chians, after sustaining repeated losses, were forced to remain subject to Athens. (Thuc. VIII. 14. et seq. 24. 55.) After the Lacedæmonians had been enabled, by the liberal aid of Cyrus, to dispute once more the empire of the sea, Chios was occupied by their fleet, and a squadron, which escaped from the defeat at Arginusæ, being stationed there, would have seized upon the town, if the plot had not been frustrated by the vigilance of Eteonicus, the commander. (Xen. Hel. II. 1.) When the successes of Conon had restored the naval ascendancy of Athens, Chios, and the other Ionian islands, reverted to that power; but the yoke proved so galling, that a vigorous effort was made by the Chians, in conjunction with the Byzantines and Rhodians, to set themselves free for ever from Athenian thraldom. In the war which ensued, and which is called the Social war, success seems rather to have favoured the confederates; the Athenians being defeated in an attack on Chios, with the loss of some ships and their general Chabrias, were at length induced to sign a treaty, in which they renounced all authority and supremacy over the states allied in this war, and declared them free from contributions in ships and money. (Isocr. de Pace. Demosth. de Rhod. Lib. Diod. Sic. XVI. c. 7. 21. Corn. Nep. Vit. Chabr.)

Near the time that Roman affairs begin to be intermixed with those of Greece and Asia, we find the Chians acting in conjunction with the Rhodians as mediators between the Ætolians and Philip, king of Macedon. (Polyb. V. 24. 28. 100. Liv. XXVII. 30.)

They assisted the Romans in their naval operations against that prince and Antiochus, and received some lands in recompense for their services. (Polyb. XXII. 27. Liv. XXXVIII. 39.) When Mithridates had expelled the Romans for a time from Asia, he sent Zenobius, one of his generals, to Chios, who treated the inhabitants with the greatest severity; compelled them to deliver up their arms, to pay a heavy fine of 2000 talents, and, not content with this, he seized on the principal inhabitants, and sent them as slaves to Colchis. A portion of these unhappy men were however detained by the Heracleotæ of Pontus, and set at liberty. (Appian. Mithr. c. 24. Nicol. Damasc. et Posidon. ap. Athen. VI. c. 18.) The Chians were again plundered by Verres, (Cic. Act. II. 19.) and suffered from an earthquake in the reign of Tiberius. (Suet. Tib. c. 8.) We collect from Pliny that this island, and the principal city of the same name, was flourishing in his time, and we have coins which bring down its history to the decline of the Roman empire. The Chians were reckoned among the most opulent and wealthy of the Greek states, and their city was adorned in a manner suitable to their affluence. They had an abundance of slaves, and they are reproached with being the first who purchased their fellow-creatures. (Thuc. VIII. 24. 40. Athen. VI. p. 265.) Their mode of living was like that of the other Ionians, delicate and voluptuous. (Athen. I. p. 25, 26, 28.)

Chios laid great claim to the honour of having given birth to Homer; and if the hymn quoted by Thucydides (III. 104.) be genuine, the question would seem to be decided in favour of its preten-

sion^k. The author of the poet's life states, that he resided in the island for several years. (c. 25. et seq.) Strabo also reports that the Chians gave the name of Homeridæ to his descendants. (XIV. p. 645.) The other distinguished individuals who added to the renown of Chios, were Ion, the tragic poet, Theopompus, the historian, Theocritus, a sophist, Metrodorus, a physician, and Scymnus, the geographer. (Strab. loc. cit. Suid. vv. Θεόπομπος. Θεόκριτος. Athen. VI. p. 230. XIII. p. 603.) The isle of Chios, according to Strabo, is 900 stadia in circuit. (XIV. p. 645.) Pliny reckons 125 miles, or about 1000 stadia. (V. 31.) The general character of the soil was mountainous and rugged; whence the epithet of παιπαλασση given to it by Homer; (ap. Thuc. loc. cit.) but it produced the best wine of all Greece. (Strab. loc. cit. Athen. I. p. 26, et seq.) Its figs, mastic, and starch, were also much esteemed. (Var. de Re Rust. I. 41. Plin. XVIII. 7. Dioscor. I. 90.) An ancient poet says, that the women of Chios and Miletus were preeminent in beauty. (Crit. ap. Athen. I. p. 28.)

The principal city, which bore the same name *Chios* with the island, stood on the eastern side towards the Ionian coast, nearly in the same latitude with Erythræ. The modern *Chio* retains its rank and position. We have seen, from Thucydides, that it was a large and handsome city, adorned with numerous edifices, and noble works of art; several of the latter were plundered by Verres, (Cic. Act. II. 19.) The harbour was excellent, and could contain eighty galleys at once. South of *Chio* we have to point

^k See, however, Ruhnken. Epist. Crit. I. p. 90.

Posidium
prom.

out Posidium, a promontory nearly opposite to cape Argennum in the Erythraean territory. (Strab. XIV. p. 645.)

Phanae
portus et
prom.

A fort called after St. Helen, is situated on the brow of this headland, which is named *Catomeria*, and sometimes *Masticio*. Next follows the harbour and cape of Phanae, close to which stood a temple of Apollo, with a grove of palms. (Strab. loc. cit. Cf. Liv. XXXVI. 43. XLIV. 28. Steph. Byz. v. Φάνειον.) The wine of this district was much esteemed, as appears from Virgil :

Sunt etiam Amineæ vites, firmissima vina :
Tmolius assurgit quibus, et rex ipse Phanæus.

GEORG. II. 97.

Cape Phanae is now called *Mastico*.

Notium
portus.
Laius
portus.

Ariusia.

Beyond is a roadstead named Notium, the *Port Mastico* of modern charts. Laius, according to Strabo, was another port further north, in the same latitude with the capital of the island, and distant from it not more than sixty stadia across the land. This observation leads to the idea that Laius agrees nearly with the modern site of *Port Mesta*. The northern part of the island comprised chiefly the district of Ariusia, celebrated for its excellent wine.

Vina novum fundam calathis Ariusia nectar.

VIRG. ECL. V. 71.

. . . . ambrosiis Arvisia pocula succis.

SIL. ITAL. VII. 210.

Cf. Plin. XIV. 7.) Athenæus distinguishes three sorts. (I. p. 32. F.) The coast was rugged, and without a port for nearly 300 stadia. (Strab. loc. cit.) The district of Arvisia still goes by that name, and the village of *Volisso*, situated on the coast, represents doubtless the ancient Bolissus noticed in Thucydides,

(VIII. 24.) and the Life of Homer. (c. 23. Cf. Auct. cit. ap. Steph. Byz. v. Βολισσός.) The cape, which forms the north-western extremity of the island, bore anciently the name of Melæna, and is now known by that of *St. Nicolas*. Strabo observes, that it faces the island of Psyra, distant from it about fifty stadia, and forty in circuit. (XIV. p. 645.) The modern name is *Psara*. Beyond cape Melæna is mount Pelinæus, the most elevated summit of all the island, and famous for its marble quarries. (Strab. loc. cit. Plin. V. 31.)

Kai Χίος ἡλιβάτου Πελληναῖου ὑπὸ πέζαν.

DION. PERIEG. 535.

Jupiter was worshipped on the summit. (Hesych. v. Πελληναῖος. Steph. Byz. v. Πελληναῖον.) It is now called after *St. Elias*. In a deep bay, more to the east, Cardamyle, a place mentioned by Thucydides, with Cardamyle. Bolissus and Phanæ, retains its name. (VIII. 24.) The historian speaks in the same chapter of Leuconium, the situation of which is unknown. But Delphinium, which he mentions (c. 25.) as a place fortified by the Athenians, (Cf. Steph. Byz. v. Δελφίνιον,) is doubtless the present *Porto Delfino*, opposite the islands Οenussæ, now *Spalmadores*, or *Egonisi*. This group belonged to the Chians, and Herodotus affirms that the Phocæans, when driven from their city by the arms of Cyrus, were anxious to purchase them, in order to settle there, but the Chians refused to cede them. (I. 165. Cf. Thuc. VIII. 24. Plin. V. 31.)

Babras, or Babrantium, is cited as a small town of Chios by Steph. Byz. on the authority of Polybius. (vv. Βαβράντιον, Βάβρας.) Pliny enumerates several islets round Chios, such as Thallusa, or Daphnusa,

Elaphitis, Eurynassa; and towards Ephesus, the isles of Pisistratus; namely, Anthine, Myonnesus, Diarrheusa: to these he adds Halone, Lepria, Bolbulæ, Phanae, Priapus, Melane, Sidusa, Anydros, Sycussa, and others which have been already named: some of these belong probably to the group of Hecatonnesi.

Samos insula.

Samos, which yields little in extent, and nought in fame, to Chios, lies towards the southern part of the bay of Ephesus, and nearly opposite to the promontory of Mycale, or Trogilum. The channel which separates it from that part of the continent being not more than seven stadia in the narrowest part. (Strab. XIV. p. 637.) It is said to have borne in ancient times the names of Parthenia, Dryusa, Anthemisa, Melamphylos, and others; that of Samos was derived either from a hero so called, or from the isle of Cephallenia, which formerly was known by that appellation, and may, as Strabo supposes, have sent a colony to its Ionian namesake. (XIV. p. 637. Cf. X. p. 437. Plin. V. 31. Heraclid. Fragm. p. 211. Steph. Byz. v. Σάμος.) The first inhabitants were Carians and Leleges, whose king Ancæus, according to the poet Asius, cited by Pausanias, married Sainia, daughter of the Meander. The first Ionian colony came into the island from Epidaurus, having been expelled from thence by the Argives. The leader of this colony was Procles, a descendant of Ion. Under his son Leogoras the settlement was invaded by the Ephesians, under the pretext that Leogoras had sided with the Carians against Ephesus. The colony being expelled from Samos, retired for a time to Anaea in Caria, whence they again invaded the island, and finally expelled the Ephesians.

(Pausan. Ach. 4.) Samos is early distinguished in the maritime annals of Greece, from the naval ascendancy it acquired in the time of Polycrates, whose history is narrated at length by Herodotus. This chief raised himself by his talents from the condition of a private person to the government of his country, which he shared at first with his two brothers, Pantaleon and Syloson; but subsequently he caused the former to be put to death, and expelled the other; after which he reigned with undivided authority. His successes were great and rapid, and he acquired a power which made him dreaded equally by his subjects and neighbours; and his alliance was courted by some of the most powerful sovereigns of that period. He conquered the Lesbians and other islanders, and had a fleet of 100 ships, a navy superior to that of any one state recorded at so early a date. (Herod. III. 39. Thuc. I. 13. Strab. loc. cit.) The Samians attempted to revolt from him, but though they were assisted in the undertaking by the Lacedæmonians, they failed of success, and many were driven into exile. (Herod. III. 44, et seq.) The Spartans landed in the island with a large force, and besieged the principal city with vigour, but they were finally forced to abandon the enterprise, after the lapse of forty days. (III. 54, et seq.) The Samian exiles then retired to Crete, where they founded Cydonia. Here they remained for five years in a flourishing condition, but on the sixth year they were attacked by the Æginetæ, with whom they had formerly been at variance, and reduced to slavery. (III. 59.) Polycrates after this did not long enjoy the good fortune which had so constantly attended him, and the course of which,

by the advice of his ally Amasis, king of Egypt, he had even attempted to break: he fell a victim to cruel and artful designs of the Persian satrap Orœtes, who lured him to his fate by the temptation of immense wealth; and having got him into his power, nailed him to a cross. (Herod. III. 125, et seq.) Polycrates, though tainted by many vices, knew how to estimate and reward merit. He cultivated a friendship with Anacreon, and retained the physician Democedes at his court. Pythagoras was also his cotemporary; but unable to witness, as it is said, the dependence of his country, he quitted Samos, in order to cultivate science in foreign countries. (Herod. III. 121, 131. Strab. XIV. p. 638.) After the death of Polycrates, the government of Samos was held for some time by Mæandrius, his secretary; but he was expelled by the troops of Darius, who placed on the throne Syloson, the brother of Polycrates, on account of some service he had rendered him in Egypt, when as yet he was but a private person. (Herod. III. 140. Strab. loc. cit.) Strabo reports that the yoke of this new tyrant pressed more heavily on the Samians than that of Polycrates, and that in consequence the island became nearly deserted; whence arose the proverb,

"Ἐκητὶ Συλοσῶντος εύρυχωρίη."

(Cf. Heraclid. Pont. p. 211.) From Herodotus, however, we learn that the Samians took an active part in the Ionian revolt, and furnished sixty ships to the fleet assembled at Lade; but by the intrigues of Æaces, son of Syloson, who had been deposed by Aristagoras, and consequently favoured the Persian arms, the greater part of their squadron deserted the confederates in the battle which ensued, and

thus contributed greatly to the defeat of the allies. (Herod. VI. 8—14.) On learning the result of the battle many of the Samians determined to quit the island rather than submit to the Persian yoke, or that of a tyrant imposed by them. They accordingly embarked on board their ships and sailed for Sicily, where they first occupied Calacte, and soon after, with the assistance of Anaxilas, tyrant of Rhegium, the important town and harbour of Zancle. Æaces was replaced on the throne of Samos, and, out of consideration for his services, the town and its temples were spared. (VI. 22—25.) After the battle of Salamis, the Samians secretly sent a deputation to the Greek fleet stationed at Delos, to urge them to liberate Ionia, they being at that time governed by a tyrant named Theomestor, appointed by the Persian king. (IX. 90.) In consequence of this invitation, Leotychides, the Spartan commander, advanced with his fleet to the coast of Ionia, and gained the important victory of Mycale. (IX. 96, et seq.) The Samians, having regained their independence, joined, together with the other Ionian states, the Grecian confederacy, and with them also passed under the protection, or rather domination, of Athens. The latter power, however, having attempted to change the constitution of the island to a democracy, had nearly been expelled by the oligarchical party, aided by Pissuthnes, satrap of Sardes. For the Samians ventured even to engage by sea with the Athenian fleet, and obtained some important advantages when blockaded both by sea and land, during the absence of Pericles; but when that able general returned to his command, they were unable to resist the overwhelming force brought

against them, and submitted to the Athenians. They were compelled to destroy their fortifications, give up their ships, deliver hostages, and pay the expenses of the war by instalments. This occurred a few years before the breaking out of the Peloponnesian war. (Thuc. I. 115, 117.) After this, we hear little of Samos till the end of the Sicilian expedition, when the maritime war was transferred to the Ionian coast and islands. At this time Samos became the great *point d'appui* of the Athenian fleet, which was stationed there for the defence of the colonies and subject states; and there is little doubt that the power of Athens was alone preserved at this time by means of that island. We learn from Thucydides that the oligarchical party at Athens had at first overthrown the democracy in Samos, as they had done at home; but by the exertions of Thrasylus and Thrasyllus, and other commanders, the supremacy of the people was again restored over that of the landholders. ($\gamma\epsilon\omega\mu\omega\pi\cdot$) (VIII. 21, 72—74¹.) The Athenian army then making common cause with the Samian people, determined to prosecute the war with vigour, and to use every exertion to restore the democratic influence at Athens. They were induced by these steps to enter into negotiations with Alcibiades, and by securing the assistance of that able leader, they contributed essentially to the successes which were afterwards obtained on the Hellespont. (VIII. 86, et seq.) We learn from Polybius, that, after the death of Alexander, Samos became for a time subject to the kings of Egypt.

¹ These appear to have been colonists sent by Athens, to the number of 2000, after the re-

duction of the island by Pericles. Strab. XIV. p. 638. Heraclid. Pont. Frag. p. 211.

(V. 35. 11.) Subsequently it fell into the hands of Antiochus, and on his defeat, into those of the Romans. The temple and worship of Juno contributed not a little to the fame and affluence of Samos. Pausanias asserts that this edifice was of very great antiquity; this, he says, was apparent from the statue of the goddess, which was of wood, and the work of Smilis, an artist contemporary with Dædalus. (Ach. 4. Callim. Epigr. ap. Euseb. Præp. Ev. III. c. 8. Clem. Alex. Protr. p. 30.) The temple, according to Menodotus, a Samian writer quoted by Athenæus, had been founded by the Carians and Leleges, the first inhabitants of the island. (XV. p. 672.) Herodotus affirms that it was the largest of any he was acquainted with. The first architect had been a Samian, named Rhœcus, son of Philes. In Strabo's time it was adorned with a profusion of the finest works of art, especially paintings, both in the nave of the building and the several chapels adjoining. The outside was equally decorated with beautiful statues by the most celebrated sculptors. Among these were three colossal figures forming one group, by Myron. Marc Antony had carried these away, but Augustus replaced two of them, which represented Minerva and Hercules; he reserved that of Jupiter to adorn the Capitol. (XIV. p. 637.) Besides this great temple, Herodotus describes two other works of the Samians, which were most worthy of admiration: one was a tunnel carried through a mountain for the length of seven stadia, for the purpose of conveying water to the city from a distant fountain. Another was a mole, made to add security to the harbour; its depth was

twenty fathoms, and its length more than two stadia. (III. 60.)

The circuit of this celebrated island, which retains its ancient name, is 600 stadia, according to Strabo. Agathemerus reckons 630. Pliny eighty-seven miles, which make upwards of 700 stadia. (Plin. V. 31.) It yielded almost every kind of produce, with the exception of wine, in such abundance, that a proverbial expression used by Menander was applied to it; *φέρει καὶ ὄρνιθων γάλα.* (Strab. XIV. p. 637.)

The city of Samos, with which we shall commence the periplus of the island, was situate to the south-east, exactly opposite to the promontory of Trogilium and mount Mycale, the channel which parted them being in width about forty stadia. The port was secure, and convenient for ships, and the town for the most part stood in a plain rising gradually from the sea towards a hill situate at some distance from it. The citadel, built by Polycrates, was called Astypalæa. (Polyæn. Strat. I. Steph. Byz. Etym. M. v. *'Αστυπάλαια.*) The Heræum, or temple of Juno, was near the suburbs and the little river Imbrasus; hence the surname of Imbrasia given to the goddess:

Imbrasus
fluvius.

. 'Ιμβρασίης ἔδος "Ηρῆς.

APOLL. RH. I. 187.

Callimachus affirmed that this stream was first called Parthenius.

'Αντὶ γὰρ ἐκλήθης 'Ιμβρασε Παρθενίου.

(ap. Schol. Apoll. Rh. II. 868. Cf. Strab. loc. cit. Plin. V. 31. Athen. VII. p. 283.) Besides the Imbrasus, Pliny mentions the Chesius and Ibettes. According to the scholiast of Callimachus, Chesium

Chesius fl.
Ibettes fl.
Chesium
prom.

was a promontory of the island, where Diana was worshipped. (Callim. Dian. 228.)

Xησιὰς Ἰμβρασίη, πρωτόθρονος.

(Cf. Apoll. Rh. ap. Athen. VII. p. 283. Steph. Byz. v. *Xήσιον*.) There was an ancient and much revered asylum attached to the temple of Juno. (Tacit. Ann. IV. 14.) Virgil reminds us that the name of Juno was nowhere so much venerated as at Samos, with the exception of Carthage.

Quam Juno fertur terris magis omnibus unam
Posthabita coluisse Samo. ÆN. I. 15.

The ruins of the city and temple are to be seen near *Megalochora*, the present capital of the island.

A little to the north is a promontory anciently called Posidium, and dedicated to Neptune. Close Posidium to this headland was the little island Narthecis, and the distance from thence to the mainland of Ionia was only seven stadia. (Strab. loc. cit.) In the same vicinity we must seek for Calami, a spot where the calami Greek fleet was stationed before the battle of Mycale. (Herod. IX. 96.) Panormus and Palinurus, two havens noticed by Livy in his account of the naval operations of Polyxenidas, admiral of Antiochus, against Pausistratus, a Rhodian officer. (XXXVII. 11.)

Ptolemy places south of Samos the city, the promontory of Ampelus, but Strabo says it was opposite to the island of Icaria: the latter description would agree with *Cape Samos*, or *S. Dominico*; the former would answer to *C. Coloni*, or *Bianco*. There was also in the centre of the island a mountain, named Ampelus. It is easily recognised under its modern appellation of *Ambelona*. (Strab. XIV.

p. 637.) Strabo, however, elsewhere speaks of the headland opposite to Icaria, under the name of Cantharium, (XIV. p. 639,) so that it will be safer to consider that as the ancient name of cape *S. Dominico*. Pliny names another mountain, Cercetius, which the poet Nicander also notices in the Alexipharmacæ :

Κερκητέω νιφάντος ὑπὸ σχοινώδεσιν ὥχθαις.

It answers to mount *Kerki*, near *C. Dominico*. Pliny adds the fountains Gigartho and Leucothea. Assorum was another mountain of this island, according to Steph. Byz., whence flowed a stream, named Amphilysus. (v. Ἀσσωρὸν.) Gorguia, a spot where Bacchus was worshipped. (Dur. ap. Steph. Byz. v. Γόργυια.) Ipnus, where a temple was erected to Juno. (v. Ἰπνοῦς.)

Icaria insula.

Isti prom.
et statio.

Dracanum
prom. et
mons.

The island of Icaria, which was said to derive its name from Icarus, the son of Dædalus, and to have transmitted it to the Icarian sea, is 300 stadia in circuit, according to Strabo. (XIV. p. 639.) The geographer adds, that it possesses no harbours, but a roadstead or two; the best of these was near a promontory called Isti, ('Ιστοὶ,) situate towards the west. The eastern point of the island, facing cape Cantharium of Samos, and distant from it only eighty stadia, was named Dracanum, now *Cape Phanari*, or *St. John*. (Strab. loc. cit.) Dracanum was also the name of a mountain in this island, where Bacchus, according to some traditions, was said to have been born.

Χαῖροι μὲν Διόνυσος ὃν ἐν Δρακάνῳ νιφόεντι
Ζεὺς ὑπατος μεγάλαν ἐπιγουνίδα θήκατο λύσας.

'Αλλὰ τὰ μὲν δολιχῆς τε καὶ αἰτεινῆς Δρακάνοιο
 'Ιχάριον ρήσσει κῦμα περὶ χροκάλαις.

EUPHOR. EPIGR. ANTH. PAL. VII. 651.

Icarus was much celebrated for its wine, especially that called Pramnian, though an ancient writer describes it as rough and harsh, and very strong. It was so called either from a hill named Pramnus, where it grew, or the particular vine which yielded it. (Eparch. ap. Athen. I. p. 30.)

Ancient writers agree in assigning to this island two towns: (Scyl. p. 22. Plin. IV. 12.) one called Dracanum, and situate near the cape of the same name; the other ΟΝΟΕ, and placed in the opposite direction. (Strab. XIV. p. 639. Athen. loc. cit. Steph. Byz. vv. Δράκανον, Οίνόη.) There was also in the interior a temple of Diana Tauropolos. Eparchides, the writer quoted above from Athenæus, and who seems to have compiled a history of Icaria, related that Euripides had at one time resided on the island. (II. p. 61.) Strabo informs us that in his time the island was nearly deserted: it was only frequented by the flocks which the Samians sent thither to pasture. Other islets round Samos were the Corassiae, or Corseæ, (Strab. loc. cit. Plin. V. 31. Steph. Byz. v. Κόρσειαι.) now *Formiche* or *Ant* isles. A ship sailing from cape Trogilium or Mycale, to Sunium, passed these and Samos and Icarus on the right, but the rocks or shoals called Melantii to the left; these therefore must either have been near Patmos, or the islets named *Stapodia*, to the east of Myconus. Apollonius Rhodius seems to place the Melantian rocks in the Cretan sea. (IV. 1706.) Near Samos was also the little isle of Tragia, noticed by Thucydides on account of a sea-fight which

Corassiae
sive Corseæ
insulæ.

Melantii
scopuli.

Tragiæ in-
sula.

took place in its vicinity, between the Athenians and Samians, when the latter were defeated. (I. 116.) Pliny reckons more than one islet of the name off the Ionian coast; perhaps they are the rocks called *Samopoulo*, close to the Ampelus promontorium. Strabo seems to place them near Lade. (XIV. p. 635.)

Camelides insulæ.

Rhypara, Nymphæa, Achillea, insulæ.

Hyettusa insula.

Pharmacusa insula.

Lepsia insula.

Patmos insula.

In this direction Pliny names the two Camelides, close to Miletus; and near to Samos, Rhypara, Nymphæa, Achillea. (V. 37.) At some distance from the coast, and nearly opposite to Panormus, the island called *Garthonisi* in modern charts is supposed to represent Hyettusa, mentioned by Pliny. (V. 31.) *Farmaco*, opposite to cape Posidium of Miletus, is evidently the isle Pharmacusa, near which Julius Cæsar was once captured by pirates. (Plut. Vit. Cæs. Suet. J. Cæs. c. 4.) Steph. Byz. says Attalus was killed there. (v. Φαρμακοῦσσα.) Further out at sea we have to notice Lepsia, (Plin. loc. cit.) now *Lipso*.

Patmos is a little to the west of Lipsia. This small island, so interesting to the Christian on account of the banishment of the apostle St. John, is mentioned by Strabo among the Sporades, (X. p. 488.) and by Pliny, who says it is thirty miles in circuit. (IV. 12.) It is the general opinion of commentators that St. John was banished to Patmos towards the close of the reign of Domitian. He himself declares, (Rev. I. 9.) “I John, who also am “your brother, and companion in tribulation, and “in the kingdom and patience of Jesus Christ, was “in the isle that is called Patmos, for the word of “God, and for the testimony of Jesus Christ.” It is not known how long his captivity lasted, but it is thought that he was released on the death of Domi-

tian, which happened A. D. 96, when he retired to Ephesus. (Iren. II. 22. 5. Euseb. Hist. Eccl. III. 18. Dio. Cass. LXVIII. 1.) The island, which is now called *Patino*, contains several churches and convents; the principal one is dedicated to the apostle. There are also the ruins of an ancient fortress, and some other remains ^m.

LYDIA.

Having now finished the survey of the Ionian coast and the adjacent islands, I shall next proceed to inquire into the ancient state of the country situate at some distance from that coast, and confined generally between the waters of the Hermus and Meander on the north and south, whilst to the east it was conterminous with the greater Phrygia. Within these limits was included the kingdom of the Lydian monarchs, before the conquests of Croesus and of his ancestors had spread that name and dominion from the coast of Caria to the Euxine, and from the Meander to the Halys. The celebrity of Croesus, and his wealth and power, have certainly conferred on this part of Asia Minor a greater interest than any other portion of that extensive country possesses, Troas perhaps excepted; and we become naturally anxious to ascend from this state of opulence and dominion to the primitive and ruder period from which it drew its existence. In this inquiry, however, we are unfortunately little likely to succeed; the clue which real history affords us for tracing the fortunes of Lydia through her

^m See Mr. Whittington's account of these remains, extracted from his journal, in Wall-

pole's Memoirs of Turkey, tom. II. p. 43:

several dynasties, soon fails, and we are left to the false and perplexing directions which fable and legendary stories supply. Some great and leading facts are certainly however to be elicited from all the authorities which have touched upon the history of Lydia; and though these facts are of a general nature only, they are such as may be considered useful in the chain of historical analogies, and at all events such as we must be satisfied with, for want of more specific information. The sum of what we learn is this, that Lydia, or that portion of Asia Minor specified above, appears to have been governed for a much greater space of time than any other part of that country, by a line of sovereigns, broken, it is true, into several dynasties, but continuing without interruption, it seems, for several centuries, and thus affording evidence of the higher civilization and prosperity of their empire. It is not to be supposed, however, that the country remained all this time undisturbed by revolutions and political changes; we have evidence to the contrary: and indeed it would have been opposed to analogy to imagine that the possession of a country so eminently favoured by nature should not have been a subject of dispute and contest, when almost every other province witnessed repeated changes of inhabitants during its progress to a permanent and settled state of things.

Our sources of information respecting the history of Lydia are almost entirely derived from Herodotus, and the high name which he bears doubtless attaches great respectability to his testimony; but as we have no opportunity of weighing his authority on this particular subject, from being unacquainted with the sources whence he drew his information,

and also from having no parallel historian with whom to compare his account, it is evident we cannot place such dependence on his Lydian history as on those of Egypt, Babylon, and Persia. Our suspicions will of course be increased, if we find that the circumstances he relates are incredible in themselves, and at variance also with other authorities. The difficulties respecting these circumstances, both as to facts and dates, have given rise to many disquisitions on the part of learned men, without however leading to any satisfactory solution of them, at least in my opinion; and this I imagine, because they have strained at little points, without seeking to clear away the real obstacles which beset our path. Time has unfortunately deprived us of the Lydian annals of Xanthus, a native of the country, somewhat anterior to Herodotus, and whose accounts were held in great estimation for accuracy and fidelity by sound judgesⁿ; but from incidental fragments preserved by later writers, we are led to infer that he had frequently adopted traditions materially differing from those which Herodotus fol-

ⁿ Dionysius of Halicarnassus, in his Roman Antiquities, (I. 30.) speaks of his history in high terms of commendation. Strabo also makes frequent citations from his writings. (XII. p. 579. XIII. p. 628. XIV. p. 680, &c.) Nicolaus of Damascus appears to have derived much information from him, and Steph. Byz. quotes him repeatedly. Nevertheless, it was pretended by some critics, that the works ascribed to this ancient historian were spurious, being really the productions of

Dionysius, surnamed Σκυτοβραχίων; but though there might be forgeries among his writings, there can scarcely be any doubt that many were genuine, since Ephorus spoke of them as well known to him, and represented Xanthus as more ancient than Herodotus, and even as paving the way for him. (Athen. XII. p. 515.) The fragments of Xanthus have been collected and published, with those of other early Greek historians, by Fr. Creuzer, Heidelberg. 1806. 8vo.

lowed, and that his history also, as might be expected, contained several important facts unknown to the latter, or which it did not enter into the plan of his work to insert. Xanthus would probably have given us some valuable information on a subject which belongs especially to the nature of our enquiries, and on which Herodotus seems scarcely to touch, I mean the origin of the Lydian nation. Without his assistance, our means of information are of course very scanty and deficient ; but, such as they are, we must endeavour to compile and arrange them to the best advantage, for the benefit of our readers. The general account which we collect from Herodotus is this : he states, that the country, known in his time by the name of Lydia, was formerly called Mæonia, and the people Mæones. (I. 7. VII. 74.) This seems confirmed by Homer, who nowhere mentions the Lydians, but numbers the Mæonian forces among the allies of Priam, and assigns to them a country which is plainly the Lydia of subsequent writers :

Μήσιν αὐτὸν Μέσθλης τε καὶ Ἀντιφος ἡγησάσθην,
Τίε Πυλαιμένεος, τῷ Γυγαίῃ τέκε λίμνη,
Οἱ καὶ Μήσονας ἥγον ὑπὸ Τμώλῳ γεγαῶτας.

II.. B. 864.

Strabo also remarks, that many writers adopted this opinion, but that others looked upon these two nations as distinct : he himself adhered to the former. (XIII. p. 625.) Herodotus further states, that the name of Lydians was derived from Lydus, a son of Atys, one of the earliest sovereigns of the country ; (loc. cit.) and in this particular he closely agrees with Xanthus, quoted by Dionysius of Halicarnassus, (Ant. Rom. I. 30.) however he may differ from

him in other considerable points. But the period to be assigned to this Lydus is a subject likely to baffle for ever the researches of the ablest chronologists. For Manes, according to Herodotus, being the first king of the country, (I. 94.) and father of Atys, consequently grandfather of Lydus, it would follow that the Mæonian name would have lasted only for two generations, and yet we find it the only one in existence when Homer wrote, or, at least, which he supposed to have existed at the period of which his poem treated. Some writers have reported that there was a prince named Meon, who was more ancient than Manes; (Diod. Sic. III.) but this is contrary to the testimony of Herodotus and Xanthus, whom Dion. Halic. probably copied^o. (Ant. Rom. I. 30.) It is possible, however, that there may have been more than one sovereign who bore the name of Manes; for Herodotus speaks of one who was father of Cotys and grandfather of Asius, from whom the district, and subsequently the whole continent of Asia, is said to have derived its appellation. (IV. 45.) Now unless Cotys and Atys were brothers, which is not stated, it must follow that there were two Manes^p. To this part of the subject seems to belong the question of the great Tyrrhenian migration recorded by Herodotus, which I have already discussed at some length

^o This Manes appears to have been sovereign of Phrygia as well as Lydia; (Alex. Polyhist. ap. Steph. Byz. vv. Μανῆσις. Ἀκμόνιον. Plut. Is. et Osir.) and it is not improbable that he was worshipped in that country under the name of Men.

(Strab. XII. p. 556, 580.)

^p This is also the opinion of the Abbé Sevin, in his learned dissertation on the kings of Lydia. (Mém. de l'Acad. des Inscr. et Belles Lettres, tom. V. p. 231.

in my work on ancient Italy, under the head of Etruria ; but I prefer making what further remarks I have to offer on this point at a later period in the present enquiry. Herodotus goes on to state, that after a number of generations, which he does not pretend to reckon, the crown passed from the line of Lydus, son of Atys, to that of Hercules. This hero had a son by a slave of Jardanus, who was then apparently sovereign of Lydia ; and this son, succeeding to the throne by the command of an oracle, became the author of a new dynasty, which reigned through two and twenty generations, and during the space of 505 years. (I. 7.) The introduction of the name of Hercules indicates at once that we have shifted our ground from history to mythology and fiction. We know how the Greeks seized upon that name as being exclusively their own, and how they adapted the legends of other countries to the exploits and wonders achieved by the son of Amphytryon. The doubts and suspicions, which this circumstance naturally creates in the mind, are rather increased than lessened on inspecting the list of the lineal descendants of Hercules, who reigned at Sardis. Well might Scaliger exclaim with astonishment, when he saw the names of Ninus and Belus following almost immediately after that of Hercules their ancestor ^q.

There seems to be here some extraordinary confusion of names, dates, and countries, out of which it is hardly possible to extract any thing intelligible or probable. For my part I cannot help imagining that these names imply some distant connexion be-

^q Scal. Can. Isagog. lib. III. p. 327.

tween the supposed Lydian dynasty of the Heraclidæ and the Assyrian empire. I confess that this is only a surmise ; but there are some curious traditions preserved apparently by Xanthus, in his history of Lydia, which go some way towards supporting this hypothesis. Stephanus of Byzantium, speaking of Ascalon in Palestine, states, that the above historian affirmed that it had been founded by Ascalus, an officer under the command of Aciamus, king of the Lydians^s. Nicolaus of Damascus repeated this story from Xanthus. (Steph. Byz. v. 'Ασκάλων.) There is a further allusion to this part of the Lydian traditions in Athenæus, who quotes a fragment of Mnaseas in his work on Asia, where, speaking of Atergatis, a Syrian queen, he adds, that Xanthus reported that Atergatis was taken by Mopsus the Lydian, and thrown, with her son Ichthys, in a lake near Ascalon. (VIII. p. 346.^t) If there is any foundation for these traditions, it must be allowed, I think, that they belong to a period when the Lydians occupied a very different situation in the map of Asia from that which they subsequently took up^u. But, so far from the Lydians having founded Ascalon, and other towns in Syria and Palestine, I think it much more probable that they derived, themselves, the original population of their country from those parts, as did the Cilicians, Cappadocians, and Phrygians ; and in that case we shall no longer be surprised to find Ninus and Belus

^s The name of this prince appears to be Phœnician, or Syrian ; Achim, or Achiam.

^t The Abbé Sevin observes, that some writers identified Atergatis with Derceto, mother

of Semiramis.

^u The scriptural name of Lud, or Ludim, may perhaps have some connexion with these traditions.

among the sovereigns of the country. It is also very possible, that the fable of Hercules and Omphale may have had its origin in some old tale imported by the Phœnicians, who laid an earlier claim, as Herodotus imagined, to the actions of that hero than the Greeks. (II. 44.) It would require a much longer space than we can devote to such an enquiry to attempt to establish a connexion between the Assyrian and Lydian empires, nor am I aware that it can be satisfactorily made out; but the surmises and hints which we have here thrown out, may perhaps be pursued by some more learned and laborious antiquarian, who will not lose sight of the great similarity which appears to have existed between the corruptions of Babylon and the conduct which history ascribes to the Lydian women: nor will it be forgotten, that the Lydians and Carians are said to have derived divinations and sacrifices from the Chaldees ^x.

Whatever connexion may have existed between the Lydians and the nations to the east of the Euphrates, it must be confessed however that the ancients themselves were hardly aware of the fact. The testimony of Herodotus, who doubtless consulted the best authorities he could procure, would seem to shew that the Lydians regarded themselves as descended from the same stock as the Carians and Mysians. Now these being confessedly of Thracian origin, it necessarily follows that the former also must have been a branch of the same primitive race. (Herod. I. 171.) Menecrates of Elæa, and Xanthus, who are cited by Strabo, also confirmed the fact, as far as the affinity of the Mysians and Ly-

^x See also Bochart, Geogr. Sacr. lib. II. c. 12.

dians is concerned, by the undeniable proof of a strong similarity of language. (XII. p. 572.) But by what name were these brethren of the Carians and Mysians known before they settled in Lydia; for I do not imagine that they imported that name from Europe into Asia? Were they called Leleges or Pelasgi? This is what cannot be now seriously enquired into. All that we know is, that the inter-mixture of these various heterogeneous tribes already named, constituted the nation which afterwards became known to the Greeks by the name of Lydians. The confusion resulting from this intermixture being such as to baffle, according to Strabo's observation, all hope of discriminating between them. (XII. p. 572. XIII. p. 629.) In the time of Herodotus a small remnant of the Mæonians, surnamed Cabelees and Lasonii, yet preserved apparently some distinctive marks, in language and manners, from the Lydians and the Carians, to whom they were contiguous. (III. 90. VII. 77.) Strabo, speaking of the small district Cabalis, which must certainly be referred to this people, remarks, that many authors looked upon it as the seat of the ancient Solymi of Homer, who were doubtless of Phœnician origin; (XIII. p. 630.) and that the Cabelees were so likewise, might be inferred from the fact, that their arms and accoutrements were precisely those of the Cilicians. (Herod. VII. 77.) The Torrœbi, who once formed a considerable portion of the Lydian nation, had long ago disappeared, since they are neither mentioned by Strabo nor Herodotus; their existence is only certified to us in a fragment of Xanthus, preserved by Dionysius of Halicarnassus. (Ant. Rom. I. 30.) According to that ancient his-

torian, the Torrœbi were so called from Torrœbus, brother of Lydus; their language did not differ much from that of the Lydians; but they had many terms in common, as the Dorians and Ionians have. Dionysius adduces this passage to prove that Xanthus knew nothing of Tyrrhenus, the brother of Lydus, and his pretended expedition into Italy; and certainly if the Lydian historian is correct, his authority would be decisive against the existence of that prince. But the great question with respect to this curious tradition preserved by Herodotus, and which must have had some foundation, is to ascertain whether it was really an Asiatic legend or an European one. What I mean is this: the Lydians, in the time of Herodotus, were no longer the indigenous or aboriginal inhabitants of the ancient Mæonia. They had come from Thrace and Macedon with the Phrygians and Carians and Mysians, and they were much intermixed with Pelasgi and Leleges and Caucones, and other primitive tribes. They may therefore have imported from those countries a tradition, which referred to events much anterior to their settlement in Lydia, but which was afterwards, by a natural confusion, adapted to their subsequent existence in that country, and was not countenanced by the more authentic records consulted by Xanthus. This mode of dealing with the tradition of Herodotus has this advantage, that it is perfectly consistent with those authorities which seem to place the original seat of the Tyrrheni in Thrace and Macedon, and in particular with that report mentioned by Plutarch, which stated that the Tyrrheni came first from Thessaly into Lydia. (Romul. c. 1.) It also removes the inconsistencies

and difficulties attending its consideration as a legend purely belonging to the latter country, and in particular the strong objections brought against it by Dionysius.

Leaving now this obscure and uncertain field of enquiry, let us proceed to take a rapid sketch of the history of Lydia at a period when its records are more sure and faithful.

Candaules, whom the Greeks named Myrsilus, was the last sovereign of the Heraclid dynasty. He was assassinated, as Herodotus relates, by his queen and Gyges, one of his principal officers. The latter succeeded to the vacant throne, and became the founder of a new line of kings. (Herod. I. 8—14.) Under his reign it is probable that the mines of mount Tmolus, and other parts of Lydia, were first brought into activity; this would account for the fabulous stories which are related respecting him, (Plato de Rep. II. Cic. de Off. III. 9.) and his extraordinary wealth. He is said by Herodotus to have made very rich offerings to the temple of Delphi, both in gold and silver, (I. 14.) and his riches formed the theme of Anacreon, (Od. XV.) and Archilochus. (Frag. X. Cf. Theopomp. ap. Athen. VI. p. 231.) Under this sovereign the Lydian empire had already made considerable progress in several districts of Asia Minor. Its sway extended over a great part of Mysia, Troas, and the shores of the Hellespont; (Strab. XIII. p. 590.) and before his death Gyges had succeeded in annexing to his dominions the cities

y The reader who wishes to search further into the early Lydian history may consult the dissertation of the Abbé Sevin,

above referred to, and also the researches of Freret on the Chronology of Lydia, which form a sequel to it.

of Colophon and Magnesia. (Herod. I. 14. Nicol. Damasc. Exc.) According to Herodotus he reigned thirty-eight years: but chronologists are not agreed as to the exact period of his accession to the throne; some removing it back as far as 718 B.C., others bringing it down to 688.^z He was succeeded by his son Ardys, who conquered Priene; but for a time was stripped of his dominions and capital by an incursion of the Cimmerians. He reigned forty-nine years, and was succeeded by his son Sadyattes, of whom nothing is recorded except the bare fact that he occupied the throne for twelve years. Alyattes, who next follows, made war against the Medes, expelled the Cimmerians from Asia, conquered Caria and some of the Ionian cities, and after a prosperous reign of fifty-seven years, left the crown to his son Crœsus, whom he appears to have already associated with him in power some years previously. (Herod. I. 16—25. I. 92. Nic. Damasc. p. 243.^a) Crœsus proved more ambitious and enterprising than any of his predecessors. He brought under subjection, or rendered tributary, all the Greek settlements in Asia, and all the barbarian nations west of the Halys, except the Lycians and Cilicians; (Herod. I. 29.) and surpassed all the sovereigns of his time in the extent of his wealth and the splendour of his court. Ambition and vanity led him, however, to think that he could reduce the Persian power, which had lately risen on the ruins of the Median empire, under the youthful Cyrus. In an evil hour he

^z See Freret, *Recherches sur la Chronologie de l'Histoire des Rois de Lydie*, Mém. de l'Acad. des Inscr. &c., tom. V. p. 280

—283. Clinton's *Fasti Hellen.* tom. I. Append. p. 296.

^a See Clinton's *Fasti Hell.* Append. p. 298. tom. I.

crossed the Halys, and entered Cappadocia, then a Persian province. The first conflict was indecisive, but Crœsus having withdrawn to his own dominions to collect reinforcements for a second campaign, he was speedily followed by his more quick-sighted and active foe, and obliged to fight a second battle nearly under the walls of Sardis. Crœsus, after sustaining a complete defeat, was soon shut up within that city, which from its great strength might have resisted for a long space of time, if accident had not put the enemy in possession of a secret path, by which they stormed the citadel, and became masters of the place. Crœsus was thus dethroned, and Lydia became annexed to the Persian empire. (Herod. I. 75—84.) The Lydians had previously been a brave and warlike people, but from this time they degenerated totally, and became the most voluptuous and effeminate of men. (I. 79. 155—157. Athen. XII. p. 515 et seq.) They were celebrated for their skill in music, (XIV. p. 617, 634.) and other arts. (X. p. 432. III. p. 112.) They are said to have invented games, and to have been the first to coin money. (Herod. I. 94.) The conquest of Lydia, so far from really increasing the power of the Persians, tended rather to weaken it, by softening their manners, and rendering them as effeminate as the subjects of Crœsus; a contagion from which the Ionians had already suffered. The great wealth and fertility of the country have always caused it to be considered as the most valuable portion of Asia Minor, and its government was probably the highest mark of distinction and trust which the king of Persia could bestow upon a subject. In the division of the empire made by Darius, the Lydians,

and some small tribes, apparently of Maeonian origin, together with the Mysians, formed the second satrapy, and paid into the royal treasury the yearly sum of 500 talents. (III. 90.) Sardis was the residence of the satrap, who appears rather to have been the king's lieutenant in Asia, and superior to the other governors. This was especially the case during the Ionian revolt, and indeed the whole of the reigns of Darius and Xerxes. (Herod. prop.) Lydia, somewhat later, became the principal seat of the power usurped by the younger Cyrus, and after his overthrow was committed to the government of his enemy Tissaphernes. (Xen. Anab. I. 1. Hell. I. 5. III. 1.) After the death of Alexander, we find it subject for a time to Antigonus; then to Achæus, who caused himself to be declared king at Sardes, but was subsequently conquered and put to death by Antiochus. (Polyb. V. 57, 4.) Lydia, after the defeat of the latter sovereign by the Romans at Magnesia, was annexed by them to the dominions of Eumenes. (Liv. XXXVIII. 39.) At a later period it formed a principal part of the proconsular province of Asia, (Plin. V. 29.) and still retained its name through all the vicissitudes of the Byzantine empire, when it finally passed under the dominion of the Turks, who now call its northern portion *Saroukhan*; the southern, *Aidin*. On the north, Lydia was contiguous to the territory of Pergamum, and that part of Mysia which was watered by the Caicus; on the east it bordered on Phrygia; and on the south it was separated from Caria by the tortuous Meander. Its western, or maritime portion was occupied by the Ionian colonies, which have been already treated of.

In describing Lydia it will be convenient to divide it into two portions; the first consisting of the country between the Caicus and the Hermus, the second of that situated between the Hermus and the Meander.

Commencing then with the former, and setting out from Pergamum, Strabo notices to the east of that city a town named Apollonia, and situate on a height. (XIII. p. 625.) It is difficult to say whether this place was in Mysia^b or Lydia, as Steph. Byz. names two in both provinces. If this is the Apollonia which Ptolemy places near the Cilbianus Campus, it would certainly belong to the latter. Beyond, continues Strabo, the road crosses a chain of hills, and then proceeds towards Sardes. The traveller has then on his left Thyatira, and on his right Apollonis, named after the wife of Attalus, a lady of Cyzicus. It was 300 stadia from Pergamum, and the same distance from Sardes. (Strab. loc. cit.) This town is frequently alluded to by Cicero. (Orat. pro Flacc. c. 21 et 32. Epist. ad Quint. I. 2. Cf. Tacit. Ann. II. 47.) In Pliny's time it was a place of little consequence. (V. 30.) The Ecclesiastical Notices mention it as the see of a bishop^c. Some vestige of this ancient town is yet perceptible in that of *Bullene*, a hamlet whose situation agrees in other respects with Strabo's description. Strabo does not take notice of a river which it is necessary to cross after the Caicus. This is the ancient Hyllus^{fl.}, the principal tributary of the Hermus, accord-^{qui et} Phrygius. ing to Herodotus. (I. 80.) It rises in Phrygia Epic-

^b It has therefore been noticed under that province.

imperial coins of Apollonis with the legend ΑΠΟΛΛΩΝΙΔΕΩΝ.

^c There are autonomous and

tetus, not far from the source of the Rhyn^dacus^d, and joins the Hermus a little above the site of the ancient Magnesia ad Sipylum. Strabo adds, that in his time this river commonly bore the name of Phrygius. Pliny, however, distinguishes between the Hyllus and the Phryx, or Phrygius; (V. 29.) and if he is correct, it is probable that, in his opinion, the Hyllus was the river of Thyatira ; the Phrygius, the larger branch which comes from the north-east, and rises in the hills of the ancient Phrygia Epictetus. Livy also, in his account of the operations of Scipio prior to the battle of Magnesia, speaks of the Phrygians as being in the vicinity of Thyatira and Magnesia. (XXXVII. 37 and 38.^e) Homer had carefully distinguished between the Hermus and the Hyllus.

. . . . τοι τέμνος πατρώϊόν ἔστιν,
"Τλλω ἐπ' ιχθύεντι, καὶ," Ερμω δινήεντι.

IL. Υ. 391.

The plain watered by the Hyllus, or Phrygius, bore
 Hyrcanius
 Campus. anciently the name of Campus Hyrcanius. Strabo
 accounts for the origin of the term by informing us, that a colony of Hyrcanians had been settled there by the Persians. (XIII. p. 629.) Xenophon probably alludes to these Hyrcanians. (Anab. VII.) Subsequently some Macedonians were settled here; whence Pliny and Tacitus term them, “Macedones “Hyrcani cognominati.” (Plin. V. 29. Tacit. Annal. II. 47. Cf. Liv. XXXVII. 37. Steph. Byz. v. Ὑρκα-

^d See Major Keppel's Travels in Asia Minor, tom. II. p. 261.

^e Col. Leake conceives that Livy gives the name of Phry-

gius to the Hermus. Asia Minor, p. 267. At all events the historian is not accurate, in omitting to distinguish the two rivers.

via.) There appears to have been also a town in this district bearing the name of Hyrcania. (Hieron. Chron. et Niceph.)

Mostene, according to Tacitus, was another town *Mostene*. belonging to these Macedones Hyrcani. (loc. cit.) It is also mentioned by Ptolemy, Hierocles, (p. 671.) and the Ecclesiastical Notices^f. Its situation, as well as that of Hyrcania, is not ascertained.

Thyatira stood further north, and on the borders of Mysia; Pliny reports that it was watered by the Lycus, a small stream apparently which joins the Hyllus, and adds, that it was anciently called Pelopia and Euhippa. (V. 29.) Strabo informs us that it was a Macedonian colony, (XIII. p. 625,) and Steph. Byz. confirms this account, while he adds to it by saying, that it was named by Seleucus Nicanor. (v. Θυάτειρα.) Antiochus was encamped in its vicinity when about to engage with the Roman army under Scipio, but retired to Magnesia on his approach. (Liv. XXXVII. 8. 21, 37.) It surrendered to the consul after the battle. (XXXVII. 44. Polyb. Frag. XVI. 1. 7. XXXII. 25, 10. Appian. Syr. Plut. Syll.) Thyatira is interesting to the Christian antiquarian, as one of the seven churches of the Apocalypse. The divine message which the apostle was commissioned to deliver unto the angel of the church in Thyatira was: “ These things saith the “ Son of God, who hath his eyes like unto a flame “ of fire, and his feet are like fine brass ; I know “ thy works, and charity, and service, and faith, “ and thy patience, and thy works ; and the last to

^f There are imperial coins belonging to the Mosteni and the Hyrcani, the legends KAI-

ΣΑΡΕΩΝ ΜΟΣΤΗΝΩΝ or ΜΟΣΤΗΝΩΝ ΛΤΔΩΝ. and ΜΑΚΕΔ. ΤΡΚΑΝΩΝ. Sestini, p. 109, 110.

" be more than the first. Notwithstanding I have a few things against thee, because thou sufferest that woman Jezebel, which calleth herself a prophetess," &c. (Rev. ii. 18.) In the Acts, xvi. 14, mention is made of Lydia, a purple-seller of Thyatira. The Ecclesiastical Notices give the names of several bishops belonging to this see. We can trace the history of Thyatira down to a late period of the Byzantine empire, but it then appears under the Turkish name of *Akhissar*, or "the white town," (M. Duc. p. 114.) which is its present appellation. Mr. T. Smith was the first to give an account of the antiquities of Thyatira, in his Notice of the Seven Churches of Asia^g. They consist chiefly of inscriptions, and fragments of walls and pillars.

Germa.

The Itineraries place between Pergamum and Thyatira a station named Germa, twenty-five miles from the former, and thirty-three from the latter. (Anton. Itin. p. 335. Tab. Pent. IX. D.) This site agrees nearly with that of *Somma*, on the road from *Bergamah* to *Akhissar*. Somewhat to the north-east, a site called *Bakhir* or *Bakri* was discovered by Chishull to represent the ancient Nacrasa of Ptolemy^h. Critics are of opinion that this town is not different from the Acrasus of Hierocles and the

Nacrasa.

^g P. 16—25. Lat. edit. See also Wheeler and Spon, tom. I. b. iii. p. 253. Chishull, Ant. Asiat. There are numerous coins, both autonomous and imperial, belonging to Thyatira; the latter extend in a series from Augustus to Saloni-nus. The epigraph is ΘΥΑΤΕΙ-ΦΝΩΝ. Sestini, p. 113.

^h Chish. Ant. Asiat. p. 146. The inscription he quotes has for its preamble, Η. ΜΑΚΕΔΟ-ΝΩΝ ΝΑΚΡΑΣΕΙΤΩΝ ΒΟΤΛΗ, and the coins of Nacrasa confirm this orthography. Sestini, p. 110. But the legend on the coins of Acrasus is ΑΚΡΑΣΙΩ-ΤΩΝ. Sestini, p. 105.

Ecclesiastical Acts; (Synecd. p. 670.) but, for the reason assigned in the note, this may be doubted.

To the west of Thyatira Ptolemy places Hiero-^{Hierocæ-}
cæsarea, a town rendered somewhat remarkable for
the worship of Diana Persica, said to have been
established there as early as the reign of Cyrus.
(Tacit. Ann. III. 62. II. 47. Pausan. Eliac. I. 27.)
This also appears on the coins of the city, which
bear the word ΠΕΡΣΙΚΗⁱ. In and about the valley
of the Hyllus, to the east and north-east of Thya-
tira, were several towns assigned to Lydia, though
closely bordering on Mysia. Of these, Gordus, a Juliagor-
place apparently at first not above the rank of a ^{dus.}
village, came afterwards to be a place of some con-
sequence, and obtained the surname of Julia in com-
pliment to Julius Cæsar or Augustus. Ptolemy
names it Juliagordus. (p. 116.) In Hierocles (Sy-
necd. p. 671.) it is simply called Gordus, as well as
in the Ecclesiastical Notices, and Socrates. (Eccl.
Hist. VII. 36^k.) According to the recent researches
of an intelligent traveller, aided by the learned
suggestions of Col. Leake, it would appear that
Julia-gordus, which retains some vestiges of its
name in that of *Ghiurdix*¹, was situate near the
Hyllus, about twelve hours to the east of *Akhissar*.
Somewhat more to the north apparently was
Blaundus, which Strabo assigns to Lydia, but ob-
serves at the same time that it was near Ancyra, a
Phrygian town, seated in the upper valley of the

ⁱ Sestini, p. 108. The usual legend is ΙΕΡΟΚΑΙCAΡΕΩΝ.

* There are several coins of Julia-Gordus. The legend is ΙΟΤΛΙΑ ΓΟΡΔΟC, and ΙΟΤΛΙΕ-ΩΝ ΓΟΡΔΗΝΩΝ. Sestini, p. 108.

¹ Major Keppel, the traveller referred to, does not mention any antiquities as observed by him at this place. Travels, tom. II. p. 272—281.

Macistus, a river which flowed through Mysia and joined the Rhynacus. (Strab. XII. pp. 567, 576.) Blaundus appears, from its coins, to have been colonized by the Macedonians, who are usually termed in ancient authors Myso-Macedones; and it is further collected from the same monuments, that it was situated on a small river, named Hippuriusⁿ. It is probable that Balandus, an episcopal town of Lydia, according to the Ecclesiastical Notices, is no other than Blaundus^o.

South of the Hyllus, on the road from Thyatira to Sardes, we find the lake of *Mermere*, or *Gheul*, anciently known by the name of Gygæa Palus.

Gygæa,
postea
Coloe
palus.

Μήσιν αὐτὸν Μέσθλης τε καὶ Ἀντιφος ἡγησάσθην,
Τὸς Πυλαιμένεος, τῷ Γυγαίῃ τέκε λίμνη.

I. B. 864.

Κεῖσαι, Ὁτρυντείδη, πάντων ἐκπαγλότατ' ἄνδρῶν,
Ἐνθάδε τοι θάνατος· γενεὴ δέ τοι ἐστ' ἐπὶ λίμνη
Γυγαίῃ, ὅθι τοι τέμενος πατρώιον ἐστιν,
Τλλω ἐπ' ιχθυόεντι, καὶ Ἐρμῷ δινήεντι.

I. T. 389.

Strabo observes that this lake, which was afterwards called Coloe, was forty stadia from Sardes. It was said to have been excavated by the hand of man, as a basin for receiving the waters which overflowed the neighbouring plains. (XIII. p. 627.) Near the lake, towards Sardes, was the tomb or tumulus of Alyattes, mentioned by Herodotus as one of the wonders of Lydia; he says, the foundation of this monument was of huge stones, but the

ⁿ They are thus described by Sestini, p. 106. BLAVNDOS. Autonomi. Epigraphe ΒΛΑΤΝΔΕΩΝ. addito MAKE. ΜΑΚΕΔΟΝΩΝ. Mentio situs a Fl. vel a

Fonte Hippurio. ΙΠΠΟΤΡΙΟΣ. Imperatorii a Nerone ad Volusianum.

^o Geogr. Sacr. Car. S. Paul, p. 244.

superstructure was a mound of earth. It was raised by the artisans and courtesans of Sardis. The historian adds, that in his time there were extant on the top of the mound five pillars, on which were inscribed the different portions of the work completed by the several trades; whence it appeared that the courtesans had the greater share in it. The circumference of this huge mound was six stadia and two plethra, and the width thirteen plethra. (I. 93.) Some writers affirmed it was called "the tomb of the "courtesan," and that it had been constructed by a mistress of king Gyges. (Clearch. ap. Athen. XIII. p. 573.) Strabo reports that there were other tombs of the Lydian kings, besides that of Alyattes; which has been confirmed by the observation of modern travellers. The same writer adds, that there was a temple sacred to Diana Coloene, on the banks of the lake, and an object of great veneration to the inhabitants. (XIII. p. 626.) Chandler describes the lake "as very large, it abounds in fish, its colour and "taste like common pond water, with beds of sedge "growing in it. The barrows (or tombs of the kings) "are of various sizes, the smaller made perhaps "for children of the younger branches of the royal "family; four or five are distinguished by their su- "perior magnitude, and are visible as hills at a great "distance: the lake, it is likely, furnished the soil. "All of them are covered with green turf; and as "many as I observed, in passing among them, re- "tain their conical form, without any sinking in of "the top. One of the barrows on the eminence, "near the middle, and towards Sardes, is remark- "ably conspicuous: it was the monument of Alyat-

" tes. It is much taller and handsomer than any I
" have seen in England, or elsewhere^p."

Hermo-
capelia.

In the valley of the Hermus were situated apparently the towns of Hermocapelia^q (Plin. V. 30. Hierocl. p. 670. Notit. Episc.) and Hermopolis, if the two should not be considered rather as one^r.

Saettæ sive
Saittæ.

Hyde.

Saettæ, or Saittæ, to judge from the reference made on its coins to the Hermus and Hyllus, was situated near the junction of these two rivers^s. Ptolemy writes the name Setæ, or Septæ, and fixes it in the north-eastern part of the province. Hierocles calls it Sitæ, (p. 669.) as do also the ecclesiastical records, from which we learn that it was an episcopal see. (Act. Conc. Nic. II. p. 591.) Near the Palus Gygæa stood anciently a place to which reference was made by Homer in the Iliad, when he said,

Τμώλῳ ὑπὸ νιφόεντι, "Υδης ἐν πίονι δήμῳ.

IL. T. 385.

Some writers pretended also that the poet had made mention of it in another line, which is not found in our copies. IL. B. 783.

Χώρῳ ἐνὶ δρυσέντι, "Υδης ἐν πίονι δήμῳ.

But Strabo is inclined to think there was no place of this name in Lydia. (XIII. p. 626.) Plin. V. 28.

^p Chandler, Travels in Asia Minor, p. 325—27.

^q The coins of Hermocapelia are numerous. Some are autonomous. The imperial coins do not ascend higher than Hadrian. The inscription is usually ΕΡΜΟΚΑΠΗΛΕΙΤΩΝ. Sestini, p. 108.

^r The only evidence for the existence of this city are its coins, which are allowed to be dubious. Sestini, p. 108.

^s Sestini, p. 3. Saetteni autonom. Epigraphe CAITTH-ΝΩΝ etiam CAITTAI. Mentio situs a binis flaviis ΕΡΜΟC. ΤΑ-ΛΟC.

" A Mæoniis civitas ipsa Hyde vocitata est, clara
 " stagno Gygæo."

To the east of the Gygæan lake, and on the Her- Attalia.
 mus, is a village named *Adala*, which probably cor-
 responds with the site of Attalia, a Lydian town,
 known to us from Steph. Byz., who says it was
 anciently called Agroira or Alloira. (v. Ἀττάλεια.)
 The Ecclesiastical Notices have recorded some of its
 bishops. A recent traveller passed through *Adala*,
 on his way from Smyrna and *Cassaba*. " It is on
 " the right bank of the Hermus, which flows at the
 " base of a rocky mountain, through a chasm of
 " which it disappears. The passage here is rather
 " dangerous. The direct road from *Cassaba* to
 " *Adala* is twelve hours^t." The same traveller, to
 whom we are indebted for the most accurate account
 we have of the course of the Hermus, and the coun-
 try through which it flows, discovered, somewhat
 higher up that river, an inscription which fixes the
 site of Bagæ, another Lydian town, on the right Bagæ.
 bank of the river, and nearly opposite to *Sirghie*,
 a Turkish village between *Kula* and *Jeni-sher*^u.
Bagæ is ascribed to Lydia by Hierocles (p. 670.)
 and the Ecclesiastical Notices, and its coins are not
 uncommon^x. *Selendi*, a small village some miles
 higher up the valley of the Hermus, has doubtless
 taken the place of Silandus, an episcopal see of Ly- Silandus.
 dia, as we collect from the Acts of the Council of

^t Major Keppel, tom. II. p. 335. No vestiges of antiquity were observed here. There are coins however of Attalea. Sestini, p. 106. Attalia. Autonomi Epigraphe ΑΤΤΑΛΕΑΤΩΝ. Numina. ΚΟΡΗ — ΒΟΠΕΙΘΗΝΗ.

Diana sic vocata.

^u Travels, p. 367, 368.

^x Sestini, p. 106. Bagæ. Autonomi Epigraphe ΒΑΓΗΝΩΝ vel ΚΑΙCAPEΩΝ ΒΑΓΗΝΩΝ. Mentio situs ab Hermo Fl. EP-MOC.

Chalcedony, and its coins ^z. Beyond Silandus we approach the territory of Cadi, which formed part of Phrygia; we must therefore retrace our steps towards the west, in order to describe that portion of Lydia which lies south of the Hermus; and first we may enter upon that section which is intercepted by the parallel streams of the Hermus and Caystrus.

Magnesia
ad Sipy-
lum.

The first town we shall notice will be Magnesia, distinguished by its proximity to mount Sipylus from its Carian namesake, seated in the valley of the Meander, (Strab. XIII. p. 622.) Plin. V. 29. Magnetes a Sipylo. (Cf. Tacit. Ann. II. 47.) We are not informed by whom or when it was founded; but its proximity to the Æolian cities leads to the conjecture that it was colonized by the Magnesians of Thessaly, not long after Cyme and Smyrna had been founded. Magnesia is most celebrated in history for the signal victory obtained under its walls by the Roman army, commanded by Lucius Scipio, assisted by the counsels of his brother Africanus, over the forces of Antiochus; a victory which drove the king of Syria for ever behind the chain of Taurus, and placed Asia Minor at the disposal of the conquerors. (Liv. XXXVII. 37—43.) Magnesia surrendered after the battle. (Ibid. c. 44. Appian. Syr. c. 35.) The Magnesians displayed great bravery in defending their town against Mithridates. (Paus. Attic. c. 20.) In the reign of Tiberius it was nearly destroyed by an earthquake, which shook and overthrew also several other cities in Asia. The emperor on this occasion granted considerable sums from the

^y Geogr. Sacr. p. 244.

ΔΕΩΝ. Imperatorii Domitiani,

^z Sestini, p. 112. Silandus.

Commodi, &c.

Autonomi Epigraphe ΣΙΛΑΝ-

treasury, to repair the losses occasioned by this disaster. (Strab. XII. p. 579. XIII. p. 622. Tacit. Ann. II. 47.) We know from its coins that Magnesia continued to flourish at a late period of the Roman empire^a. It is often alluded to by the Byzantine historians, and still preserves, under the corrupt appellation of *Manissa*, evident traces of its classical name. It was once the residence of the Turkish sultans, but is now much reduced^b.

Mount Sipylus rises to the south of *Manissa*, and is separated by a small valley from the chain of Tmolus to the south-east, and by another from mount Mastusia to the south. Sipylus is celebrated in Grecian mythology as the residence of Tantalus and Niobe, and the cradle of Pelops. These princes, though more commonly referred to by classical writers as belonging to Phrygia, must in reality have reigned in Lydia, if they occupied Sipylus, not in the mountain merely, but a city of the same name situated on its slope, and which, according to traditions preserved in the country, had been swallowed up by an earthquake and plunged into a crater afterwards filled by a lake. The existence of this lake, named Sale or Saloe, is attested by Pausanias, who reports that for some time the ruins of the town, which he calls Idea, if the word be not corrupt, could be seen at the bottom. (Ach. c. 24.) Strabo also confirms the destruction of this town by an earthquake. (I. p. 58.) Pliny reports that it had often changed its

^a Sestini, p. 109. Magnesia. Auton. copiosi. Epig. ΜΑΓΝΗΤΩΝ ΣΙΠΤΛΟΥ. Imperatorii ab Augusto cum Livia usque ad Saloninam. Conditor Tiberius, ΤΙΒΕΡΙΟΝ ΣΕΒΑΣΤΟΝ ΚΤΙ-

ΣΤΗΝ. Mentio situs a Monte Sipylo et a Fl. Hermo.

^b Chandler, Travels in Asia, tom. II. p. 332. Major Keppel's Travels, tom. II. p. 295.

name, and he mentions besides the destruction of two other places. (V. 29.) “*Interiere intus Daphnus et Hermesia, et Sipylum quod ante Tantalis vocabatur, caput Mæoniæ, ubi nunc est stagnum Sale: obiit et Archæopolis substituta Sipylo, et inde illi Colpe et huic Lebade.*” Pausanias elsewhere calls this lake the marsh of Tantalus; and he adds, that the tomb of that prince was conspicuous near it. (Eliac. I. c. 13.) The same writer adds, that the throne of Pelops was shewn on the summit of the mountain above the temple of Cybele, surnamed Plastene. It certainly was the prevailing opinion among the ancients that Pelops came from Sipylus. (Athen. XIV. p. 625. Strab. XII. p. 571.) Homer has made an allusion to this mountain as the scene of Niobe’s metamorphosis :

Νῦν δέ που ἐν πέτρησιν, ἐν οὔρεσιν οἰοπόλοισιν,
Ἐν Σικύλῳ, δῆι φασὶ θεάων ἔμμεναι εύνας
Νυμφάσιν, αἵτ’ ἀμφ’ Ἀχελώιον ἐρράσαντο,
Ἐνδια, λίθος περ ἐοῦσα, θεῶν ἐκ, κήδει πέσσει.

IL. Ω. 614.

This passage has been beautifully imitated by Sophocles in the Antigone. (v. 822.)

*Ηκουσα δὴ λυγρόταταν ὄλεσθαι
Τὰν Φρυγίαν ξέναν.
Ταντάλου, Σικύλῳ πρὸς ἄκρῳ
Τὰν, χισσὸς ώς ἀτενῆς,
Περγαία βλάστα δάμασεν· καὶ νῦν
*Ομβρῷ τακομένας,
‘Ως φάτις ἀνδρῶν,
Χιών τ’ οὐδαμὰ λείπει,
Τέγγει θ’ ὑπ’ ὁφρύσι παγκλαύτοις
Δείραδας—

and Ovid. (Metam. VI. 310.)

Flet tamen, et validi circumdata turbine venti
 In patriam rapta est. Ibi fixa cacumine montis
 Liquitur, et lacrymas etiamnum marmora manant.

(Cf. Pausan. Arcad. c. 2. Apollod. III. 5, 6.) This part of the story of Niobe is to be accounted for by some optical phenomenon exhibited by the mountain. Pausanias states, “that he visited mount Sipylus, and witnessed this appearance himself: “when viewed close, he saw only the rock and precipices; nothing whatever which resembled a woman, either weeping, or in any other posture; “but if you stood at a distance, you would fancy “that you beheld a woman in an attitude of grief, “and in tears.” (Attic. c. 21.) “The phantom of Niobe,” says Chandler, “may be defined an effect “of a certain portion of light and shade on a part “of Sipylus, perceivable at a particular point of “view. The traveller, who shall visit Magnesia “after this information, is requested to observe carefully a steep and remarkable cliff, about a mile “from the town: varying his distance, while the “sun and shade, which come gradually on, pass “over it, I have reason to believe he will see “Niobe.” The same traveller elsewhere observes, that “the mountain, terminating on the north-east “in a vast naked precipice, has now beneath it a “very limpid water, with a small marsh, not far “from a sepulchre cut in the rock, and there perhaps was Sale, and the site of Sipylus.^d” Pausanias speaks of the rock of Coddinus near Magnesia,

^c Chandler's Travels in Asia Minor, p. 331. This remark has been confirmed by a subsequent traveller, who describes

the phenomenon very fully. Emerson's Letters from the Ægean, tom. II. in fin.

^d Travels, p. 331.

Nym-
phæum.

Chliara.

Ægara.

Cryon fl.

Draco
mons.

where was a most ancient statue of Cybele, said to be the work of Broteas, son of Tantalus. (Lacon. c. 22.) The modern appellation of Sipylus is *Saboundji Dagh*, and sometimes *Sipuli Dagh*. On the southern side of the mountain, and near the road leading from Smyrna to the ruins of Sardes, a spot named *Nif*, or *Nymphi*, recalls to mind the Nymphæum of the Byzantine emperors, a spot where they are represented by the historians of that period, to have enjoyed the fine season, apart from the cares of public life and the tumult of war. (G. Acropol. p. 56. G. Pachym. Andr. Pal. p. 153. M. Duc. p. 45.) The same writers often speak of Chliara, in conjunction with Nymphæum and the coast of Ionia. (Ann. Comn. p. 421. D. p. 429. C.) Judging from the name, it would seem to have been a place noted for warm springs and baths. It suffered from a disastrous earthquake in the time of Andronicus Palæologus. (G. Pach. p. 158.) In this direction Ptolemy places Ægara, which is unknown to all other geographers. It answers perhaps to *Dourgoutli*, or *Cassaba*, between Smyrna and Sardes. The river which passes near it and falls into the Hermus is perhaps the Cryon of Pliny. (V. 29.) From Smyrna and the Ionian coast there extends a continued chain of mountains throughout the whole length of Lydia. It commences, as Pliny remarks, with Mastusia, which answers to the modern *Tartali*. This, he says, is connected on one side with mount Termes ^e, which joins the roots of Olympus; on the other with mount Draco, which joins Tmolus, this Cadmus, and that finally the central ridge

^e For Termes, we should perhaps read Temnus.

of Taurus. Mount Draco seems to answer to the summit called by the Turks *Kizil-djeh Mousseh Dagh*. Tmolus is a broad and elevated mass of mountains, which sends several tributary torrents into the Hermus on the one side, and into the Cayster on the other, and divides, in fact, the valleys through which those two rivers flow. It was said to derive its name from Timolus, or Tmolus, a Lydian king, having been previously called Carmarnorius. (Auct. de Fluv. in Pactol.) This mountain was much celebrated for its wine. (Plin. V. 29.)

Sunt etiam Amineæ vites, firmissima vina :

Tmolius assurgit quibus, et rex ipse Phanæus.

VIRG. GEORG. II. 97.

Hinc nota Baccho Tmolus attollit juga.

SENEC. PHÆN. v. 602.

Deseruere sui Nymphæ vineta Timoli.

OVID. METAM. VI. 15.

Hence the frequent reference to it in the Bacchæ of Euripides.

XO. Ἀσίας ἀπὸ γῆς

Ιερὸν Τμῶλον ἀμείψασα, θοάζω

Βρομίω.

v. 64.

ἀλλ' ὁ λιποῦσαι Τμῶλον, ἔρυμα Λυδίας.

v. 55.

(Cf. Strab. XIV. p. 637.) It appears also to have abounded with shrubs and evergreens. (Callim. Frag. XCIII.) nor was it less noted for its mineral productions. It yielded tin; and Pactolus washed *Pactolus fl.* from its cavities a rich supply of golden ore. (Strab. (XIII. p. 610. p. 625.) This little stream, which is so closely connected by the ancient poets with the name and wealth of Croesus, rose on mount Tmolus,

and after flowing beneath the walls of Sardes was received by the Hermus. Pliny reports, that it was sometimes called Chrysorrhoas, and its source Tarne. (V. 29. Conf. Athen. V. p. 203. C. Herod. V. 101. Auct. de Fluv. in Pactol.)

Mæonia generose domo : ubi pinguia culta
Exercentque viri, Pactolusque irrigat auro.

VIRG. ÆN. X. 141.

Et qua trahens opulenta Pactolus vada
Inundat auro rura. SENECA. PHÆN. 604.

Sed cuius votis modo non sufficerat aurum,
Quod Tagus et rutila volvit Pactolus arena.

JUVEN. SAT. XIV. 298.

A celebrated temple of Cybele rose on its banks, which is alluded to by Sophocles :

'Ορεστέρα παμβῶτι Γᾶ,
Μᾶτερ αὐτοῦ Διὸς,
Ἄ τὸν μέγαν Πακτωλὸν εὔχρυσον νέμεις.

PHILOST. 391.

This temple appears to have suffered in the burning of Sardes by the Ionians and Athenians. (Herod. V. 102.)

Callimachus and Dionysius Periegetes speak of the swans of Pactolus :

'Η μὲν ἔφη· κύκνοι δὲ θεοῦ μέλποντες ἀοιδοί¹
Μηόνιον Πακτωλὸν ἔχυκλώσαντο λιπόντες
Ἐβδομάχις περὶ Δῆλον. HYMN. IN DEL. 249.

Μηνίη δὲ ἐπὶ τῆσιν ἐπ' ἀντολίην τετάνυσται
Τμώλῳ ύπ' ἡνεμόεντι· τόθεν Πακτωλὸς ὁδεύων
Χρυσὸν ὁμοῦ δίνησιν ἐφελκόμενος κελαρύζει.
Τοῦ δὲ ἀν ἐπὶ πλευρῆσι καθήμενος εἴαρος ὥρη
Κύκνων εἰσαῖτοις λιγυρὴν ὅπα, τοῖ τε καθ' ὕδωρ
Ἐνθα καὶ ἔνθα νέμονται ἀεξομένης ἐπὶ ποίης.

DION. PERIEG. 830.

The Turkish name of this poetical rivulet is *Ba-*

gouly. Some extensive ruins, belonging apparently to the temple of Cybele, were observed by Chishull in 1699; but Chandler, who visited them subsequently, found that they had materially suffered in the interval. There were, however, five Ionic columns still standing; the shafts fluted, and the capitals designed and carved with exquisite taste and skill^f. Strabo reports, that on the top of Tmolus there was a watch-tower erected by the Persians: it was of white marble, and commanded an extensive view of the surrounding country. (XIII. p. 625.) The mountain is called *Bous Dagh* by the Turks. It is described by Chishull as “pleasant, “ and garnished with an infinite variety of plants, “ shrubs, and trees. Besides a fine prospect of the “ country, the traveller is amused with impending “ rocks, perpendicular precipices, and the murmurs “ of a brook, probably the Pactolus. On the top “ is a fruitful vale between two lofty ridges, with a “ vein of marble as clear and pellucid as alabaster.” In the central part of the ridge, as the name indicates, was a town, or community, entitled Mesotimolitæ, or Mesotmolitæ. They are mentioned by Pliny, (V. 29.) and the Ecclesiastical Notitiæ, together with Hierocles. (p. 671.) Tacitus speaks of a town named Tmolus, which was destroyed by an earthquake under Tiberius. (Ann. II. 47. Niceph. Call. I. 17.^b)

Sardes, the capital of Lydia, was situated in a fertile plain at the foot of the northern slope of Tmolus. Pactolus flowed through the forum, and soon

^f Travels in Asia Minor, p. 319.

^g Travels, p. 16.

^h Some coins are extant with the inscription ΤΜΩΛΕΙΤΩΝ. Sestini, p. 114.

after joined the Hermus. (Herod. V. 101.) Its foundation, as Strabo reports, does not reach to the Trojan era, but it was nevertheless a city of great antiquity. (XIII. p. 625.) Herodotus informs us that it was first fortified by Meles, who, according to the Chronicle of Eusebius, preceded Candaules. That prince was ordered by the oracle of Telmissus to carry his infant son Leon round the fortifications of the city ; but he neglected to do this, with respect to that part of the citadel which looks toward Tmolus, conceiving that this point was unassailable. It was nevertheless in this quarter that Cyrus succeeded in storming the place. (I. 84.) Herodotus however affirms, that Agron had reigned at Sardes, and this prince must have preceded Meles by several generations. (I. 7.) In the reign of Ardys, son of Gyges, this city was taken by the Cimmerians during the incursion they made into Asia ; but they could not conquer the citadel, and they were finally expelled by Alyattes, father of Croesus. (I. 15, 16. Cf. Callisth. ap. Strab. XIII. p. 627.) Under the reign of the latter, Sardes became a great and flourishing city, the resort of men of talent and learning, attracted thither by the fame and hospitality of Croesus. (I. 29.) After the overthrow of this monarch by Cyrus, it still continued to be the chief town of the Persian dominions in this part of Asia, and the residence of the lieutenant of the great king. (V. 25. Pausan. Lacon. c. 9.) On the revolt excited by Aristagoras and Histiaeus, the Ionians, assisted by an Athenian force, marched suddenly from Ephesus up the river Caystrus, and having crossed mount Tmolus surprised Sardes, except the citadel, which was defended by Artaphernes with a numerous gar-

rison. Sardes on this occasion was accidentally set on fire and burned to the ground, as most of the houses were constructed of reeds; even those which were of brick had roofs made of the former substance. After this event the Ionians and their allies were forced to evacuate the place and retire to the coast: but the burning of Sardes was long remembered by Darius, and it was to avenge this insult that he invaded Attica, and fought the battle of Marathon. (V. 100—105.) It was at Sardes that Xerxes passed the winter previous to his expedition into Greece. (VII. 32—37.) It was here also that the younger Cyrus collected his army when about to march against the king, his brother. (Xen. Anab. I. 2. 5.) This prince had indeed made it his chief residence; and the beauty of his gardens is reported to have excited the admiration of Lysander, especially when he learnt that he often laboured there with his own hands. (Xen. Econ. p. 830. C. Cic. de Senect. c. 17.)

. . . quid Croesi regia Sardis?
Smyrna quid, et Colophon ?

HOR. EPIST. I. 11. 2.

Sardes surrendered to Alexander without resistance soon after the battle of the Granicus. Arrian reports, that he visited the citadel, and admired the height and strength of its position, defended besides by a triple line of fortifications. He gave orders on this occasion that a temple and altar should be erected to Olympian Jove. Alexander also commanded that the Lydians should regain their freedom, and resume their ancient laws and usages. (I. 17.) On the death of the king of Macedon, Sardes and Lydia came into the possession of Antigonus, and after the defeat of

that general at Ipsus, into that of the Seleucidæ : but Seleucus Ceraunus having been assassinated, this part of his dominions was usurped by Achæus, his relation by marriage. That officer at first conducted himself with great prudence and moderation, professing to hold the reins of government for Antiochus, brother of Seleucus ; but, finally, urged by his ambition, and emboldened by success, he threw off the mask, and assumed the crown, and title of king. (Polyb. IV. 48. V. 57.) Antiochus, however, having ascended the throne of Syria, did not suffer Achæus to enjoy long the principality of which he sought to defraud him. He invaded Lydia, and Achæus, being too weak to cope with the Syrian forces in the field, was shut up in Sardes, where he defied, for a whole year, all the efforts of the enemy to become master of the town and citadel. At length, however, Lagoras, a Cretan officer in the service of Antiochus, having observed a part of the fortifications called Prion, where the citadel joined the town, unguarded, scaled the ramparts, and won the city. (Polyb. VII. 4—7.) From the possession of Antiochus, Sardes passed into that of the Romans, having surrendered to the two Scipios after their victory at Magnesia. (Id. XXI. 13. 1.) In the reign of Tiberius, the Sardians preferred their claim to the honour of erecting a temple to the emperor, and alleged their connexion with Italy through the migration of Tyrrhenus ; but their arguments were not thought so valid as those urged by the people of Smyrna, and the latter city was preferred. (Tacit. Ann. IV. 55.) Sardes was indebted to Tiberius for its restoration after a disastrous earthquake, which had made it a heap of ruins. (Tacit. Ann. II. 47. Strab.

XIII. p. 627.) We are not informed in the sacred writings when Christianity was first established at Sardes, but it was probably not long after St. Paul had founded the church at Ephesus; and there can be little doubt that the metropolis of Lydia is included in the declaration made by St. Luke, that "all they which dwelt in Asia heard the word of "the Lord Jesus, both Jews and Greeks;" (Acts xix. 10.) and in the salutation to the Corinthians from all the churches of Asia. (1 Cor. xvi. 19.) This is rendered manifest by the Book of Revelations, where Sardes is expressly named among the seven churches of that province. When the warning voice was addressed to it by the mouth of the apostle, it was then evidently already declining. "And unto the "angel of the church in Sardis write; These things "saith he that hath the seven Spirits of God, and "the seven stars; I know thy works, that thou hast "a name that thou livest, and art dead. Be watch- "ful, and strengthen the things which remain, that "are ready to die: for I have not found thy works "perfect before God. Remember therefore how "thou hast received and heard, and hold fast, and "repent. If therefore thou shalt not watch, I will "come on thee as a thief, and thou shalt not know "what hour I will come upon thee. Thou hast a "few names even in Sardis which have not defiled "their garments; and they shall walk with me in "white: for they are worthy." (Rev. iii. 1—5.) Ecclesiastical history mentions more than one council held in this see. From Pliny we learn that it was the capital of a conventus juridicus. (V. 29.) We trace the history of this once flourishing and

opulent city through the Roman emperors to the close of the Byzantine dynasty. (Eunap. p. 154. Hierocl. p. 669.ⁱ) The Turks took possession of it in the eleventh century, and two centuries later it was nearly destroyed by Tamerlane. (Ann. Comn. p. 323. Pachym. tom. II. p. 279. M. Duc. p. 39.) It is now little more than a village, built in the midst of extensive ruins, to which the name of *Sart* is yet attached. Mr. Smith, in his Notice of the Seven Churches, describes the remains of Sardis as very considerable, and giving a great idea of the size and magnificence of the city ^k.

"The site of this once noble city," says Chandler, "was now green and flowery. Coming from the east we had the ground-plot of the theatre at some distance on our left hand, with a small brook near us running before it. The structure was in a brow, which unites with the hill of the citadel, and was called Prion. Going on, we passed by remnants of massive buildings; marble piers sustaining heavy fragments of arches of brick, and more indistinct ruins. These are in the plain before the hill of the citadel. On our right hand, near the road, was a portion of a large edifice, with a heap of ponderous materials before and behind it. The walls are standing of two large, lofty, and very long rooms, with a space between them, as of a passage. This remain, it has been conjectured, was the house of Croesus, once appropriated by the Sardians as a place of retirement to superan-

ⁱ The imperial coins of Sardis may be traced from Augustus to Salonina: the common legend is ΣΑΡΔΙΑΝΩΝ. Some

are inscribed ΣΑΡΔΙΣ. ΛΣΙΑΣ. ΛΥΔΙΑΣ. ΜΗΤΡΟΠΟΛΙΣ. Sestini, p. 111.

^k P. 27—31. Lat. ed.

"nuated citizens. It was called the Gerusia, and in "it, as some Roman authors have remarked, was "exemplified the extreme durability of the ancient "brick. (Vitruv. II. 8. Plin. XXXV. 14.) The "hill on which the citadel stood, appears from the "plain to be triangular. It is sandy, and the sides "rough. The fortress is abandoned, but has a "double wall, besides outworks, in ruins. The "eminence affords a fine prospect of the country, "and in the walls are two or three fragments with "inscriptions. Not far from the west end is the "celebrated river Pactolus, which rises in the moun- "tain behind, and once flowed through the middle "of the market-place of Sardes. We passed the "miserable village of *Sart*, which stands, with a "ruinous mosque, above the river, on a root or spur "of the hill of the citadel¹." Before quitting Sardes we may remark, that this city has given birth to the poet Alcman, who is thought to have been contemporary with Gyges, and to have afterwards resided in Laconia. This is proved by an epigram of Alexander the Ætolian. (Anth. Pal. VII. 709.)

Σάρδιες ἀρχαῖαι, πατέρων νομός, εἰ μὲν ἐν ὑμῖν
 'Ετρεφόμαν, χέρνας ἦν τις ἀνὴρ βακέλας
 Χρυσοφόρος, βῆσσων καλὰ τύμπανα· νῦν δέ μοι Ἀλκμὰν
 Οὔνομα, καὶ Σπάρτας εἰμὶ πολυτρίποδος.
 Καὶ Μούσας ἐδάην Ἐλικωνίδας, αἴ με τυράννων
 Θῆκαν Δασκύλεω μείζονα καὶ Γύγεω.

Strabo also mentions two orators, named Diodorus, who were of Sardes; and we may add to them Eunapius, the historian. On the southern slope of

¹ Travels in Asia Minor, p. 316—318. There is a view and plan of Sardis in the Travels of Mons. Peysonnel.

Hypæpa. mount Tmolus, and near the sources of the Caystrus, stood Hypæpa, a city of no extent, but frequently mentioned by classical authors. (Strab. XIII. p. 627.)

. riget arduus alto
Tmolus in ascensu; clivoque extensus utroque,
Sardibus hinc, illinc parvis finitur Hypæpis.

OVID. METAM. XI. 150.

Orta domo parva, parvis habitabat Hypæpis.

ID. VI. 13.

Pausanias reports, that sacrifices were offered here by some Lydians, who were of Persian extraction. The ceremony was performed by a magus (Eliac. I. 27.) The Hypæpeni claimed the honour of erecting a temple to Tiberius, probably on account of these local rites, but they were rejected. (Tacit. Annal. IV. 55.) The sex here was said to be remarkably beautiful. (Steph. Byz. v. "Τπαικα.) The Lydian women generally were entitled to the same praise; and their grace in the dance has been celebrated by Dionysius Periegetes, in these elegant lines. (v. 839.)

Οὐ μὰν οὐδὲ γυναικας ὀνόσσεαι, αἱ περὶ κεῖνο
Θεῖον ἔδος, χρυσοῖο κατ' ιξύος ἄμμα βαλοῦσαι
Ὀρχεῦνται, θηητὸν ἐλισσόμεναι περὶ κύκλου·
Εὖτε Διωνύσου ο χοροστασίας τελέοιεν
Σὺν καὶ παρθενικαὶ, νεοθηλέες οἵα τε νεβροὶ,
Σκαίρουσιν τῆσιν δὲ πέρι σμαραγεῦντες ἀηται
Ίμερτοὺς δονέουσιν ἐπὶ στήθεσσι χιτῶνας.

Hypæpa is also noticed by Ptolemy, Pliny, (V. 29.) and the Ecclesiastical records and Acts of Councils^m.

^m Geogr. Sacr. p. 236. The coins of this city are not rare: the epigraph is ΤΠΑΙΠΗΝΩΝ. The name of the Cayster is visible on some. Sestini, p. 108.

Its ruins are to be seen close to the little town of *Pirghé*, or *Birkhé*, probably a corruption of Πύργον. Chandler conjectures that a fortress was erected there to command the pass of mount Tmolus ⁿ.

In the immediate vicinity of Hypæpa stood a village, named Caloe, where Leo Diaconus, the Byzantine historian, was born, as he himself informs us. He describes it as a beautiful spot on the slope of Tmolus, and near the source of the Caystrus. (Leo Diac. Hist. I. c. 1.) In Hierocles, it is probable we ought to substitute Caloe for Colose, (p. 660.) as mention is made of its bishops in the Acts of Councils. There is little doubt that the site answers to the spot marked in Lapie's map under the name of *Caliveh Khan*, on a mountain tract leading from *Birghé* to *Dourgoutli*.

The Caystrus, on leaving the mountain, flows through a rich and beautiful plain, anciently called Cilbianus ^{Campus.}. This was divided into Upper and Lower; a fact which we learn from Pliny, (V. 29.) and also from the coins struck by the inhabitants of both valleys ^o. Strabo reports, that the Cilbianus Campus was extensive, fertile, and well peopled. (XIII. p. 629.) The lower plain, which belonged to the Ephesians, contained some mines of cinnabar. (Vitruv. VII. 8. Plin. XXXIII. 7.) The only Lydian town we have to notice in the western part of the province is Metropolis, whose ruins are to be seen near a place called *Cabadja*, at the back of mount Gallesus, which, as we have seen, rose above Colo-

ⁿ Travels in Asia Minor, p. 321.

^o Sestini, p. 107. Cilbiani Inferiores, ΚΙΛΒΙΑΝΩΝ ΤΩΝ ΚΑΤΩ. Cilbiani Superiores, ΚΙΛ-

ΒΙΑΝΩΝ ΤΩΝ ΑΝΩ. From the same numismatic writer we learn that there were other Cilbiani, styled ΝΕΙΚΑΙΕΙΣ, ΠΕΡΓΑΜΗΝΟΙ, and ΚΕΑΙΤΟΙ.

Hypæpa. mount Tmolus, and near the sources of the Caystrus, stood Hypæpa, a city of no extent, but frequently mentioned by classical authors. (Strab. XIII. p. 627.)

. riget arduus alto
Tmolus in ascensu; clivoque extensus utroque,
Sardibus hinc, illinc parvis finitur Hypæpis.

OVID. METAM. XI. 150.

Orta domo parva, parvis habitabat Hypæpis.

ID. VI. 13.

Pausanias reports, that sacrifices were offered here by some Lydians, who were of Persian extraction. The ceremony was performed by a magus (Eliac. I. 27.) The Hypæpeni claimed the honour of erecting a temple to Tiberius, probably on account of these local rites, but they were rejected. (Tacit. Annal. IV. 55.) The sex here was said to be remarkably beautiful. (Steph. Byz. v. "Τπαιπα.) The Lydian women generally were entitled to the same praise; and their grace in the dance has been celebrated by Dionysius Periegetes, in these elegant lines. (v. 839.)

Οὐ μὰν οὐδὲ γυναικας ὀνόστεαι, αἱ περὶ κεῖνο
Θεῖον ἔδος, χρυσοῖο κατ' ἵξυος ἄμμα βαλοῦσαι
Ὀρχεῦνται, θηητὸν ἐλισσόμεναι περὶ κύκλου·
Εὗτε Διωνύσου οι χοροστασίας τελέοιεν
Σὺν καὶ παρθενικαὶ, νεοθηλέες οἵα τε νεβροὶ,
Σκαίρουσιν τῆσιν δὲ πέρι σμαραγδεῦντες ἀηται
Ίμερτοὺς δονέουσιν ἐπὶ στήθεσσι χιτῶνας.

Hypæpa is also noticed by Ptolemy, Pliny, (V. 29.) and the Ecclesiastical records and Acts of Councils^m.

^m Geogr. Sacr. p. 236. The coins of this city are not rare: the epigraph is ΤΠΑΙΠΗΝΩΝ. The name of the Cayster is visible on some. Sestini, p. 108.

Its ruins are to be seen close to the little town of *Pirghé*, or *Birkhé*, probably a corruption of Πύργιον. Chandler conjectures that a fortress was erected there to command the pass of mount Tmolus ⁿ.

In the immediate vicinity of Hypæpa stood a village, named Caloe, where Leo Diaconus, the Byzantine historian, was born, as he himself informs us. He describes it as a beautiful spot on the slope of Tmolus, and near the source of the Caystrus. (Leo Diac. Hist. I. c. 1.) In Hierocles, it is probable we ought to substitute Caloe for Colose, (p. 660.) as mention is made of its bishops in the Acts of Councils. There is little doubt that the site answers to the spot marked in Lapie's map under the name of *Caliveh Khan*, on a mountain tract leading from *Birghé* to *Dourgoutli*.

The Caystrus, on leaving the mountain, flows through a rich and beautiful plain, anciently called Cilbianus ^{Campus.}. This was divided into Upper and Lower; a fact which we learn from Pliny, (V. 29.) and also from the coins struck by the inhabitants of both valleys ^o. Strabo reports, that the Cilbianus Campus was extensive, fertile, and well peopled. (XIII. p. 629.) The lower plain, which belonged to the Ephesians, contained some mines of cinnabar. (Vitruv. VII. 8. Plin. XXXIII. 7.) The only Lydian town we have to notice in the western part of the province is Metropolis, whose ruins are to be seen near a place called *Cabadja*, at the back of mount Gallesus, which, as we have seen, rose above Colo-

ⁿ Travels in Asia Minor, p. 321.

^o Sestini, p. 107. Cilbiani Inferiores, ΚΙΛΒΙΑΝΩΝ ΤΩΝ ΝΕΙΚΑΙΕΙΣ, ΠΕΡΓΑΜΗΝΟΙ, and KEAITOI.

ΒΙΑΝΩΝ ΤΩΝ ΑΝΩ. From the same numismatic writer we learn that there were other Cilbiani, styled ΝΕΙΚΑΙΕΙΣ, ΠΕΡΓΑΜΗΝΟΙ, and KEAITOI.

phon and Notium. It is mentioned by Ptolemy and Steph. Byz. (v. Μητρόπολις.) One of its bishops subscribed to the Council of Chalcedon ^{P.}

Catacecau-
mene re-
gio.

Returning to Sardes and its territory, the Sardianus Campus of Herodotus, (I. 80.) and proceeding along the left bank of the Hermus towards its source, we shall reach that district of Lydia, or Mæonia, which was named by the Greeks Catacecaumene, (Κατακεκαυμένη,) or “the Burnt,” from its volcanic appearance and character. Strabo observes, that this country was traversed by the Hermus, and by some was assigned to Mysia. He also states, that Xanthus, the Lydian historian, and other writers, placed here the Arimi of Homer, and the scene of Typhœus' punishment. (XII. p. 579. XIII. p. 628.) According to Strabo, this district was 500 stadia in length, and 400 in breadth: the valleys were covered with ashes, and the rocks and hills were blackened as with fire. This judicious writer does not hesitate to ascribe this to the effect of extinct volcanoes, the three principal craters of which were visible in his time, at a distance of about forty stadia from each other. There were also hillocks, formed of lava and other substances, which attested the existence of igneous action at some previous period. The only produce of the country was wine, which, however, was of an excellent quality; hence it was wittily observed, that it was with reason that Bacchus was termed Πυριγενῆς, or born of fire. The account which a recent traveller gives of this country, accords strikingly with the description given of it by Strabo. Having crossed the Hermus at *Adala*, Attalea, he says, “we continued to march in an

“ easterly direction, and traversed a range of mountains of white and coloured marble. As we approached *Kula*, the road was entirely black, and strewed with cinder-looking substances. Wherever the rock was broken, it exhibited the same black appearance. The people here call this mountain *Kara dewit*, or Black Ink-stand. On the opposite side of the hill, the face of the country under-goes a complete change. Instead of a continued chain of mountains, like those we had quitted, was a succession of detached hills of a conical shape, and covered for the most part with vines. In the midst of these eminences, at the further extremity of a circular plain, is the highly picturesque town of *Kula*, situate amidst huge black vitrified masses in the bed of an extinct volcano ^q.”

Kula itself appears to represent some ancient city, Mæonia ^{urbs.} being full of inscriptions and architectural fragments; and from one of the inscriptions, which contains the name *Mηιόνες*, one might be inclined to think that it has been built on or near the site of Mæonia. Major Keppel, however, informs us, “ that the inscription in question was brought from a village two leagues distant, actually bearing the name of *Megna*, which closely resembles Mæonia.” He was informed also, that several of the surrounding villages abounded with inscriptions and monuments ^r. The wine which he drank here was observed to be the best he had tasted in the course of his journey ^s. Mæonia is mentioned as a Lydian town by Pliny; (V. 29.) also by Hierocles, and the Episcopal Notitia: and it is further known from its

^q Major Keppel's Travels in Asia Minor, tom. II. p. 340.

^r P. 344.

^s P. 355.

coins of the reigns of Nero, Hadrian, and others ^t. Vitruvius also speaks of its wine, called Catacecaumenes. (VIII. 3.)

Near *Kula* is a village called *Ghiuldix*, which, from the vestiges of antiquity, consisting of foundations of houses and temples, fragments of marble, and numerous bas-reliefs, observed there by Major Keppel, must have been the site of some Lydian town ^u. From some analogy of the name it may be

^{Daldes vel Daldia.} Daldes, or Daldia, assigned to Mæonia by Ptolemy, (p. 120.) and the Episcopal Notitiæ ^x.

Artemidorus, the writer on dreams, who was a native of the place, (Oneirocr. II. c. ult.) mentions that Apollo Mystes was worshipped there. There are several existing coins of this town ^y.

^{Tabala.} Tabala, another obscure town of the same province, appears from its coins ^z to have been seated on or near the Hermus, and some vestige of the name may be traced in that of *Tonbaili*, a village on the left bank of the river, between *Adala* and *Kula*. In Hierocles the name is corruptly written Talaza, (p. 670.) and in the Ecclesiastical Notices, Gabala ^z: but the coins shew incontrovertibly how it should be written ^a.

^{Julianopolis.} Hierocles names, after Mæonia, Julianopolis, which is

^{Aureliopolis.} unknown to other writers; and Aureliopolis, a see whose bishops are known to have subscribed to the councils of Constantinople and Nicæa ^b.

^t Sestini, p. 109. Epigraphe ΜΑΙΟΝΩΝ et ΔΗΜΟΣ ΜΑΙΟΝΩΝ. Imperatorii a Nerone, indeque ab Hadriano usque ad Etruscum.

^u P. 356.

^x Geogr. Sacr. p. 244.

^y Sestini, p. 107. Daldis. Epigraphe ΔΑΛΔΙΑΝΩΝ. Impera-

torii ab Augusto usque ad Philippum Jun.

^z See a note of Wesselink on Hierocles, loc. cit.

^a Sestini, p. 113. Tabala. Epigraphe. ΣΤΝΚΛΗΤΟΣ ΤΑΒΑΛΕΩΝ.

^b See Wesselink on Hierocles, p. 670. Sestini produces

Apollonoshieron, so called from a temple of Apollo, ^{Apollonos-}
is noticed by Pliny as a place of little note. (V. 29.) ^{hieron.}
It appears to have been afterwards a bishopric; (Hierocl. p. 670.) and if it is the place mentioned by Aristides, (I. p. 625, 629.) it was seated on a hill, and about 300 stadia from Pergamum, a distance which rather agrees with the Apollonias of Strabo.

Ptolemy places in Mæonia, which he makes a separate district between Lydia and Phrygia, besides Daldia, Septæ, or Settæ, of which we have already spoken, and Sattala. (p. 120.) The latter is known ^{Sattala.} also from Hierocles, (p. 670.) and the Acts of the Council of Chalcedon, to which its bishop subscribed. Reference is likewise made to it in the Dionysiacs of Nonnus, (XIII. 474.) under the form Στάταλα. The poet's description leads us to place it in the heart of the volcanic district.

Καὶ Στατάλων κεκόρυστο πολὺς στρατὸς, ἦχι Τυφωεύς
Θερμὸν ἀναβλύζων πυριθαλπέος ἀσθμα κεραυνοῦ
Ἐφλεγε γείτονα χώρον.

It is either *Kula* itself, or one of the neighbouring sites, where antiquities are found.

Sirghié, a place near which Major Keppel observed some antiquities^c, may perhaps correspond with Cerasæ, a Lydian bishopric, named by Hierocles (p. 671.) after Bagæ, which we have seen, from the traveller above quoted, to have been opposite to *Sirghié*. The bishops of Cerasæ are also referred to in the Acts of the council of Chalcedon and Nicæa. Nonnus speaks of Cerassæ, and gives a

some coins with the legend ΑΤ-
ΡΗΛΙΟΠΟΛΙΤΩΝ; they are not
earlier than Commodus.

^c Travels, tom. II. p. 363—
365.

fanciful derivation of the name; at the same time he informs us that it was in the wine country. (XIII. 468.)

*Καὶ χθόνα Βακχεῖην σταφυληκόμων, ἥχιτε κοῦρος
Αμπελόεις Διόνυσος, ἔχων δέπτας ἐμπλεον οἴγου,
Ρείη πρῶτα κέρασσε, πόλιν δ' ὀνόμην Κέρασσας.*

Philadelphia.

But the most considerable and important town in this part of Lydia was Philadelphia, which owed its foundation to Attalus Philadelphus, brother of Eumenes, king of Pergamum. (Steph. Byz. v. *Φιλαδέλφεια*.) Pliny reports, that it was seated on the river Cogamus, at the foot of Tmolus. (V. 29.) Strabo places it on the borders of Catacecaumene, and observes, that it suffered repeatedly from violent shocks of earthquakes. The walls and houses were constantly liable to be demolished, and as the inhabitants were continually apprehensive of some disaster to themselves and their property, it had nearly become deserted. (XIII. p. 628. XII. p. 579.) Tacitus mentions it among the towns restored by Tiberius, after a more than ordinary calamity of this kind. (Annal. II. 47.) In the midst of these alarms Christianity however flourished in Philadelphia, a fact which is well attested by the Book of Revelations, where it is mentioned as one of the seven churches. (iii. 7.) “ And to the angel of the “ church in Philadelphia write; These things saith “ he that is holy, he that is true, he that hath the key “ of David, he that openeth, and no man shutteth; “ and shutteth, and no man openeth; I know thy “ works: behold, I have set before thee an open door, “ and no man can shut it: for thou hast a little “ strength, and hast kept my word, and hast not de-

^d Note to Hierocles by Wesseling, p. 671.

“ nied my name.” And a little further, “Because thou hast kept the word of my patience, I also will keep thee from the hour of temptation, which shall come upon all the world, to try them that dwell upon the earth. Behold, I come quickly: hold that fast which thou hast, that no man take thy crown.”

The zeal of the Philadelphians shone forth conspicuously in the gallant defence they made against the Turks on more than one occasion. (G. Pachym. p. 290.) At length they were conquered by Bajazet in 1390. (M. Duc. p. 70. Chalcond. p. 33.) It is now called *Allah-sher*, and preserves some remains of Christianity, and also a few monuments of heathen antiquity. Chandler states, “that it is now a mean but considerable town, of large extent, spreading up the slopes of three or four hills. Of the walls which encompassed it, many remnants are standing, but with large gaps. The materials of this fortification are small stones, with strong cement. It is thick and lofty, and has round towers. The bed of the Cogamus, which is on the north-east side, was almost dry. The number of churches is reckoned at twenty-four, mostly in ruins. Only six are in better condition, and have their priests^e.” The Table Itinerary lays down a road leading from Philadelphia to Cotyæum in Phrygia, and divided into four stages: the first is Clanudda, distant thirty-five miles from Philadelphia. I conceive this spot to be the fortress which

Clanudda
et Calyd-

nium.

^e Travels, p. 310, 311. The coins of Philadelphia are very numerous. The imperial series extends from Augustus to Valerian. The epigraph is ΦΙΛΑΔΕΛΦΕΩΝ. On one of them

is the word ΠΗΓΗ, denoting some spring, or fountain, near the town. It is probably the hot source observed by Chandler near the Cogamus, p. 311.

Strabo calls Callydium, and Eustathius, who quotes him, Calydnium. The geographer speaks of it as a place of great strength, long occupied by Cleon of Gordus during his marauding expeditions in these parts. (XII. p. 574.) We should expect to find some remains of this post in the vicinity of *Ienisher*, where there are some antiquities, as we have learnt from Major Keppel^f. Aludda, or Attalyda, as it should probably be read, is thirty miles beyond, and seems to belong to Phrygia.

Dioshie-
ron.

There remains now only to speak of that portion of Lydia which lies between the Caystrus and the Meander. Near the former river, and perhaps in the Cilbianus Campus, was Dioshieron, or the temple of Jove, a town mentioned by Ptolemy; (p. 119.) and Pliny. (V. 29.) Hierocles assigns it to Asia. (p. 659.) Steph. Byz. says it was a small town between Lebedos and Colophon. (v. Διός ἱερὸν.) From the mention of the Caystrus on its coins, it however appears plainly to have been near that river^g; and Ptolemy's numbers accord with this idea. When it became a bishopric, the heathen name was dropped for that of Christopolis. (Concil. Constant. III. p. 500. ed. Labb.) *Tirieh*, on the left bank of the Caystrus, about twenty miles above Ephesus, possibly corresponds with the ancient site of Larissa, which Strabo says is 180 stadia from that city. (XIII. p. 620.) The chain of mountains which

Larissa.

^f Strabo seems to place Calydnium in Mysia, the limits of which, it must be remembered, were very indefinite, involving districts which at other times were assigned to Maeonia and Phrygia. Col. Leake, in a note appended to Major Keppel's

work, states, "having learnt "that a coin exists in the pos- "session of a gentleman at "Smyrna, bearing the inscrip- "tion Κλαυδέων." p. 371.

^g Sestini, p. 107. Epigraphe ΔΙΟCIEPEITΩΝ, mentio situs ad Fl. Caystrum ΚΑΤCTPOC.

divides the valley of the Caystrus from that of the Meander begins above Ephesus, where its roots form the hills of Pactyas and Coressus ; it then runs parallel to Tmolus from west to east, under the ancient name of Messogis, till, having passed beyond the head of the Caystrus, it bends to the north, to meet the great Lydian range. To the east it however continues to extend its ramifications with Phrygia beyond the sources of the Meander^{h.} (Strab. XII. p. 629.) In Ptolemy the name is faultily written Misatis. (p. 119.) To the Turks it is known by that of *Kestenous Dagh*.

If a traveller proceeds from Ephesus to the south-east, across mount Pactyas, and follows a small stream which winds in a valley towards the Meander, he will reach, not far from their junction, the ruined site of Magnesia, which took its surname from the latter river. Founded by a colony of Magnesians from near Dotium in Thessaly, who were joined by some Cretans, (Strab. XIV. p. 636, 647.) it had attained to a high rank among the surrounding cities of Greek origin, and was able to cope with success against the powerful city of Ephesus. (Callin. ap. Strab. XIV. p. 647.) Subsequently, however, the Magnesians were overcome by the Treres, a Thracian horde which overran Ionia and Lydia, and were nearly destroyed. The year following, the city being deserted was occupied by the Milesians, or, as Athenæus reports, by the Ephesians. (XII. p. 525.) These disasters were alluded to by Archilochus. (ap. Strab. loc. cit. Athen. loc. cit.) It is probable, however, that the Magnesians recovered from this ruinous

^h The name of this mountain evidently refers to its extent toward the interior, & μεσογεία.

condition, since we find their city assigned by Artaxerxes to Themistocles when residing in his dominions, for the purpose of supplying his table with bread. (Plut. Vit. Themist. Thuc. I. 138.)

Its territory, indeed, was extremely fertile, and produced excellent wine, figs, and cucumbers. (Athen. I. p. 29. II. p. 59. Polyb. ap. eund. III. p. 78.) Before that period, it appears from Herodotus to have been occasionally the residence of the Lydian satrap. (III. 122. Cf. I. 161.) Strabo reports that there was anciently a celebrated temple of Dindymene, or Cybele, at Magnesia, of which, as it is said, the wife or daughter of Themistocles was once priestess. But he adds that the temple no longer existed in his day, the site of the town having been removed to that occupied by the temple of Diana Leucophrys. Strabo does not inform us of the cause which led to this change in the situation of Magnesia, nor of the period at which it took place; but it will appear to have occurred posterior to the age of Xenophon, who mentions in the Hellenics Leucophrys as a spot distinct from Magnesia, which he does not name at all; at the same time there can be no doubt that it is the site which Strabo alludes to, for he says, there is there a temple of Diana much venerated, and a lake more than one stadium in circuit, with a sandy bottom, and producing a never failing supply of water, fit for drinking, and warm. (Hell. III. 2. 14.) And elsewhere he speaks of Leucophrys as a town in the vicinity of Priene and the Meander. (Hell. IV. 8. 17.) The poet Nicander, speaking of the roses which bloomed on the spot, evidently connects it with Magnesia.

Οὐδ' αὐτὴ Λεύκοφρυν ἀγασσαμένης ἐπιμεμφής,
Ληθαίου Μάγυντος ἐφ' ὅδασιν εὐθαλέουσα.

GEORG. II. AP. ATHEN. XV. p. 683.

For the Lethæus is known, from Strabo and other Lethæus fl. writers, to have flowed close to Magnesia, on its way from mount Pactyas to join the Meander. (XIV. p. 646.) The temple of Diana, though inferior in size and riches to that of Ephesus, was allowed to excel it in the beauty and skill of its architectural contrivance; and in magnitude it only yielded to the edifice above named, and that of Apollo at Didymi. (Strab. loc. cit.) The style was Ionic, and the architect Hermogenes of Alabanda, who is said to have invented the order. (Vitruv. VII. præf. Cf. Pausan. Lacon. c. 18.) Magnesia, with the rest of Lydia, was annexed to the kingdom of Pergamum by the Roman senate, after Antiochus had been driven beyond mount Taurus. (Liv. XXXVII. 45.) And Strabo relates, that a poet named Daphidas, having written some satirical lines on the new sovereign, was crucified on mount Thorax, above Thorax mons. the town. (XIV. p. 647. Cf. Suid. v. Δαφίδας. Cic. de Fat. c. 3. Val. Max. I. 8. 8.) Little is known respecting this town after this period, but it is noticed by Pliny (V. 29.) and Tacitus. (Ann. IV. 55.) Hierocles ranks it among the bishoprics of Asia, and later documents seem to imply that it once had the name of Meandropolis. (Concil. Constant. III. p. 666ⁱ.) Magnesia is now well known to correspond with the site and ruins of *Inek-basar*; former tra-

ⁱ The coins of Magnesia prove its existence in the time of Aurelius and Gallienus. The legend is ΜΑΓΝ. and ΜΑΓΝΗ-

ΤΩΝ. Allusion is also frequently made to the worship of Diana Leucophryne, and the river Meander. Sestini, p. 83.

vellers, as Pococke and Chandler, had identified it with *Guzel-hissar*; but Mr. Hamilton was the first to examine the remains of antiquity at *Inek-bazar*, and to prove that the position of that place agrees with the accounts of Strabo and other ancient writers. This is demonstrated by the discovery he made of the ruined temple of Diana Leucophryne, views of which have been published by the Dilettanti society. We know besides, that Magnesia was fifteen miles from Ephesus, (Plin. V. 29.) or 120 stadia, according to Artemidorus. (ap. Strab. XIV. p. 663.) Pausanias mentions that there was at Hylæ, a spot near Magnesia, a cave sacred to Apollo, containing a very ancient image of the god. (Phoc. c. 32.)

Anæa.

It is uncertain whether we should assign Anæa, a town not unfrequently spoken of by ancient writers, to Lydia, or Caria. Scylax is in favour of the former location, but Ptolemy and Stephanus pronounce for the latter. The Byzantine geographer adds, that it was opposite to Samos; if so, it must have been within the limits of Lydia, since no part of the Samian coast extends south of the Meander. Hierocles also, and the Ecclesiastical Notices, by assigning it to the province of Asia, with Ephesus and Magnesia, evidently lead us to suppose it was on the right or Lydian bank of the river. Anæa is often referred to by Thucydides, who mentions its being occupied by some Samian exiles in the early part of the Peloponnesian war. (IV. 75. Cf. III. 32.) That it was a maritime place, or at least accessible by water, is also clear, from (VIII. 19.) where it is said that the Chians sailed there from their island, in order to obtain intelligence about Miletus,

and draw other towns to revolt. If we examine another passage again in the same historian, it appears that an Athenian officer, named Lysicles, having sailed to Myus with twelve ships, landed with a detachment, and marched up the land through the Meandrian plain, but being attacked by the Carians and Anaiitæ, near a hill called Sandius, was defeated and slain with most of his corps. (III. 19.) It will be seen therefore that the Anaiitæ, or people of Anæa, must have lived in the vicinity of the Meander, and between Magnesia and Priene, but on the high ground above the river, as the name seems to imply, and it is not improbable that their territory extended also on the other side of the hills towards Ephesus, and the coast opposite Samos. And they might have a port in that direction, where the Chians, in the passage from Thucydides above referred to, would naturally have landed, without going so far round as the mouth of the Meander, and then up the river beyond Priene and Myus. Stephanus says, on the authority of Ephorus, that Anæa was so called from an Amazon who was interred there. He adds, that it was the birthplace of Menelaus, a peripatetic philosopher, and considerable historian. In Hierocles, there is little doubt that for Ἐνέα we should substitute Ἀναιά. In this vicinity we must also place Achilleum, a town or fort mentioned by Xenophon, in conjunction with Priene and Leucophrys, and other cities in the Meandrian plain. (Hell. IV. 8. 17. Cf. III. 2. 13.) Stephanus Byz. states more vaguely that it was a fortress near Smyrna. (v. Ἀχίλλειος Δρόμος.)

The plain of the Meander, “ Meandrius Campus,” is constantly referred to by ancient autho- Mæandrius
Campus.

ties, as the richest and most fertile soil in all Asia Minor. (Xen. Hell. III. 2. 13. Herod. I. 161.) It was subject to be overflowed by the waters of the river, which however fertilized it by means of the mud and slime which it brought down. Strabo informs us that the inhabitants had a strange custom of bringing actions against the Meander for changing its course, and thus altering the limits of their lands. (XII. p. 580.) Herodotus appears to have imagined that the whole of this plain was once a gulf washed by the sea; (II. 10.) and Pliny does not scruple to affirm that the sea even came up as far as Magnesia, and that the islands named Derasidæ, were joined to the land on its subsequent retiring. (V. 29.) Strabo seems to restrict the Meandrian plain to the right bank of the river, and remarks, that it was common to the Lydians, Carians, Milesians, and Magnesians. (XIV. p. 648.) In the middle ages, this district appears to have received the name of Mænomenus Campus, (*μαινόμενος*,) probably from the fertility of its pastures^k. (Georg. Pachym. Andr. Pal. p. 216. M. Duc. p. 46.) It was then almost constantly the seat of war, and exposed to destructive ravages. Beyond Magnesia to the south-west, and somewhat nearer the Meander, was Tralles, one of the most flourishing cities of Asia Minor in the time of Strabo, and noted for the opulence of its inhabitants. It was said to have been founded by some Argives, together with a body of Thracians, from whom it took the name of Tralles. (XIV. p. 649. Hesych. v. Τράλλεις. Diod. Sic. XVII. 65. Plut. Ages. c. 16.) It had previously

^k As in Sophocles, *ππομανῆ* by some ἐφ' ḡ εἰ πποι μαινον-λειμῶνα (Aj. 143.) is explained ται.

borne those of Anthea, or Euanthea, Erymna, Charax, Seleucia, and Antiochia. (Steph. Byz. vv. Τράλλις, Χάραξ. Etym. M. p. 389. Plin. V. 29.) The shape of the town was that of a trapezium, and it was defended by a citadel, and other forts. The river Eudon, or Eudonus, flowed near the walls, Eudon fl. and another little stream or fountain, named Thebais fons. Thebais, traversed the city. (Plin. V. 29.) It was situated on the high road leading from Ephesus, through Lydia and Phrygia, as far as Cappadocia and the Euphrates, and consequently must have been a place of great traffick. (Cic. Ep. ad Att. V. 14. ad Fam. III. 5. Q. Frat. Ep. I. 1. 6. Artemid. ap. Strab. XIV. p. 663.) The citizens of Tralles, on account of their great wealth, were generally elected to the office of asiarchs, or presidents of the games, celebrated in the province. Pythodorus, who had held this situation, was very intimate with Pompey, a circumstance which exposed him to the vengeance of Cæsar. His estates, worth, it is said, more than 2000 talents, were confiscated in consequence; but he was nevertheless enabled to redeem them, and leave the whole to his children, of whom Pythodoris, princess of Pontus, was one. Menodorus, a man of learning and priest of Jupiter Larissæus, was another distinguished individual who flourished at Tralles in the time of Strabo; but he fell under the persecution and false accusations of Domitius Ænobarbus' party. (XIV. p. 648.) The country around Tralles was much subject to earthquakes, and in the reign of Augustus several public edifices were destroyed by a violent shock, which damaged other cities also; these received a grant from the emperor to repair the losses they had sustained.

(Strab. XII. p. 579.) The Trallians petitioned for the honour of erecting a temple to Tiberius, but without effect. (Tacit. IV. 55.) Mention of this city is likewise made in Polybius, (Exc. XXII. 27. 10.) Liv. (XXXVII. 45. XXXVIII. 39.) Cæs. (B. Civ. III. 15.) Juv. (Sat. III. 70.) and Hierocles. (p. 659.) In the middle ages it was repaired by Andronicus Palæologus. (G. Pachym. p. 320.) Chandler mistook the ruins of Tralles for those of Magnesia, as Monsieur Barbier du Bocage has well proved in his notes to the French translation of his work. They are situated above the modern *Ghiuzel-hissar*, in a position corresponding with Strabo's description. Pococke had also discovered there an inscription, in which mention was made of Tralles; and others were found afterwards by Mr. Sherard¹. Chandler says he saw at *Ghiuzel-hissar* many fragments of architecture of the Corinthian and Ionic orders: on the castle, and a hill somewhat beyond it, were some massive remains of a wall and arches^m. Vitruvius mentions a temple of Æsculapius at Tralles. (Præf. lib. VII.) Besides the Eudon, there was a stream named Characometes, which flowed in the vicinity of this city: the name has evidently some reference to a small place called Charax, which existed prior to the foundation of Tralles. (Steph. Byz. v. Χάραξ.) The river might be discovered by means of the hot spring which Athenæus refers to. (II. p. 43.) Nysa, another considerable city of Ly-

Characo-
metes fl.

Nysa.

¹ Col. Leake's Asia Minor, p. 246.

^m Travels in Asia Minor, p. 258, 259. The medals of Tralles are to be found in every collection: the epigraph

is ΤΡΑΛΛ. or ΤΡΑΛΛΙΑΝΩΝ; sometimes ΚΑΙΣΑΡΕΩΝ ΤΡΑΛΛ. in allusion, probably, to the restoration by Augustus. Sestini, p. 115.

dia, was situated to the east of Tralles, and between mount Messogis and the Meander, backed by the mountain, and divided by a torrent which descended from it. Tradition assigned the foundation of Nysa to three brothers, named Athymbrus, Athymbradus, and Hydrelus, who came from Sparta, and founded three towns in the Meandrian plain; but in process of time Nysa absorbed them all. The Nysæans themselves acknowledged more especially Athymbrus as their founder. (Strab. XIV. p. 650. Steph. Byz. v. *Αθυμβρα*.) Their city was also once named Pythopolis. (Id. vv. *Νύσαι*, *Πυθόπολις*.) Literature seems to have greatly flourished here, and Strabo mentions several distinguished philosophers and rhetoricians who taught in the place. Strabo himself, when a youth, had attended the lectures of Aristodemus, a stoic and disciple of Panætius: another Aristodemus, his cousin, also of Nysa, had been preceptor to Pompey. (XIV. p. 650. Cf. Cic. ad Fam. XIII. 64. Plin. V. 29.) Hierocles classes Nysa among the sees of Asia, and its bishops are recorded in the councils of Ephesus and Constantinopleⁿ. The vestiges of Nysa have been recognised by Chandler and others, at *Sultan*, or *Eski-hissar*, above the plain of the Meander, on a site much resembling Strabo's account. He describes it as divided into two towns by a torrent, over which was thrown a bridge: its waters also flowed under the amphitheatre. Besides this public building, he notices a theatre, a forum, a gymnasium for youth, and another for elders. (XIV. p. 649.) Chandler found vestiges of a large theatre in the mountain side,

^h Wesseling's note to Hierocles. The medals of Nysa are inscribed ΝΤΣΑΕΩΝ. They ex-

hibit a series of Roman emperors, from Augustus to Gallienus. Sestini, p. 89.

with many rows of seats, almost entire; also of the amphitheatre, gymnasium, senate-house, market-place, &c.ⁿ The country around Nysa, and generally in the vicinity of the Meander, bore evidence of the existence of subterraneous fires, either by exhalations and vapours, or the bursting forth of hot mineral springs. Between Nysa and Tralles, but nearer the former, was a place called Acharaca, celebrated for a Plutonium, or a beautiful grove and temple of Pluto, and a cave, named Charonium, where some wonderful cures were performed under the influence of Pluto and Proserpine, and by means of remedies suggested in dreams to the priests. The patients were sometimes shut up in the cave for several days, fasting. Every year there was a great concourse at this place, during which a bull was driven by the youth of the gymnasium to the cave, where he presently expired. There was another cave at Limon, about thirty stadia from Nysa, also dedicated to the same deities, and supposed to communicate with that of Acharaca. Some pretended that this meadow was the Asius Campus of Homer. (Strab. XIV. p. 650.) The slope of mount Messogis, above Acharaca, produced the best wine of the whole chain. It took its name of Aromeus from Aromata, (*Ἄροματα*,) a small town near which it grew. (Strab. loc. cit. Steph. Byz. vv. *Μέσσωγις*, *Ἄρωμα*.)

Briula. Near Nysa Strabo also places Briula and Mastaura. These towns are likewise mentioned by Pliny, (V. 29.) Hierocles, (p. 659.) and the other Notices and Acts of Councils. Mastaura, as appears from Stephanus Byz. (v. *Μάσταυρα*,) was watered by a stream named Chrysorrhoeas. Some vestiges, to-

Mastaura.

**Chrysor-
rhoas fl.**

gether with the name of *Mastauro* attached to them, a little to the east of *Eski-hissar*, mark the site of this ancient town^o.

It is a matter of uncertainty where to look for the positions of Aninetum, Enara, and Arcadiopolis, episcopal towns of Asia, according to Hierocles, whose authority is also confirmed by the records of various councils^p. Aninetum, or Aninesum, in particular, has the additional evidence of coins in its favour^q.

The last town of Lydia we have to mention on the Meander was Tripolis, placed by the Itineraries on the road leading from Sardes by Philadelphia to Laodicea, and other towns of Phrygia. (Itin. Anton. p. 336. Cf. Tab. Pent.) It is not noticed by any writer prior to Pliny, who says, in his concise way, "Tripolitani iidem et Antoniopolitæ Mæandro alluntur;" (V. 29.) whence it would appear to have been also called Antoniopolis. The name of Tripolis, however, is much more frequently used, being found in Ptolemy, (p. 119.) the Ecclesiastical Notices, and Hierocles. (p. 669.) This place must have been near the junction of the two roads leading from Lydia and Caria into Phrygia, and consequently in the vicinity of Callatebus, a Lydian town mentioned by Herodotus in his account of Xerxes' march from Cappadocia and Phrygia to Sardes. (VII. 31.) The Persian monarch, having left Colossæ in the latter

^o Pococke's Travels. There are coins of Briula and Mastauro. The former are inscribed ΒΡΙΟΤΛΕΙΤΩΝ, the latter ΜΑΣΤΑΤΡΕΙΤΩΝ; these are more numerous, and prove Mastauro to have been the more

considerable town of the two. Sestini, p. 106, 110.

^p Wesseling on Hierocles, p. 659.

^q Sestini, p. 105, Aninesum. Epigraphe ΑΝΙΝΗΣΙΩΝ.

province, reached Cydrara on the confines of Lydia, where the limits of the two provinces were marked by a pillar erected by Croesus. Cydrara must therefore have been very near Hierapolis, now *Pambouk Calesse*, where the two routes indicated by Herodotus branch off. Xerxes, following the road to Sardes, took to the right, and, having crossed the Meander, came to Callatebus, where confectioners, says Herodotus, made honey from tamarisk and wheat.

Callatebus. Mannert is inclined to identify Callatebus with Philadelphia^r; but the account of Herodotus leads one rather to seek for it nearer the Meander and the Carian frontier. In Mons. Lapie's map there are some ruins laid down to the north of Tripolis, at a place called *Eski Kaleh*, which is not unlikely to be the Callatebus of Herodotus. Steph. Byz. is the only geographer who names this place besides him, and he copies merely from his account. (v. Καλλάτηβος.) Tripolis, according to some church traditions, is connected with the apostles St. Philip and St. Bartholomew. It is also frequently referred to by the Byzantine historians in the course of the Turkish wars. (G. Acrop. p. 38.) Its ruins consist of confused heaps of stones, with some vestiges of a theatre and castle^s.

Having now terminated the tour of Lydia, it only remains for me to close the section with the names of such places as have no fixed site assigned to them in it, and are consequently of a more dubious character than those hitherto mentioned.

^r Geogr. t. VI. P. 3. p. 365-6. He inadvertently writes it Cal-labetus.

^s Chandler's Travels, p. 305. There are coins of Tripolis of

the reigns of Augustus and downwards to that of Gallienus. Allusion is made on them to the proximity of the Meander. Sestini, p. 90.

Acrasus has already been alluded to as differing Acrasus from Nacrasa, though identified with it by some antiquaries ^t.

Anolus is assigned to Lydia by Steph. Byz. (v. Anolus. "Ανωλος,) and there are some coins which may possibly be referred to it ^u. We learn from Hierocles, (p. 670.) and other ecclesiastical documents, that it was an episcopal town.

Asia, according to Steph. Byz. was a city of Ly-Asia. dia, near Tmolus, (v. 'Ασια,) where the harp with three strings was invented. (Cf. Etym. M. v. 'Ασιάτις.) According to Herodotus, it was a portion of Sardes. (IV. 45. Cf. Callin. et Demetr. Sceps. ap. Strab. XIII. p. 627.)

Assus, a meadow in the Cilbianus Campus, and Assus. near the Cayster. (Steph. Byz. v. "Ασσος.) This is perhaps a mistake for Asius.

Astelebe and Asteria are ascribed to Lydia by Astelebe. Steph. Byz. on the authority of Xanthus. (vv. 'Αστε- Asteria. λέβη, 'Αστερία.)

Attalyda, according to the same lexicographer, Attalyda. was founded by Atys. (v. 'Αττάλυδα.)

Aphneium, a town of Lydia. (Steph. Byz. v. "Αφ- Aphneium. νειον.) It is however probably the same place spoken of near Cyzicus.

Diospolis. Among other cities of this name Steph. Diospolis. Byz. assigns the sixth in his list to Lydia; it is probably the same as Dioshieron.

Eupatria is given to the same province, on the Eupatria. authority of Xanthus. (v. Εὐπατρία.) There are two Heracleas in the list of Stephanus, which seem to Heraclea.

^t The legend on its coins is ΑΚΡΑΣΙΩΤΩΝ. Sestini, p. 105.

^u Sestini, p. 105. Anolus? Autonomi Epigraphe, ^{AV} Ω. ΑΕ.

belong to Lydia. One was near Magnesia, and is noted for producing the magnet, called **Magnes**, or **Heraclius**, by the ancients^x. (Eustath. ad Hom. Il. B.) Another is said to have been ἐν Λυδίῳ Ταύρῳ. If this reading is right, we should understand by this mountain Messogis, which joined Mount Taurus; but perhaps we ought to correct it to ἐν τῷ Ἀντιταύρῳ.

Thyessus. **Thyessus**, said to have been named after a trader so called, (Steph. Byz. v. Θυεσσός,) is known also from its coins^y.

Thymbrara, vel Thymbra. **Thymbrara**, or **Thymbrara**, where the great battle was fought, according to Xenophon, which decided the fate of the empire of Crœsus, is assigned by Steph. Byz. to Lydia, and placed on the banks of Pactolus. But it is plain, from Xenophon's account, that Thymbrara, or Thymbria, (the MSS. differ very much about the orthography of the name,) (Cyrop. VI. p. 158, Leuncl.) was beyond Pactolus: he adds, that in his time it was the rendezvous of all the barbarian forces under the Persian monarch in Lower Asia. This seems to point also to the plain called in the Anabasis **Castoli Campus**, Καστωλοῦ πεδίον, (I. 1.) where it is said that Cyrus was appointed by his brother Artaxerxes governor of all the nations which assembled in the plain of Castolus. This was probably a river, but Steph. Byz. calls it a town. I do not understand the lexicographer, Καστωλοῦ πεδίον Δωριέων ἐκλήθη δὲ ὅτι Καστωλοὺς τοὺς Δωριεῖς οἱ Λυδοί φασιν. There must be some confusion here.

^x There are some imperial coins of the Lydian Heraclea. Sestini, p. 108.

^y Sestini, p. 114. Thyessus, autonomus unicus. Epigraphe ΘΤΕΣΣΕΩΝ.

Ibeni, a people of Lydia, called also Iaonitæ. Ibeni. (Steph. Byz. v. Ἰβαιοι.) According to the same lexicographer we have likewise an Itone in this province. Itone. It is also mentioned by Nonnus in conjunction with a torrent or river named Cimpusus :

Λυδῶν δὲ ἀβρὸς ὅμιλος ἐπέρρεεν, οὗτ' ἔχον ἄμφω
Κίμψον ἐϋψήφιδα, καὶ ὁρυσσάνταν Ἰτάνην.

DIONYS. XIII. 465.

Cyalus, a town of Lydia, founded by Cyalus, son of Cyalus. of Jove. (Id. v. Κύαλος.) Cyne is assigned to the same country on the testimony of Hecatæus. (Id. v. Κυνῆ.)

Lycapsus, a spot near Lydia, according to Eu-Lycapsus. phorion. (Id. v. Λύκαψος.)

Lycosthene, or Lycosthenea, a town of Lydia, Lycos- mentioned by Xanthus and Nicolaus of Damascus. ^{thene.} (Id. v. Λυκυσθένη.)

Melampea, cited from Xanthus. (v. Μελάμπεια.) Melampea.

Oanus, a place noticed by Dionysius in the Bas-Oanus. sarica. (Id. v. Ὁανος) and Nonnus.

Καὶ σκοπιὰς Ὁανοῖο, καὶ οἱ ροῦν ἔλλαχον Ἐρμοῦ
Τύδατόεν τε Μέταλλον, δῆν Πακτώλιον ἴλια
Ξανθὸς ἀποκτύων ἀμαρύσσεται ὄλβος ἐέρσης.

DIONYS. XIII. 470.

Pelope, a village on the borders of Phrygia. Pelope. (v. Πελόπη.)

Progasia, so called from Progasus, son of Melampus. (Id. v. Προγάσεια.) Procle, a town of Lydia. (Id. Πρόκλη.)

Strogola, cited from the history of Xanthus. (Id. v. Στρόγωλα.)

Tarrha, a town of Lydia. (Id. v. Τάρρα.) the Etym. Tarrha, vel Magnum calls it Tyrrha. Tyrrha.

Tomarene. Tomarene, a town known only from its coins, is assigned to Lydia by Sestini ^z.

Torrhebus. Torrhebus derived its appellation from Torrhebus, a son of Atys. It gave its name to the district Torrhebis, in which was Mount Carius, and a temple of the hero Carius, son of Jove and the nymph Torrhebia. There was also a lake, Torrhebia. All this seems derived from Nicolaus of Damascus, who copied Xanthus. (Steph. Byz. v. Τόρρηβος. Cf. Dion. Halic. Pont. and Nonnus Dionys. XIII. 467.)

Οἱ τε Τορῆβιον εύρù, καὶ οἱ Πλούτοιο τιθήνας
Σάρδιας εὐώδινας ὁμήλικας Ἡριγενείης.

Hysbe. Hysbe, a town of Lydia. (Id. v. "Τσβη.") Hierocles has, under the head of Asia, the following obscure sees, belonging either to Lydia or Ionia: Algiza, Nicopolis, Palæapolis, Baretta, Auliucome, Neaule. (p. 660.) Mostine, which Wesseling supposed to be a correction for Mystene, crept in from the margin, (p. 671.) appears to be genuine, if its coins are so. They teach us that the true name of the town is Mossine, and that it was near a small stream, or fountain, called Aligomon ^a. The Table Itinerary places on a road leading from Sardes to Ephesus by Hypæpa, a station named Anagome, nine miles from the last mentioned town, and thirty-four from the former. The site seems to answer nearly to that of *Bainder*, near the Caystrus.

^z Lett. Numism. II. 13. p. 81.
Caput Herculis barbatum nudum, cum pelle leonis ad collum
TOMA
PHNΩΝ Leo gradiens. AE. 3. p.

^a Sestini, p. 110. Mossina, vel Mossinus. Autonomi epigraphe, ΜΟΣΣΙΝΩΝ ΛΤΔΩΝ; in alio ΘΕΟΝ ΣΤΝΚΛΗΤΟΝ. Fons sacer ΑΛΙΓΟΜΩΝ.


ERRATA.


VOL. I.

- P. 28, l. 21, for Pomponius, Mela read Pomponius Mela.
P. 71, l. 1 and 10, for Arisba read Arisbe.
P. 87, l. 22, insert a comma after Ida.
P. 103, l. 28, for Θυμβαῖ read Θυμβρᾶ.
P. 112, l. 12, for χρύσον read Χρύσον.
P. 180, l. 8, the quotations from Aristotle and Pliny probably refer to the Palus Ascania of Pisidia or Phrygia.
P. 193, l. 23, for P. Gythius read P. Gyllius.
P. 282, l. 8, for Chaerades read Chœrades.
P. 412, l. 11, for Garthonisi read Gaitonisi.
P. 454, l. 15, for Tabula read Tabala.

VOL. II.


- P. 24, l. 26, it is more correct to write Berecyntian, Berecyntii and Berecyntia.
P. 53, l. 4, for, it is not frequently, read, it is not unfrequently.
P. 85, l. 28, for Ambitrii read Ambituī.
Ibid. l. 30, for Thynbres read Thymbres.
P. 114, l. 26, for ψέφου read ψέφω.
P. 150, l. 13, for Turnberan read Turnuberan.
P. 196, l. 13, for Calynda read Calydna.
P. 209, last line, for Gengere read Gongere.
P. 275, l. 9, for Cydrema read Cadrema.





[REDACTED]







3 2044 022 681 5



